COOS BAY DISTRICT OFFICE UMPQUA RESOURCE AREA

SALE DATE: December 18, 2015

SALE TIME: 10:00 a.m.

SALE NO. ORC00-TS-2016.0002, STEELE 15 CT

COOS COUNTY: OREGON: CBWR: ORAL AUCTION: Bid deposit required: \$154,400.00

All timber designated for cutting on: T. 27S, R. 12W, Sec. 15, N1/2, E1/2SW1/4, SE1/4, Will. Mer.

Approx. No. Merch. Trees	Est. Vol. MBF 32' Log	Species	Est. Vol. MBF 16' Log	Appraised Price Per MBF	Estimated Vol. Times Appraised Price
26,669	5,676	Douglas-fir	6,452	\$228.70	\$1,475,572.40
3,557	394	red alder	494	\$115.90	\$57,254.60
482	24	western redcedar	28	\$307.10	\$8,598.80
33	12	grand fir	15	\$99.00	\$1,485.00
177	5	western hemlock	7	\$29.10	\$203.70
30,918	6,111	Totals	6,996		\$1,543,114.50

THIS TIMBER SALE HAS BEEN CRUISED, APPRAISED, AND ADVERTISED BASED UPON SCRIBNER BOARD FOOT MEASURE (16 FOOT LOG). THE MINIMUM BID FIGURES SHOWN BY SPECIES ARE DOLLARS PER THOUSAND BOARD FEET (MBF). THE MINIMUM BID INCREMENT WILL BE \$0.50 PER MBF. SCRIBNER BOARD FOOT VOLUMES (32 FOOT LOG) BY SPECIES ARE DISPLAYED FOR INFORMATIONAL PURPOSES.

<u>LOG EXPORT AND SUBSTITUTION</u>: All timber sales, including timber from Federal rights-of-ways, shall be subject to the restrictions relating to the export and substitution of unprocessed timber from the United States in accordance with P.L. 94-165 and 43 CFR 5400 and 5424 as amended.

<u>LOG EXPORT AND SUBSTITUTION RESTRICTIONS</u>: Excepting Port-Orford-cedar, all timber offered for sale hereunder is restricted from export from the United States in the form of unprocessed timber and is prohibited from being used as a substitute for exported private timber.

<u>CRUISE INFORMATION</u>: With respect to merchantable trees of all species in all cruise strata: the average DBHOB is 13.7 inches: the average gross merchantable log contains 49 bd. ft.; the total gross volume is approximately 7,343 thousand bd. ft.; and 95% recovery is expected. The average DBHOB for Douglas-fir is 13.9 inches; and the average gross merchantable log contains 50 bd. ft. The following cruise methods were used for volume determination:

<u>VARIABLE PLOT</u>: Timber volumes in Units 1-3 were based on a variable plot cruise. Using a 20 basal area

factor (BAF), 238 plots were measured and 121 trees were randomly selected to be sampled. The sample trees have been cruised and their volumes computed using form class tables for estimating board foot volumes of trees in 16-foot logs. A portion of the sample trees have been felled, bucked, and scaled and a portion of the sample trees have been cruised and the volumes computed using form class tables for estimating board foot volumes of trees in 16-foot logs. Volume from both methods is then expanded to a total stratum volume.

<u>3P</u>: The Douglas-fir in the right-of-way has been cruised using the 3P system to select 34 sample trees. The sample trees have been cruised and the volumes computed using form class tables for estimating board foot volumes of trees in 16-foot logs.

<u>100% CRUISE</u>: The minor species timber volumes were based on a 100% cruise using form class tables for estimating board foot volume of trees in 16-foot logs.

<u>CUTTING AREA</u>: Three units totaling approximately 378 acres must be partial cut and 11 acres of road right-of-way must be clear cut. Acreage data was collected using a Trimble Geo XT Global Positioning System receiver. Acreage was calculated based on Global Positioning System traverse procedures including differential correction.

<u>ACCESS</u>: Access to the sale area is provided via: Oregon State highways, Coos County roads, Government and privately controlled roads. A gate restricts access to Unit 3. Keys are available at the Coos Bay District Office. A refundable deposit of \$100 is required to obtain a key.

<u>DIRECTIONS TO SALE AREA</u>: From Coquille turn on West Central and travel approximately 1.0 miles to Fairview Road. Turn left onto Fairview Road and travel 8.7 miles. Turn left at the four way stop onto Fairview-Sumner Lane. Travel 2.0 miles and refer to Exhibits A and A-1 for unit locations.

<u>ROAD USE & MAINTENANCE</u>: Purchaser shall pay a maintenance obligation to the Government totaling \$1,527.47. Purchaser shall pay a road use fee totaling \$1,568.00 to Coos County Sheep Company as detailed in the License Agreement. Operator maintenance is required on 4.9 miles of road.

ROAD CONSTRUCTION:

Road construction and improvement estimates include the following:

37.9 stations Class SN-12 road 99.05 stations Class SN-16 road

Surfacing:

230 cu. yds. of 1½-inch minus crushed hardrock 8294 cu. yds. of 3-inch minus crushed hardrock 50 cu. yds. of Riprap barrier rock

Drainage:

40 linear feet of 12-inch CMP culvert

<u>DURATION OF CONTRACT</u>: Will be 36 months for cutting and removal of timber. The contract will contain special stipulations regarding logging, road construction, road use and maintenance, fire prevention, hazard reduction and logging residue reduction, log export and substitution, optional scale check of lump sum sales, equal opportunity in employment, cultural resource protection, and sensitive, threatened, or endangered plants or animals.

SPECIAL PROVISIONS:

- 1. Snags that are felled for safety reasons will be left on site. 41c.
- 2. All Pacific yew and hardwood trees, other than red alder, are reserved from cutting, except within road right-of-ways. 41d.
- 3. Directional felling is required away from roads, property lines, posted boundaries, orange-painted reserve trees, Stream Channels, and snags. 42b. (3)
- 4. Cutting or yarding during high sap flow, March 31 through July 1, may be restricted by the Authorized Officer. 42b. (4)
- 5. Hauling on dirt surfaced roads will be permitted between July 1 and October 15, unless dry conditions extend the hauling season. 42b. (5)
- 6. In the Partial Cut Area, conifer trees will be bucked to a maximum of 41-foot lengths. 42b. (7)
- 7. In the Cable Yarding Area, yarding shall be completed with cable-type equipment capable of lateral yarding 75 feet each side of the skyline road. 42b. (9)
- 8. In the Cable Yarding Area, one-end suspension is required. Lift trees and/or intermediate support trees may be necessary to achieve suspension. 42b. (11)
- 9. No-harvest zones will be maintained adjacent to Stream Channels. Corridor trees felled within the no-harvest zone shall be left on site. 42b. (14)
- 10. Full-log suspension will be required over Stream Channels. Where full suspension cannot be achieved, yarding will occur during the dry season. 42b. (15)
- 11. Within safety standards, harvest trees will be directionally felled away from any Stream Channels; however, trees that must be felled toward or parallel to the Stream Channel should be temporarily retained on site to provide bank armament if other trees need to be yarded across the channel. 42b. (16)
- 12. In the Ground-based Yarding area, any equipment must be approved in writing by the Authorized Officer prior to any operations. 42b. (18)(a)
- 13. The location and use of yarding roads and harvester roads in the Ground-based Yarding Area and Cable Yarding Area shall be approved by BLM prior to use by the Purchaser. 42b. (19)
- 14. Thirty days prior to any operations adjacent to the power line right-of-way, a pre-work meeting shall be scheduled and subsequently held with Coos-Curry Electric Co-op representatives (541-332-3931). In addition, contact the Oregon Utility Notification Center (800-332-2344 or 811) prior to commencing any operations. 42b. (25)
- 15. Road building and logging equipment will be washed prior to moving into the Contract Area to minimize the spread of noxious weeds. 42b. (26)
- 16. Any required construction, improvement, or renovation of structures and roads shall occur during the dry season, June 1 through October 1, both days inclusive, of the same calendar year. 42c. (1)
- 17. Prior to any road construction, improvement, or renovation of structures and roads, contact Oregon Utility Notification Center (800-332-2344 or 811) for the location of buried lines and or cables. 42c. (3)

COOS BAY SALE NO. ORC00-TS-2016.0002 STEELE 15 CT

- 18. In the use of Fairview-Sumner Lane, the purchaser shall obtain an Operator's Permit from the Coos County Road Master. Prior to the commencement of operations, the Purchaser shall furnish to the Authorized Officer a copy of the required executed Operator's Permit. 42d. (4)
- 19. In the use of Fairview-Sumner Lane, the Purchaser shall abide by the conditions of the Operator's Permit obtained from the Coos County Road Master. Flaggers, traffic control measures, and coordination will be required when operations are on or adjacent to Fairview-Sumner Lane. 42b. (24)
- 20. Fairview-Sumner Lane is a well-traveled public road and all efforts must be taken to minimize inconvenience to road users. Fairview-Sumner Lane shall be kept clear of trees, rock, dirt, and other debris so far as is practicable and shall not be blocked by operations for more than 20 minutes. 42b. (24)
- 21. Purchaser must enter into a License Agreement with Coos County Sheep Company. The Purchaser will pay appropriate road use fees and cost of right-of-way timber upon execution of said License Agreement. All trees within the right-of-way on Coos County Sheep Company property are marked with teal green paint. 42d. (5)
- 22. BLM will assume supervisory responsibility for disposal of logging slash. 42e. (1)
- 23. Hand piling of approximately 28 acres is required in the Hazardous Fuels Reduction Area.42b. (3)(w)

SCHEDULE I

- Sec. 41. TIMBER RESERVED FROM CUTTING. The following timber on the Contract Area, shown on Exhibit A, which is attached hereto and made a part hereof, is hereby reserved from cutting and removal under the terms of this contract and is retained as the property of the Government:
- a. All timber on the Reserve Area, shown on Exhibit A, and all blazed, orange painted and/or posted trees which are on or mark the boundaries of the Reserve Area.
- b. All orange painted reserve trees marked above and or below stump height within the Partial Cut Area, shown on Exhibit A.
- c. All existing standing dead trees within the Partial Cut Area, as shown on Exhibit A, except those trees which must be felled to permit safe working operations. Snags felled for safety reasons shall be left on site.
- d. All Pacific yew and hardwood trees, other than red alder, are reserved from cutting, except within road right-of-ways.
- e. All existing coarse woody debris within the Contract Area, unless the Authorized Officer determines the volume to be included in the Exhibit B, which is attached hereto and made a part hereof.
 - f. All Bearing Trees with metal tags which mark property corners.

SPECIAL PROVISIONS - Page 1 of 21 pages

Sec. 42. SPECIAL PROVISIONS. Purchaser shall comply with the special provisions which are attached hereto and made a part hereof unless otherwise authorized, in writing, by the Authorized Officer:

- a. Periodic Payment and First Installment Adjustment
- (1) Notwithstanding the provisions of Sec. 3(b), the amount of the first installment may be reduced by the Government when the Contracting Officer requests the Purchaser to interrupt or delay operations for a period expected to last more than thirty days during the operating season. Such interruption or delay must be beyond the Purchaser's control. Operating Season shall be defined, for this purpose, as the time of year in which operations of the type required are normally conducted and not specifically restricted under the contract. The first installment may be reduced to five percent of the installment amount listed in Sec. 3(b), during the delay period. The Purchaser must request such a reduction in writing. When the Contracting Officer notifies the Purchaser that operations may proceed, the purchaser shall have fifteen days after such notification to return the first installment to the full value within the allotted time will be considered a material breach of contract. No timber shall be cut or removed from the contract area until the first installment is restored to the full amount.
 - (2) Notwithstanding the provisions of Sec. 3(b), adjustments in the due dates for periodic payments may

be made by the Government if the Contracting Officer interrupts or delays contract operations for a period expected to last at least thirty days, and the interruption or delay is beyond the Purchasers control. Any adjustment made shall provide the Purchaser with an equal amount of operating time as would have been available without the delay. The Purchaser shall request such adjustment in writing before the due date for a periodic payment contained in Sec. 3(b).

b. Logging

- (1) Prior to commencement of operations, the Purchaser shall obtain from the Authorized Officer written approval of a written operations and logging plan commensurate with the terms and conditions of the contract which shall include measures needed to assure protection of the environment and watershed. A prework conference between the Purchaser's authorized representative and the Authorized Officer's representative must be held at a location designated by the Authorized Officer before the logging plan will be approved.
- (2) Before beginning operations on the contract area for the first time, or after a shutdown of ten or more days, the Purchaser shall notify the Authorized Officer in writing of the date he plans to begin operations. He shall also notify the Authorized Officer in writing if he intends to cease operations for any period of ten or more days
- (3) Directional felling is required away from roads, property lines, posted boundaries, orange-painted reserve trees, no-harvest areas and snags.
- (4) Cutting or yarding during high sap flow, March 31 through July 1, may be restricted by the Authorized Officer.
- (5) Hauling on dirt surfaced roads will be permitted between July 1 and October 15 unless dry conditions extend the hauling season, as directed by Authorized Officer.
- (6) All trees designated for cutting in the Partial Cut Area, shall be felled to the lead of the pre-marked yarding corridors or pre-marked skid roads.
- (7) All trees designated for cutting in the Partial Cut Area shall be felled, limbed, topped, and cut into log lengths not to exceed 41 feet before yarding.
- (8) Rub trees may be cut and yarded after all lateral yarding is complete on each setting, as directed by Authorized Officer.
- (9) Yarding shall be completed with cable-type equipment. A carriage capable of yarding in a fixed position 75 feet in either direction from the skyline corridor will be required.
 - (10) Complete re-spooling of lines is required in making cable yarding road changes.

- (11) One-end suspension will be required for in-haul of logs during cable yarding operations. Lift trees and or intermediate supports may be required to obtain the required suspension.
- (12) Cable yarding corridors will be 150 feet apart, as measured from the tail hold or where the skyline reaches the far edge of the unit, as measured perpendicular to the preceding corridor.
- (13) Where yarding road locations allow, cable yarding will be done so that corridors are parallel rather than radiating from one central landing, and are placed to avoid a Stream Channel, shown on Exhibit A. Where yarding is to occur over a Stream Channel, the yarding roads will be kept as perpendicular to the Stream Channel as possible.
- (14) A minimum 35 foot slope distance no-harvest zone shall be maintained on either side of a Stream Channel. Corridor trees felled within the no-harvest zone will be felled toward the Stream Channel and left in place. All trees within the no-harvest zone are painted orange, except those reserved in Sec. 41(d.).
- (15) Where cable yarding must occur through the no-harvest area adjacent to a Stream Channel, logs will be fully suspended to protect stream banks. Where full suspension is not feasible, operations over any Stream Channel with visible surface flow will occur only during the dry season, as designated by the Authorized Officer. Bare mineral soil within 50 feet of a Stream Channel, which has been exposed by yarding, shall be covered with slash to trap sediment and prevent erosion.
- (16) Within safety standards, harvest trees will be directionally felled away from any Stream Channels; however, trees that must be felled toward or parallel to the Stream Channel should be temporarily retained on site to provide bank armament if other trees need to be yarded across the channel.
- (17) Prior to attaching any logging equipment to a reserve tree, the Purchaser shall obtain written approval from the Authorized Officer and shall take precautions to protect the tree from damage as directed in writing by the Authorized Officer
 - (18) In the Ground-based Yarding Area, as shown on the Exhibit A:
- (a) A harvester-forwarder system, tractor, rubber-tired skidder, or track mounted log loader may be used. Any equipment must be approved in writing by the Authorized Officer prior to any operations.
- (b) Ground-based operations shall be conducted when soil moisture content is below 25% plastic limit, as determined by the Authorized Officer. Unseasonably dry or wet weather may shorten or extend the operating season. The Purchaser shall be notified in writing when weather conditions extend the operating season. The Purchaser may be required to suspend ground-based operations during periods of rain, as directed by the Authorized Officer.
- (c) Trees shall be felled manually or by a mechanized harvester utilizing a "cut-to-length" system capable of directionally felling, cutting to length, and depositing slash along the harvesting path.

The yarding machine shall utilize slash on skid trails and continually place slash on trails so as to not expose bare mineral soil.

- (d) The yarding machine must be approved by the Authorized Officer. It must be equipped with a grapple or an extendable and retractable arch and fairlead which is an integral part of the machine that is capable of lifting the leading end of the turn clear of the ground. All logs in the Ground-based Yarding Area shall be yarded with their leading end clear of the ground. A forwarder or tracked log loader may also be used to yard logs within the Ground-based Yarding Area.
- (e) Primary skid trails shall use existing trails wherever possible, be spaced at least 100 feet apart, and be no wider than 12 feet as measured between reserve trees.
- (f) Primary skid trails shall be blocked with slash or cull material after completion of harvest where the Authorized Officer determines vehicle access is possible.
- (g) All ground-based equipment shall be restricted to operating on slopes less than 35% and shall not operate within 50 feet of a stream channel.
- (h) Upon completion of seasonal forwarding use, any skid trail with more than 100 feet of continuous bare ground shall have water bars installed and or be covered with slash for erosion control prior to October 15th.
- (19) Before cutting and removing any trees necessary to facilitate logging in the Partial Cut Area, the Purchaser shall identify the location of the harvester roads, cable yarding roads and tailhold, tieback, guyline, lift, intermediate support, and danger trees on the ground in a manner approved by the Authorized Officer at the pre-work conference and documented in the Logging Plan. Said Purchaser's identification of trees to be cut and removed does not constitute authority to proceed with cutting and removal. In addition, before proceeding the following conditions must be met:
- (a) All cable yarding roads upon which timber is identified by the Purchaser to be cut and removed in accordance with this special provision must be necessary for the safe removal of timber sold under this contract and shall be limited to the minimum width necessary for yarding of logs with minimum damage to reserve trees, however, unless otherwise approved in writing by the Authorized Officer, the width of each cable yarding corridor shall be limited to 12 feet.
- (b) The Purchaser may immediately cut and remove additional timber to clear cable yarding corridors; and provide tailhold, tieback, guyline, lift and intermediate support trees; and clear danger trees when the trees have been marked with blue paint above and below stump height by the Authorized Officer and thereby approved for cutting and removal by the Authorized Officer. The volume of the timber to be sold will be determined by the Authorized Officer in accordance with Bureau of Land Management prescribed procedures. No timber may be cut or removed under terms of this provision unless sufficient installment payments have been made in accordance with Sec. 3.(b). of the contract or sufficient bonding has been provided in accordance with Sec. 3.(d). of the contract.

- (c) The Purchaser agrees that sale of this additional timber shall be accomplished by a unilateral modification of the contract executed by the Authorized Officer and that such timber shall be sold at the unit prices shown in the Exhibit B of this contract unless the value of the timber must be reappraised subject to the terms for contract extension set forth in Sec. 9 of the contract; or, the Authorized Officer determines that any tree that exceeds 24 inches diameter at breast height shall be appraised and sold by bilateral modification of the contract at current fair market value in accordance with Sec. 8 of the contract.
- (d) This authorization for the Purchaser to cut and remove additional timber prior to the execution of a modification may be withdrawn by the Contracting Officer if the Authorized Officer determines that the Purchaser has cut and removed any tree not previously marked and approved for cutting by the Authorized Officer which, under Sec. 10 of the contract, constitutes a violation of the contract, and, under Sec. 13 of the contract, may constitute a trespass rendering the Purchaser liable for damages under applicable law.
- (e) If authorization is withdrawn, the Authorized Officer shall issue a written notice to the Purchaser that the sale of additional timber under this special provision is no longer approved. In this case, the Purchaser shall inform the Authorized Officer at least three working days prior to the need for cutting and removing any additional timber, and execute a bilateral modification prior to cutting for such additional approved timber at the unit prices shown in the Exhibit B of the contract or in accordance with Sec. 8 or Sec. 9 of the contract as determined by the Authorized Officer in accordance with this provision. The Authorized Officer may issue a written order to the Purchaser to suspend, delay, or interrupt any or all contract work for the period of time deemed necessary and appropriate for the Government to safely measure and mark additional timber.
- (f) The Government may reserve trees previously designated for cutting and removal by applying orange paint as replacements for additional trees cut and removed for skid roads and/or cable yarding road corridors when the Authorized Officer determines such reservation is necessary to maintain stand densities consistent with objectives set forth in the management prescription. This may include the replacement of trees damaged by storm events, insects or disease. The volume of this timber to be reserved will be determined by the Authorized Officer in accordance with Bureau of Land Management prescribed procedures and the value shall be based on the unit prices shown in Exhibit B of the contract. The Purchaser agrees that the Total Purchase Price stated in Sec. 2 of this contract shall be reduced accordingly through a unilateral modification to the contract executed by the Authorized Officer.
- (20) In accordance with the requirements of Sec. 8, it has been determined that it is in the best interest of the government and within the provisions of 43 CFR 5402.0-6 to sell additional timber located in the Contract Area that is: obstructing needed cable yarding corridors, hazardous to workers in accordance with applicable State safety laws, codes, or regulations and must be cut or removed so that the Purchaser can continue active falling or yarding operations; needed for guyline trees to meet all applicable State safety laws, codes or regulations and must be cut or removed so the Purchaser can continue active yarding operations; or are severely damaged from the normal conduct of felling or yarding operations. The Purchaser is therefore authorized to cut and remove such additional timber in accordance with the provisions of Sec. 8; provided, however, that:

- (a) the Purchaser shall identify each tree sold and cut in accordance with this provision by marking the surface of the stump immediately after cutting with a large "X", cut with a chain saw, and by painting the stump with fluorescent red paint so that the stump can be visually located from a distance of not less than 100 feet;
- (b) concurrently with falling, paint the butt of each tree with fluorescent red paint. When butt logs are yarded, deck separately for inspection by Authorized Officer;
- (c) The Purchaser conforms to all requirements of Sec. 8 of this contract; provided that (1) the unit prices for additional timber within unit boundaries shall be the unit prices shown in Exhibit B of this contract, or the reappraised unit prices arrived at in accordance with Sec. 9 of this contract, and (2) timber outside of unit boundaries shall be sold at fair market value:
- (d) no timber may be cut or removed under the terms of this provision if all contract payments required by Sec. 3. (b) or 3.(d) have not been made; and,
- (e) permission to cut and remove additional timber contained in this provision may be withdrawn by the Contracting Officer if the Authorized Officer determines that the Purchaser:
 - (1) failed to properly mark any stump with the "X" mark.
 - (2) failed to properly mark any butt log with the "X" mark.
 - (3) cut any tree that was reserved for tree improvement and/or wildlife habitat.
 - (4) cut any tree in or adjacent to cable yarding corridors that was not necessary to facilitate cable yarding.
 - (5) cut any reserve tree in or adjacent to tractor skid roads that was not necessary to facilitate ground-based yarding.
 - (6) cut any reserve tree that was not severely (as defined during the pre-work conference and documented in the approved logging plan) damaged from felling and yarding operations.
 - (7) cut more than the minimum number of trees necessary to properly serve as guyline anchor stumps.
 - (8) cut or topped more than the minimum number of trees necessary to properly serve as tailhold trees.
 - (9) cut more than the minimum number of trees necessary to properly serve as tie-backs for topped tailhold trees.

Failure to perform any of the conditions listed above may be considered a trespass.

(21) As directed by Authorized Officer, for a distance of 100 feet from the perimeter of each landing, all logs more than eight inches diameter at the large end and longer than eight feet in length shall be decked or windrowed at the location designated by the Authorized Officer except logs removed from the contract area. If a log or a piece of a log meeting or exceeding the above specifications is bucked all portions of that log shall be yarded and decked at the above described location.

- (22) In the Partial Cut Area, significant damage to residual trees shall be kept to a minimum. Significant damage is defined as any tree having greater than twelve square inches of the bark removed from the circumference of the tree, any tree with top diameter broken at three inches in diameter or greater, or any tree being visually root-sprung. If the Authorized Officer determines that damage has become commonplace due to a lack of caution or operator negligence, a written warning of non-compliance will immediately be issued to the Purchaser. The Authorized Officer may suspend operations until safeguards are put in place to protect the reserve trees. If the damage continues, it will result in a violation of Sec. 13 of the contract, Timber Trespass, and the Purchaser will be held liable for damages. Any reserved trees significantly damaged or destroyed by the Purchaser shall be valued at current market value of the merchantable volume for purposes of determining damages.
- (23) In the Partial Cut Area, any reserved hardwood cut to facilitate logging shall be limbed, topped and yarded and shall be decked separately as directed by the Authorized Officer. Felled reserved hardwoods shall remain property of the Government.
- (24) In the use of Fairview-Sumner Lane, the Purchaser shall abide by the conditions of the Operator's Permit obtained from the Coos County Road Master. Flaggers, traffic control measures, and coordination will be required when operations are on or adjacent to Fairview-Sumner Lane. Fairview-Sumner Lane is a well-traveled public road and all efforts must be taken to minimize inconvenience to road users. Fairview-Sumner Lane shall be kept clear of trees, rock, dirt, and other debris so far as is practicable and shall not be blocked by operations for more than 20 minutes.
- (25) Thirty days prior to any operations adjacent to the power line right-of-way, a pre-work meeting shall be scheduled and subsequently held with Coos-Curry Electric Co-op representatives (541-332-3931). In addition, contact the Oregon Utility Notification Center (800-332-2344 or 811) prior to commencing any operations.
- (26) To control the spread of noxious weeds, the Purchaser shall conduct all operations involving the transportation and use of equipment and vehicles in strict accordance with the requirements shown on Exhibit F, which is attached hereto and made part hereof. All road building and logging equipment which will be used off of existing roads will be washed prior to moving into the Contract Area to minimize the spread of noxious weeds.

c. Road Construction

- (1) The Purchaser shall construct, improve, or renovate a road in strict accordance with the road plans and specifications shown on Exhibit C, which is attached hereto and made a part hereof.
- (2) Any required construction, improvement, or renovation of structures and roads shall occur during the dry season, June 1 through October 1, unless dry conditions exist that may extend those dates as approved by the authorized officer.
 - (3) Prior to any road construction, improvement, or renovation of structures and roads, contact Oregon

Utility Notification Center (800-332-2344 or 811) for the location of buried lines and or cables.

- (4) Any required construction, improvement, or renovation of structures and roads shall be completed and accepted prior to the haul of any timber, except right-of-way timber, over that road.
- (5) In addition to the requirements set forth in Sec. 25 of this contract, the Purchaser shall complete erosion control and soil stabilization measures on all cuts, fills, waste areas, and scarified areas, as designated by the Authorized Officer, along all sections of roadway disturbed during the year prior to October 1 of each year. The Authorized Officer may set time limits for the beginning and completion of erosion control and soil stabilization measures and modify seasonal dates to conform to existing weather conditions and changes in the construction schedule. Such work shall be accomplished in accordance with Erosion Control and Soil Stabilization, 1700 and 1800 Series, contained in Exhibit C.
- (6) The Purchaser shall, prior to construction of landings, stake all landing locations in accordance with the requirements set forth in Exhibit C. Concurrently with, or at the termination of logging operations, the Purchaser shall pull back and shape onto the landings all overhanging materials to prevent erosion in accordance with the requirements set forth in Exhibit C.

d. Road Use and Maintenance

(1) The Purchaser shall be required to secure written approval to use or haul equipment over Government owned or controlled structures when that equipment exceeds the maximum allowable weights or dimensions established by the State for vehicles operating without a permit.

Tracked type equipment shall not be allowed to cross over concrete bridge decks, other concrete surfaced structures or asphalt surfaced roads without the proper protection of that surface. Prior approval shall be obtained from the Authorized Officer when crossing with protective devices.

Details of such equipment shall be furnished to the Authorized Officer for evaluation of load characteristics, at least 15 days prior to proposed move in. Details shall include:

- (a) axle weights when fully loaded;
- (b) axle spacing;
- (c) transverse wheel spacing;
- (d) tire size:
- (e) outside width of vehicle;
- (f) operating speed;
- (g) frequency of use; and,
- (h) special features (e.g. running tracks, overhang loads, etc.).

The Purchaser shall be responsible for repair of any damage to structures caused by the use of overweight or over-dimension vehicles: (1) without written approval, (2) in violation of the conditions of a written approval or (3) in a negligent manner. The amount of actual damage shall be determined by the

Authorized Officer following a technical inspection and evaluation.

- (2) At all times during the period of operations on the contract area, and upon completion of said operations, the Purchaser shall be liable for maintenance and repair of such roads shown on Exhibit D, which is attached hereto and made a part hereof, resulting from wear or damage in accordance with the maintenance specifications as shown on Exhibit D
- (3) The Purchaser is authorized to use the roads shown on Exhibit E, which is attached hereto and made a part hereof, for the removal of Government timber sold under the terms of this contract and for haul of mineral material required under the terms of this contract; provided, that the Purchaser shall pay a Maintenance Obligation to the Government totaling \$1,527.47, as shown on Exhibit E. Unless the total Maintenance Obligation due to the BLM is paid prior to commencement of operations on the contract area, payments shall be made in installments payable in the same manner as and together with payments required by Sec. 3 of this contract. Timber modification volume will be assessed at a rate of \$0.21/MBF for removal of timber over Government controlled roads.
- (4) In the use of Fairview-Sumner Lane, the purchaser shall obtain an Operator's Permit from Coos County. Prior to the commencement of operations, the Purchaser shall furnish to the Authorized Officer a copy of the required executed Operator's Permit between the Purchaser and Coos County.
- (5) In the use of Coos County Sheep Company roads, shown on Exhibit E, the Purchaser shall comply with the conditions of Right-of-Way and Road Use Agreement C-957 between the United States and Coos County Sheep Company, available for inspection at the Bureau of Land Management, North Bend, Oregon. Prior to commencement of operations, the Purchaser shall furnish to the Authorized Officer a copy of the required executed License Agreement. The private right-of-way timber and road use fees shall be paid for at the time the License Agreement is executed. Road use fees totaling \$1,568.00 are payable to Coos County Sheep Company. A \$10,000 insurance bond is required by the Coos County Sheep Company. Right-of-way volume totaling 29.9 MBF shall be purchased and payment totaling \$8,232.69 will be paid to Coos County Sheep Company under the terms of the BLM timber sale contract. The purchaser shall contact Coos County Sheep Company at least 30 days prior to harvesting any private right-of-way timber. All right-of-way timber, as shown on Exhibit A labeled as "yarding wedges"; marked with teal green paint on the ground, shall be harvested prior to removing timber from Unit 3.

e. Fire Prevention, Hazard Reduction and Logging Residue Reduction

- (1) BLM will assume supervisory responsibility for disposal of logging slash. The assumption by the Government of all obligations for the disposal or reduction of fire hazard under state law does not relieve the Purchaser of the obligations to perform the fire prevention, hazard reduction and logging residue reduction measures required by this contract.
- (2) <u>Fire Prevention and Hazard Reduction</u>. Primarily for purposes of fire prevention and fire hazard reduction, the Purchaser shall comply with the following provisions:

- (a) Prior to the operation of power driven equipment in construction or logging operations under this contract during the closed fire season or periods of fire danger, the Purchaser shall complete a fire prevention and control plan to the satisfaction of the Authorized Officer.
- (b) Slash shall be disposed of in accordance with the written instructions of the Authorized Officer.
- (3) <u>Logging Residue Reduction</u>. In addition to the requirements of Section 15 of this contract and for hazardous fuel reduction, watershed protection and silvicultural purposes, the Purchaser shall be responsible for logging residue reduction at all landing sites in the sale area and in the hazardous fuels reduction areas (HFRA) identified on the Exhibit A.
- (a) In lieu of burning, the Purchaser may remove landing residue for offsite utilization. If the utilization method is selected, the Purchaser shall upon request from the Authorized Officer, provide information on the total tonnage of landing residue being removed from the sale area.
- (b) Prior to commencement of landing residue removal, the Purchaser shall provide advanced notification to the Authorized Officer in order to arrange for on-site inspections of the removal operations. Upon completion of landing debris removal, the Purchaser shall notify the Authorized Officer to arrange for a final inspection of the landing sites.
- (c) Any logs or trees identified in the contract as reserved remain the property of the Government and shall not be shipped for offsite utilization.

Specifications for Landing Piling

- (d) Unless otherwise approved in advance by the Authorized Officer, landing piling shall be completed at each yarding location (setting) concurrently with the conclusion of yarding operations while logging equipment is on site.
- (e) Logging residue within the immediate vicinity of the landing and any residue that overhangs the landing sites that can be reached with the logging equipment shall be pulled completely back up onto the landing surface and either piled for burning or segregated for other uses.
- (f) Logging residue meeting the criteria described in Sec. 42.b.(21) and (23) shall not be piled for burning but shall be segregated into separate piles that are no closer than twenty feet from landing residue piles that will be burned.
- (g) If during the course of landing pile construction or during a subsequent inspection, the Authorized Officer determines that landing piles contain reserved logs or trees and/or excessive amounts of logging residue that meets the specifications as described in Sec. 42.b.(21) and (23), the purchaser may be required to remove the specified residue from the burn piles.

- (h) Root wads from road and landing construction activities shall not be included in the landing piles. Piling of slash on top of root wad piles is not permitted. Any root wad piles found by the Authorized Officer to be capped by slash will require the removal and re-piling of the slash by the Purchaser.
- (i) Stable landing piles shall be constructed. Landing piles shall be constructed as upright as possible and have a solid base to promote stability and prevent toppling.
- (j) During or after pile construction, landing piles shall be shaped and contoured in such a manner that will allow for polyethylene (PE) sheeting to lay in a smooth and uniform manner completely across the top and partially down the sides of the pile to promote shedding of water, prevent pooling of water and to reduce the possibility of PE being ripped or torn by underlying slash or from wind. Landing piles found by the Authorized Officer not meeting this shaping requirement shall be reconstructed or reshaped by the Purchaser.
- (k) The Purchaser shall request an inspection of landing piling before piling equipment is moved off site. If piling equipment is moved off site before inspection and the landing piles are subsequently found to be noncompliant with (j), the Purchaser shall be responsible for costs associated with move-in of equipment to rework piles. All requests for inspection of landing piling shall be made in writing (email is acceptable) at least ten days in advance of planned equipment removal.
- (l) Unless directed or approved by the Authorized Officer, no landing piles shall be within twenty feet of any reserved green trees, snags or marked wildlife trees.

Specifications for Landing Pile Covering

- (m) Only landing piles that have been inspected and approved by the Authorized Officer shall be covered. Pile covering shall be completed no later than September 15 of the current year at all landing sites where yarding activities have been completed. This applies to each year that the timber sale is active.
- (n) The Purchaser shall place polyethylene sheeting (PE), four MIL thickness and black in color over the pile so as to provide an adequate level of protection from fall/winter rains. PE sheeting shall lie uniformly and smoothly across the top of the pile and shall extend partially down the sides. For small properly constructed piles with base dimensions of approximately 10 ft. x 10 ft. or less, the size of the PE sheeting should not need to exceed approximately 100 square feet.
- (o) To meet ignition and combustion needs, larger piles will require additional PE sheeting in excess of 100 square feet to adequately cover the pile and protect it from wetting fall/winter rains. The Purchaser shall contact the Authorized Officer before any pile covering begins to receive specific direction on which piles will require additional covering. At that time, the Authorized Officer will identify all piles that shall have additional PE covering. If piles are covered without the advice and consent of the Authorized Officer and are subsequently found to be inadequately covered, the Purchaser may be required to re-cover or add additional covering to the piles before acceptance is made.
 - (p) At landing sites with excessive logging residue that overhangs the landing which cannot be

reached and pulled back up onto the landing with equipment on site, the Purchaser shall place additional PE sheeting over the residue concentrations below the landings.

- (q) On roads that have been closed and/or decommissioned, decks of Purchaser owned logs that were not shipped by the Purchaser shall be covered with PE for burning. The Authorized Officer may waive this requirement if future utilization is determined to be feasible. Decks of reserved logs belonging to the Government are exempt from this requirement.
- (r) All PE shall be weighted down with slash or logging debris in order to prevent blowing off or sliding. An adequate amount of anchoring material should be placed on top of the pile but no more than 20 percent of the material to be piled may be placed on top of the PE. For piles described in (o) above, the Authorized Officer may require the removal of PE before burning so the Purchaser should exercise discretion with respect to the method of application, the amount and composition of anchoring material used when securing the PE.
- (s) Piles of root wads generated from road and landing construction activities and piles of residue identified by the Authorized Officer for other uses shall not be covered with PE sheeting.

Specifications for Hazardous Fuels Reduction Area (HFRA) Treatments

(t) In accordance with written or verbal instructions to be issued by the Authorized Officer at least ten days in advance of the earliest date of required performance, within the HFRA boundaries as shown on Exhibit A, the Purchaser shall commence slashing, piling and pile covering. The HFRA treatment area is measured at a distance of approximately 100 feet (horizontal distance) from each side of the Fairview-Sumner Lane county road. Measurements are from the edge of the gravel surface. Power line right-of-ways intersected by the HFRA are excluded from this treatment requirement. HFRA boundaries will be identified by the Authorized Officer after harvest activities in the various treatment segments have been completed. At the Authorized Officer's discretion and to meet prescribed fire and hazardous fuels reduction objectives, slashing, piling and pile covering may be ordered to be completed in these segments over multiple seasons. All work will be in accordance with the following specifications:

Specifications for Slashing and Piling within the HFRA

- (u) Within the boundaries of the HFRA as shown on the Exhibit A, the Purchaser shall slash all brush and stump sprouts greater than one foot in height, including prostrate brush pinned down by logging debris. Unless otherwise directed by the Authorized Officer, trees (primarily hardwoods) that are severely damaged or that have been cut but were not yarded shall be slashed for piling. Stump heights of slashed vegetation shall not exceed six inches as measured from the uphill side.
- (v) The Purchaser shall hand pile slashed vegetation and logging debris that is between ½ inches to 6 inches in diameter (measured on the small end). Material exceeding the diameter limits specified may be left un-piled; however, attached limbs and/or tops falling within the diameter limits shall be cut off and piled.

- (w) Hand piles shall be constructed in an upright manner with a solid base to prevent toppling and with a core of compact small diameter fuel less than one inch that will provide for an ignition source within the pile. Piles found to be without these features or with large air pockets will be rejected and shall be re-piled. To prevent sliding, all hand piled material shall be laid perpendicular to the slope.
- (x) Unless approved by the Authorized Officer, maximum pile dimensions shall not exceed an approximate 8 ft. x 8 ft. x 5 ft. Piled material that is more than 8 ft. in length shall be cut off to no more than 8 ft. and added back into the pile. Minimum pile dimensions shall not be less than an approximate 4 ft. x 4 ft. and 3 ft. in height or depth.
- (y) Unless directed by the Authorized Officer, no hand piles shall be constructed within ten feet of any standing green trees, snags, wildlife trees or material identified as suitable coarse woody debris.

Specifications for Pile Covering in the HFRA

- (z) The Contractor shall place polyethylene sheeting (PE) on the piles to protect them from wetting rains. The PE shall be 4 mil thickness and black in color.
- (aa) For average sized hand piles (8'x 8'x 4'), the PE covering shall not exceed an approximate 100 square feet in size or approximately ten by ten (10 x 10) feet.
- (ab) All PE sheeting shall be weighted down with slash or logging debris in order to prevent blowing off or sliding. No more than twenty percent of the material to be piled may be placed on top of the PE.

Specifications Applicable to Landing and HFRA Pile Burning

- (ac) In accordance with verbal or written instructions to be issued by the Authorized Officer at least ten days in advance of the earliest date of required performance, the Purchaser shall, under supervision of the Authorized Officer or his/her designated representative, assist in burning and fire control, at the Purchaser's expense, provide the services of personnel and equipment as follows:
 - 1. The Purchaser shall begin pile burning within fourteen hours of notification by the Authorized Officer.
 - 2. In accordance with the Authorized Officer's verbal instruction, immediately before ignition on piles with coverings in excess of 100 sq. ft., the Purchaser may be required to remove as much polyethylene sheeting from the pile as feasibly possible.
 - 3. The Purchaser shall dispose of removed polyethylene sheeting in accordance with any applicable Federal, State, and municipal laws. Removed polyethylene sheeting shall not be disposed of in burn piles
 - 4. For each entry, the Purchaser may provide more personnel, equipment and materials

than indicated but no less than the minimum requirements below unless approved in advance by the Authorized Officer. Minimum personnel, equipment and materials requirements for burning landing and HFRA hand piles are:

- a. One English-speaking foreman for crew supervision.
- b. Seven people to assist the foreman in pile burning.
- c. Eight drip torches and sufficient mixed fuel to complete all pile burning.
- 5. A minimum of ninety percent consumption of each pile is required. Stoking of piled material around pile edges may be required to meet the 90% consumption requirement. Stoking can be accomplished by hand or the Purchaser will be allowed to use heavy equipment (if onsite) to facilitate stoking or re-piling of residue during pile burn operations. If used, the heavy equipment shall not be allowed to operate off of all-weather road surfaces.
- 6. No mop-up is required of the Purchaser.
- (ad) Based on the time of year and sequence in which harvest and treatment of the units is completed, burning may be required to be accomplished over multiple seasons using multiple entries.
- (ae) Time is of the essence in complying with this provision. In the event the Purchaser fails to provide the personnel, equipment, materials and slash disposal services required herein, the Purchaser shall be responsible for all additional costs incurred by the Government in disposing of slash including but not limited to the wages and other costs of providing federal employees and others as substitute labor force, the cost of providing substitute equipment, materials and appropriate additional overhead expenses. If the Purchaser's failure results in deferral of burning, and new conditions necessitate additional site preparation work and/or the use of additional personnel and equipment to accomplish the planned burn, the Purchaser also shall be responsible for such additional costs.

f. Log Export and Substitution

All timber sales, including timber from Federal rights-of-ways, shall be subject to the restrictions relating to the export and substitution of unprocessed timber from the United States in accordance with P.L. 94-165 and 43 CFR 5400 and 5424 as amended.

(1) All timber sold to the Purchaser under the terms of the contract, except exempted species, is restricted from export under the United States in the form of unprocessed timber, and is prohibited from being used as a substitute for exported private timber. For the purpose of this contract, unprocessed timber is defined as (1) any logs except those of utility grade or below, such as saw logs, peeler logs, and pulp logs; (2) cants or squares to be subsequently remanufactured exceeding eight and three-quarters inches in thickness; (3) split or round bolts or other roundwood not processed to standards and specifications suitable for end-product uses; or (4) western redcedar lumber which does not meet lumber of American Lumber Standards Grades of Number 3 dimension or better, or Pacific Lumber Inspection Bureau R-List Grades of Number 3 Common or better. Thus, timber manufactured into the following will be considered processed: (1) lumber and construction timbers, regardless of size, manufactured to standards and specifications suitable for end-product uses; (2) chips, pulp and pulp

products; (3) green or dry veneer and plywood; (4) poles and piling cut or treated for use as such; (5) cants, squares, and lumber cut for remanufacturing of eight and three-quarters inches in thickness or less; (6) shakes and shingles.

Substitution will be determined under the definition found in 43 CFR 5400.0-5(n).

The Purchaser is required to maintain and upon request to furnish the following information:

- (a) date of last export sale;
- (b) volume of timber contained in last export sale;
- (c) volume of timber exported in the past 12 months from the date of last export sale;
- (d) volume of Federal timber purchased in the past 12 months from the date of last export sale;
- (e) volume of timber exported in succeeding 12 months from date of last export sale; and,
- (f) volume of Federal timber purchased in succeeding 12 months from date of last export sale.
- (2) In the event the Purchaser elects to sell any or all of the timber sold under this contract in the form of unprocessed timber, the Purchaser shall require each party buying, exchanging, or receiving such timber to execute a "Certificate as to Nonsubstitution and the Domestic Processing of Timber" (Form 5460-16). The original of such certification shall be filed with the Authorized Officer. Additionally, when the other party is an affiliate of the Purchaser, the Purchaser will be required to update information under item (2) of Form 5450-17 (Export Determination) and file the form with the Authorized Officer.
- (3) In the event an affiliate of the Purchaser has exported private timber within twelve months prior to purchasing or otherwise acquiring Federal timber sold under this contract, the Purchaser shall, upon request, obtain from the affiliate information in a form specified by the Authorized Officer and furnish the information to the Authorized Officer.
- (4) Prior to the termination of this contract, the Purchaser shall submit to the Authorized Officer a "Log Scale and Disposition of Timber Removed Report" (Form 5460-15) which shall be executed by the Purchaser. In addition, the Purchaser is required under the terms of this contract to retain for a three-year period from the date of termination of the contract the records of all sales or transfer of logs involving timber from the sale for inspection and use of the Bureau of Land Management.
- (5) Unless otherwise authorized in writing by the Contracting Officer, the Purchaser shall brand clearly and legibly one end of all logs with a scaling diameter (small end inside bark) of over ten inches, prior to the removal of timber from the contract area. All loads of eleven logs or more will have a minimum of ten logs clearly and legibly branded on one end regardless of the diameter of the logs. All logs will be branded on loads of ten logs or less. One end of all branded logs to be processed domestically will be marked with a three square inch spot of highway yellow paint. The Purchaser will stop trucks for accountability monitoring at mutually agreed upon locations when notified by the Authorized Officer.

If multiple trailers (mule trains) are used, each bunked load shall be considered an individual load, and these guidelines will apply to each bunked load. If a flatbed stake trailer is used, each bundle will be treated as a

separate load.

At the discretion of the Contracting Officer, the Purchaser may be required to brand and paint all logs. Any increased costs for log branding and painting shall be the responsibility of the Purchaser.

(6) In the event of the Purchaser's noncompliance with this subsection of the contract, the Authorized Officer may take appropriate action as set forth in Sec. 10 of this contract. In addition, the Purchaser may be declared ineligible to receive future awards of Government timber for a period of one year.

g. Optional Scale Check of Lump Sum Sales

- (1) The Government, at its option, may administratively check scale any portion of the timber removed from the contract area, and if necessary, conduct check scaling of independent scalers contracted to BLM for administrative check scaling purposes. The Purchaser hereby agrees to make such contract timber available for such scaling at a location or locations to be approved in writing by the Authorized Officer. At the approved location or locations, the Purchaser shall provide an area for logs to be safely rolled out for scaling, to unload logs from trucks, place logs in a manner so that both ends and three faces of each log are visible for scaling, and to reload or remove logs after scaling has been completed.
- (2) In the event that BLM elects to administratively check scale and if such check scaling causes a delay in log transportation time, an adjustment will be made to the purchase price as follows. If the entire sale is check scaled by yard scale, the purchase price of this contract shall be reduced by \$5,247.00. In the event only a portion of the contract timber is scaled, the purchase price shall be reduced by that portion of \$5,247.00 which is equal to the percentage of timber sold which was actually scaled by the Government. For purposes of computing this price reduction, the percentage of timber sold which has been scaled shall be determined by the Government. Any reduction in purchase price under the terms of this provision shall be full compensation to the Purchaser for any expense or loss incurred as a result of such scaling. Scaling shall be conducted in accordance with the Eastside Scribner Scaling Rules by BLM scalers, and/or independent scalers contracted to BLM. A copy of the scale report will be made available to the Purchaser upon request.

h. Equal Opportunity in Employment

(1) Certification of Nonsegregated Facilities, Form 1140-3, is attached hereto and made a part hereof.

i. Cultural Resource Protection

(1) If in connection with operations under this contract, the Purchaser, his contractors, sub-contractors, or the employees of any of them, discovers, encounters or becomes aware of any objects or sites of cultural value on the contract area such as historical or prehistorical ruins, fossils, or artifacts, the Purchaser shall immediately suspend all operations in the vicinity of the cultural value and notify the Authorized Officer of the findings. Operations may resume at the discovery site upon receipt of written instructions and authorization by the Authorized Officer.

- (2) Pursuant to 43 CFR 10.4(g) the holder of this authorization must notify the Authorized Officer, by telephone, with written confirmation, immediately upon discovery of human remains, funerary items, sacred objects, or objects of cultural patrimony. Further, pursuant to 43 CFR 10.4(c) and (d), you must stop activities in the vicinity of the discovery and protect it for 30 days or until notified to proceed by the Authorized Officer.
- j. Sensitive, Threatened, or Endangered Plants or Animals

The Purchaser shall immediately discontinue specified construction or timber harvesting operations upon written notice from the Contracting Officer that:

- (1) threatened or endangered plants or animals protected under the Endangered Species Act of 1973, as amended, may be affected by the operation, and a determination is made that consultation or reinitiation of consultation is required concerning the species prior to continuing operation, or;
- when, in order to comply with the Endangered Species Act or to protect occupied marbled murrelet sites in accordance with the Standards and Guidelines of the Coos Bay District Record of Decision (ROD) and Resource Management Plan (RMP), the Contracting Officer determines it may be necessary to modify or terminate the contract, or;
- (3) federal proposed, federal candidate, Bureau sensitive or State listed species protected under BLM Manual 6840 Special Status Species Management have been identified, and a determination is made that continued operations would affect the species or its habitat, or;
- (4) other active raptor nests have been discovered, and a determination is made that continued operations under this contract would adversely affect the present use of the discovered nesting area by the raptor, or;
- (5) when, in order to comply with a court order which enjoins operations on the sale or otherwise requires the Bureau of Land Management to suspend operations, or;
- (6) when, in order to comply with a court order, the Contracting Officer determines it may be necessary to modify or terminate the contract, or;
- (7) species have been discovered which were identified for protection through survey and manage and/or protection buffer standards and guidelines established in the ROD and RMP, and the Contracting Officer determines that continued operations would affect the species or its habitat, or;
- (8) when, in order to protect species which were identified for protection through survey and manage and/or protection buffer standards and guidelines established in the ROD and

RMP, the Contracting Officer determines it may be necessary to modify or terminate the contract.

Those operations necessary for a safe removal of personnel and equipment from the contract area and those directed by the Contracting Officer which are required in order to leave the contract area in an acceptable condition will be permitted. Discontinued operations may be resumed upon receipt of written instructions and authorization by the Contracting Officer.

During any period of suspension, the Purchaser may withdraw performance and payment bond coverage aside from that deemed necessary by the Authorized Officer to secure cut and/or removed timber for which the Bureau of Land Management has not received payment, and/or unfulfilled contract requirements associated with harvest operations that have already occurred and associated post-harvest requirements.

In the event of a suspension period or a combination of suspension periods that exceed a total of 30 days, the First Installment held on deposit may be temporarily reduced upon the written request of the Purchaser. For the period of suspension extending beyond 30 days, the First Installment on deposit may be reduced to five percent of the First Installment amount listed in Sec. 3.b. of the contract. Any First Installment amount temporarily reduced may be refunded or transferred to another BLM contract at the request of the Purchaser. However, if the Purchaser has outstanding debt owing the United States, the Contracting Officer must first apply the amount of First Installment that could be refunded to the debt owed in accordance with the Debt Collection Improvement Act, as amended (31 USC 3710, et seq.). Upon Purchaser's receipt of a bill for collection and written notice from the Contracting Officer lifting the suspension, the Purchaser shall restore the First Installment to the full amount shown in Sec. 3.b. of the contract within fifteen days after the bill for collection is issued, subject to Sec. 3.h. of the contract. The Purchaser shall not resume contract operations until the First Installment amount is fully restored.

In the event of a suspension period or a combination of suspension periods that exceed a total of thirty days, the unamortized Out-of-Pocket Expenses for road or other construction required pursuant to Exhibit C of the contract shall be refunded or transferred to another BLM contract at the request of the Purchaser. Upon written notice from the Contracting Officer lifting the suspension, the Purchaser shall reimburse the Government the amounts refunded or transferred. The Purchaser may choose to pay this reimbursement at once or in installments payable at the same time as payments are due for the timber under the contract and in amounts approximately equal to the expenses associated with the timber for which payment is due.

In the event that operating time is lost as a result of the incorporation of additional contract requirements, or delays due to Endangered Species Act consultation with the U.S. Fish and Wildlife Service or U.S. National Marine Fisheries Service, or court-ordered injunctions, the Purchaser agrees that an extension of time, without reappraisal, will constitute a full and complete remedy for any claim that delays due to the suspension hindered performance of the contract or resulted in damages of any kind to the Purchaser.


The Contracting Officer may determine that it is necessary to terminate the cutting and removal rights under the contract in order to comply with the Endangered Species Act, protect occupied marbled murrelet sites in accordance with the ROD and RMP, protect species that have been discovered which were identified for protection through survey and manage and/or protection buffer standards and guidelines established in the ROD and RMP, or comply with a court order. Following the issuance of a written notice that cutting and removal rights will be terminated, the Purchaser will be permitted to remove timber cut under the contract, if allowed by the Endangered Species Act, marbled murrelet occupied site protection in accordance with the ROD and RMP, survey and manage and/or protection buffer standards and guidelines established in the ROD and RMP, or court order requirements necessitating the modification or termination.

In the event cutting and removal rights are terminated under this subsection, the Purchaser agrees that the liability of the United States shall be limited to the actual costs incurred by the Purchaser which have not been amortized by timber removed from the contract area. This calculation of liability shall utilize actual Purchaser costs and Government estimates of timber volumes. At the Authorized Officer's request, the Purchaser agrees to provide documentation of the actual costs incurred in the performance of the contract. In addition, the Purchaser shall be released from the obligation to pay the contract price for any timber which is not authorized to be removed from the contract area.

The Purchaser specifically and expressly waives any right to claim damages, other than those described in the preceding paragraphs, based on an alleged breach of any duty to the Purchaser, whether express or implied, in regard to the manner in which the Government defended the litigation which resulted in the court order affecting the operation of the contract. This waiver also extends to any claims based on effects on the operation of the contract that arise from litigation against another agency. Furthermore, the Purchaser specifically acknowledges and agrees that a court ruling that the Government violated the Administrative Procedures Act cannot be interpreted, in itself, to mean that the Government had not acted reasonably in regard to its duties to the Purchaser under this contract.


TIMBER SALE CONTRACT MAP USDI-BLM COOS BAY DISTRICT T. 27 S., R. 12 W., Sec. 15, Will. Mer.

SALE NO. ORC00-TS-2016.0002 EXHIBIT A-1 Page 1 of 1 Steele 15 CT



TIMBER SALE CONTRACT MAP USDI-BLM COOS BAY DISTRICT T. 27 S., R. 12 W., Sec. 15, Will. Mer.

SALE NO. ORC00-TS-2016.0002 EXHIBIT A Page 1 of 2 Steele 15 CT



TIMBER SALE CONTRACT MAP USDI-BLM COOS BAY DISTRICT T. 27 S., R. 12 W., Sec. 15, Will. Mer. SALE NO. ORC00-TS-2016.0002 EXHIBIT A Page 2 of 2 Steele 15 CT

Cable Yarding Area

Reserve Area


Private Property- Coos County Sheep Company

Yarding Wedge

Property Boundary

Landing

> Acreage data was collected using a Trimble Geo XT Global Positioning System receiver. Acreage was calculated based on Global Positioning System traverse procedures including differential correction.



UNITED STATES DEPARTMENT OF THE INTERIOR BUREAU OF LAND MANAGEMENT

Exhibit B

The following estimates and calculations of timber sold are made solely as an administrative aid for determining: (1) Adjustments made or credits given in accordance with Sections 6, 9, or 11; (2) When payments are due; and (3) Value of timber subject to any special bonding provisions. The value of timber will be determined by multiplying the value per acre as shown below, times the amount of acreage as determined by the authorized officer, which has been cut or removed or designated for taking.

Except provided in Section 2, Purchaser shall be liable for the total purchase price even though the quantity of timber actually cut or removed or designated for taking is less than the estimated volume or quantity shown. Cutting areas are shown on the Exhibit A.

Sale Totals (16' MBF)

Species	Net Volume	Bid Price	Sale SubTotal
Douglas-fir	6,452		
Red Alder	494		
Western red-cedar	28		
Grand Fir	15		
Western Hemlock	7		
Sale Totals	6,996		

Unit Details (16' MB)

Unit	1	311 Acres	Value per Acre: \$0.00

Species	Net Volume	Bid Price	Species Value
Douglas-fir	4,850		
Grand Fir	12		
Red Alder	400		
Western Hemlock	6	<u>-</u>	
Western red-cedar	22		
Unit Totals	5,290		

Unit	2	46 Acres	Value per Acre: \$0.00

Species	Net Volume	Bid Price	Species Value
Douglas-fir	717		
Grand Fir	2		
Red Alder	59		
Western Hemlock	1		
Western red-cedar	3		
Unit Totals	782		

Printed: 11/10/2015 9:17:04AM Page 5 of 6

Coos Bay Steele 15 CT ORC00-TS-2016.0002

UNITED STATES DEPARTMENT OF THE INTERIOR BUREAU OF LAND MANAGEMENT

Unit 3

21 Acres

Value per Acre: \$0.00

Species	Net Volume	Bid Price	Species Value
Douglas-fir	327		
Grand Fir	1		
Red Alder	27		
Western red-cedar	2		
Unit Totals	357		

Unit	RV
	17.1

11 Acres

Value per Acre: \$0.00

Species	Net Volume	Bid Price	Species Value
Douglas-fir	558		
Red Alder	. 8		
Western red-cedar	1		
Unit Totals	567		


Printed: 11/10/2015 9:17:04AM Page 6 of 6

EXHIBIT C

TIMBER SALE NAME STEELE 15 CT

TIMBER SALE NO. ORC00-TS-2016.0002

UNITED STATES DEPARTMENT OF THE INTERIOR BUREAU OF LAND MANAGEMENT COOS BAY DISTRICT OFFICE UMPQUA RESOURCE AREA




SHEET	CONTENTS
1	TITLE SHEET
2	WORK LOCATION MAP
3	TYPICAL CROSS SECTION DETAIL
4	CULVERT INSTALLATION DETAILS
5-6	ESTIMATE OF QUANTITIES
7	ROADSIDE BRUSHING DETAIL
B-11	SPECIAL DETAILS
12-24	CONSTRUCTION DETAILS
25-47	ROAD CONSTRUCTION SPECIFICATIONS

U.	S.	DEF	ARTM	ENT	OF	THE	INTER	IOR
	BU	REAL	J OF	LAN	D M	ANAG	EMENT	
	CC	201	DAY	DIST	PICT	OF	PECON	

TITLE SHEET

REVIEWED_	J.	MENGUITA	
APPROVED-	T.	BUCHHOLZ	
DRAWN IC		SCALE AS S	SHOW

DATE 08/15 SHEET 1 OF 47



	Luci Silva Salitfalle Africano	15227000	codi-shorteti ndi - 5e	TYPICAL	ROAD	WIDTH ¹	CLEAF WID	RING E	RUSHIN WIDTH	G			SURF	ACING				
ROAD	FROM MILEPOST/	TO MILEPOST/	LENGTH MILES/	SECTION TYPE	Subgrade	Ditch	BEYO	OND E	EXISTINI ROADS	9	BASE CO	JRSE				JRFACE COURSE	T	REMARKS
NUMBER **	STATION	STATION	STATIONS	11132			CUT	FILL	L R	Minimum Top Width	Depth	Type ²	Grading	Minir Top	mum Width	Comp. Type²	Grading	
27-12-3.1 R	0+00	17+50	17.50	1	12'	0'		-	10 10									2% OUTSLOPE W/ NO DITCH
27-12-9.6 R	0.00	0.15	0.15	4	16'	2'			10 10					AP	PLY 2	20 CY 3" SPOT	ROCK	
27-12-10.1 R	0.00	18+35	18.35	1	12'	0'			10 10									2% OUTSLOPE W/ NO DITCH
27-12-15.0 R	0.00	0.45	0.45	4	16'	2'			10 10			0		AP	PLY 2	20 CY 3" SPOT	ROCK	
27-12-15.3 C	0+00	5+95	5.95	3	16'	2'	10	5		12.0'	12"	D	3-0"			8		
-15.3 I	5+95	31+50	25.55	2	16'	0'			10 10		12"	D	3-0"				1	2% OUTSLOPE W/ NO DITCH
-15.3 R	31+50	36+50	5.00	1	12'	0'		1	10 10	ć.		6				Ÿ		2% OUTSLOPE W/ NO DITCH
27-12-15.4 C	0+00	16+80	16.80	2	16'	0'	10	5		12.0'	12"	D	3-0"			7		2% OUTSLOPE W/ NO DITCH
27-12-15.5 C	0+00	9+10	9.10	1	12'	0'	10	5										2% OUTSLOPE W/ NO DITCH
27-12-15.6 C	0+00	8+35	8.35	2	16'	0'	10	5		12.0'	12"	D	3-0"			,		2% OUTSLOPE W/ NO DITCH
27-12-15.7 C	0+00	23+60	23.60	2	16'	0'	10	5		12.0'	12"	D	3-0"			y o		2% OUTSLOPE W/ NO DITCH
27-12-15.8 C	0+00	9+30	9.30	1	12'	0'	10	5				2						2% OUTSLOPE W/ NO DITCH
27-12-15.9 C	0+00	10+80	10.80	2	16'	0'	10	5		12.0'	12"	D	3-0"					2% OUTSLOPE W/ NO DITCH
27-12-15.10 C	0+00	8+95	8.95	2	16'	0'	10	5							0.0			2% OUTSLOPE W/ NO DITCH
27-12-15.11 I	0+00	3+00	3.00	3	16'	2'		1	10 10	12.0'	12"	D	3-0"					
-15.11 C	3+00	5+40	2.40	2	16'	0'	10	5		12.0'	12"	D	3-0"					2% OUTSLOPE W/ NO DITCH
SPUR NO. 1 C	0+00	AND DIVERSE OF	2.95	1	12'	0,	10	5										2% OUTSLOPE W/ NO DITCH
SPUR NO. 2 C	0+00	4+85	4.85	1	12'	0,	10	5										2% OUTSLOPE W/ NO DITCH
SPUR NO. 4 C	0+00	2+75	2.75	1	12'	0'	10	5										2% OUTSLOPE W/ NO DITCH
SPUR NO. 5 C	0+00	2+60	2.60	2	16'	0'	10	5		12.0'	12"	D	3-0"					2% OUTSLOPE W/ NO DITCH

SHOULDER SLOPE 2:1

FILL SLOPE

NOTES

1. EXTRA SUBGRADE WIDTHS

ADD TO EACH FILL SHOULDER 1 FT. FOR FILLS OF 1-6 FT. AND 2 FT. FOR FILLS OVER 6 FT. WIDEN THE INSIDE SHOULDER OF ALL CURVES AS FOLLOWS:

> WHEN THE RADIUS OF CURVE EQUALS 270-800 ADD 1FT. 165-270 ADD 2FT. 120-165 ADD 3FT. 90-120 ADD 4FT.

60-90 ADD 5FT.

OR AS SHOWN ON PLANS.

MATERIALS	CUT SLOPES	FILL SLOPES
СОММОН	1/2:1	1 1/2:1
SOFT ROCK & SHALE	1/2:1	1 1/2:1
SOLID ROCK	1/4:1	REPOSE

FULL BENCH CONSTRUCTION IS REQUIRED ON SIDE SLOPES EXCEEDING 60%.

2. SURFACING TYPE

- A. PIT RUN ROCK MATERIAL.
- B. GRID ROLLED ROCK MATERIAL C. SCREENED ROCK MATERIAL.
- D. CRUSHED ROCK MATERIAL. E. CLASS 'C' ASPHALT MIX.

SURFACING

A. TURNOUTS, CURVE WIDENING AND ROAD APPROACH APRONS SHALL BE SURFACED.


4. DITCHES

A. 4:1 SLOPE FROM SUBGRADE, OR AS OTHERWISE NOTED. DEPTH MAY BE EXCEEDED TO OBTAIN REQUIRED DRAINAGE.

5. TURNOUTS

A. WIDTH 10 FT. IN ADDITION TO SUBGRADE WIDTH, OR AS SHOWN ON THE PLANS.

B. LOCATED APPROXIMATELY AS SHOWN ON THE ROAD PLANS OR NARRATIVE.




SUBGRADE WIDTH

OUTSLOPE/INSLOPE @ 2%

TYPE 2

TYPICAL SURFACING SECTION




UTILIZE EXCAVATED AND RETRIEVED MATERIALS IN THE CONSTRUCTION OF THE SUB-GRADE. GROUND LINE FILL SLOPE DITCH SUBGRADE WIDTH CROWN SHALL BE 2% TYPICAL GRADING SECTION

** RENOVATION = R

IMPROVEMENT = I

CONSTRUCTION = C



TYPE 4

BUREAU OF LAND MANAGEMENT COOS BAY DISTRICT OREGON TYPICAL CROSS SECTION


U. S. DEPARTMENT OF THE INTERIOR


DETAIL DESIGNED J. COUNTS REVIEWED J. MENGUITA APPROVED T. BUCHHOLZ

DRAWN JC SCALE NONE DATE 08/15 SHEET 3 OF 47

10'-0" 25'MIN.TAPER TURNOUT LENGTH | 25'MIN.TAPER


PLAN TYPICAL TURNOUT






HORIZONTAL SKEW SHALL BE AS SHOWN, OR PERPINDICULAR TO DITCH LINE IN GRADE DIPS.
THE GRADE OF CROSSDRAINS SHALL BE AT LEAST 2% GREATER THAN THE GRADE OF THE DITCH, WITH A MAXIMUM GRADIENT OF 5%.

BEDDING OF CULVERTS




BEDDING OF CULVERTS ON STABLE NATURAL GROUND FOUNDATION OR COMPACTED EMBANKMENT BEDDING MATERIAL SHALL BE SHAPED TO FIT THE BOTTOM OF THE CULVERT.


BEDDING OF CULVERTS ON SOFT SPONGY OR UNSTABLE SOIL FOUNDATION




BEDDING MATERIAL SHALL BE SHAPED TO FIT THE BOTTOM OF THE CULVERT. EARTH CUSHIONING OF SILTY CLAY LOAM OR SAND MAY BE USED IF MATERIAL CAN BE PLACED IN THE DRY CONDITION. IF THE EXCAVATION IS WET, USE GRANULAR FOUNDATION FILL MATERIAL. MAIN—TAIN 8" MIN. DEPTH BETWEEN HIGH POINTS OF ROCKS AND/OR BOULDERS AND THE BOTTOM OF THE CULVERT.


BEDDING OF CULVERT IN SOLID ROCK OR BOULDER FOUNDATION








CATCH BASIN




BEDDING MATERIAL SHALL BE SHAPED TO FIT THE BOTTOM OF THE CULVERT. BACKFILL MATERIAL SHALL BE APPROVED GRANULAR MATERIAL.

BEDDING OF CULVERTS
ON EXISTING SURFACED ROADS

USE "ADJUSTABLE ELBOW" FOR CPE AND CMP DOWNSPOUTS 1/3 D 1/3 D 1/3 D 1/2 d x 1 od GALV. WASHER NOTE: ANCHOR DOWNSPOUTS ACCORDING TO SECTION 407b OF THE ROAD CONSTRUCTION SPECIFICATIONS 1/2 d x 1 od GALV. WASHER





U. S. DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT
COOS BAY DISTRICT OREGON

CULVERT INSTALLATION

ALWAYS THINK SAFETY

DESIGNED J. COUNTS
REVIEWED J. MENGUITA
APPROVED T. BUCHHOLZ

DRAWN JC SCALE NONE

DATE 08/15 SHEET 4 OF 47

DRAWING NO.

DETAILS

	z	7	5	10001000		177 1770070.00			EAR	THWORK	(DESIGNI	ED)		CP	E *1	СМІ	P *2		DOWNSP	POUTS *3		
2042	E	훁	Ε̈́	2	모돕	N N	'nδ				1 Vfi			35007320	2002	1070	963	FULL	ROUND	FULL	ROUND	to.
ROAD NUMBER	NEW CONSTRUCTION	RENOVATION	IMPROVEMENT	GRUBBING	SLASH	ROADSIDE BRUSHING	SLOPE	соммон	RIPPABLE	ROCK CUT	FILL	SHORT HAUL 200-5000'	HAUL 5000'+	18"	24"	12"	48"	18" CPE	24" CPE	24" CMP	36" CMP	MARKERS
SECTION NO.	300	500	500	200	200	2100	2300	300	300	300	300	300	300	400	400	400	400	400	400	400	400	400
UNITS	STA.	STA.	STA.	ACRES	ACRES	STA.	SIDES	C.Y.	C.Y.	C.Y.	YDS.	STA.YD.	YD.MI.	L.F.	L.F.	L.F.	L.F.	L.F.	L.F.	L.F.	L.F.	EA.
27-12-3.1		17.50	r 3			17.50		7												7		7
27-12-9.6		7.92				7.92																
27-12-10.1		18.35				18.35																
27-12-15.0		23.76				23.76																
27-12-15.3	5.95	5.00	25.55	0.3	0.5											40						
27-12-15.4	16.80			0.7	1.3																	
27-12-15.5	9.10			0.4	0.7																	
27-12-15.6	8.35			0.4	0.7																	
27-12-15.7	23.60			1.0	1.9																	
27-12-15.8	9.30			0.4	0.7																	
27-12-15.9	10.80			0.5	0.9																	
27-12-15.10	8.95			0.4	0.7		7															
27-12-15.11	2.40		3.00	0.1	0.2																	
SPUR NO. 1	2.95			0.1	0.2			10														
SPUR NO. 2	4.85			0.2	0.4																	
SPUR NO. 4	2.75			0.1	0.2																	
SPUR NO. 5	2.60			0.1	0.2																	
								7												7		
								3										L.				
TOTAL	108,40	72 57	28.55	4.7	B 6	67.53	£	i i						E.		40						
IOIAL	100.40	/2.53	26.35	4./	8.6	07.55										40						

ESTIMATE OF QUANTITIES**



*1 CPE - CORRUGATED POLYETHYLENE PIPE

*2 CMP - CORRUGATED METAL PIPE

*3 SEE DOWNSPOUT INSTALLATION SHEET

U. S. DEPARTMENT OF THE INTERIOR BUREAU OF LAND MANAGEMENT COOS BAY DISTRICT OREGON

ESTIMATE OF QUANTITIES

DESIGNED_	J.	COUNTS	
REVIEWED_	J.	MENGUITA	
APPROVED-	-	BUCHHOLZ	-15
DRAWN IC	8	SCALE NONE	

**FOR INFORMATIONAL USE ONLY. QUANTITIES SHOWN ARE NOT PAY ITEMS.

ESTIMATE OF QUANTITIES*

			SURF	ACING			OTHER		SEE	DING		
ROAD NUMBER	BASE ROCK	SPOT ROCK	LANDING ROCK	SURFACE ROCK	SPOT ROCK	RIPRAP	DRAINAGE	GEO- TEXTIILE	SEED, F AND MU	ERTILIZE JLCH	OTHER (SEDIMENT CONTROL	
			NO SIX	111.70.70.00					1800	1800	DEVICES)	
SECTION NO.	1000	1000	1000	1200	1200	500	400		DRY	HYDRO		
UNITS	C.Y.	C.Y.	C.Y.	C.Y.	C.Y.	C.Y.	C.Y.	S.Y.	ACRES	ACRES	EACH	
27-12-3.1	A	A	A	©	0	A	A		0.4			
27-12-9.6	A	20 (A)	A	O	0	(A)	(A)					
27-12-10.1	A	A	A	O	O	(A)	(A)		0.1			
27-12-15.0	A	20 (A)	A	0	0	A	(A)					
27-12-15.3	2478 A	A	A	0	0	A	(A)		0.9			
27-12-15.4	1316 A	A	160 A	O	0	A	A		0.6			
27-12-15.5	A	A	A	O	0	(A)	(A)		0.2			
27-12-15.6	605 A	A	140 A	0	0	A	(A)		0.3			
27-12-15.7	1808 (A)	A	60 A	O	O	A	A		0.7			
27-12-15.8	A	A	A	0	0	A	(A)		0.3			
27-12-15.9	782 A	A	60 A	0	0	(A)	A		0.3			
27-12-15.10	A	A	A	0	0	(A)	A		0.3			
27-12-15.11	387 (A)	(A)	110 A	O	O	10 (A)	(A)		0.4			
	A	A	A	0	0	A	(A)					
SPUR NO. 1	A	A	A	O	0	(A)	(A)		0.2			
SPUR NO. 2	A	A	A	O	0	(A)	(A)		0.2			
SPUR NO. 4	A	A	A	O	O	(A)	(A)		0.2			
SPUR NO. 5	188 A	A	60 A	0	0	A	A		0.2			
100 miles (100 miles (A	A	A	0	0	A	(A)					
	A	(A)	A	0	0	(A)	(A)					
	A	A	A	0	0	A	A					
	A	A	A	O	0	A	A					
	A	A	A	0	0	A	A					
	A	Ā	Ā	©	Ō	A						
	Ā	A	Ã	Ö	Õ	A						
	A	A	A	Ö	Ö	A						
	A	A	A	0	0	A	A					
	A	A	A	©	Ō	A						
	A	A	A	©	O	A						
TOTALS	7564 A	40 (A)	590 (A)	©	©	10 (A)	(A)		5.3			


SECTION	GRADE	SIZE
700	Α	6"
1000	A	3"
	В	
	С	
	D	
	F.	
1100	В	4"
1200	С	1 1/2 "
	A	
500	A	CLASS 6 RIPRAP
CHIP SEAL ROCK	s	3/4 "

GRADE INDICATED IN CIRCLE



U. S. DEPARTMENT OF THE INTERIOR BUREAU OF LAND MANAGEMENT COOS BAY DISTRICT OREGON
ESTIMATE OF QUANTITIES
DESIGNED J. COUNTS
REVIEWED J. MENGUITA
APPROVED T. BUCHHOLZ
DRAWN JC SCALE NONE
DATE 08/15 SHEET 6 OF 47

^{*} FOR INFORMATIONAL USE ONLY. QUANTITIES SHOWN ARE NOT PAY ITEMS. ALL ROCK QUANTITIES ARE TRUCK MEASUREMENT / LOOSE YARDS



- * Variable distance between running surface and start of fill slope.
- ** All areas within the variable distance shall be free of all vegetation capable of growing one (1) foot in height or higher, and free of all over—hanging limbs and branches 12 feet in elevation above the running surface.

BUREAU OF LAN	OF THE INTERIOR ID MANAGEMENT TRICT OREGON
	BRUSHING AIL
	OUNTS ENGUITA
	UCHHOLZ
DRAWN JC	SCALE NONE
DATE 08/15	SHEET 7 OF 47

SALE NO. ORC00-TS-2016.0002 STEELE 15 CT EXHIBIT C Sheet 8 of 47 sheets

SPECIAL DETAILS

FAIRVIEW-SUMNER LANE (CBWR)

<u>Milepost</u>	Remarks
10.50	Junction, renovate Road No. 27-12-15.0 right (Steinnen Creek).
9.92	Junction, construct Spur No. 2 right.
9.90	Junction, construct Road No. 27-12-15.3 left.
9.65	Junction, improve Road No. 27-12-15.11 left.
8.70	Junction, renovate Road No. 27-12-9.6 right.
0.00	Junction with Hwy. 42 south.
	RENOVATION OF ROAD NO. 27-12-3.1 Station 0+00 to Station 17+50
Station	Remarks
0+00	Junction with Road No. 27-12-9.6. Begin brushing, slough and slide removal and grading and shaping in accordance with Section 500 and and 2100 of the Road Specifications, Typical Cross Section Sheet No. 3, and Roadside Brushing Detail Sheet No. 7.
NOTE:	Utilize slough and slide material on existing subgrade.
1+70	Tanktrap – fill and compact.
2+00	Borrow area right (slough and slide material at junction with spur right).
3+20	Deep ruts – utilize borrow as needed to fill and compact.
6+00	Turnout left.
17+50	Property line – leave private and enter B.L.M. Junction, construct Road No. 27-12-15.10 left. End renovation.
	RENOVATION OF ROAD NO. 27-12-9.6 Milepost 0.00 to Milepost 0.15
Milepost	Remarks
0.00	Junction with Fairview-Sumner Lane (CBWR). Begin brushing, slough and slide removal, and grading and shaping in accordance with Section 500 and 2100 of the Road Specifications, Typical Cross Section Sheet No. 3, and Roadside Brushing Detail Sheet No. 7.
	Apply 20 CY of spot rock conforming to Section 1000 at junction to eliminate grade dip.
0.15	Junction, renovate Road No. 27-12-3.1 right. End renovation.

SALE NO. ORC00-TS-2016.0002 STEELE 15 CT EXHIBIT C Sheet 9 of 47 sheets

RENOVATION OF ROAD NO. 27-12-10.1 Milepost 0.00 to Station 18+35

Milepost / Station	Remarks	
0.00	Junction with Road No. 27-12-15.0. Begin brushing, slough and slide removal, and grading and shaping in accordance with Section 500 and 2100 of the Road Specifications, Typical Cross Section Sheet No. 3, and Roadside Brushing Detail Sheet No. 7.	
0.13	Turnout right.	
0.15	Junction, construct Spur No. 1 left.	
0.25 = 13+20	Existing landing.	
13+20 to 18+35	Favorable grade exceeds 20%.	
	RE: Oregon Administrative Rules Oregon Occupational Safety and Health Division Subdivision F	
	437-007-0500 Roads (4) When haul road grades exceed 20 percent slope:	
	(a) The vehicle or machine must be approved by the manufacturer for operation on the steeper grades.	
	(b) Additional precautions must be taken, such as assisting or snubbing the vehicle or machine down the slope.	
18+35	Construct landing in accordance with Sections 200 and 300 of the Road Specifications. End renovation.	
	RENOVATION OF ROAD NO. 27-12-15.0 (Steinnon Creek Road) Milepost 0.00 to Milepost 0.45	
<u>Milepost</u>	Remarks	
0.00	Junction with Fairview-Sumner Lane (CBWR). Begin brushing, slough and slide removal, and grading and shaping in accordance with Section 500 and 2100 of the Road Specifications, Typical Cross Section Sheet No. 3, and Roadside Brushing Detail Sheet No. 7.	
	Gate, BLM Lock No. 2A250. Restore deformed (bent) "farmer's gate" as closely as possible to original dimensions.	
	Apply 20 CY of spot rock conforming to Section 1000 as directed by the Authorized Officer.	
0.45	Junction, renovate Road No. 27-12-10.1 left. End renovation.	

SALE NO. ORC00-TS-2016.0002 STEELE 15 CT EXHIBIT C Sheet 10 of 47 sheets

IMPROVEMENT OF ROAD NO. 27-12-15.3 Station 5+95 to Station 31+50

Station	Remarks
NOTE:	Buried waterline in subgrade from Sta. 5+95 to Sta. 43+50. Exact depth and location unknown. Any waterline exposed during construction activities shall be completely removed and disposed of in a legal manner off of U.S government lands.
5+95	End new construction. Begin slough and slide removal, subgrade improvement, rocking, and soil stabilization in accordance with Sections 500, 1000, and 1800 of the Road Specifications and Typical Cross Section Sheet No. 3.
NOTE:	Utilize slough and slide material on existing subgrade.
	Install a 12" lift of crushed aggregate in accordance with Section 1000 of the Road Specifications and Typical Cross Section Sheet No. 3.
9+00	Junction, construct Road No. 27-12-15.4 left.
9+40	Junction, construct Road No. 27-12-15.5 right.
10+00	Eliminate berm on outside edge of road. Cut 3 - 4', drift ahead and back as needed and utilize on subgrade.
13+50	Construct 50' turnout right.
19+00	Junction, construct Road No. 27-12-15.6 right.
22+00	Construct 50' turnout left.
27+00	Construct 50' turnout left.
31+50	Junction, construct Road No. 27-12-15.7 right. End improvement / rocking. Begin renovation.
	RENOVATION OF ROAD NO. 27-12-15.3 Station 31+50 to Station 36+50
Station	Remarks
31+50	End Improvement. Begin subgrade renovation, grading and shaping, and soil stabilization in accordance with Sections 500 and 1800 of the Road Specifications and Typical Cross Section Sheet No. 3.

NOTE: Utilize slough and slide material on existing subgrade.

35+40 Construct truck-turnaround left.

Construct end landing. End renovation. 36+50

SALE NO. ORC00-TS-2016.0002 STEELE 15 CT EXHIBIT C Sheet 11 of 47 sheets

Station	Remarks
43+20	Construct 40' long tanktrap as ribboned, in accordance with Sheet No. 2 of the Exhibit D and as directed by the Authorized Officer.
	Apply seed, fertilizer, and mulch in accordance with Section 1800 of the Road Construction Specifications.
43+50	Unit boundary and edge of timber.
	MPPOVEMENT OF POAD NO 27-12-15 11

MPROVEMENT OF ROAD NO. 27-12-15.11

Station 0+00 to Station 3+00

NOTE: Purchaser shall contact Coos County Road Department, John Rowe, Roadmaster, at 1281 W. Central St., Coquille, OR 97423, (541)396-7665, and obtain a "Working R/W Permit" for road No. 27-12-15.11 10-days prior to operations.

Purchaser shall provide notification to the county at least 48-hours prior to commencing work and complete operations within the 90-day duration of the permit work period per terms of the permit.

<u>Station</u>	Remarks
NOTE:	Buried waterline in subgrade from Sta. 0+00 to Sta. 3+00. Exact depth and location unknown. Any waterline exposed during construction activities shall be completely removed and disposed of in a legal manner off of U.S government lands.
0+00	Junction with Fairview-Sumner Lane (CBWR). Begin slough and slide removal, subgrade improvement, rocking, and soil stabilization in accordance with Sections 500, 1000, and 1800 of the Road Specifications and Typical Cross Section Sheet No. 3.
	Realign junction as ribboned and as as directed by the Authorized Officer. Utilize excess excavation for curve widening right. Existing subgrade right to be utilized for toe of embankment. Scarify entire length (170') and full width of "old adjacent subgrade" right to a depth of 12" and
	shape to drain. Seed, fertilize, and mulch all scarified and disturbed areas in accordance with Section 1800 of the Exhibit C.
	Construct riprap barrier at the junction of "old subgrade" with Fairview Sumner Lane (CBWR) in accordance with Sheet No. 2 of the Exhibit D and as directed by the Authorized Officer.
NOTE:	Utilize slough and slide material on existing subgrade.
	Install a 12" lift of crushed aggregate in accordance with Section 1000 of the Road Specifications and Typical Cross Section Sheet No. 3.
2+10	Cut 3', drift back and utilize on subgrade.
3+00	End improvement and begin new construction.

EQUIPMENT WASHING

The purchaser is responsible for conforming to the Exhibit F.

SALE NO. ORC00-TS-2016.0002 STEELE 15 CT EXHIBIT C Sheet 12 of 47 sheets

CONSTRUCTION DETAIL SHEET ROAD NO. 27-12-15.3 CONTROL POINT ROAD

NOTE: Purchaser shall contact Coos County Road Department, John Rowe, Roadmaster, at 1281 W. Central St., Coquille, OR 97423, (541)396-7665, and obtain a "Working R/W Permit" for road No. 27-12-15.3 10-days prior to operations.

Purchaser shall provide notification to the county at least 48-hours prior to commencing work and complete operations within the 90-day duration of the permit work period per terms of the permit.

GENERAL

Purchaser shall construct Road No. 27-12-15.3 from Sta. 0+00 to Sta. 5+95 as shown on the location map. This work shall be accomplished in accordance with details and road specifications which follow:

SHAPING

The roadway shall be constructed and shaped to conform to standards shown on Sheet No. 3.

TURNOUTS

Construct 50' turnout right at Sta. 4+50.

SUBGRADE

The subgrade shall be excavated and compacted in accordance with the Road Specifications, 200 and 300 Sections.

DRAINAGE FEATURES

Install 12" x 40' CMP at Sta. 0+00 in existing dicthline in accordance with Section 400 of the Road Specifications and Culvert Installation Detail Sheet No. 4.

Ditch from Sta. 0+00 to Sta. 4+20, outslope &/or inslope at 2% with no ditch from Sta. 4+20 to Sta. 5+95.

SURFACING

The Purchaser shall apply a compacted 12" lift of crushed aggregate in accordance with Section 1000 of the Road Specifications and Typical Cross Section Sheet No. 3.

ALIGNMENT

Roadway shall be constructed within posted or painted right-of-way boundaries. Minimum curve radius shall be sixty (60) feet.

Sta. 0+00: Junction with Fairview Sumner Lane county road (Coos Bay Wagon Road) at M.P. 9.65. Call "811 DIG" for buried utility location prior to any construction activity.

GRADE

Grade shall not exceed 18% favorable and 15% adverse.

TRUCK TURNAROUND

None

LANDINGS

None

SOIL STABILIZATION

SALE NO. ORC00-TS-2016.0002 STEELE 15 CT EXHIBIT C Sheet 13 of 47 sheets

CONSTRUCTION DETAIL SHEET ROAD NO. 27-12-15.4 CONTROL POINT ROAD

GENERAL

Purchaser shall construct Road No. 27-12-15.4 from Sta. 0+00 to Sta. 16+80 as shown on the location map. This work shall be accomplished in accordance with details and road specifications which follow:

SHAPING

The roadway shall be constructed and shaped to conform to standards shown on Sheet No. 3.

TURNOUTS

Construct 50' turnout right at Sta. 3+20.

Construct 50' turnout right at Sta. 8+40.

SUBGRADE

The subgrade shall be excavated and compacted in accordance with the Road Specifications, 200 and 300 Sections.

DRAINAGE FEATURES

Outslope &/or inslope at 2% with no ditch to achieve drainage.

SURFACING

The Purchaser shall apply a compacted 12" lift of crushed aggregate in accordance with Section 1000 of the Road Specifications and Typical Cross Section Sheet No. 3.

ALIGNMENT

Roadway shall be constructed within posted or painted right-of-way boundaries. Minimum curve radius shall be sixty (60) feet.

Sta. 0+00: Junction with Road No. 27-12-15.3 at Sta. 9+00.

GRADE

Grade shall not exceed 18% favorable and 15% adverse.

Sta. 0+00 to

Sta. 0+30: Drift excavation back and utilize on subgrade of the -15.3 at junction.

0+70 Cut 6-8', drift back to junction and utilize for "ramp" at 12-15% favorable grade.

TRUCK TURNAROUND

Utilize "Y" junction at Sta. 13+75. 10 CY landing rock allocated.

LANDINGS

Construct approach and landing left at Sta. 13+75.

100 CY landing rock allocated.

Construct end landing at Sta. 16+80.

50 CY landing rock allocated.

Grade of landings shall not exceed 5%.

SOIL STABILIZATION

SALE NO. ORC00-TS-2016.0002 STEELE 15 CT EXHIBIT C Sheet 14 of 47 sheets

CONSTRUCTION DETAIL SHEET ROAD NO. 27-12-15.5 CONTROL POINT ROAD

GENERAL

Purchaser shall construct Road No. 27-12-15.5 from Sta. 0+00 to Sta. 9+10 as shown on the location map. This work shall be accomplished in accordance with details and road specifications which follow:

SHAPING

The roadway shall be constructed and shaped to conform to standards shown on Sheet No. 3.

TURNOUTS

None

SUBGRADE

The subgrade shall be excavated and compacted in accordance with the Road Specifications, 200 and 300 Sections.

DRAINAGE FEATURES

Outslope &/or inslope at 2% with no ditch to achieve drainage.

SURFACING

None

ALIGNMENT

Roadway shall be constructed within posted or painted right-of-way boundaries. Minimum curve radius shall be sixty (60) feet.

Sta. 0+00: Junction with Road No. 27-12-15.3 at Sta.9+40.

GRADE

Grade shall not exceed 20% adverse.

TRUCK TURNAROUND

None

LANDINGS

Construct landing at Sta. 3+60.

Construct landing at Sta. 7+30.

Construct end landing at Sta. 9+10.

Grade of landings shall not exceed 5%.

SOIL STABILIZATION

SALE NO. ORC00-TS-2016.0002 STEELE 15 CT EXHIBIT C Sheet 15 of 47 sheets

CONSTRUCTION DETAIL SHEET ROAD NO. 27-12-15.6 CONTROL POINT ROAD

GENERAL

Purchaser shall construct Road No. 27-12-15.6 from Sta. 0+00 to Sta. 8+35 as shown on the location map. This work shall be accomplished in accordance with details and road specifications which follow:

SHAPING

The roadway shall be constructed and shaped to conform to standards shown on Sheet No. 3.

TURNOUTS

None

SUBGRADE

The subgrade shall be excavated and compacted in accordance with the Road Specifications, 200 and 300 Sections.

DRAINAGE FEATURES

Outslope &/or inslope at 2% with no ditch to achieve drainage.

SURFACING

The Purchaser shall apply a compacted 12" lift of crushed aggregate in accordance with Section 1000 of the Road Specifications and Typical Cross Section Sheet No. 3.

ALIGNMENT

Roadway shall be constructed within posted or painted right-of-way boundaries. Minimum curve radius shall be sixty (60) feet.

Sta. 0+00: Junction with Road No. 27-12-15.3 at Sta.19+00.

Construct "Y" junction and utilize for truck-turnaround.

10 CY landing rock allocated.

Sta. 1+85 Junction, construct Spur No. 4 right.

GRADE

Grade shall not exceed 15% adverse.

TRUCK TURNAROUND

Construct truck-turnaround at Sta. 6+45.

10 CY landing rock allocated.

LANDINGS

Construct approach and landing right at Sta. 7+75.

70 CY landing rock allocated.

Construct end landing at Sta. 8+35.

50 CY landing rock allocated.

Grade of landings shall not exceed 5%.

SOIL STABILIZATION

SALE NO. ORC00-TS-2016.0002 STEELE 15 CT EXHIBIT C Sheet 16 of 47 sheets

CONSTRUCTION DETAIL SHEET ROAD NO. 27-12-15.7 CONTROL POINT ROAD

GENERAL

Purchaser shall construct Road No. 27-12-15.7 from Sta. 0+00 to Sta. 23+60 as shown on the location map. This work shall be accomplished in accordance with details and road specifications which follow:

SHAPING

The roadway shall be constructed and shaped to conform to standards shown on Sheet No. 3.

TURNOUTS

Construct 50' turnout right at Sta. 7+50.

Construct 50' turnout right at Sta. 16+80.

SUBGRADE

The subgrade shall be excavated and compacted in accordance with the Road Specifications, 200 and 300 Sections.

DRAINAGE FEATURES

Outslope &/or inslope at 2% with no ditch to achieve drainage.

SURFACING

The Purchaser shall apply a compacted 12" lift of crushed aggregate in accordance with Section 1000 of the Road Specifications and Typical Cross Section Sheet No. 3.

ALIGNMENT

Roadway shall be constructed within posted or painted right-of-way boundaries. Minimum curve radius shall be sixty (60) feet.

Sta. 0+00: Junction with Road No. 27-12-15.3 at Sta.31+50.

Sta. 6+25 Junction, construct Road No. 27-12-15.8 right.

Sta.12+00 Junction, construct Road No. 27-12-15.9 right.

GRADE

Grade shall not exceed 15% adverse.

TRUCK TURNAROUND

Construct truck-turnaround right at Sta. 22+60.

10 CY landing rock allocated.

LANDINGS

Construct end landing at Sta. 23+60.

50 CY landing rock allocated.

Grade of landings shall not exceed 5%.

SOIL STABILIZATION

SALE NO. ORC00-TS-2016.0002 STEELE 15 CT EXHIBIT C Sheet 17 of 47 sheets

CONSTRUCTION DETAIL SHEET ROAD NO. 27-12-15.8 CONTROL POINT ROAD

GENERAL

Purchaser shall construct Road No. 27-12-15.8 from Sta. 0+00 to Sta. 9+30 as shown on the location map. This work shall be accomplished in accordance with details and road specifications which follow:

SHAPING

The roadway shall be constructed and shaped to conform to standards shown on Sheet No. 3.

TURNOUTS

Construct 50' turnout right at Sta. 6+50.

SUBGRADE

The subgrade shall be excavated and compacted in accordance with the Road Specifications, 200 and 300 Sections.

DRAINAGE FEATURES

Outslope &/or inslope at 2% with no ditch to achieve drainage.

SURFACING

None

ALIGNMENT

Roadway shall be constructed within posted or painted right-of-way boundaries. Minimum curve radius shall be sixty (60) feet.

Sta. 0+00: Junction with Road No. 27-12-15.7 at Sta.6+25.

GRADE

Grade shall not exceed 18% adverse.

TRUCK TURNAROUND

Construct truck-turnaround right at Sta. 8+30.

LANDINGS

Construct end landing at Sta. 9+30.

Grade of landings shall not exceed 5%.

SOIL STABILIZATION

SALE NO. ORC00-TS-2016.0002 STEELE 15 CT EXHIBIT C Sheet 18 of 47 sheets

CONSTRUCTION DETAIL SHEET ROAD NO. 27-12-15.9 CONTROL POINT ROAD

GENERAL

Purchaser shall construct Road No. 27-12-15.9 from Sta. 0+00 to Sta. 10+80 as shown on the location map. This work shall be accomplished in accordance with details and road specifications which follow:

SHAPING

The roadway shall be constructed and shaped to conform to standards shown on Sheet No. 3.

TURNOUTS

None

SUBGRADE

The subgrade shall be excavated and compacted in accordance with the Road Specifications, 200 and 300 Sections.

DRAINAGE FEATURES

Outslope &/or inslope at 2% with no ditch to achieve drainage.

SURFACING

The Purchaser shall apply a compacted 12" lift of crushed aggregate in accordance with Section 1000 of the Road Specifications and Typical Cross Section Sheet No. 3.

ALIGNMENT

Roadway shall be constructed within posted or painted right-of-way boundaries. Minimum curve radius shall be sixty (60) feet.

Sta. 0+00: Junction with Road No. 27-12-15.7 at Sta.12+00.

Sta. 6+65 Junction, construct Spur No. 5 right.

GRADE

Grade shall not exceed 18% favorable and 15% adverse.

TRUCK TURNAROUND

Construct truck-turnaround right at Sta. 9+00.

10 CY landing rock allocated.

LANDINGS

Construct end landing at Sta. 10+80.

50 CY landing rock allocated.

Grade of landings shall not exceed 5%.

SOIL STABILIZATION

SALE NO. ORC00-TS-2016.0002 STEELE 15 CT EXHIBIT C Sheet 19 of 47 sheets

CONSTRUCTION DETAIL SHEET ROAD NO. 27-12-15.10 CONTROL POINT ROAD

GENERAL

Purchaser shall construct Road No. 27-12-15.10 from Sta. 0+00 to Sta. 8+95 as shown on the location map. This work shall be accomplished in accordance with details and road specifications which follow:

SHAPING

The roadway shall be constructed and shaped to conform to standards shown on Sheet No. 3.

TURNOUTS

Construct 50' turnout right at Sta. 4+25.

SUBGRADE

The subgrade shall be excavated and compacted in accordance with the Road Specifications, 200 and 300 Sections.

DRAINAGE FEATURES

Outslope &/or inslope at 2% with no ditch to achieve drainage.

SURFACING

None

ALIGNMENT

Roadway shall be constructed within posted or painted right-of-way boundaries. Minimum curve radius shall be sixty (60) feet.

Sta. 0+00: Junction with Road No. 27-12-3.1 at Sta.17+50.

GRADE

Grade shall not exceed 15% adverse.

TRUCK TURNAROUND

Construct truck-turnaround right at Sta. 8+00.

LANDINGS

Construct end landing at Sta. 8+95.

Grade of landings shall not exceed 5%.

SOIL STABILIZATION

SALE NO. ORC00-TS-2016.0002 STEELE 15 CT EXHIBIT C Sheet 20 of 47 sheets

CONSTRUCTION DETAIL SHEET ROAD NO. 27-12-15.11 CONTROL POINT ROAD

GENERAL

Purchaser shall construct Road No. 27-12-15.11 from Sta. 3+00 to Sta. 5+40 as shown on the location map. This work shall be accomplished in accordance with details and road specifications which follow:

SHAPING

The roadway shall be constructed and shaped to conform to standards shown on Sheet No. 3.

TURNOUTS

None

SUBGRADE

The subgrade shall be excavated and compacted in accordance with the Road Specifications, 200 and 300 Sections.

DRAINAGE FEATURES

Outslope &/or inslope at 2% with no ditch to achieve drainage.

SURFACING

The Purchaser shall apply a compacted 12" lift of crushed aggregate in accordance with Section 1000 of the Road Specifications and Typical Cross Section Sheet No. 3.

ALIGNMENT

Roadway shall be constructed within posted or painted right-of-way boundaries. Minimum curve radius shall be sixty (60) feet.

GRADE

Grade shall not exceed 10% favorable and 8% adverse.

TRUCK TURNAROUND

Construct truck-turnaround right at Sta. 3+00. 10 CY landing rock allocated.

LANDINGS

Construct landing at Sta. 3+85. 50 CY landing rock allocated.

Construct end landing at Sta. 5+40. 50 CY landing rock allocated.

Grade of landings shall not exceed 5%.

SALE NO. ORC00-TS-2016.0002 STEELE 15 CT EXHIBIT C Sheet 21 of 47 sheets

CONSTRUCTION DETAIL SHEET SPUR NO. 1 CONTROL POINT ROAD

GENERAL

Purchaser shall construct Spur No. 1 from Sta. 0+00 to Sta. 2+95 as shown on the location map. This work shall be accomplished in accordance with details and road specifications which follow:

SHAPING

The roadway shall be constructed and shaped to conform to standards shown on Sheet No. 3.

TURNOUTS

None

SUBGRADE

The subgrade shall be excavated and compacted in accordance with the Road Specifications, 200 and 300 Sections.

DRAINAGE FEATURES

Outslope &/or inslope at 2% with no ditch to achieve drainage.

SURFACING

None

ALIGNMENT

Roadway shall be constructed within posted or painted right-of-way boundaries. Minimum curve radius shall be sixty (60) feet.

Sta. 0+00: Junction with Road No. 27-12-10.1 at M.P. 0.15.

Construct "Y" junction and utilize for truck-turnaround.

GRADE

Grade shall not exceed 20% favorable.

TRUCK TURNAROUND

None

LANDINGS

Construct end landing at Sta. 2+95. Grade of landings shall not exceed 5%.

SOIL STABILIZATION

SALE NO. ORC00-TS-2016.0002 STEELE 15 CT EXHIBIT C Sheet 22 of 47 sheets

CONSTRUCTION DETAIL SHEET SPUR NO. 2 CONTROL POINT ROAD

NOTE: Purchaser shall contact Coos County Road Department, John Rowe, Roadmaster, at 1281 W. Central St., Coquille, OR 97423, (541)396-7665, and obtain a "Working R/W Permit" for Spur No. 2 10-days prior to operations.

Purchaser shall provide notification to the county at least 48-hours prior to commencing work and complete operations within the 90-day duration of the permit work period per terms of the permit.

GENERAL

Purchaser shall construct Spur No. 2 from Sta. 0+00 to Sta. 4+85 as shown on the location map. This work shall be accomplished in accordance with details and road specifications which follow:

SHAPING

The roadway shall be constructed and shaped to conform to standards shown on Sheet No. 3.

TURNOUTS

None

SUBGRADE

The subgrade shall be excavated and compacted in accordance with the Road Specifications, 200 and 300 Sections.

DRAINAGE FEATURES

Outslope &/or inslope at 2% with no ditch to achieve drainage.

SURFACING

None

ALIGNMENT

Roadway shall be constructed within posted or painted right-of-way boundaries. Minimum curve radius shall be sixty (60) feet.

Sta. 0+00: Junction with Fairview Sumner Lane county road (Coos Bay Wagon Road) at M.P. 9.92. Call "811 DIG" for buried utility location prior to any construction activity.

GRADE

Cut 3' at Sta. 2+85 and drift ahead to Sta. 4+85 and utilize on subgrade.

Grade shall not exceed 14% favorable and 20% adverse.

TRUCK TURNAROUND

None

LANDINGS

Construct end landing at Sta. 4+85.

Daylight left side of landing (existing cutbank) to attain landing width.

Utilize excavation for landing.

Grade of landings shall not exceed 5%.

SOIL STABILIZATION

SALE NO. ORC00-TS-2016.0002 STEELE 15 CT EXHIBIT C Sheet 23 of 47 sheets

CONSTRUCTION DETAIL SHEET SPUR NO. 4 CONTROL POINT ROAD

GENERAL

Purchaser shall construct Spur No. 4 from Sta. 0+00 to Sta. 2+75 as shown on the location map. This work shall be accomplished in accordance with details and road specifications which follow:

SHAPING

The roadway shall be constructed and shaped to conform to standards shown on Sheet No. 3.

TURNOUTS

None

SUBGRADE

The subgrade shall be excavated and compacted in accordance with the Road Specifications, 200 and 300 Sections.

DRAINAGE FEATURES

Outslope &/or inslope at 2% with no ditch to achieve drainage.

SURFACING

None

ALIGNMENT

Roadway shall be constructed within posted or painted right-of-way boundaries. Minimum curve radius shall be sixty (60) feet.

Sta. 0+00: Junction with Road No. 27-12-15.6 at Sta.1+85.

GRADE

Grade shall not exceed 15% adverse.

TRUCK TURNAROUND

None

LANDINGS

Construct end landing at Sta. 2+75. Grade of landings shall not exceed 5%.

SOIL STABILIZATION

SALE NO. ORC00-TS-2016.0002 STEELE 15 CT EXHIBIT C Sheet 24 of 47 sheets

CONSTRUCTION DETAIL SHEET SPUR NO. 5 CONTROL POINT ROAD

GENERAL

Purchaser shall construct Spur No. 5 from Sta. 0+00 to Sta. 2+60 as shown on the location map. This work shall be accomplished in accordance with details and road specifications which follow:

SHAPING

The roadway shall be constructed and shaped to conform to standards shown on Sheet No. 3.

TURNOUTS

None

SUBGRADE

The subgrade shall be excavated and compacted in accordance with the Road Specifications, 200 and 300 Sections.

DRAINAGE FEATURES

Outslope &/or inslope at 2% with no ditch to achieve drainage.

SURFACING

The Purchaser shall apply a compacted 12" lift of crushed aggregate in accordance with Section 1000 of the Road Specifications and Typical Cross Section Sheet No. 3.

ALIGNMENT

Roadway shall be constructed within posted or painted right-of-way boundaries. Minimum curve radius shall be sixty (60) feet.

Sta. 0+00: Junction with Road No. 27-12-15.9 at Sta.6+65.

Construct "Y" junction and utilize for truck-turnaround.

10 CY landing rock allocated.

GRADE

Grade shall not exceed 10% adverse.

TRUCK TURNAROUND

None

LANDINGS

Construct end landing at Sta. 2+60. 50 CY landing rock allocated.

Grade of landings shall not exceed 5%.

SOIL STABILIZATION

SALE NO. ORC00-TS-2016.0002 STEELE 15 CT EXHIBIT C Sheet 25 of 47 sheets

ROAD CONSTRUCTION SPECIFICATIONS

General road construction specifications are designated by numeric symbols according to the type of road work to be performed, as follows:

<u>Section</u>	
100	GENERAL
200	CLEARING AND GRUBBING
300	EXCAVATION AND EMBANKMENT
400	PIPE CULVERTS
500	RENOVATION AND IMPROVEMENT OF EXISTING ROADS
600	WATERING
1000	AGGREGATE BASE COURSE (CRUSHED ROCK)
1200	AGGREGATE SURFACE COURSE (CRUSHED ROCK)
1400	SLOPE PROTECTION
1700	EROSION CONTROL
1800	SOIL STABILIZATION
2100	ROADSIDE BRUSHING

SALE NO. ORC00-TS-2016.0002 STEELE 15 CT EXHIBIT C Sheet 26 of 47 sheets

GENERAL - 100

101 - Pre-work Conference(s):

A pre-work conference will be held prior to the start of operations. The Purchaser shall request the conference at least 48 hours prior to the time it is to be held. The conference will be attended by the Purchaser and/or his representative(s), subcontractor(s) and/or his or their representative(s) and the Authorized Officer and/or his representative(s).

The purpose will be to review the required work, exhibits and specifications, and to establish a work schedule and a list of the Purchaser's representatives and subcontractor(s).

102 - Definitions:

<u>AASHTO</u> - American Association of State Highway and Transportation Officials. Current editions of tests and specifications.

Abrasion Resistance - The ability of a fabric surface to resist wear by friction.

ACI - American Concrete Institute

<u>Apparent Opening Size (AOS)</u> - Number of the U.S. Bureau of Standard sieve (or its opening size in millimeters or inches) having openings closest in size to the diameter of uniform particles which will allow 5 percent by weight to pass through the geotextile material when shaken in a prescribed manner. Also referred to as Equivalent Opening Size (EOS).

ASTM - American Society for Testing and Materials.

<u>Base Course</u> - Surfacing structure consisting of crushed gravel or stone, crushed sandstone, pitrun rock, bank or river-run gravels, etc., to provide support and, in the event no surface course is placed, the running surface for traffic load.

BLM - Bureau of Land Management

Borrow - Excavated material required for embankments and other portions of the work.

<u>Burst Strength</u> - The resistance of a geotextile material to rupture from pressure applied at right angles to the plane of the geotextile material under specified conditions, usually expressed as the amount of pressure causing failure. Rupture or burst results from tensile failure of the geotextile material.

<u>Culvert</u> - A pipe, pipe-arch, arch, or box structure constructed of metal, concrete, plastic or wood which provides an opening under the roadway primarily for the conveyance of liquids, pedestrians or livestock.

<u>Curve Widening</u> - Widening required on inside of curves to accommodate long log and equipment hauling trucks.

<u>Embankment</u> - A structure of soil, aggregate, or rock material placed on a prepared ground surface and constructed to subgrade.

<u>End Haul</u> - Excavated material moved, other than by dozer, to an embankment or waste area to prevent sidecasting material outside of the road prism.

<u>Excess Excavation</u> - Material from the roadway in excess of that needed for construction of the designed roadway (waste).

SALE NO. ORC00-TS-2016.0002 STEELE 15 CT EXHIBIT C Sheet 27 of 47 sheets

<u>Grab Tensile Strength</u> - A modified tensile strength of a geotextile material. The strength of a specific width of geotextile material together with the additional strength contributed by adjacent areas. Typically, grab strength is determined on a 12-inch-wide strip of geotextile material, with the tensile load applied at the midpoint of the geotextile material width through 1-inch-wide jaw faces.

<u>Grading</u> - Leveling to grade, shaping and smoothing of a road subgrade; the shaping of roadside ditches as to grade and contour. In some instances includes smoothing of the cut bank.

Nonwoven Geotextile Material - A textile structure produced by bonding or interlocking of fibers, or both, accomplished by mechanical or chemical means.

Overhaul - Distance excavated material is transported in excess of the distance included in the cost for excavation.

Pioneer Road - Temporary construction access built along the route of the project.

<u>Penetration Resistance</u> - The geotextile material property determined by the force required to penetrate a geotextile material with a sharp pointed object. Initial penetration is by separating the fibers. Further penetration is essentially a tearing process.

<u>Percent Open Area</u> - The net area of a geotextile material that is not occupied by geotextile material filaments, normally determinable only for woven and nonwoven geotextile material having distinct, visible, and measurable openings that continue directly through the geotextile material.

<u>Permeability</u> - The geotextile material property which permits water to be transmitted in the longitudinal or transverse planes of the geotextile material.

<u>Piping</u> - The process by which soil particles are washed in or through pore spaces in drains and filters or poorly compacted fill/backfill material.

<u>Plans</u> - The approved drawings, or exact reproductions thereof which show the locations, character, dimensions, and details of the work to be done.

<u>Pore Size</u> - The size of an opening between geotextile material filaments; apparent opening size (AOS) is used to quantify this geotextile material property.

<u>Puncture Resistance</u> - The geotextile material property determined by the force required to penetrate a geotextile material with a blunt object. Failure results in a tearing of the geotextile material.

<u>Purchaser</u> - The individual, partnership, joint venture, or corporation contracting with the Government under the terms of a Timber Sale Contract and acting independently or through their, or its agents, employees, or contractors.

<u>Reasonably Close Conformity</u> - Compliance with reasonable and customary manufacturing and construction tolerances where working tolerances are not specified.

<u>Reinforcement</u> - Strengthening of concrete with iron bars or mesh: geotextile with geotextile material inclusion: subgrade with aggregate: etc.

<u>Roadbed</u> - The graded portion of the road within top and side slopes, prepared as a foundation for the pavement structure and shoulders.

Road Centerline - Longitudinal center of roadbed.

Road Improvement - Work done to an existing road which improves it over its original design standard.

SALE NO. ORC00-TS-2016.0002 STEELE 15 CT EXHIBIT C Sheet 28 of 47 sheets

Road Renovation - Work done to an existing road which restores it to its original design.

<u>Roadway</u> - The portion of a road within limits of construction. Usually from the toe of the fill slope to a point where the cut slope intersects natural ground line. Synonym - road prism.

<u>Scale</u> - In quarrying, consists of the removal of loose or overhanging rock adhering to the solid face after a shot or a round of shots has been fired.

<u>Scarification</u> - The process of loosening or breaking up of the surface layer of soil or road, usually to a specified depth.

<u>Separation</u> - Function of geotextile material as a partition between adjacent materials to prevent mixing of those materials.

<u>Shoulder</u> - The portion of the roadbed contiguous with the traveled way designed for accommodation of stopped vehicles, safety, and lateral support of base and surface courses.

Spalls - Flakes or chips of stone.

<u>Specifications</u> - A general term applied to all directions, provisions, and requirements pertaining to performance of the work.

<u>Specific Gravity</u> - The ratio of the density of a material to the density of water obtained by weighing known volumes of both items in air. A specific gravity less than one implies that the material will float.

<u>Structures</u> - Bridges, culverts, catch basins, retaining walls, underdrains, flumes, splash pads, downspouts, and other project features which may be involved in the work and not otherwise classified in these specifications.

<u>Subbase</u> - Reinforcement of the subgrade with large particles of pitrun or crushed stone. Usually confined to roads having wet subgrades or subgrades with weak support characteristics.

<u>Surface Course</u> - Top layer of a road structure consisting of finely crushed gravels or asphalt designed to provide a smooth running surface for traffic load.

Subgrade - The top surface of a roadbed upon which the traveled way and shoulders are constructed.

<u>Tackifier</u> - A compound which penetrates into the earth and assists in creating a crust through the cohesive bonding of the surface materials to a depth sufficient to stabilize the soil surface and/or a compound used to mat together mulching material.

<u>Tensile Strength</u> - The strength shown by a geotextile material subjected to tension as distinct from torsion, compression, or shear.

<u>Tensile Stress - Strain Modulus</u> - A measure of the resistance to elongation under stress. The ratio of the change in tensile stress to the corresponding change in strain.

<u>Tensile Test</u> - A test which subjects geotextile material to tensile forces and measures resultant stresses and strains.

<u>Timber</u> - Standing trees, downed trees, or logs, or portions thereof, which are capable of being measured in board feet.

Traveled Way - The portion of the roadbed used for the movement of vehicles, exclusive of shoulders.

<u>Typical Cross Sections</u> - Cross-sectional plane of a typical roadway; showing natural ground line and designed roadway in relation to cut and fill, through cut, and through fill.

SALE NO. ORC00-TS-2016.0002 STEELE 15 CT EXHIBIT C Sheet 29 of 47 sheets

<u>Turnout</u> - Extra widening of the roadbed at appropriate intervals on single-lane roads for passing purposes.

<u>Ultraviolet (UV) Radiation Stability</u> - The ability of geotextile material to resist deterioration from exposure to sunlight.

Unaged Cloth - Cloth in condition received from the manufacturer or distributor.

<u>Woven Geotextile Material</u> - A textile structure comprising two or more sets of filaments of yarns interlaced in such a way that the elements pass each other at essentially right angles with one set of elements parallel to the geotextile material axis.

102a - Tests Used in These Specifications:

	·
AASHTO T 11	Quantity of rock finer than No. 200 sieve.
AASHTO T 27	Sieve analysis of fine and coarse aggregate using sieves with square openings; gradation.
AASHTO T 89	Liquid limit of material passing the No. 40 sieve. Water content at which the soil passes from a plastic to a liquid state.
AASHTO T 90	Plastic limits and plasticity index of soil. a. Plastic limit - lowest water content at which the soil remains plastic. b. Plasticity index - range of water content, within which the material is in a plastic state. Numerical difference between the liquid and plastic limits of the soil.
AASHTO T 96	Resistance to abrasion of small size coarse aggregate by use of the Los Angeles machine.
AASHTO T 99	Relationship between soil moisture and maximum density of soil. Method A - 4" mold, soil passing a No. 4 Sieve. 25 blows/layer & 3 layers. Method D - 6" mold, soil passing a 19.00 mm (3/4 inches) sieve. 56 blows/layer & 5 layers.
AASHTO T 176	Shows relative portions of fine dust or clay-like materials in soil or graded aggregate.
AASHTO T 180	(OSHD 106-71) moisture density relationship of soil same as AASHTO T 99 proctor but uses a 10-lb rammer & 18-in drop.
<u>AASHTO T 191</u>	Sand Cone. Density of soil in place: For subgrade use 6-inch or 12-inch cone. For rock surfacing for 1-1/2-inch minus to 3-inch minus use 12-inch cone.
AASHTO T 205	Rubber balloon. Density of soil in place. Use for compacted or firmly bonded soil.
AASHTO T 210	Durability of aggregates based on resistance to produce fines.
AASHTO T 224	Correction for coarse particles in the soil.
AASHTO T 238	Determination of density of soil and soil-aggregates in place by nuclear methods.
AASHTO T 248	Reducing field samples of aggregate to testing size by mechanical splitter, quartering, or miniature stockpile sampling.
DES. E-12	Determination of relative density of cohesionless soils.

SALE NO. ORC00-TS-2016.0002 STEELE 15 CT EXHIBIT C Sheet 30 of 47 sheets

<u>DMSO (dimethyl sulfide)</u> - Determines volume of expanding clays in aggregates. Usually associated with marine basalts.

- 103 Compaction equipment shall meet the following requirements:
- Sheepfoot roller. A tamping roller unit shall consist of two watertight metal drums mounted in frames in such manner as to be fully oscillating, together with a tractor having sufficient weight and power under actual working conditions to pull the roller drums at a minimum speed of 2.5 miles per hour. The drums shall be no less than 60 inches in diameter and no less than 54 inches in length, measured at the drum's surface, and shall be studded with tamping feet projecting not less than 7 inches from the face of the drums.

The distance between circumferential rows of tamper feet shall be such that the diagonal distance from any foot to the nearest foot in each adjacent row shall be not more than 12 inches. The cross-sectional area of the face of each tamper foot, measured perpendicular to the axis of the stud, shall be not less than 5-1/2 square inches nor more than 8 square inches.

The weight of the tamping-roller unit shall be such as to exert a minimum pressure of 250 pounds per square inch on the ground area in contact with the tamping feet, and the roller shall be so designed that the weight may be increased to exert a pressure up to 500 pounds per square inch on the ground area in contact with the tamping feet. The ground pressure shall be determined by dividing the total weight of the roller unit, not including the weight of the tractor, by the total cross-sectional area of the tamping feet in one row of tamping feet parallel to the axis of the roller.

- Grid roller. A grid roller shall consist of two or more cylindrical drums independently mounted on a common shaft in a rigid frame. Each drum shall have a minimum outside diameter of 5 feet and a minimum width of 2 feet 6 inches. The overall width of the roller exclusive of frame shall be not less than 5 feet 6 inches of which not more than 6 inches shall be used for center spacing between two roller drums. The face of the drums shall have the appearance of woven open-mesh made by interlacing bars of not less than 1-1/4 inches nor more than 1-3/4 inches diameter space spaced on 4-1/2 inches to 5-1/2 inches center. Net opening between the bars shall be not less than 3-inches nor more than 4 inches. The roller shall be so constructed that counterweights can be used to adjust the gross weight of the roller to not less than 27,000 pounds. The grid roller shall be drawn by a power unit capable of propelling the fully loaded roller at a speed of at least 4 miles per hour.
- Vibratory roller. The drum diameter shall be not less than 48 inches, the drum width not less than 58 inches, and have a turning radius of 15 feet or less. Vibration frequency shall be regulated in steps to 1400, 1500, and 1600 vibrations per minute (VPM), corresponding to engine speeds of 1575, 1690, and 1800 RPM. The centrifugal force developed shall be 7 tons at 1600 RPM. It shall be activated by a power unit of not less than 25 horsepower. The vibratory roller shall be self-propelled or drawn by a vehicle of sufficient horsepower to enable the unit to travel through a loose layer of material at a speed ranging from 0.9 mile to 1.8 miles per hour, as directed by the Authorized Officer.

The towing vehicle and roller or self-propelled unit meeting the above requirements shall be considered a vibratory roller unit.

103i - Other. Compaction equipment approved by the Authorized Officer.

CLEARING AND GRUBBING - 200

- This work shall consist of clearing, grubbing, removing and disposing of vegetation, debris, surface objects, and protruding obstructions within the clearing limits in accordance with these specifications and conforming to the lines, grades, dimensions and typical cross sections as shown on the plans.
- Where clearing limits have not been staked, established by these specifications or shown on the plans, the limits shall extend 10 feet back of the top of the cut slope and 5 feet out from the toe of the fill slope.

SALE NO. ORC00-TS-2016.0002 STEELE 15 CT EXHIBIT C Sheet 31 of 47 sheets

- Clearing shall consist of the removal and disposal of trees, logs, rotten material, brush, and other vegetative
 materials and surface objects in accordance with these specifications and
 within the limits established for clearing as specified under Subsection 202 and as shown on the plans.
- 203a Brush under 2 feet in height need not be cut within the limits established for clearing.
- Standing trees and snags to be cleared shall be felled within the limits established for clearing unless otherwise authorized.
- Grubbing shall consist of the removal and disposal of stumps, roots, and other wood material embedded in the ground and protruding obstacles remaining as a result of the clearing operation in accordance with Subsection(s) 204a, 204b, 204c, 204d, 204e between the top of the cut slope and the toe of the fill slope. Undisturbed stumps, roots and other solid objects which will be a minimum of 3 feet below subgrades or slope surfaces or embankments are excepted.
- 204a Stumps, including those overhanging cut banks, shall be removed within the required excavation limits.
- Stumps and other protruding objects shall be completely removed within the limits of required embankments having heights of less than 4 feet. When authorized, stumps and other nonperishable objects may be left provided they do not extend more than 6 inches above the existing ground line.
- On excavated areas, roots and embedded wood shall be removed to a depth not less than 6 inches below the subgrade.
- On areas to be occupied by embankments having heights greater than 4 feet, no stump or portion thereof shall remain within 3 feet of embankment subgrades or slope surfaces after grubbing is completed.
- 204e Roots and embedded wood material shall be removed to a depth not less than 1 foot below embankment subgrades or slope surfaces.
- Clearing and grubbing debris shall not be placed or permitted to remain in or under road embankment sections.
- Clearing and grubbing debris shall be disposed of by scattering in accordance with Subsection 210.
- Disposal of clearing and grubbing debris shall be by scattering over government owned lands outside of
 established clearing limits in a manner acceptable to the Authorized Officer. The areas for such scattering
 shall have the prior approval of the Authorized Officer.
- 213 No clearing or grubbing debris shall be left lodged against standing trees.

EXCAVATION AND EMBANKMENT - 300

- This work shall consist of excavating, overhaul, placement of embankments, backfilling, borrowing, leveling, ditching, grading, insloping, outsloping, crowning and scarification of the subgrade, compaction, disposal of excess and unsuitable materials, and other earth-moving work in accordance with these specifications and conforming to the lines, grades, dimensions, and typical cross sections shown on the plans.
- Excavation shall also consist of the excavation of road and landing cut sections, borrow sites, backfilling, leveling, ditching, grading, compaction, and other earth moving work necessary for the construction of the roadway in accordance with these specifications and conforming to the lines, grades, dimensions, and typical cross sections shown on the plans.
- Suitable material removed from the excavation shall be used in the formation of embankment subgrade, shoulders, slopes, bedding, backfill for structures, and for other purposes as shown on the plans.

- Excavated material shall not be wasted as sidecast or perched. All material perched or sidecast as waste shall be retrieved and disposed of at the Purchaser's expense and at the direction of the Authorized Officer.
- Embankment construction shall consist of the placement of excavated and borrowed materials, backfilling, leveling, grading, compaction, and other earth-moving work necessary for the construction of the roadway and landings in accordance with these specifications and conforming to the lines, grades, dimensions, and typical cross sections shown on the plans.
- Material used in the construction of embankment sections shall be free of stumps, cull logs, brush, muck, sod, roots, frozen material, and other deleterious materials and shall be placed and compacted as specified.
- Embankment materials shall be placed in successive parallel layers on areas cleared of stumps, cull logs,
 brush, sod, and other vegetative and deleterious materials, except as provided under Subsection 204.
 Roadway embankments of earth material shall be placed in horizontal layers not exceeding 8 inches in depth.
- Embankments formed of material containing less than 25 percent rock not larger than 8 inches in the greatest dimension shall be placed in 12-inch layers. Material containing more than 25 percent rock not larger than 12 inches in the greatest dimension shall be placed in successive layers not exceeding 2 feet in thickness. Individual rocks and boulders greater than 12 inches in diameter may be used to construct 2-foot embankment layers, provided they are carefully distributed, with interstices filled with fine material to form a dense and compact mass.
- Where embankments are constructed predominantly of blasted rock material, depth of layers shall not exceed 4 feet. Rock fragments having dimensions greater than 4 feet will be permitted provided that they have no dimensions greater than 6 feet and that clearance between adjacent fragments is adequate for the placing and compacting of material in horizontal layers as specified, and that no part of the larger fragments comes within 4 feet of subgrade.
- Layers of embankment and final subgrade material as specified under Subsection(s) 305a and 305b shall be moistened or dried to a uniform optimum moisture content suitable for maximum density and compacted to full width with compacting equipment conforming to requirements of Subsection 103b or 103f, as directed by the Authorized Officer, and in accordance with the following table:

Road No.	From Sta./M.P.	To Sta./M.P.
27-12-15.3	0+00	5+95
27-12-15.4	0+00	16+80
27-12-15.5	0+00	9+10
27-12-15.6	0+00	8+35
27-12-15.7	0+00	23+60
27-12-15.8	0+00	9+30
27-12-15.9	0+00	10+80
27-12-15.10	0+00	8+95
27-12-15.11	3+00	5+40
Spur No. 1	0+00	2+95
Spur No. 2	0+00	4+85
Spur No. 4	0+00	2+75
Spur No. 5	0+00	2+60

SALE NO. ORC00-TS-2016.0002 STEELE 15 CT EXHIBIT C Sheet 33 of 47 sheets

- Compacted materials within 1 foot of the established subgrade elevation shall have a density in place of not less than 95 percent of maximum density, and below the 1-foot limit, these materials shall have a density in place of not less than 90 percent of maximum density. Maximum density shall be determined by AASHTO T 99, Method A or Method D.
- Compaction of embankment layers placed as specified under Subsection 305b above shall be accomplished by routing construction equipment over full width of embankment structures except as specified in Subsection 306.
- The face of all fill slopes shall be compacted to 85% of maximum density, either by walking with cat/excavator or by pressing with excavator bucket, to prevent surface erosion and raveling.
- In solid rock cuts where pockets that will not drain are formed by blasting below the subgrade elevation, drainage shall be provided by ditching to the edge of the subgrade and backfilling to grade and compacting both the pockets and the ditch with rock fragments, gravel, or other suitable porous material.
- When material, except solid rock, encountered in cuts at subgrade, is suitable for use in forming the finished roadbed, the top 6-inch layer of the subgrade shall be thoroughly scarified for the full width of the roadbed. Roots, sod, and other deleterious material or stones that will not pass a 6-inch square opening shall be removed. The scarified material shall be processed to the optimum moisture content suitable for maximum density and compacted in accordance with Subsection 306.
- In cut areas where solid rock is encountered at or near subgrade, the rock shall be excavated to a minimum depth of 6 inches below subgrade elevation and the excavated area backfilled with suitable material. The backfill material shall be processed to the optimum moisture content suitable for maximum density and compacted to full width in accordance with the requirements of Subsection 306.
- When heavy clays, muck, clay shale, or other deleterious material for forming the roadbed is encountered in cuts at subgrade, it shall be excavated to a minimum depth of 2 feet below the subgrade elevation and the excavated area backfilled with a selected borrow material approved by the Authorized Officer. The backfill material shall be uniformly moistened or dried to the optimum moisture content suitable for maximum density in accordance with the requirements of Subsection 306. Unsuitable material shall be disposed of as directed by the Authorized Officer.
- Ditches shall conform to the slope, grade, dimensions, and shape of the required cross section shown on the plans. Roots, stumps, rocks, and other projections shall be removed to form smooth, even slopes.
- Excess excavated, unsuitable, or slide materials shall not be disposed of on areas where the material will
 encroach on a stream course or other body of water. Such materials shall be disposed of in accordance with
 Subsection 321c.
- NOTE: Any material being hauled over gravel or bituminous surfaced roads will be done in vehicles which meet legal highway weight requirements while hauling.
- End-dumping will be permitted for the placement of excess materials under Subsection 321 in designated disposal areas or within areas approved by the Authorized Officer. Placement in layers is required. Materials placed shall be sloped, shaped, and otherwise brought to a neat and sightly condition acceptable to the Authorized Officer.
- Excavated material shall not be allowed to cover boles of standing trees to a depth in excess of 2 feet on the uphill side.
- The finished grading shall be approved in writing by the Authorized Officer. The Purchaser shall give the Authorized Officer 3 days notice prior to final inspection of the grading operations.

SALE NO. ORC00-TS-2016.0002 STEELE 15 CT EXHIBIT C Sheet 34 of 47 sheets

- The Purchaser shall adopt methods and procedures in using explosives which will prevent damage to adjacent landscape features and which will minimize scattering rocks and other debris outside the road prism.

PIPE CULVERTS - 400

- This work shall consist of furnishing and installing pipe culverts, pipe arch culverts, full rounds, flume(s), perforated pipe culverts, downspout(s), elbow(s), and other erosion control device(s) in accordance with these specifications and conforming to the lines, grades, dimensions, and typical cross sections shown on the plans. Individual lengths and locations are approximate; final lengths and locations will be determined by the Authorized Officer. Additional pipe and erosion control devices may be required at the option of the Authorized Officer, in which case a reduction in the total purchase price shall be made to offset the cost of furnishing and installing such items. Costs will be based upon the unit prices set forth in the current BLM Timber Appraisal Production Cost Schedule.
- Grade culverts shall have a gradient of from 2 percent to 4 percent greater than the adjacent road grade and shall be skewed down grade 30 degrees as measured from the perpendicular to the centerline unless otherwise specified on the plans.
- Damage to the spelter, or burn back in excess of 3/8 inch, shall be wire brushed and painted with two coats of zinc-rich paint on zinc-coated, steel pipe and aluminum-rich paint on aluminum or aluminum-coated pipe.
- Corrugated steel riveted and helical pipe culverts and pipe-arch culverts and special sections shall conform to the requirements of AASHTO M 36 and AASHTO M 218 or AASHTO M 274 as specified on the plans.
- 405a Corrugated-steel-welded pipe culverts and pipe-arch culverts and special sections shall conform to the requirements of AASHTO M 36 and AASHTO M 218 or AASHTO M 274 as specified on the plans.
- 405e Corrugated-polyethylene pipe for culverts 12-inch through 24-inch diameter shall meet the requirements of AASHTO M 294 for type S. Installation will be subject to the same specification as other pipe materials.
- Coupling bands shall conform to the requirements of AASHTO M 36 and AASHTO M 218 or AASHTO M 274 with the exception of band widths and the "Hugger"-type band which shall conform to the details, dimensions, and typical diagram shown on the plans.
- "Hugger"-type coupling bands shall only be used with annular corrugated pipe and pipe-arch culverts or helically corrugated pipe and pipe-arch culverts having annular reformed ends. Annular reformed ends shall consist of 2 annular corrugations.
- Coupling bands produced from flat galvanized steel sheets with impressed dimples will be permitted only for connecting annular corrugated steel pipe to helically corrugated steel pipe. Such coupling bands shall conform to the width requirements shown on the plans
- Channel-type or flanged-end coupling bands may be used on helical pipe with reformed rolled ends and flanged specifically to receive these bands. Such coupling bands shall conform to the requirements shown on the plans.
- Special sections, such as elbows, branch connections, and flared end sections, shall be of the same gauge as the pipe to which they are joined and shall conform to the requirements of AASHTO M 36 and AASHTO M 218 or AASHTO M 274.
- Full round **culvert downspouts** conforming to the material and construction requirements as shown on the plans shall be **anchored with two six-foot steel fence posts** (one on each side of the pipe) **wired together with No. 12 galvanized wire in a manner approved by the Authorized Officer.** These anchors shall be placed every ten feet along the pipe beginning at the outlet of the culvert pipe.

SALE NO. ORC00-TS-2016.0002 STEELE 15 CT EXHIBIT C Sheet 35 of 47 sheets

- Pipe culverts and pipe-arch culverts shall be placed on the bed starting at the downstream end with the inside circumferential laps pointing downstream and with the longitudinal laps at the side or quarter points. Coupling bands of the type required under these specifications shall be installed so as to provide the circumferential and longitudinal strength necessary to preserve the pipe alignment, prevent separation of the pipe sections, and minimize infiltration of fill material.
- Structural-plate pipe culverts and pipe-arch culverts shall be installed in accordance with the plans and detailed erection instructions furnished by the manufacturer. One copy of the erection instructions shall be furnished to the Authorized Officer prior to erection.
- Pipe shall be unloaded and handled with reasonable care. If the Authorized Officer determines any structure
 is damaged to the extent that it is unsuitable for use in the road construction, it shall be replaced at the
 Purchaser's expense.
- Trenches necessary for the installation of pipe culverts shall conform to the lines, grades, dimensions, and typical diagram included in the plans shown on Exhibit C and the Culvert Installation Detail Sheet.
- Where ledge rock, boulders, soft, or spongy soils are encountered, they shall be excavated a minimum of 24 inches below the invert grade for a width of at least one pipe diameter or span on each side of the pipe and shall be backfilled with selected granular or fine readily compactable soil material.
- Pipe culverts and pipe-arch culverts shall be bedded on a selected granular or fine readily compactable soil
 material. Foundation material shall be of uniform density throughout the length of the structure and shall be
 shaped to fit the pipe.
- Bedding material for pipe culverts on existing surfaced roads shall be 1½ inch minus crushed aggregate meeting the requirements of Sections 1204, 1205, 1206, 1207, and 1208 of these specifications.
- The invert grade of the bedding shall be cambered at the middle ordinate a minimum of 1 percent of the total length of the drainage structure. Camber shall be developed on a parabolic curve.
- Inspection of pipe culverts having a diameter of 48 inches and pipe-arch culverts having a height of 40 inches or a cross sectional area of 13 square feet or larger shall be made before backfill is placed. Culverts found to be out of alignment or damaged shall be replaced, reinstalled, or repaired as directed by the Authorized Officer at the Purchaser's expense.
- Side-fill material for pipe culverts shall be placed within 1 pipe diameter, or a minimum of 2 feet, of the sides of the pipe barrel and to 1 foot over the pipe with fine, readily compactable soil or granular fill material free of excess moisture, muck, frozen material, roots, sod, or other deleterious or caustic material and devoid of rocks or stones of sizes which may impinge upon and damage the pipe or otherwise interfere with proper compaction.
- For pipe culvert(s) side-fill material conforming to the requirements of Subsection 416 shall be placed and compacted under the haunches of the pipe and shall be brought up evenly and simultaneously on both sides of the pipe to 1 foot above the pipe in layers not exceeding 6 inches in depth and 1 pipe diameter/span or a minimum of 2 feet in width each side of, and adjacent to, the full length of the pipe barrel. Each layer shall be moistened or dried to a uniform moisture content suitable for maximum compaction and immediately compacted by approved hand or pneumatic tampers until a uniform density of 95 percent of the maximum density is attained as determined by AASHTO T 99, Method C.
- Side fills beyond the compaction limits specified under Subsection 417 shall be compacted as specified under Section 300.
- Construction of catch basins and ditch dams conforming to lines, grades, dimensions and typical diagrams shown on the plans, shall be required for grade culverts.

- Where pervious materials are used for backfill and bedding, collars consisting of selected impervious material shall be placed at the inlet and at various intervals along the pipe barrel as shown on the plans and as directed by the Authorized Officer.
- Culvert marker(s) consisting of ½-inch round steel bars 4 feet in length bolted to the culvert at the inlet or 6 foot steel fence posts painted white, shall be furnished, fabricated, and installed by the Purchaser at all grade culverts.

RENOVATION AND IMPROVEMENT OF EXISTING ROADS - 500

- This work shall consist of reconditioning and preparing the roadbed and shoulders, cleaning and shaping drainage ditches, trimming vegetation from cut and embankment slopes, and cleaning and repairing drainage structures of existing roads in accordance with these specifications and as shown on the plans.
- 501a This work shall include the removal and disposal of slides in accordance with these specifications.
- The existing road surface shall be scarified to its full width and to a sufficient depth to eliminate surface irregularities and bladed and shaped to the lines, grades, dimensions, and typical cross sections shown on the plans at the following location(s):

Road No.	From Sta./M.P.	To Sta./M.P.
27-12-3.1	0+00	17+50
27-12-9.6	0.00	0.15
27-12-10.1	0.00	18+35
27-12-15.0	0.00	0.45
27-12-15.3	5+95	36+50
27-12-15.11	0+00	3+00

- Rocks larger than 4 inches in maximum dimension shall be removed from the scarified layers of the roadbed. Material so removed will not be permitted to remain on road shoulders or in ditches.
- Drainage ditches shall be bladed and shaped in accordance with the lines, grades, dimensions, and typical cross sections shown on the plans.
 Drainage ditches that are vegetated, capable of adequate water flow, and are in accordance with the lines, grades, dimensions, and typical cross sections shown on the plans shall not be bladed.
- 503 Debris from slides shall be disposed of as directed by the Authorized Officer.
- Scarified material and existing road surface shall be uniformly moistened or dried to the optimum moisture content suitable for maximum density and compacted to full width with equipment conforming to requirements of Subsection 103f and in accordance with the following table:

Road No.	From Sta./M.P.	To Sta./M.P.
27-12-3.1	0+00	17+50
27-12-9.6	0.00	0.15
27-12-10.1	0.00	18+35
27-12-15.3	5+95	36+50
27-12-15.11	0+00	3+00

SALE NO. ORC00-TS-2016.0002 STEELE 15 CT EXHIBIT C Sheet 37 of 47 sheets

- Minimum compaction required shall be 1 hour of continuous rolling for each 4 stations of road, or fraction thereof, as measured along the centerline per layer of material.
- The inlet end of existing drainage structures shall be cleared of vegetative debris and boulders that are of sufficient size to obstruct normal stream flow. Pipe inverts shall be cleared of sediment and other debris lodged in the barrel of the pipe. The outflow area of designated pipe structures shall be cleared of rock and vegetative obstructions which will impede the structure's designed outflow configuration. Catch basins shall conform to the lines, grade, dimensions, and typical diagram shown on the plans.
- The finished grading shall be approved in writing by the Authorized Officer. The Purchaser shall give the Authorized Officer 3 days notice prior to final inspection of the grading operations.

WATERING - 600

- This work shall consist of furnishing and applying water required for the compaction of embankments, roadbeds, backfills, base courses, surface courses, finishing and reconditioning of existing roadbeds laying dust, or for other uses in accordance with these specifications.
- Water, when needed for compaction shall be applied at the locations in the amounts and during the hours as
 directed by the Authorized Officer. Amounts of water to be provided will be the minimum needed to properly
 execute the compaction requirements in conformance with these specifications.
- Water trucks used in this work shall be equipped with a distributing device of ample capacity and of such design as to ensure uniform application of water on the road bed.

AGGREGATE BASE COURSE AND LANDING ROCK - 1000 CRUSHED ROCK MATERIAL

- This work shall consist of furnishing, hauling, and placing one or more lifts of crushed rock material on roadbeds and landings approved for placing crushed rock material, in accordance with these specifications and conforming to the dimensions and typical cross sections shown on the plans. Material not conforming to these specifications will be rejected and shall be removed from the road.
- 1002a Crushed rock materials may be obtained from commercial sources selected by the Purchaser at his option and expense providing that the rock materials selected comply with the specifications in this section.
- Crushed rock material produced from gravel shall have 3 manufactured fractured face(s) on 75 percent, by weight, of the material retained on the No. 4 sieve.

SALE NO. ORC00-TS-2016.0002 STEELE 15 CT EXHIBIT C Sheet 38 of 47 sheets

1004 - Crushed rock materials shall consist of hard durable rock fragments conforming to the following gradation requirements:

TABLE 1004

AGGREGATE BASE COURSE

CRUSHED ROCK MATERIAL

Percentage by Weight Passing Square Mesh Sieves

(AASHTO T 11 & T 27)

GRADATION

Sieve Designation	А
4-inch	-
3-inch	100
2-inch	90- 95
1½-inch	-
1-inch	45- 75
3/4-inch	-
½-inch	-
3/8-inch	-
No. 4	15- 45
No. 8	-
No. 10	-
No. 30	-
No. 40	5-25
No. 200	2-15

- Crushed rock material retained on the No. 4 sieve shall have a percentage of loss of not more than 35 at 500 revolutions, as determined by AASHTO T 96.
- 1006 Crushed rock material shall show durability value of not less than 35 as determined by AASHTO T 210.
- That portion of crushed rock material passing the No. 40 sieve, including blending filler, shall have liquid limits of not more than 35 and a plasticity index of not less than 4 and not more than 12, as determined by AASHTO T 89 and AASHTO T 90.
- That portion of crushed rock material passing No. 4 sieve, including blending filler, shall have a sand equivalent of not less than 35 as determined by AASHTO T 176, except where that portion exhibits a sand equivalent of less than 35, the aggregate will be accepted if it complies with the additional requirement as follows:

Sand Equivalent AASHTO T 176 Maximum	Percentage Passing No. 200 Sieve AASHTO T 27 Maximum
34	9
33	8
32	7
31	6
30	5
29 or less	4

- If additional binder or filler is necessary in order to meet the grading or plasticity requirements, or for satisfactory bonding of the material, it shall be uniformly blended with the crushed rock material at the crushing and screening plant prior to placing on the road, unless otherwise agreed. The material for such purposes shall be obtained from sources approved by the Authorized Officer and shall be free from stones, vegetative matter, and other deleterious materials.
- Each layer of crushed rock material shall be thoroughly mixed on the roadbed by alternately blading to full depth until a uniform mixture has been obtained. The mixture shall then be spread to full width. When completed, the spreading shall produce a surface which is smooth, presents uniform shoulder lines, and conforms to the specified cross section.
- The roadbed, as shaped and compacted under Sections 300 and 500 of these specifications, shall be approved in writing by the Authorized Officer prior to placement of crushed rock materials. Notification for subgrade approval prior to rocking shall be 3 days prior to that approval and shall be 6 days prior to start of rocking operations.
- Crushed rock materials shall be placed and processed on the approved roadbed in accordance with these specifications and conforming to the lines, grades, dimensions, and typical cross sections shown on the plans and compacted in layers not to exceed 4 inches in depth. When more than one layer is required, each shall be shaped, processed, and compacted, before the succeeding layer is placed. Irregularities or depressions that develop during compaction of the top layer shall be corrected by loosening the material at these places and adding or removing crushed rock material until the surface is smooth and uniform.
- 1010a Crushed rock material used to repair or reinforce a soft, muddy, frozen, yielding, or rutted roadbed shall not be construed as surfacing under this specification.
- Each layer of crushed rock material shall be placed, processed, shaped, moistened, or dried to a uniform moisture content suitable for maximum compaction, and compacted to full width by compaction equipment conforming to the requirements of Subsection 103f. Minimum compaction shall be one (1) hour of continuous compacting for each 150 cubic yards, or fraction thereof, of crushed rock material placed per layer.

SALE NO. ORC00-TS-2016.0002 STEELE 15 CT EXHIBIT C Sheet 40 of 47 sheets

AGGREGATE SURFACE COURSE, SPOT, AND MAINTENANCE ROCK - 1200 CRUSHED ROCK MATERIAL

- This work shall consist of furnishing, hauling, and placing one or more layers of crushed rock material on roadbeds and base courses approved for placing crushed rock material in accordance with these specifications and conforming to the dimensions and typical cross sections shown on the plans. Material not conforming to these specifications will be rejected and shall be removed from the road.
- 1202a Crushed rock materials used in this work may be obtained from commercial source(s) selected by the Purchaser at his option and expense, providing rock materials furnished comply with the specifications in this section.
- When crushed rock material is produced from gravel, not less than 75 percent by weight of the particles retained on the No. 4 sieve will have 3 manufactured fractured face(s).
- 1204 Crushed rock material shall consist of hard durable rock fragments conforming to the following gradation requirements:

TABLE 1204

AGGREGATE SURFACE COURSE CRUSHED ROCK MATERIAL Percentage by weight passing square mesh sieves AASHTO T 11 & T 27

GRADATION

Sieve Designation	А
1-1/2-inch	100
1-inch	-
3/4-inch	50-90
½-inch	-
No. 4	25-50
No. 8	-
No. 30	-
No. 40	5-25
No. 200	2-15

- Crushed rock material retained on the No. 4 sieve shall have a percentage of loss of not more than 35 at 500 revolutions, as determined by AASHTO T 96.
- 1206 Crushed rock material shall show a durability value of not less than 35 as determined by AASHTO T 210.
- That portion of crushed rock material passing the No. 40 sieve, including blending filler, shall have liquid limits of not more than 35 and a plasticity index of not less than 4 and not more than 12 as determined by AASHTO T 89 and AASHTO T 90.
- That portion of crushed rock material passing No. 4 sieve, including blending filler, shall have a sand equivalent of not less than 35, as determined by AASHTO T 176, except where that portion exhibits a sand equivalence of less than 35, the aggregate will be accepted if it complies with the additional requirement as follows:

Sand Equivalent AASHTO T 176 Maximum	Liquid Limit AASHTO T 89 Maximum	Plasticity Index AASHTO T 90 Maximum	Percentage Passing No. 200 Sieve AASHTO T 27 Maximum
34	25	9	9
33	25	8	8
32	25	7	7
31	25	6	6
30	25	5	5
29 or less	25	4	4

- If additional binder or filler material is necessary to meet the grading or plasticity requirements or for satisfactory bonding of the material, it shall be uniformly blended with the crushed rock material at the crushing and screening plant prior to placing on the road, unless otherwise agreed. The material for such purposes shall be obtained from sourcesfrom sources approved by the Authorized Officer and shall be free from stones, vegetative matter, and other deleterious materials.
- Each layer of crushed rock material shall be thoroughly mixed on the roadbed by alternately blading, to full depth, until a uniform mixture has been obtained. The mixture shall then be spread to full width. When completed, the spreading shall produce a surface which is smooth, presents uniform shoulder lines, and conforms to the specified cross section.
- Shaping and compacting of roadbed shall be completed and approved in writing, prior to placing crushed rock material, in accordance to the requirements of Subsections 500 for placing on the roadbeds. Notification for roadbed inspection, prior to rocking, shall be 3 days prior to that inspection and shall be 6 days prior to start of rocking operations.
- Crushed rock material conforming to the requirements of these specifications shall be placed on the approved roadbed in accordance with these specifications and conforming to the lines, grades, dimensions, and typical cross sections shown on the plans. Compacted layers shall not exceed 4 inches in depth. When more than one layer is required, each shall be shaped, processed, compacted, and approved by the Authorized Officer before the succeeding layer is placed. Irregularities or depressions that develop during compaction of the top layer shall be corrected by loosening the material at these places and then adding or removing crushed rock material until the surface is smooth and uniform.
- 1210a Crushed rock material used to repair or reinforce soft, muddy, frozen, yielding, or rutted roadbed shall not be construed as surfacing required by this specification.
- Each layer of crushed rock material placed, processed, and shaped as specified shall be moistened or dried to a uniform moisture content suitable for maximum compaction and compacted to full width by compacting equipment conforming to the requirements of Subsection 103i. Minimum compaction shall be 1 hour of continuous compacting for each 150 cubic yards or fraction thereof, of crushed rock material placed per layer.

SLOPE PROTECTION – 1400

This work shall consist of furnishing, hauling, and placing stone materials (riprap) for slope protection structures (energy dissipaters at culvert outlets) in accordance with these specifications. Material not conforming to these specifications will be rejected, and shall be removed from the slope protection structure as directed by the Authorized Officer.

SALE NO. ORC00-TS-2016.0002 STEELE 15 CT EXHIBIT C Sheet 42 of 47 sheets

- Riprap shall be hard, durable, angular in shape, and resistant to weathering and water action. Thickness of a single stone should be more than one-third its length. Do not use rounded rock or boulders. Stone shall be free from overburden, spoil, shale, and organic material and conforming to the following:

a. Apparent Specific Gravity (AASHTO T85) 2.50 Min.

b. Absorption (AASHTO T85) 4.2% Max.

c. Coarse Durability Index (AASHTO T210) 20 Min.

1403 - Loose riprap shall meet the following gradation (Class 6):

Equivalent	Percent of
Cubic	Rock
<u>Dimensions</u>	<u>By Mass</u>
00 (- 04 !!	00
28 to 34 inches	20
22 to 28 inches	30
10 to 22 inches	40
0 to 10 inches	10

- 1404 The placement of slope protection riprap by the end dumping method is not permitted.
- Riprap shall be placed to produce a well keyed mass of rock with the least practical amount of void spaces.
 The foundation course is the course placed in contact with the ground surface, and shall be placed on a stable key bench. Bearing shall not be on smaller rocks that may be used for filling voids.
- Riprap shall be placed directly under the culvert outlet and extend to the point where a 45-degree angle from the outlet invert intersects the key bench. Riprap shall extend a minimum distance equal to the culvert diameter on all sides.
- Determination of the acceptability of the slope protection structure will be by visual inspection and / or physical measurements by the Authorized Officer.

EROSION CONTROL - 1700

- This work shall consist of measures to control soil erosion or water pollution during the construction operation through the use of berms, dikes dams, sediment basins, fiber mats, netting, gravel, mulches, grasses, slope drains and other erosion control devices or methods in accordance with these specifications and conforming to the lines, grades, dimensions, and typical cross sections shown on the plans.
- The Purchaser shall construct dike(s), dam(s), diversion channel(s), settling basin(s) and other erosion control structure(s) as directed by the Authorized Officer.
- 1704 The erosion control provisions specified under this subsection shall be coordinated with the soil stabilization requirement(s) of Section 1800.
- The surface area of erodible earth material exposed at any one time by clearing and grubbing shall not exceed 25,000 square feet without prior approval by the Authorized Officer.
- 1706 The surface area of erodible earth material exposed at one time by excavation, borrow, or fill within the right-of-way shall not exceed 25,000 square feet without prior approval by the Authorized Officer.
- 1706a The Purchaser shall perform, during the same construction season, erosion control measures specified in the plans on all exposed excavation, borrow, and embankment areas.

SALE NO. ORC00-TS-2016.0002 STEELE 15 CT EXHIBIT C Sheet 43 of 47 sheets

- 1707 Completed and partially completed segments of road(s) to be carried over the winter and early spring periods shall be stabilized by mulching exposed areas at the rate of 2,000 pounds per acre.
- 1708a Road segments not completed during dry weather periods shall be winterized, by providing a well drained roadway by waterbarring, maintaining drainage, and performing additional measures necessary to minimize erosion and other damage to the roadway, as directed by the Authorized Officer. Portions of roads not having surface rock in place will be blocked or barricaded to prevent vehicular traffic.

SOIL STABILIZATION - 1800

- This work shall consist of seeding, fertilizing and mulching on designated cut, fill, borrow, disposal, and special areas in accordance with these specifications and as shown on the plans. This work is not required for road acceptance under Section 18 of this contract.
- 1802a Soil stabilization work consisting of seeding, fertilizing and mulching shall be performed on new road construction, road renovation, improvements, landings and disturbed areas in accordance with these specifications and as shown on the plans.
- Soil stabilization work as specified under Subsection 1802a shall be performed during the following seasonal periods:

From: March 15 To: April 30 From: September 1 To: October 15

If soil stabilization of disturbed areas is not completed by the specified fall date, the Purchaser shall treat disturbed areas in accordance with Section 1707 and then complete the requirements of Soil Stabilization 1800 the next construction season.

The Authorized Officer may modify the above seasonal dates to conform to existing weather conditions and changes in the construction schedule.

1804 - The Purchaser shall furnish the following species of grass seed meeting corresponding germination, purity, and weed content requirements:

Species	Germination Min. %	Purity Min. %	Weed Content Max. %
Annual ryegrass Lolium multiflorum	85%	95%	0.5%
Perennial rye grass Lolium perenne	85%	95%	0.5%

The grass seed furnished shall meet the minimum requirement for Blue Tag Seed as set forth in the latest edition of Oregon Certification Standards published by Oregon State University.

The Purchaser shall furnish the Authorized Officer a Certificate of Compliance from Oregon State University, Crop Certification Service, which shall include: date of test; lot number of each kind of seed; and results of tests as to name, percentages of purity and of germination, and percentage of weed content for each kind of seed furnished and, in case of mixture, the proportions of each kind of seed. The seed must have been tested within the last 2 years to be accepted for use on this contract.

1805 - The Purchaser shall mix and sack grass seed specified under Subsection 1804 in the following proportions:

Species	% of Total by Weight	Lbs. per Acre
Annual ryegrass Lolium multiflorum	40%	24
Perennial rye grass <i>Lolium perenne</i>	60%	36
Totals	100	60 lbs./ac.

- 1805a The Purchaser shall certify, in writing, compliance with seed mixture(s) specified under Subsection 1805. Seed weight and seed mixture type shall be shown on the tag attached to each sack.
- 1805b Seed shall be sacked in quantities proportional to the capacity of the Purchaser's slurry tank and the required rate of application as specified under Subsection 1812.
- 1806 The Purchaser shall apply the seed mixtures specified under Subsection 1805 to the corresponding seeding projects as shown on **Sheet No. 7**.
- Additional soil stabilization work consisting of seeding, fertilizing and mulching may be required at the option of the Authorized Officer. Providing the additional stabilization is not due to Purchaser negligence as specified in Section 12 of the contract, a reduction in the total purchased price shall be made to offset the cost of furnishing and applying such additional stabilization material. Cost shall be based upon the unit price set forth in the current BLM Timber Appraisal Production Cost Schedule.
- Fertilizer shall be a standard commercial grade of fertilizer conforming to all State and Federal regulations and to the standards of the Association of Official Agricultural Chemists. Fertilizer furnished shall provide the minimum percentage of available nutrients as specified below:

Available nitrogen	16%
Available phosphoric acid	20%
Potassium	0%

The Authorized Officer will take what samples he deems necessary for determining compliance with the above requirements.

Fertilizer shall be furnished in new sealed and properly labeled containers with name, weight, and guaranteed analysis of contents clearly marked. Material failing to meet these requirements, or that which has become wet or otherwise damaged in transit or storage, will be subject to rejection by the Authorized Officer.

- Mulch materials conforming to the requirements of Subsections 1809b, 1809d or 1809e shall be furnished by the Purchaser in the amounts specified under Subsection 1812.
- Natural wood cellulose or grass fiber shall have the property of dispersing readily in water and shall have no toxic effect when combined with seed or other materials. The homogeneous slurry or mixture shall be capable of application with power spray equipment. A green colored dye which is noninjurious to plant growth shall be used. Processed wood cellulose or grass fiber shall be packaged in new, labeled containers in an air dry condition. Processed wood cellulose or grass fiber furnished by the Purchaser shall be one of the following brand names or approved equal:

Silva Fiber - Weyerhaeuser Timber Co.
Conweb Fiber - Wood Conversion Co.
Spra-Mulch Industries, Inc.

Grass-Mulch - Grass Mulch, Inc.

SALE NO. ORC00-TS-2016.0002 STEELE 15 CT EXHIBIT C Sheet 45 of 47 sheets

If the Purchaser proposes using a wood or grass fiber other than those listed above, he shall furnish a sample and descriptive literature to the Authorized Officer for approval prior to application. Processed wood cellulose or grass fiber furnished by the Purchaser which has become wet or otherwise damaged in transit or storage will not be accepted.

- 1809d Straw mulch shall be from oats, wheat, rye, or other approved grain crops which are free from noxious weeds, mold, or other objectionable materials. Straw mulch shall be in an air-dry condition and suitable for placing with power spray equipment.
- 1809e Grass straw mulch shall be from perennial grass or, if specified, an annual rye grass, from which the seed has been removed. The straw shall be free from noxious weed seed, mold, or other objectionable materials.
- Mulch material shall be delivered to the work area in a dry state. Material found to be wet will not be accepted. Material to be used in the mulching operation may be stockpiled along the road designated for treatment provided that it be maintained in a dry state and has the approval of the Authorized Officer.
- 1811 Bulk mulching material required under these specifications shall be delivered to the work area bound either by twine, string, or hemp rope. Wire binding and plastic twine will not be permitted.
- The Purchaser shall furnish and apply to approximately **5.3 acres** designated for treatment as shown on the plans and as specified under Subsection 1806, a mixture of water, grass seed, fertilizer and mulch material, or a mixture of grass seed and fertilizer material at the following rate of application:
 - a. Single Stage (Hydraulic):

Water 3,000 gals./acre
Grass Seed 60 lbs./acre
Fertilizer 200 lbs./acre
Mulch 3,000 lbs./acre

b. Dry Application:

Grass Seed 60 lbs./acre
Fertilizer 200 lbs./acre
Mulch/Straw 3,000 lbs./acre

The above proportion and application rate are subject to adjustment by the Authorized Officer during the application operation.

- The Purchaser may reduce the application rate on partially covered slopes and no application on areas already well stocked with grass or on rock surfaces.
- The seed, fertilizer and mulch materials shall be placed by the hydraulic or dry method in accordance with the requirements set forth in Subsection 1816a and 1816b.
- 1816a Hydraulic Method The seed, fertilizer and mulch materials shall be mixed with water to form a slurry and then applied under pressure by hydroseeder.
 When processed wood cellulose or grass fiber mulch material is to be incorporated as an integral part of the slurry mix, it shall be added after the seed and fertilizer have been thoroughly mixed.
- 1816b Dry Method Blowers, mechanical seeders, seed drills, landscape seeders, cultipaker seeders, fertilizer spreaders, or other approved mechanical seeding equipment may be used when seed and fertilizer are to be applied in dry form.

SALE NO. ORC00-TS-2016.0002 STEELE 15 CT EXHIBIT C Sheet 46 of 47 sheets

1817 - Hydraulic equipment used for the application of slurry shall meet the following requirements:

The equipment shall have a built-in agitation system. The slurry distribution lines shall be large enough to prevent stoppage. Discharge line shall be equipped with a set of hydraulic spray nozzles which will provide even distribution of the slurry on the various slopes to be treated. The slurry tank shall have a minimum operation capacity of 1,300 gallons and shall be mounted on a traveling unit which will place the slurry tank and spray nozzles within sufficient proximity to the areas to be treated so as to provide uniform distribution without waste. Lug- or track type units are not authorized. The hydroseeder must be capable of spraying the slurry a minimum distance of 100 feet. The nozzle, mounted on a stand, must be capable of traversing 360 degrees on a horizontal plane and a minimum of 70 degrees on a vertical plane.

- 1817a Hydromulch slurry mixing shall be with water and seed first, followed by fertilizer, and finally fiber. The time between mixing and application shall not exceed 1 hour.
- 1819 The maximum distance to be seeded, fertilized and mulched from the road centerline shall be 100 feet for the cut slopes and 150 feet for the fill slopes.
- 1820 The Purchaser shall notify the Authorized Officer at least 3 days in advance of date he intends to commence the specified soil stabilization work.
- Mulch that collects at the end of culverts or accumulates to excessive depths on the slopes shall be evenly spread by hand methods, as directed by the Authorized Officer.
- No materials shall be applied when wind velocities would prevent a uniform application of the mix or slurry or when winds would drift the mix or slurry spray outside of the designated treatment area.
- 1826 Twine, rope, sacks, and other debris resulting from the soil stabilization operation shall be picked up and disposed of to the satisfaction of the Authorized Officer.

ROADSIDE BRUSHING - 2100

- This work shall consist of cutting and the removal of vegetation from the road prism variable distance and inside curves in accordance with these specifications. This work shall conform to the lines, grades, dimensions, and typical cross sections shown on the Roadside Brushing Detail Sheet, at designated locations as shown in the plans.
- Roadside brushing may be performed mechanically with self powered, self-propelled equipment and/or manually with hand tools, including chainsaws.
- Vegetation cut manually or mechanically less than 6 inches in diameter at D.B.H. shall be cut to a maximum height of 6 inches above the ground surface or above obstructions such as rocks or stumps on cut and fill sloped and all limbs will be severed from the trunk.
- Vegetation shall be cut and removed from the road bed between the outside shoulders and the ditch centerline and such vegetation shall be cut to a maximum height of 1 inch above the ground and running surface. All limbs will be severed from the trunk. Sharp pointed ends will not be permitted. Cuts shall be parallel to the ground line or running surface.
- 2104 Trees in excess of 6 inches in diameter at D.B.H. shall be limbed, so that no limbs extend into the treated area or over the roadbed to a height of 12 feet above the running surface of the roadway on cut and fill slopes, within the road prism variable distance. Limbs shall be cut to within 1 inch of the trunk to produce a smooth vertical face. Removal of trees larger than 6 inches in diameter for sight distance or safety may be directed by the Authorized Officer.
- Vegetation that is outside of the road prism variable distance that protrudes into the road prism and within 12 feet in elevation above the running surface shall be cut, to within 1 inch of the trunk to produce a smooth vertical face.

SALE NO. ORC00-TS-2016.0002 STEELE 15 CT EXHIBIT C Sheet 47 of 47 sheets

- 2106 Vegetative growth capable of growing 1 foot in height or higher shall be cut within the road prism/variable distance or as directed by the Authorized Officer.
- 2108 Self propelled equipment shall not be permitted on cut and fill slopes or in ditches.
- Debris resulting from roadside brushing shall be scattered downslope from the roadway. Debris shall not be allowed to accumulate in concentrations. Debris in excess of 1 foot in length and 2 inches in diameter shall not be allowed to remain on cut slopes, ditches, roadways or water courses, or as directed by the Authorized Officer.
- 2113 Roadside brushing shall be accomplished as specified on **Sheet No. 7** on the roads listed on **Sheet No. 5**.
- 2116 Mechanical brush cutters shall not be operated when there are people and occupied vehicles within 400 feet of the immediate operating area.
- 2117 Traffic warning signs shall be required at each end of the work area. Signs shall meet the requirements of the Manual on Uniform Traffic Devices.

UNITED STATES DEPARTMENT OF THE INTERIOR BUREAU OF LAND MANAGEMENT

Version: 5.1.0.32

Summary of All Roads and Projects		: 6/30/2014
T.S. Contract Name: Steele 15 CT Prepared by: JC Ph: 279		
Construction: 108.40 sta		
Improve: 28.55 sta Renov: 72.53 sta Decom: 0.00 sta Temp: 0	.00 sta	
200 Clearing and Grubbing: 0.0 acres		\$0.00
300 Excavation:		\$39,777.13
400 Drainage: Culvert: 0 lf DownSpout: 0 lf PolyPipe: 0 lf		\$880.00
500 Renovation: Blading 1.82 mi		\$12,380.21
700-1200 Surfacing: Quarry Name: Jarvis 3" Base 7,564 lcy Quarry Name: Jarvis 3" Landing 590 lcy Quarry Name: Jarvis 3" Spot 40 lcy		\$188,234.12
1300 Geotextiles:		\$0.00
1400 Slope Protection:		\$0.00
1800 Soil Stabilization: 5.3 acres		\$5,441.25
1900 Cattleguards:		\$0.00
2100 RoadSide Brushing: 2.3 acres		\$980.22
2300 Engineering: 0.00 sta		\$0.00
2400 Minor Concrete:		\$0.00
2500 Gabions:		\$0.00
8000 Miscellaneous:		\$0.00
Mobilization: Const. \$5,227.00 Surf. \$0.00		\$5,227.00
Quarry Development:		\$0.00
	Total:	\$252,919.92

Note:

T.S. Contract Name: Steele 15 CT Sale Date: Road Number: 27-11-15.11 C Road Name: Road Construction: 0.05 mi 16 ft Subgrade 0 ft ditch 6/30/2014	
200 Clearing and Grubbing: acres	\$0.00
300 Excavation:	\$1,398.82
400 Drainage: Culvert: 0 lf DownSpout: 0 lf PolyPipe: 0 lf	\$0.00
500 Renovation:	\$0.00
700-1200 Surfacing:	\$6,241.50
1300 Geotextiles:	\$0.00
1400 Slope Protection:	\$0.00
1800 Soil Stabilization: 0.2 acres	\$205.33
1900 Cattleguards:	\$0.00
2100 RoadSide Brushing: 0.0 acres	\$0.00
2300 Engineering: 0.00 sta	\$0.00
2400 Minor Concrete:	\$0.00
2500 Gabions:	\$0.00
8000 Miscellaneous:	\$0.00
Mobilization: Const. \$165.56 Surf. \$0.00	\$165.56
Quarry Development:	\$0.00
Total:	\$8,011.22

Notes:

Road Construction Worksheet Road Number: 27-11-15.11 C Road Name: Section 200 Clearing and Grubbing: Subtotal: \$0.00 Section 300 Excavation: Subgrade Compaction: 4 Sta/hr \$33.62/sta. x 2.4 sta = \$80.69 Blading without ditch: \$12.14/station x 2.40 stations = \$29.14Subgrade Construction Excavator - Large (2 CY) 10 hr x \$128.90/hr = \$1,289.00Subtotal: \$1,398.82 Section 400 Drainage: Subtotal: \$0.00 Section 500 Renovation: Subtotal: \$0.00 Section 700-1200 Surfacing: Cr. Aggregate Quarry Name: Jarvis 3" Base BotW Depth CWid #TOs Width F.W.L Taper Length TopW Other 0.05mi 12ft 16ft 12in Rock Volume = 166 lcy Purchase Price / Royalty: $$10.00/lcy \times 166 lcy = $1,660.00$ Processing: $$0.90/lcy \times 166 lcy = 149.40 Compaction: $$1.34/lcy \times 166 lcy = 222.44 Basic Rock Haul cost: \$0.74/lcy x 166 lcy = \$122.84 Rock Haul -15% grades: \$1.10/lcy-mi x 166 lcy x 0.10 mi= \$18.26 Rock Haul St& Co Roads: \$0.49/lcy-mi x 166 lcy x 18.00 mi= \$1,464.12 Basic Water Haul cost: $$0.60/lcy \times 166 lcy = 99.60 Water Haul -15% grades: \$0.14/lcy-mi x 166 lcy x 1.00 mi= \$23.24 Cr Aggregate Quarry Name: Jarvis 3" Landing Comment: 3+00 TTA Length TopW BotW Depth CWid #TOs Width F.W.L Taper Other 10 lcv Rock Volume = 10 lcy Purchase Price / Royalty: \$10.00/lcy x 10 lcy = \$100.00 Processing: $$0.90/lcy \times 10 lcy = 9.00 Compaction: $$1.34/lcy \times 10 lcy = 13.40 Basic Rock Haul cost: $$0.74/lcy \times 10 lcy = 7.40 Rock Haul -15% grades: \$1.10/lcy-mi x 10 lcy x 0.10 mi= \$1.10 Rock Haul St& Co Roads: \$0.49/lcy-mi x 10 lcy x 18.00 mi= \$88.20 Basic Water Haul cost: $$0.60/lcy \times 10 lcy = 6.00 Water Haul -15% grades: $\$0.14/lcy-mi \times 10 lcy \times 1.00 mi= \1.40 Cr Aggregate Quarry Name: Jarvis 3" Landing Comment: 3+85 Ldg Length TopW BotW Depth CWid #TOs Width F.W.L Taper Other 50 lcy Rock Volume = 50 lcyPurchase Price / Royalty: \$10.00/1cy x 50 1cy = \$500.00Processing: $$0.90/lcy \times 50 lcy = 45.00 Compaction: $$1.34/lcy \times 50 lcy = 67.00

Cr Aggregate Quarry Name: Jarvis 3" Landing

Basic Rock Haul cost: $$0.74/lcy \times 50 lcy = 37.00

Basic Water Haul cost: $$0.60/lcy \times 50 lcy = 30.00

Rock Haul -15% grades: $$1.10/lcy-mi \times 50 lcy \times 0.01 mi= 0.55 Rock Haul St& Co Roads: $$0.49/lcy-mi \times 50 lcy \times 18.00 mi= 441.00

Water Haul -15% grades: \$0.14/lcy-mi x 50 lcy x 1.00 mi= \$7.00

Road Number: 27-11-15.11 C Continued

Comment: 5+40 End Ldg

Rock Volume = 50 lcy

Purchase Price / Royalty: $$10.00/lcy \times 50 lcy = 500.00

Processing: $$0.90/lcy \times 50 lcy = 45.00 Compaction: $$1.34/lcy \times 50 lcy = 67.00

Basic Rock Haul cost: $$0.74/lcy \times 50 lcy = 37.00

Rock Haul -15% grades: $$1.10/lcy-mi \times 50 lcy \times 0.01 mi= 0.55 Rock Haul St& Co Roads: $$0.49/lcy-mi \times 50 lcy \times 18.00 mi= 441.00

Basic Water Haul cost: $$0.60/lcy \times 50 lcy = 30.00

Water Haul -15% grades: \$0.14/lcy-mi x 50 lcy x 1.00 mi= \$7.00

Subtotal: \$6,241.50

Section 1300 Geotextiles:

Subtotal: \$0.00

Section 1400 Slope Protection:

Subtotal: \$0.00

Section 1800 Soil Stabilization:

Dry Method with Mulch: $$540.65/acre \times 0.20 acres = 108.13

Includes Small Quantity Factor of 1.42

+ Seed Cost: \$132.00/acre x 0.20 acres = \$26.40

+ Fertilizer Cost: \$34.00/acre x 0.20 acres = \$6.80

+ Mulch Cost: \$320.00/acre x 0.20 acres = \$64.00

Subtotal: \$205.33

Section 1900 Cattleguards:

Subtotal: \$0.00

Section 2100 Roadside Brushing:

Subtotal: \$0.00

Section 2300 Engineering:

Subtotal: \$0.00

Section 2400 Minor Concrete:

Subtotal: \$0.00

Section 2500 Gabions:

Subtotal: \$0.00

Section 8000 Miscellaneous:

Subtotal: \$0.00

Mobilization:

Construction - 3.17% of total Costs = \$165.56

Surfacing - 3.37% by rock volume = \$0.00

Subtotal: \$165.56

Quarry Development:

Based on 3.37% of total rock volume

Subtotal: \$0.00

Total: \$8,011.22

T.S. Contract Name: Steele 15 CT Sale Date: Road Number: 27-12-10.1 R Road Name:	
Road Renovation: 0.35 mi 12 ft Subgrade ft ditch 6/30/2014	
200 Clearing and Grubbing: acres	\$0.00
300 Excavation:	\$0.00
400 Drainage: Culvert: 0 lf DownSpout: 0 lf PolyPipe: 0 lf	\$0.00
500 Renovation:	\$684.27
700-1200 Surfacing:	\$0.00
1300 Geotextiles:	\$0.00
1400 Slope Protection:	\$0.00
1800 Soil Stabilization: 0.1 acres	\$102.67
1900 Cattleguards:	\$0.00
2100 RoadSide Brushing: 0.8 acres	\$230.64
2300 Engineering: 0.00 sta	\$0.00
2400 Minor Concrete:	\$0.00
2500 Gabions:	\$0.00
8000 Miscellaneous:	\$0.00
Mobilization: Const. \$21.47 Surf. \$0.00	\$21.47
Quarry Development:	\$0.00
Total:	\$1,039.05
110000	

Notes:

Road Number: 27-12-10.1 R Road Name:

Section 200 Clearing and Grubbing:

Subtotal: \$0.00

Section 300 Excavation:

Subtotal: \$0.00

Section 400 Drainage:

Subtotal: \$0.00

Section 500 Renovation:

Blading w/o Ditches: $$446.73/mi \times 0.35 mi = 156.36

Compaction: $$403.47/mi \times 0.35 mi = 141.21

18+35 End Landing

Excavator - Large (2 CY) 3 hr x \$128.90/hr = \$386.70

Subtotal: \$684.27

Section 700-1200 Surfacing:

Surfacing:

Subtotal: \$0.00

Section 1300 Geotextiles:

Subtotal: \$0.00

Section 1400 Slope Protection:

Subtotal: \$0.00

Section 1800 Soil Stabilization:

Dry Method with Mulch: $$540.65/acre \times 0.10 acres = 54.07

Includes Small Quantity Factor of 1.42

+ Seed Cost: \$132.00/acre x 0.10 acres = \$13.20

+ Fertilizer Cost: \$34.00/acre x 0.10 acres = \$3.40

+ Mulch Cost: \$320.00/acre x 0.10 acres = \$32.00

Subtotal: \$102.67

Section 1900 Cattleguards:

Subtotal: \$0.00

Section 2100 Roadside Brushing:

Brushing width Left: 10ft. Right: 10ft.

RoadSide Brushing Light: \$288.30/acre x 0.80 acres = \$230.64

Subtotal: \$230.64

Mobilization:

Construction - 0.41% of total Costs = \$21.47

Surfacing - 0.00% by rock volume = \$0.00

Subtotal: \$21.47

Quarry Development:

Based on 0.00% of total rock volume

Subtotal: \$0.00

Total: \$1,039.05

T.S. Contract Name: Steele 15 CT Sale Date: Road Number: 27-12-15.0 R Road Name: Steinnen Creek	
Road Renovation: 0.45 mi 16 ft Subgrade 2 ft ditch 6/30/2014	
200 Clearing and Grubbing: acres	\$0.00
300 Excavation:	\$0.00
400 Drainage: Culvert: 0 lf DownSpout: 0 lf PolyPipe: 0 lf	\$0.00
500 Renovation:	\$574.60
700-1200 Surfacing:	\$199.62
1300 Geotextiles:	\$0.00
1400 Slope Protection:	\$0.00
1800 Soil Stabilization: 0.0 acres	\$0.00
1900 Cattleguards:	\$0.00
2100 RoadSide Brushing: 1.1 acres	\$518.94
2300 Engineering: 0.00 sta	\$0.00
2400 Minor Concrete:	\$0.00
2500 Gabions:	\$0.00
8000 Miscellaneous:	\$0.00
Mobilization: Const. \$27.29 Surf. \$0.00	\$27.29
Quarry Development:	\$0.00
Total:	\$1,320.45

Notes:

Road Number: 27-12-15.0 R Road Name: Steinnen Creek

Section 200 Clearing and Grubbing:

Subtotal: \$0.00

Section 300 Excavation:

Subtotal: \$0.00

Section 400 Drainage:

Subtotal: \$0.00

Section 500 Renovation:

Blading: $$720.50/mi \times 0.45 mi = 324.23

Clean Culverts: $$334.17/mi \times 0.45 mi = 150.38

Gate Restoration

Labor 1 LS x \$100.00/LS = \$100.00

Subtotal: \$574.60

Section 700-1200 Surfacing:

Cr Aggregate Quarry Name: Jarvis 3" Spot

Rock Volume = 20 lcy

Processing: $$0.90/lcy \times 20 lcy = 18.00

Basic Rock Haul cost: $$0.74/lcy \times 20 lcy = 14.80

Rock Haul -15% grades: \$1.10/lcy-mi x 20 lcy x 0.01 mi= \$0.22

Rock Haul St& Co Roads: \$0.49/lcy-mi x 20 lcy x 17.00 mi= \$166.60

Subtotal: \$199.62

Section 1300 Geotextiles:

Subtotal: \$0.00

Section 1400 Slope Protection:

Subtotal: \$0.00

Section 1800 Soil Stabilization:

Subtotal: \$0.00

Section 1900 Cattleguards:

Subtotal: \$0.00

Section 2100 Roadside Brushing:

Brushing width Left: 10ft. Right: 10ft.

RoadSide Brushing Light: \$288.30/acre x 0.60 acres = \$172.98

RoadSide Brushing Medium: $$576.60/acre \times 0.40 acres = 230.64

RoadSide Brushing Heavy: \$1153.20/acre x 0.10 acres = \$115.32

Subtotal: \$518.94

Mobilization:

Construction - 0.52% of total Costs = \$27.29

Surfacing - 0.24% by rock volume = \$0.00

Subtotal: \$27.29

Quarry Development:

Based on 0.24% of total rock volume

Subtotal: \$0.00

Total: \$1,320.45

T.S. Contract Name: Steele 15 CT Sale Date: Road Number: 27-12-15.10 C Road Name: Road Construction: 0.17 mi 12 ft Subgrade 0 ft ditch 6/30/2014	
200 Clearing and Grubbing: acres	\$0.00
300 Excavation:	\$2,987.55
400 Drainage: Culvert: 0 lf DownSpout: 0 lf PolyPipe: 0 lf	\$0.00
500 Renovation:	\$0.00
700-1200 Surfacing:	\$0.00
1300 Geotextiles:	\$0.00
1400 Slope Protection:	\$0.00
1800 Soil Stabilization: 0.3 acres	\$308.00
1900 Cattleguards:	\$0.00
2100 RoadSide Brushing: 0.0 acres	\$0.00
2300 Engineering: 0.00 sta	\$0.00
2400 Minor Concrete:	\$0.00
2500 Gabions:	\$0.00
8000 Miscellaneous:	\$0.00
Mobilization: Const. \$69.55 Surf. \$0.00	\$69.55
Quarry Development:	\$0.00
Total: Notes:	\$3,365.09

Road Number: 27-12-15.10 C Road Name:

Section 200 Clearing and Grubbing:

Subtotal: \$0.00 Section 300 Excavation: Subgrade Compaction: 4 Sta/hr \$33.62/sta. x 9.0 sta = \$300.90 Blading without ditch: \$12.14/station x 8.95 stations = \$108.65Subgrade Construction Excavator - Large (2 CY) 20 hr x \$128.90/hr = \$2,578.00Subtotal: \$2,987.55 Section 400 Drainage: Subtotal: \$0.00 Section 500 Renovation: Subtotal: \$0.00 Section 700-1200 Surfacing: Surfacing: Subtotal: \$0.00 Section 1300 Geotextiles: Subtotal: \$0.00 Section 1400 Slope Protection: Subtotal: \$0.00 Section 1800 Soil Stabilization: Dry Method with Mulch: $$540.65/acre \times 0.30 acres = 162.20 Includes Small Quantity Factor of 1.42 + Seed Cost: \$132.00/acre x 0.30 acres = \$39.60 + Fertilizer Cost: \$34.00/acre x 0.30 acres = \$10.20 + Mulch Cost: \$320.00/acre x 0.30 acres = \$96.00 Subtotal: \$308.00 Section 1900 Cattleguards: Subtotal: \$0.00 Section 2100 Roadside Brushing: Subtotal: \$0.00 Section 2300 Engineering: Subtotal: \$0.00 Mobilization: Construction - 1.33% of total Costs = \$69.55 Surfacing - 0.00% by rock volume = \$0.00 Subtotal: \$69.55 Quarry Development: Based on 0.00% of total rock volume

Subtotal:

Total: \$3,365.09

\$0.00

T.S. Contract Name: Steele 15 CT Sale Date: Road Number: 27-12-15.11 I Road Name: Road Improvement: 0.06 mi 16 ft Subgrade 2 ft ditch 6/30/2014	
200 Clearing and Grubbing: acres	\$0.00
	,
300 Excavation:	\$0.00
400 Drainage: Culvert: 0 lf DownSpout: 0 lf PolyPipe: 0 lf	\$0.00
500 Renovation: Blading 0.06 mi	\$1,849.97
700-1200 Surfacing:	\$4,993.50
1300 Geotextiles:	\$0.00
1400 Slope Protection:	\$0.00
1800 Soil Stabilization: 0.2 acres	\$205.33
1900 Cattleguards:	\$0.00
2100 RoadSide Brushing: 0.0 acres	\$0.00
2300 Engineering: 0.00 sta	\$0.00
2400 Minor Concrete:	\$0.00
2500 Gabions:	\$0.00
8000 Miscellaneous:	\$0.00
Mobilization: Const. \$148.75 Surf. \$0.00	\$148.75
Quarry Development:	\$0.00
Total: Notes:	\$7,197.54
Overtities shows and actimates only and not may items	

Road Number: 27-12-15.11 I Road Name:

Section 200 Clearing and Grubbing:

Subtotal: \$0.00

Section 300 Excavation:

Subtotal: \$0.00

Section 400 Drainage:

Subtotal: \$0.00

Section 500 Renovation:

Blading: $$720.50/mi \times 0.06 mi = 43.23 Compaction: $$403.47/mi \times 0.06 mi = 24.21

Subgrade Improvement

Excavator - Large (2 CY) 10 hr x \$128.90/hr = \$1,289.00

Waterline removal / disposal

Labor and equipment 1 LS x \$100.00/LS = \$100.00

Old Subgrade Scarificationa

Tractor: D7 with rippers 1 hr x \$163.53/hr = \$163.53

"Old Subgrade" Riprap Barrier

Riprap in place 10 CY x \$23.00/CY = \$230.00

Subtotal: \$1,849.97

Section 700-1200 Surfacing:

Cr. Aggregate Quarry Name: Jarvis 3" Base

Length TopW BotW Depth CWid #TOs Width F.W.L Taper Other

0.06mi 12ft 12in 7% 16ft

Rock Volume = 221 lcy

Purchase Price / Royalty: $$10.00/lcy \times 221 lcy = $2,210.00$

Processing: $$0.90/lcy \times 221 lcy = 198.90

Compaction: $$1.34/1cy \times 221 1cy = 296.14

Basic Rock Haul cost: \$0.74/lcy x 221 lcy = \$163.54

Rock Haul -15% grades: \$1.10/lcy-mi x 221 lcy x 0.05 mi= \$12.16

Rock Haul St& Co Roads: \$0.49/lcy-mi x 221 lcy x 18.00 mi= \$1,949.22

Basic Water Haul cost: $$0.60/lcy \times 221 lcy = 132.60

Water Haul -15% grades: \$0.14/lcy-mi x 221 lcy x 1.00 mi= \$30.94

Subtotal: \$4,993.50

Section 1300 Geotextiles:

Subtotal: \$0.00

Section 1800 Soil Stabilization:

Dry Method with Mulch: $$540.65/acre \times 0.20 acres = 108.13

Includes Small Quantity Factor of 1.42

+ Seed Cost: \$132.00/acre x 0.20 acres = \$26.40

+ Fertilizer Cost: \$34.00/acre x 0.20 acres = \$6.80

+ Mulch Cost: \$320.00/acre x 0.20 acres = \$64.00

Subtotal: \$205.33

Mobilization:

Construction - 2.85% of total Costs = \$148.75

Surfacing - 2.70% by rock volume = \$0.00

Subtotal: \$148.75

Quarry Development:

Based on 2.70% of total rock volume

Subtotal: \$0.00

Total: \$7,197.54

T.S. Contract Name: Steele 15 CT Sale Date: Road Number: 27-12-15.3 C Road Name: Road Construction: 0.11 mi 16 ft Subgrade 2 ft ditch 6/30/2014	
200 Clearing and Grubbing: acres	. \$0.00
300 Excavation:	. \$2,219.52
400 Drainage: Culvert: 0 lf DownSpout: 0 lf PolyPipe: 0 lf	. \$880.00
500 Renovation:	. \$0.00
700-1200 Surfacing:	. \$10,845.60
1300 Geotextiles:	. \$0.00
1400 Slope Protection:	. \$0.00
1800 Soil Stabilization: 0.1 acres	. \$102.67
1900 Cattleguards:	. \$0.00
2100 RoadSide Brushing: 0.0 acres	. \$0.00
2300 Engineering: 0.00 sta	. \$0.00
2400 Minor Concrete:	. \$0.00
2500 Gabions:	. \$0.00
8000 Miscellaneous:	. \$0.00
Mobilization: Const. \$296.45 Surf. \$0.00	. \$296.45
Quarry Development:	. \$0.00
Total:	\$14,344.23

Notes:

Road Number: 27-12-15.3 C Road Name:

Section 200 Clearing and Grubbing:

Subtotal: \$0.00

Section 300 Excavation:

Subgrade Compaction: 4 Sta/hr \$33.62/sta. x 6.0 sta = \$200.04 Blading with ditch: \$14.45/station x 5.95 stations = \$85.98

Subgrade Excavation

Excavator - Large (2 CY) 15 hr x \$128.90/hr = \$1,933.50

Subtotal: \$2,219.52

Section 400 Drainage:

0+00 / Exist Ditchline

12"x40' Aluminized CMP 40 LF x \$22.00/LF = \$880.00

Subtotal: \$880.00

Section 500 Renovation:

Subtotal: \$0.00

Section 700-1200 Surfacing:

Cr. Aggregate Quarry Name: Jarvis 3" Base

 $\frac{\text{Length}}{\text{0.11mi}} \ \frac{\text{TopW}}{\text{12ft}} \qquad \frac{\text{BotW}}{\text{16ft}} \qquad \frac{\text{Depth}}{\text{12in}} \ \frac{\text{CWid}}{\text{5\%}} \qquad \frac{\#\text{TOs}}{1} \ \frac{\text{Width}}{\text{10ft}} \ \frac{\text{F.W.L}}{\text{50ft}} \ \frac{\text{Taper}}{\text{50ft}} \qquad \frac{\text{Other}}{\text{10ft}}$

Rock Volume = 480 lcy

Purchase Price / Royalty: $$10.00/lcy \times 480 lcy = $4,800.00$

Processing: $$0.90/lcy \times 480 lcy = 432.00

Compaction: $$1.34/lcy \times 480 lcy = 643.20

Basic Rock Haul cost: $$0.74/lcy \times 480 lcy = 355.20

Rock Haul -15% grades: \$1.10/lcy-mi x 480 lcy x 0.05 mi= \$26.40

Rock Haul St& Co Roads: \$0.49/lcy-mi x 480 lcy x 18.00 mi= \$4,233.60

Basic Water Haul cost: $$0.60/lcy \times 480 lcy = 288.00

Water Haul -15% grades: $\$0.14/lcy-mi \times 480 lcy \times 1.00 mi = \67.20

Subtotal: \$10,845.60

Section 1300 Geotextiles:

Subtotal: \$0.00

Section 1400 Slope Protection:

Subtotal: \$0.00

Section 1800 Soil Stabilization:

Dry Method with Mulch: $$540.65/acre \times 0.10 acres = 54.07

Includes Small Quantity Factor of 1.42

+ Seed Cost: \$132.00/acre x 0.10 acres = \$13.20

+ Fertilizer Cost: \$34.00/acre x 0.10 acres = \$3.40

+ Mulch Cost: \$320.00/acre x 0.10 acres = \$32.00

Subtotal: \$102.67

Section 1900 Cattleguards:

Subtotal: \$0.00

Section 2100 Roadside Brushing:

Subtotal: \$0.00

Section 2300 Engineering:

Subtotal: \$0.00

Section 2400 Minor Concrete:

Road Number: 27-12-15.3 C Continued

Subtotal: \$0.00

Section 2500 Gabions:

Subtotal: \$0.00

Section 8000 Miscellaneous:

Subtotal: \$0.00

Mobilization:

Construction - 5.67% of total Costs = \$296.45

Surfacing - 5.86% by rock volume = \$0.00

Subtotal: \$296.45

Quarry Development:

Based on 5.86% of total rock volume

Subtotal: \$0.00

Total: \$14,344.23

T.S. Contract Name: Steele 15 CT Sale Date: Road Number: 27-12-15.3 I Road Name: Road Improvement: 0.48 mi 16 ft Subgrade 0 ft ditch 6/30/2014	
Road Implovement. 0.40 ml 10 it Subglade 0 it ditti 0/30/2014	
200 Clearing and Grubbing: acres	\$0.00
300 Excavation:	\$0.00
400 Drainage: Culvert: 0 lf DownSpout: 0 lf PolyPipe: 0 lf	\$0.00
500 Renovation:	\$4,775.10
700-1200 Surfacing:	\$45,694.26
1300 Geotextiles:	\$0.00
1400 Slope Protection:	\$0.00
1800 Soil Stabilization: 0.6 acres	\$615.99
1900 Cattleguards:	\$0.00
2100 RoadSide Brushing: 0.0 acres	\$0.00
2300 Engineering: 0.00 sta	\$0.00
2400 Minor Concrete:	\$0.00
2500 Gabions:	\$0.00
8000 Miscellaneous:	\$0.00
Mobilization: Const. \$1,078.04 Surf. \$0.00	\$1,078.04
Quarry Development:	\$0.00
Total:	\$52,163.39
Notes:	

Road Number: 27-12-15.3 I Road Name:

Section 200 Clearing and Grubbing:

Subtotal: \$0.00

Section 300 Excavation:

Subtotal: \$0.00

Section 400 Drainage:

Subtotal: \$0.00

Section 500 Renovation:

Blading w/o Ditches: $$446.73/mi \times 0.48 mi = 214.43

Compaction: $$403.47/mi \times 0.48 mi = 193.67

Subgrade Improvement

Excavator - Large (2 CY) 30 hr x \$128.90/hr = \$3,867.00

Waterline removal / disposal

Labor and equipment 1 LS x \$500.00/LS = \$500.00

Subtotal: \$4,775.10

Section 700-1200 Surfacing:

Cr. Aggregate Quarry Name: Jarvis 3" Base

0.48mi 12ft 16ft 12in 5% 3 10ft 50ft 50ft

Rock Volume = 1,998 lcy

Purchase Price / Royalty: \$10.00/lcy x 1,998 lcy = \$19,980.00

Processing: $$0.90/lcy \times 1,998 lcy = $1,798.20$

Compaction: $$1.34/lcy \times 1,998 lcy = $2,677.32$

Basic Rock Haul cost: $$0.74/lcy \times 1,998 lcy = $1,478.52$

Rock Haul -15% grades: \$1.10/lcy-mi x 1,998 lcy x 0.30 mi= \$659.34

Rock Haul St& Co Roads: \$0.49/lcy-mi x 1,998 lcy x 18.00 mi= \$17,622.36

Basic Water Haul cost: $$0.60/lcy \times 1,998 lcy = $1,198.80$

Water Haul -15% grades: \$0.14/lcy-mi x 1,998 lcy x 1.00 mi= \$279.72

Subtotal: \$45,694.26

Section 1300 Geotextiles:

Subtotal: \$0.00

Section 1400 Slope Protection:

Subtotal: \$0.00

Section 1800 Soil Stabilization:

Dry Method with Mulch: $$540.65/acre \times 0.60 acres = 324.39

Includes Small Quantity Factor of 1.42

+ Seed Cost: \$132.00/acre x 0.60 acres = \$79.20

+ Fertilizer Cost: \$34.00/acre x 0.60 acres = \$20.40

+ Mulch Cost: \$320.00/acre x 0.60 acres = \$192.00

Subtotal: \$615.99

Section 1900 Cattleguards:

Subtotal: \$0.00

Section 2100 Roadside Brushing:

Subtotal: \$0.00

Section 2300 Engineering:

Subtotal: \$0.00

Section 2400 Minor Concrete:

Road Number: 27-12-15.3 I Continued

Subtotal: \$0.00

Section 2500 Gabions:

Subtotal: \$0.00

Section 8000 Miscellaneous:

Subtotal: \$0.00

Mobilization:

Construction - 20.62% of total Costs = \$1,078.04

Surfacing - 24.39% by rock volume = \$0.00

Subtotal: \$1,078.04

Quarry Development:

Based on 24.39% of total rock volume

Subtotal: \$0.00

Total: \$52,163.39

T.S. Contract Name: Steele 15 CT Sale Date: Road Number: 27-12-15.3 R Road Name: Road Renovation: 0.09 mi 12 ft Subgrade 0 ft ditch 6/30/2014	
200 Clearing and Grubbing: acres	\$0.00
300 Excavation:	\$0.00
400 Drainage: Culvert: 0 lf DownSpout: 0 lf PolyPipe: 0 lf	\$0.00
500 Renovation:	\$1,291.77
700-1200 Surfacing:	\$0.00
1300 Geotextiles:	\$0.00
1400 Slope Protection:	\$0.00
1800 Soil Stabilization: 0.2 acres	\$205.33
1900 Cattleguards:	\$0.00
2100 RoadSide Brushing: 0.0 acres	\$0.00
2300 Engineering: 0.00 sta	\$0.00
2400 Minor Concrete:	\$0.00
2500 Gabions:	\$0.00
8000 Miscellaneous:	\$0.00
Mobilization: Const. \$31.59 Surf. \$0.00	\$31.59
Quarry Development:	\$0.00
Total: Notes:	\$1,528.69

Road Number: 27-12-15.3 R Road Name:

Section 200 Clearing and Grubbing:

Subtotal: \$0.00

Section 300 Excavation:

Subtotal: \$0.00

Section 400 Drainage:

Subtotal: \$0.00

Section 500 Renovation:

Compaction: $$403.47/mi \times 0.09 mi = 36.31 Clean Culverts: $$334.17/mi \times 0.09 mi = 30.08

Subgrade Renovation

Excavator - Large (2 CY) 8 hr x \$128.90/hr = \$1,031.20

43+20 Tanktrap

Excavator -Small (1.5 CY) 2 hr x \$97.09/hr = \$194.18

Subtotal: \$1,291.77

Section 700-1200 Surfacing:

Surfacing:

Subtotal: \$0.00

Section 1300 Geotextiles:

Subtotal: \$0.00

Section 1400 Slope Protection:

Subtotal: \$0.00

Section 1800 Soil Stabilization:

Dry Method with Mulch: $$540.65/acre \times 0.20 acres = 108.13

Includes Small Quantity Factor of 1.42

+ Seed Cost: \$132.00/acre x 0.20 acres = \$26.40

+ Fertilizer Cost: \$34.00/acre x 0.20 acres = \$6.80

+ Mulch Cost: \$320.00/acre x 0.20 acres = \$64.00

Subtotal: \$205.33

Subtotal: \$0.00

Mobilization:

Construction - 0.60% of total Costs = \$31.59

Surfacing - 0.00% by rock volume = \$0.00

Subtotal: \$31.59

Quarry Development:

Based on 0.00% of total rock volume

Subtotal: \$0.00

Total: \$1,528.69

T.S. Contract Name: Steele 15 CT Sale Date: Road Number: 27-12-15.4 C Road Name: Road Construction: 0.32 mi 16 ft Subgrade 0 ft ditch 6/30/2014	
Road Constitution. 0.32 Mil 16 It Subgrade 0 It ditti 6/30/2014	
200 Clearing and Grubbing: acres	\$0.00
300 Excavation:	\$5 , 924.77
400 Drainage: Culvert: 0 lf DownSpout: 0 lf PolyPipe: 0 lf	\$0.00
500 Renovation:	\$0.00
700-1200 Surfacing:	\$33,614.85
1300 Geotextiles:	\$0.00
1400 Slope Protection:	\$0.00
1800 Soil Stabilization: 0.6 acres	\$615.99
1900 Cattleguards:	\$0.00
2100 RoadSide Brushing: 0.0 acres	\$0.00
2300 Engineering: 0.00 sta	\$0.00
2400 Minor Concrete:	\$0.00
2500 Gabions:	\$0.00
8000 Miscellaneous:	\$0.00
Mobilization: Const. \$847.39 Surf. \$0.00	\$847.39
Quarry Development:	\$0.00
Total: Notes:	\$41,003.00
Notes.	

Road Construction Worksheet Road Number: 27-12-15.4 C Road Name: Section 200 Clearing and Grubbing: Subtotal: \$0.00 Section 300 Excavation: Subgrade Compaction: 4 Sta/hr $$33.62/sta. \times 16.8 sta = 564.82 Blading without ditch: \$12.14/station x 16.80 stations = \$203.95Subgrade Construction Excavator - Large (2 CY) 40 hr x \$128.90/hr = \$5,156.00Subtotal: \$5,924.77 Section 400 Drainage: Subtotal: \$0.00 Section 500 Renovation: Subtotal: \$0.00 Section 700-1200 Surfacing: Cr. Aggregate Quarry Name: Jarvis 3" Base BotW Length TopW Depth CWid #TOs Width F.W.L Taper Other 0.32mi 12ft 16ft 12in 5% 2 10ft 50ft 50ft Rock Volume = 1,315 lcy Purchase Price / Royalty: $$10.00/lcy \times 1,315 lcy = $13,150.00$ Processing: $$0.90/lcy \times 1,315 lcy = $1,183.50$ Compaction: $$1.34/lcy \times 1,315 lcy = $1,762.10$ Basic Rock Haul cost: $$0.74/lcy \times 1,315 lcy = 973.10 Rock Haul -15% grades: \$1.10/lcy-mi x 1,315 lcy x 0.30 mi= \$433.95 Rock Haul St& Co Roads: \$0.49/lcy-mi x 1,315 lcy x 18.00 mi= \$11,598.30 Basic Water Haul cost: $$0.60/lcy \times 1,315 lcy = 789.00 Water Haul -15% grades: \$0.14/lcy-mi x 1,315 lcy x 1.00 mi= \$184.10 Cr Aggregate Quarry Name: Jarvis 3" Landing Comment: 13+75 "Y" Jct Length TopW BotW Depth CWid #TOs Width F.W.L Taper Other 10 lcv Rock Volume = 10 lcy Purchase Price / Royalty: \$10.00/lcy x 10 lcy = \$100.00 Processing: $$0.90/lcy \times 10 lcy = 9.00 Compaction: $$1.34/lcy \times 10 lcy = 13.40 Basic Rock Haul cost: $$0.74/lcy \times 10 lcy = 7.40 Rock Haul -15% grades: \$1.10/lcy-mi x 10 lcy x 0.30 mi= \$3.30 Rock Haul St& Co Roads: \$0.49/lcy-mi x 10 lcy x 18.00 mi= \$88.20 Cr Aggregate Quarry Name: Jarvis 3" Landing Comment: 13+75 Ldg and approach Length TopW BotW Depth CWid #TOs Width F.W.L Taper Other 100 lcy Rock Volume = 100 lcyPurchase Price / Royalty: $$10.00/lcy \times 100 lcy = $1,000.00$ Processing: $$0.90/lcy \times 100 lcy = 90.00 Compaction: $$1.34/lcy \times 100 lcy = 134.00 Basic Rock Haul cost: $$0.74/lcy \times 100 lcy = 74.00 Rock Haul -15% grades: \$1.10/lcy-mi x 100 lcy x 0.30 mi= \$33.00 Rock Haul St& Co Roads: \$0.49/lcy-mi x 100 lcy x 18.00 mi= \$882.00 Cr Aggregate Quarry Name: Jarvis 3" Landing Comment: 16+80 End Ldg

#TOs Width F.W.L Taper

50 lcy

Rock Volume = 50 lcy Purchase Price / Royalty: $$10.00/lcy \times 50 lcy = 500.00

Depth CWid

BotW

Length TopW

Road Number: 27-12-15.4 C Continued

Processing: $$0.90/1 \text{cy} \times 50 \text{ lcy} = 45.00 Compaction: $$1.34/1 \text{cy} \times 50 \text{ lcy} = 67.00

Basic Rock Haul cost: $$0.74/lcy \times 50 lcy = 37.00

Rock Haul -15% grades: \$1.10/lcy-mi x 50 lcy x 0.30 mi= \$16.50 Rock Haul St& Co Roads: \$0.49/lcy-mi x 50 lcy x 18.00 mi= \$441.00

Subtotal: \$33,614.85

Section 1300 Geotextiles:

Subtotal: \$0.00

Section 1400 Slope Protection:

Subtotal: \$0.00

Section 1800 Soil Stabilization:

Dry Method with Mulch: $$540.65/acre \times 0.60 acres = 324.39

Includes Small Quantity Factor of 1.42

+ Seed Cost: \$132.00/acre x 0.60 acres = \$79.20

+ Fertilizer Cost: \$34.00/acre x 0.60 acres = \$20.40

+ Mulch Cost: \$320.00/acre x 0.60 acres = \$192.00

Subtotal: \$615.99

Section 1900 Cattleguards:

Subtotal: \$0.00

Section 2100 Roadside Brushing:

Subtotal: \$0.00

Section 2300 Engineering:

Subtotal: \$0.00

Section 2400 Minor Concrete:

Subtotal: \$0.00

Section 2500 Gabions:

Subtotal: \$0.00

Section 8000 Miscellaneous:

Subtotal: \$0.00

Mobilization:

Construction - 16.21% of total Costs = \$847.39

Surfacing - 18.01% by rock volume = \$0.00

Subtotal: \$847.39

Quarry Development:

Based on 18.01% of total rock volume

Subtotal: \$0.00

Total: \$41,003.00

T.S. Contract Name: Steele 15 CT Sale Date: Road Number: 27-12-15.5 C Road Name:	
Road Construction: 0.17 mi 12 ft Subgrade 0 ft ditch 6/30/2014	
200 Clearing and Grubbing: acres	\$0.00
300 Excavation:	\$3,638.92
400 Drainage: Culvert: 0 lf DownSpout: 0 lf PolyPipe: 0 lf	\$0.00
500 Renovation:	\$0.00
700-1200 Surfacing:	\$0.00
1300 Geotextiles:	\$0.00
1400 Slope Protection:	\$0.00
1800 Soil Stabilization: 0.2 acres	\$205.33
1900 Cattleguards:	\$0.00
2100 RoadSide Brushing: 0.0 acres	\$0.00
2300 Engineering: 0.00 sta	\$0.00
2400 Minor Concrete:	\$0.00
2500 Gabions:	\$0.00
8000 Miscellaneous:	\$0.00
Mobilization: Const. \$81.12 Surf. \$0.00	\$81.12
Quarry Development:	\$0.00
Total:	\$3,925.37
Notes:	

Road Number: 27-12-15.5 C Road Name:

Section 200 Clearing and Grubbing:

Subtotal: \$0.00

Section 300 Excavation:

Subgrade Compaction: 4 Sta/hr $$33.62/sta. \times 9.1 sta = 305.94 Blading without ditch: $$12.14/station \times 9.10 stations = 110.47

Subgrade Construction

Excavator - Large (2 CY) 25 hr x \$128.90/hr = \$3,222.50

Subtotal: \$3,638.92

Section 400 Drainage:

Subtotal: \$0.00

Section 500 Renovation:

Subtotal: \$0.00

Section 700-1200 Surfacing:

Surfacing:

Subtotal: \$0.00

Section 1300 Geotextiles:

Subtotal: \$0.00

Section 1400 Slope Protection:

Subtotal: \$0.00

Section 1800 Soil Stabilization:

Dry Method with Mulch: \$540.65/acre x 0.20 acres = \$108.13

Includes Small Quantity Factor of 1.42

+ Seed Cost: \$132.00/acre x 0.20 acres = \$26.40

+ Fertilizer Cost: \$34.00/acre x 0.20 acres = \$6.80

+ Mulch Cost: \$320.00/acre x 0.20 acres = \$64.00

Subtotal: \$205.33

Section 1900 Cattleguards:

Subtotal: \$0.00

Section 2100 Roadside Brushing:

Subtotal: \$0.00

Mobilization:

Construction - 1.55% of total Costs = \$81.12

Surfacing - 0.00% by rock volume = \$0.00

Subtotal: \$81.12

Quarry Development:

Based on 0.00% of total rock volume

Subtotal: \$0.00

Total: \$3,925.37

T.S. Contract Name: Steele 15 CT Sale Date: Road Number: 27-12-15.6 C Road Name: Road Construction: 0.16 mi 16 ft Subgrade 0 ft ditch 6/30/2014	
200 Clearing and Grubbing: acres	\$0.00
300 Excavation:	\$3,604.60
400 Drainage: Culvert: 0 lf DownSpout: 0 lf PolyPipe: 0 lf	\$0.00
500 Renovation:	\$0.00
700-1200 Surfacing:	\$17,038.15
1300 Geotextiles:	\$0.00
1400 Slope Protection:	\$0.00
1800 Soil Stabilization: 0.3 acres	\$308.00
1900 Cattleguards:	\$0.00
2100 RoadSide Brushing: 0.0 acres	\$0.00
2300 Engineering: 0.00 sta	\$0.00
2400 Minor Concrete:	\$0.00
2500 Gabions:	\$0.00
8000 Miscellaneous:	\$0.00
Mobilization: Const. \$442.12 Surf. \$0.00	\$442.12
Quarry Development:	\$0.00
Total: Notes:	\$21,392.86

Road Construction Worksheet Road Number: 27-12-15.6 C Road Name: Section 200 Clearing and Grubbing: Subtotal: \$0.00 Section 300 Excavation: Subgrade Compaction: 4 Sta/hr $$33.62/sta. \times 8.4 sta = 280.73 Blading without ditch: \$12.14/station x 8.35 stations = \$101.37Subgrade Construction Excavator - Large (2 CY) 25 hr x \$128.90/hr = \$3,222.50Subtotal: \$3,604.60 Section 400 Drainage: Subtotal: \$0.00 Section 500 Renovation: Subtotal: \$0.00 Section 700-1200 Surfacing: Cr. Aggregate Quarry Name: Jarvis 3" Base BotW Depth CWid #TOs Width F.W.L Taper 16ft 12in 5% Length TopW Other 0.16mi 12ft Rock Volume = 605 lcyPurchase Price / Royalty: $$10.00/lcy \times 605 lcy = $6,050.00$ Processing: $$0.90/1cy \times 605 1cy = 544.50 Compaction: $$1.34/lcy \times 605 lcy = 810.70 Basic Rock Haul cost: $$0.74/lcy \times 605 lcy = 447.70 Rock Haul -15% grades: \$1.10/lcy-mi x 605 lcy x 0.30 mi= \$199.65 Rock Haul St& Co Roads: \$0.49/lcy-mi x 605 lcy x 18.00 mi= \$5,336.10 Basic Water Haul cost: $$0.60/lcy \times 605 lcy = 363.00 Water Haul -15% grades: $\$0.14/lcy-mi \times 605 lcy \times 1.00 mi= \84.70 Cr Aggregate Quarry Name: Jarvis 3" Landing Comment: 0+00 "Y" Juction Length TopW BotW Depth CWid #TOs Width F.W.L Taper Other 10 lcv Rock Volume = 10 lcy Purchase Price / Royalty: \$10.00/lcy x 10 lcy = \$100.00 Processing: $$0.90/lcy \times 10 lcy = 9.00 Compaction: $$1.34/lcy \times 10 lcy = 13.40 Basic Rock Haul cost: $$0.74/lcy \times 10 lcy = 7.40 Rock Haul -15% grades: \$1.10/lcy-mi x 10 lcy x 0.30 mi= \$3.30 Rock Haul St& Co Roads: \$0.49/lcy-mi x 10 lcy x 18.00 mi= \$88.20 Basic Water Haul cost: $$0.60/lcy \times 10 lcy = 6.00 Water Haul -15% grades: $\$0.14/lcy-mi \times 10 lcy \times 1.00 mi= \1.40 Cr Aggregate Quarry Name: Jarvis 3" Landing Comment: 7+75 Ldg and approach Length TopW BotW Depth CWid #TOs Width F.W.L Taper Other 70 lcy Rock Volume = 70 lcyPurchase Price / Royalty: $$10.00/lcy \times 70 lcy = 700.00 Processing: $$0.90/lcy \times 70 lcy = 63.00 Compaction: $$1.34/lcy \times 70 lcy = 93.80 Basic Rock Haul cost: $$0.74/lcy \times 70 lcy = 51.80

Cr Aggregate Quarry Name: Jarvis 3" Landing

Basic Water Haul cost: $$0.60/lcy \times 70 lcy = 42.00

Rock Haul -15% grades: $$1.10/lcy-mi \times 70 lcy \times 0.30 mi= 23.10 Rock Haul St& Co Roads: $$0.49/lcy-mi \times 70 lcy \times 18.00 mi= 617.40

Water Haul -15% grades: \$0.14/lcy-mi x 70 lcy x 1.00 mi= \$9.80

Road Number: 27-12-15.6 C Continued

Comment: 8+35 End Ldg

<u>Length TopW</u> <u>BotW</u> <u>Depth CWid</u> <u>#TOs Width F.W.L Taper</u> <u>Other</u> 50 lcy

Rock Volume = 50 lcy

Purchase Price / Royalty: $$10.00/lcy \times 50 lcy = 500.00

Processing: $$0.90/lcy \times 50 lcy = 45.00 Compaction: $$1.34/lcy \times 50 lcy = 67.00

Basic Rock Haul cost: $$0.74/lcy \times 50 lcy = 37.00

Rock Haul -15% grades: $$1.10/lcy-mi \times 50 lcy \times 0.30 mi= 16.50 Rock Haul St& Co Roads: $$0.49/lcy-mi \times 50 lcy \times 18.00 mi= 441.00

Basic Water Haul cost: $$0.60/lcy \times 50 lcy = 30.00

Water Haul -15% grades: \$0.14/lcy-mi x 50 lcy x 1.00 mi= \$7.00

Cr Aggregate Quarry Name: Jarvis 3" Landing

Comment: 6+45 TTA

<u>Length TopW</u> <u>BotW</u> <u>Depth CWid</u> <u>#TOs Width F.W.L Taper</u> <u>Other</u> 10 lcy

Rock Volume = 10 lcy

Purchase Price / Royalty: \$10.00/lcy x 10 lcy = \$100.00

Processing: $$0.90/lcy \times 10 lcy = 9.00 Compaction: $$1.34/lcy \times 10 lcy = 13.40

Basic Rock Haul cost: $$0.74/lcy \times 10 lcy = 7.40

Rock Haul -15% grades: \$1.10/lcy-mi x 10 lcy x 0.30 mi= \$3.30 Rock Haul St& Co Roads: \$0.49/lcy-mi x 10 lcy x 18.00 mi= \$88.20

Basic Water Haul cost: $$0.60/lcy \times 10 lcy = 6.00

Water Haul -15% grades: \$0.14/lcy-mi x 10 lcy x 1.00 mi= \$1.40

Subtotal: \$17,038.15

Section 1300 Geotextiles:

Subtotal: \$0.00

Section 1400 Slope Protection:

Subtotal: \$0.00

Section 1800 Soil Stabilization:

Dry Method with Mulch: $$540.65/acre \times 0.30 acres = 162.20

Includes Small Quantity Factor of 1.42

+ Seed Cost: \$132.00/acre x 0.30 acres = \$39.60

+ Fertilizer Cost: \$34.00/acre x 0.30 acres = \$10.20

+ Mulch Cost: \$320.00/acre x 0.30 acres = \$96.00

Subtotal: \$308.00

Section 1900 Cattleguards:

Subtotal: \$0.00

Section 2100 Roadside Brushing:

Subtotal: \$0.00

Mobilization:

Construction - 8.46% of total Costs = \$442.12

Surfacing - 9.09% by rock volume = \$0.00

Subtotal: \$442.12

Quarry Development:

Based on 9.09% of total rock volume

Subtotal: \$0.00

Total: \$21,392.86

T.S. Contract Name: Steele 15 CT Sale Date: Road Number: 27-12-15.7 C Road Name: Road Construction: 0.45 mi 16 ft Subgrade 0 ft ditch 6/30/2014	
200 Clearing and Grubbing: acres	\$0.00
300 Excavation:	\$7 , 524.94
400 Drainage: Culvert: 0 lf DownSpout: 0 lf PolyPipe: 0 lf	\$0.00
500 Renovation:	\$0.00
700-1200 Surfacing:	\$43,725.14
1300 Geotextiles:	\$0.00
1400 Slope Protection:	\$0.00
1800 Soil Stabilization: 0.7 acres	\$718.66
1900 Cattleguards:	\$0.00
2100 RoadSide Brushing: 0.0 acres	\$0.00
2300 Engineering: 0.00 sta	\$0.00
2400 Minor Concrete:	\$0.00
2500 Gabions:	\$0.00
8000 Miscellaneous:	\$0.00
Mobilization: Const. \$1,096.68 Surf. \$0.00	\$1,096.68
Quarry Development:	\$0.00
Total:	\$53,065.41
Quantities shown are estimates only and not pay items.	

Road Number: 27-12-15.7 C Road Name: Section 200 Clearing and Grubbing:

Subtotal: \$0.00

Section 300 Excavation:

Subgrade Compaction: 4 Sta/hr $$33.62/sta. \times 23.6 sta = 793.43 Blading without ditch: $$12.14/station \times 23.60 stations = 286.50

Subgrade Construction

Excavator - Large (2 CY) 50 hr x \$128.90/hr = \$6,445.00

Subtotal: \$7,524.94

Section 400 Drainage:

Subtotal: \$0.00

Section 500 Renovation:

Subtotal: \$0.00

Section 700-1200 Surfacing:

Cr. Aggregate Quarry Name: Jarvis 3" Base

Rock Volume = 1,807 lcy

Purchase Price / Royalty: $$10.00/lcy \times 1,807 lcy = $18,070.00$

Processing: $\$0.90/\text{lcy} \times 1,807 \text{ lcy} = \$1,626.30$

Compaction: $$1.34/lcy \times 1,807 lcy = $2,421.38$

Basic Rock Haul cost: $$0.74/lcy \times 1,807 lcy = $1,337.18$ Rock Haul -15% grades: $$1.10/lcy-mi \times 1,807 lcy \times 0.80 mi= $1,590.16$

Rock Haul St& Co Roads: \$0.49/lcy-mi x 1,807 lcy x 18.00 mi= \$15,937.74

Basic Water Haul cost: $$0.60/lcy \times 1,807 lcy = $1,084.20$

Water Haul -15% grades: \$0.14/lcy-mi x 1,807 lcy x 1.00 mi= \$252.98

Cr Aggregate Quarry Name: Jarvis 3" Landing

Comment: 22+60 TTA

<u>Length TopW</u> <u>BotW</u> <u>Depth CWid</u> <u>#TOs Width F.W.L Taper</u> <u>Other</u> 10 lcy

Rock Volume = 10 lcy

Purchase Price / Royalty: $$10.00/lcy \times 10 lcy = 100.00

Processing: $$0.90/lcy \times 10 lcy = 9.00

Compaction: $$1.34/lcy \times 10 lcy = 13.40

Basic Rock Haul cost: $$0.74/lcy \times 10 lcy = 7.40

Rock Haul -15% grades: \$1.10/lcy-mi x 10 lcy x 0.80 mi= \$8.80

Rock Haul St& Co Roads: \$0.49/lcy-mi x 10 lcy x 18.00 mi= \$88.20

Basic Water Haul cost: $$0.60/lcy \times 10 lcy = 6.00

Water Haul -15% grades: \$0.14/lcy-mi x 10 lcy x 1.00 mi= \$1.40

Cr Aggregate Quarry Name: Jarvis 3" Landing

Comment: 23+60 End Ldg

<u>Length TopW</u> <u>BotW</u> <u>Depth CWid</u> <u>#TOs Width F.W.L Taper</u> <u>Other</u> 50 lcy

Rock Volume = 50 lcy

Purchase Price / Royalty: $$10.00/lcy \times 50 lcy = 500.00

Processing: $$0.90/lcy \times 50 lcy = 45.00

Compaction: $$1.34/lcy \times 50 lcy = 67.00

Basic Rock Haul cost: $$0.74/lcy \times 50 lcy = 37.00

Rock Haul -15% grades: \$1.10/lcy-mi x 50 lcy x 0.80 mi= \$44.00

Rock Haul St& Co Roads: \$0.49/lcy-mi x 50 lcy x 18.00 mi= \$441.00

Basic Water Haul cost: $$0.60/lcy \times 50 lcy = 30.00

Water Haul -15% grades: \$0.14/lcy-mi x 50 lcy x 1.00 mi= \$7.00

Subtotal: \$43,725.14

Road Number: 27-12-15.7 C Continued

Section 1300 Geotextiles:

Subtotal: \$0.00

Section 1400 Slope Protection:

Subtotal: \$0.00

Section 1800 Soil Stabilization:

Dry Method with Mulch: $$540.65/acre \times 0.70 acres = 378.46

Includes Small Quantity Factor of 1.42

+ Seed Cost: \$132.00/acre x 0.70 acres = \$92.40

+ Fertilizer Cost: \$34.00/acre x 0.70 acres = \$23.80

+ Mulch Cost: \$320.00/acre x 0.70 acres = \$224.00

Subtotal: \$718.66

Section 1900 Cattleguards:

Subtotal: \$0.00

Section 2100 Roadside Brushing:

Subtotal: \$0.00

Section 2300 Engineering:

Subtotal: \$0.00

Section 2400 Minor Concrete:

Subtotal: \$0.00

Section 2500 Gabions:

Subtotal: \$0.00

Section 8000 Miscellaneous:

Subtotal: \$0.00

Mobilization:

Construction - 20.98% of total Costs = \$1,096.68

Surfacing - 22.79% by rock volume = \$0.00

Subtotal: \$1,096.68

Quarry Development:

Based on 22.79% of total rock volume

Subtotal: \$0.00

Total: \$53,065.41

T.S. Contract Name: Steele 15 CT Sale Date: Road Number: 27-12-15.8 C Road Name:	
Road Construction: 0.18 mi 12 ft Subgrade 0 ft ditch 6/30/2014	
200 Clearing and Grubbing: acres	\$0.00
300 Excavation:	\$3,648.07
400 Drainage: Culvert: 0 lf DownSpout: 0 lf PolyPipe: 0 lf	\$0.00
500 Renovation:	\$0.00
700-1200 Surfacing:	\$0.00
1300 Geotextiles:	\$0.00
1400 Slope Protection:	\$0.00
1800 Soil Stabilization: 0.3 acres	\$308.00
1900 Cattleguards:	\$0.00
2100 RoadSide Brushing: 0.0 acres	\$0.00
2300 Engineering: 0.00 sta	\$0.00
2400 Minor Concrete:	\$0.00
2500 Gabions:	\$0.00
8000 Miscellaneous:	\$0.00
Mobilization: Const. \$83.48 Surf. \$0.00	\$83.48
Quarry Development:	\$0.00
Total:	\$4,039.55
Notes.	

Road Number: 27-12-15.8 C Road Name:

Section 200 Clearing and Grubbing:

Subtotal: \$0.00

Section 300 Excavation:

Subgrade Compaction: 4 Sta/hr $$33.62/sta. \times 9.3 sta = 312.67 Blading without ditch: $$12.14/station \times 9.30 stations = 112.90

Subgrade Construction

Excavator - Large (2 CY) 25 hr x \$128.90/hr = \$3,222.50

Subtotal: \$3,648.07

Section 400 Drainage:

Subtotal: \$0.00

Section 500 Renovation:

Subtotal: \$0.00

Section 700-1200 Surfacing:

Surfacing:

Subtotal: \$0.00

Section 1300 Geotextiles:

Subtotal: \$0.00

Section 1400 Slope Protection:

Subtotal: \$0.00

Section 1800 Soil Stabilization:

Dry Method with Mulch: $$540.65/acre \times 0.30 acres = 162.20

Includes Small Quantity Factor of 1.42

+ Seed Cost: \$132.00/acre x 0.30 acres = \$39.60

+ Fertilizer Cost: \$34.00/acre x 0.30 acres = \$10.20

+ Mulch Cost: \$320.00/acre x 0.30 acres = \$96.00

Subtotal: \$308.00

Section 1900 Cattleguards:

Subtotal: \$0.00

Section 2100 Roadside Brushing:

Subtotal: \$0.00

Mobilization:

Construction - 1.60% of total Costs = \$83.48

Surfacing - 0.00% by rock volume = \$0.00

Subtotal: \$83.48

Quarry Development:

Based on 0.00% of total rock volume

Subtotal: \$0.00

Total: \$4,039.55

ROAD CONSTRUCTION SUMMARY

T.S. Contract Name: Steele 15 CT Sale Date: Road Number: 27-12-15.9 C Road Name: Road Construction: 0.20 mi 16 ft Subgrade 0 ft ditch 6/30/2014	
200 Clearing and Grubbing: acres	\$0.00
300 Excavation:	\$4,361.21
400 Drainage:	\$0.00
500 Renovation:	\$0.00
700-1200 Surfacing:	\$19,812.26
1300 Geotextiles:	\$0.00
1400 Slope Protection:	\$0.00
1800 Soil Stabilization: 0.3 acres	\$308.00
1900 Cattleguards:	\$0.00
2100 RoadSide Brushing: 0.0 acres	\$0.00
2300 Engineering: 0.00 sta	\$0.00
2400 Minor Concrete:	\$0.00
2500 Gabions:	\$0.00
8000 Miscellaneous:	\$0.00
Mobilization: Const. \$516.63 Surf. \$0.00	\$516.63
Quarry Development:	\$0.00
Total: Notes:	\$24,998.09

Quantities shown are estimates only and not pay items. Surfacing Quantities shown are loose cubic yards.

Road Construction Worksheet Road Number: 27-12-15.9 C Road Name: Section 200 Clearing and Grubbing: Subtotal: \$0.00 Section 300 Excavation: Subgrade Compaction: $4 \text{ Sta/hr} \quad $33.62/\text{sta.} \times 10.8 \text{ sta} = 363.10 Blading without ditch: \$12.14/station x 10.80 stations = \$131.11 Subgrade Construction Excavator - Large (2 CY) 30 hr x \$128.90/hr = \$3,867.00Subtotal: \$4,361.21 Section 400 Drainage: Subtotal: \$0.00 Section 500 Renovation: Subtotal: \$0.00 Section 700-1200 Surfacing: Cr. Aggregate Quarry Name: Jarvis 3" Base BotW 16ft #TOs Width F.W.L Taper Length TopW Depth CWid Other 0.20mi 12ft 12in 5% Rock Volume = 782 lcyPurchase Price / Royalty: $$10.00/lcy \times 782 lcy = $7,820.00$ Processing: $$0.90/1cy \times 782 lcy = 703.80 Compaction: $$1.34/lcy \times 782 lcy = $1,047.88$ Basic Rock Haul cost: $$0.74/lcy \times 782 lcy = 578.68 Rock Haul -15% grades: \$1.10/lcy-mi x 782 lcy x 0.90 mi= \$774.18 Rock Haul St& Co Roads: \$0.49/lcy-mi x 782 lcy x 18.00 mi= \$6,897.24 Basic Water Haul cost: $$0.60/lcy \times 782 lcy = 469.20 Water Haul -15% grades: \$0.14/lcy-mi x 782 lcy x 1.00 mi= \$109.48 Cr Aggregate Quarry Name: Jarvis 3" Landing Comment: 9+00 TTA Length TopW BotW Depth CWid #TOs Width F.W.L Taper Other 10 lcv Rock Volume = 10 lcy Purchase Price / Royalty: \$10.00/lcy x 10 lcy = \$100.00 Processing: $$0.90/lcy \times 10 lcy = 9.00 Compaction: $$1.34/lcy \times 10 lcy = 13.40 Basic Rock Haul cost: $$0.74/lcy \times 10 lcy = 7.40 Rock Haul -15% grades: $$1.10/lcy-mi \times 10 lcy \times 0.90 mi= 9.90 Rock Haul St& Co Roads: \$0.49/lcy-mi x 10 lcy x 18.00 mi= \$88.20 Basic Water Haul cost: $$0.60/lcy \times 10 lcy = 6.00 Water Haul -15% grades: \$0.14/lcy-mi x 10 lcy x 1.00 mi= \$1.40 Cr Aggregate Quarry Name: Jarvis 3" Landing Comment: 10+80 End Ldg Length TopW BotW Depth CWid #TOs Width F.W.L Taper Other 50 lcy Rock Volume = 50 lcyPurchase Price / Royalty: $$10.00/lcy \times 50 lcy = 500.00 Processing: $$0.90/lcy \times 50 lcy = 45.00 Compaction: $$1.34/lcy \times 50 lcy = 67.00 Basic Rock Haul cost: $$0.74/lcy \times 50 lcy = 37.00

Water Haul -15% grades: \$0.14/lcy-mi x 50 lcy x 1.00 mi= \$7.00 Subtotal: \$19,812.26

Rock Haul -15% grades: $$1.10/lcy-mi \times 50 lcy \times 0.90 mi= 49.50 Rock Haul St& Co Roads: $$0.49/lcy-mi \times 50 lcy \times 18.00 mi= 441.00

Basic Water Haul cost: $$0.60/lcy \times 50 lcy = 30.00

Road Number: 27-12-15.9 C Continued

Section 1300 Geotextiles:

Subtotal: \$0.00

Section 1400 Slope Protection:

Subtotal: \$0.00

Section 1800 Soil Stabilization:

Dry Method with Mulch: $$540.65/acre \times 0.30 acres = 162.20

Includes Small Quantity Factor of 1.42

+ Seed Cost: \$132.00/acre x 0.30 acres = \$39.60

+ Fertilizer Cost: \$34.00/acre x 0.30 acres = \$10.20

+ Mulch Cost: \$320.00/acre x 0.30 acres = \$96.00

Subtotal: \$308.00

Section 1900 Cattleguards:

Subtotal: \$0.00

Section 2100 Roadside Brushing:

Section 2300 Engineering:

Section 2400 Minor Concrete:

Subtotal: \$0.00

Section 2500 Gabions:

Subtotal: \$0.00

Section 8000 Miscellaneous:

Subtotal: \$0.00

Mobilization:

Construction - 9.88% of total Costs = \$516.63

Surfacing - 10.28% by rock volume = \$0.00

Subtotal: \$516.63

Quarry Development:

Based on 10.28% of total rock volume

Subtotal: \$0.00

Total: \$24,998.09

Subtotal:

Subtotal: \$0.00

\$0.00

ROAD CONSTRUCTION SUMMARY

T.S. Contract Name: Steele 15 CT Sale Date: Road Number: 27-12-3.1 R Road Name: Road Renovation: 0.33 mi 12 ft Subgrade 0 ft ditch 6/30/2014	
200 Clearing and Grubbing: acres	\$0.00
300 Excavation:	\$0.00
400 Drainage: Culvert: 0 lf DownSpout: 0 lf PolyPipe: 0 lf	\$0.00
500 Renovation:	\$3,046.31
700-1200 Surfacing:	\$0.00
1300 Geotextiles:	\$0.00
1400 Slope Protection:	\$0.00
1800 Soil Stabilization: 0.4 acres	\$410.66
1900 Cattleguards:	\$0.00
2100 RoadSide Brushing: 0.0 acres	\$0.00
2300 Engineering: 0.00 sta	\$0.00
2400 Minor Concrete:	\$0.00
2500 Gabions:	\$0.00
8000 Miscellaneous:	\$0.00
Mobilization: Const. \$72.95 Surf. \$0.00	\$72.95
Quarry Development:	\$0.00
Total:	\$3,529.92

Notes:

Quantities shown are estimates only and not pay items. Surfacing Quantities shown are loose cubic yards.

Road Construction Worksheet

Road Number: 27-12-3.1 R Road Name:

Section 200 Clearing and Grubbing:

Subtotal: \$0.00

Section 300 Excavation:

Subtotal: \$0.00

Section 400 Drainage:

Subtotal: \$0.00

Section 500 Renovation:

Blading w/o Ditches: $$446.73/mi \times 0.33 mi = 147.42

Compaction: $$403.47/mi \times 0.33 mi = 133.15

Subgrade Renovation

Excavator - Large (2 CY) 20 hr x \$128.90/hr = \$2,578.00

2+00 Borrow

Dump Truck 12 cy 2 hr x \$93.87/hr = \$187.74

Subtotal: \$3,046.31

Section 700-1200 Surfacing:

Surfacing:

Subtotal: \$0.00

Section 1300 Geotextiles:

Subtotal: \$0.00

Section 1400 Slope Protection:

Subtotal: \$0.00

Section 1800 Soil Stabilization:

Dry Method with Mulch: $$540.65/acre \times 0.40 acres = 216.26

Includes Small Quantity Factor of 1.42

+ Seed Cost: \$132.00/acre x 0.40 acres = \$52.80

+ Fertilizer Cost: \$34.00/acre x 0.40 acres = \$13.60

+ Mulch Cost: \$320.00/acre x 0.40 acres = \$128.00

Subtotal: \$410.66

Section 1900 Cattleguards:

Subtotal: \$0.00

Section 2100 Roadside Brushing:

Subtotal: \$0.00

Mobilization:

Construction - 1.40% of total Costs = \$72.95

Surfacing - 0.00% by rock volume = \$0.00

Subtotal: \$72.95

Quarry Development:

Based on 0.00% of total rock volume

Subtotal: \$0.00

Total: \$3,529.92

ROAD CONSTRUCTION SUMMARY

T.S. Contract Name: Steele 15 CT Sale Date: Road Number: 27-12-9.6 R Road Name:	
Road Renovation: 0.15 mi 16 ft Subgrade 2 ft ditch 6/30/2014	
200 Clearing and Grubbing: acres	\$0.00
300 Excavation:	\$0.00
400 Drainage: Culvert: 0 lf DownSpout: 0 lf PolyPipe: 0 lf	\$0.00
500 Renovation:	\$158.20
700-1200 Surfacing:	\$233.80
1300 Geotextiles:	\$0.00
1400 Slope Protection:	\$0.00
1800 Soil Stabilization: 0.0 acres	\$0.00
1900 Cattleguards:	\$0.00
2100 RoadSide Brushing: 0.4 acres	\$230.64
2300 Engineering: 0.00 sta	\$0.00
2400 Minor Concrete:	\$0.00
2500 Gabions:	\$0.00
8000 Miscellaneous:	\$0.00
Mobilization: Const. \$13.14 Surf. \$0.00	\$13.14
Quarry Development:	\$0.00
Total: Notes:	\$635.78

Notes:

Quantities shown are estimates only and not pay items. Surfacing Quantities shown are loose cubic yards.

Road Construction Worksheet

Road Number: 27-12-9.6 R Road Name:

Section 200 Clearing and Grubbing:

Subtotal: \$0.00

Section 300 Excavation:

Subtotal: \$0.00

Section 400 Drainage:

Subtotal: \$0.00

Section 500 Renovation:

Blading: $$720.50/mi \times 0.15 mi = 108.08

Clean Culverts: $$334.17/mi \times 0.15 mi = 50.13

Subtotal: \$158.20

Section 700-1200 Surfacing:

Cr Aggregate Quarry Name: Jarvis 3" Spot

Comment: 0+00 Grade Dip

Rock Volume = 20 lcy

Processing: $$0.90/lcy \times 20 lcy = 18.00

Basic Rock Haul cost: $$0.74/lcy \times 20 lcy = 14.80

Rock Haul St& Co Roads: \$0.49/lcy-mi x 20 lcy x 19.00 mi= \$186.20

Basic Water Haul cost: $$0.60/lcy \times 20 lcy = 12.00

Water Haul -15% grades: \$0.14/lcy-mi x 20 lcy x 1.00 mi= \$2.80

Subtotal: \$233.80

Section 1300 Geotextiles:

Subtotal: \$0.00

Section 1400 Slope Protection:

Subtotal: \$0.00

Section 1800 Soil Stabilization:

Subtotal: \$0.00

Section 1900 Cattleguards:

Subtotal: \$0.00

Section 2100 Roadside Brushing:

RoadSide Brushing Medium: \$576.60/acre x 0.40 acres = \$230.64

Subtotal: \$230.64

Mobilization:

Construction - 0.25% of total Costs = \$13.14

Surfacing - 0.24% by rock volume = \$0.00

Subtotal: \$13.14

Quarry Development:

Based on 0.24% of total rock volume

Subtotal: \$0.00

Total: \$635.78

ROAD CONSTRUCTION SUMMARY

T.S. Contract Name: Steele 15 CT Sale Date: Road Number: Spur No. 1 C Road Name: Road Construction: 0.06 mi 12 ft Subgrade 0 ft ditch 6/30/2014	
200 Clearing and Grubbing: acres	\$0.00
300 Excavation:	\$1,166.19
400 Drainage: Culvert: 0 lf DownSpout: 0 lf PolyPipe: 0 lf	\$0.00
500 Renovation:	\$0.00
700-1200 Surfacing:	\$0.00
1300 Geotextiles:	\$0.00
1400 Slope Protection:	\$0.00
1800 Soil Stabilization: 0.2 acres	\$205.33
1900 Cattleguards:	\$0.00
2100 RoadSide Brushing: 0.0 acres	\$0.00
2300 Engineering: 0.00 sta	\$0.00
2400 Minor Concrete:	\$0.00
2500 Gabions:	\$0.00
8000 Miscellaneous:	\$0.00
Mobilization: Const. \$28.94 Surf. \$0.00	\$28.94
Quarry Development:	\$0.00
Total:	\$1,400.47
Notes:	

Quantities shown are estimates only and not pay items. Surfacing Quantities shown are loose cubic yards.

Road Construction Worksheet

Road Number: Spur No. 1 C Road Name:

Section 200 Clearing and Grubbing:

Subtotal: \$0.00

Section 300 Excavation:

Subgrade Compaction: 4 Sta/hr \$33.62/sta. x 3.0 sta = \$99.18 Blading without ditch: \$12.14/station x 2.95 stations = \$35.81

Subgrade Construction

Excavator - Large (2 CY) 8 hr x \$128.90/hr = \$1,031.20

Subtotal: \$1,166.19

Section 400 Drainage:

Subtotal: \$0.00

Section 500 Renovation:

Subtotal: \$0.00

Section 700-1200 Surfacing:

Surfacing:

Subtotal: \$0.00

Section 1300 Geotextiles:

Subtotal: \$0.00

Section 1400 Slope Protection:

Subtotal: \$0.00

Section 1800 Soil Stabilization:

Dry Method with Mulch: $$540.65/acre \times 0.20 acres = 108.13

Includes Small Quantity Factor of 1.42

+ Seed Cost: \$132.00/acre x 0.20 acres = \$26.40

+ Fertilizer Cost: \$34.00/acre x 0.20 acres = \$6.80

+ Mulch Cost: \$320.00/acre x 0.20 acres = \$64.00

Subtotal: \$205.33

Section 1900 Cattleguards:

Subtotal: \$0.00

Section 2100 Roadside Brushing:

Subtotal: \$0.00

Mobilization:

Construction - 0.55% of total Costs = \$28.94

Surfacing - 0.00% by rock volume = \$0.00

Subtotal: \$28.94

Quarry Development:

Based on 0.00% of total rock volume Subtotal: \$0.00

Total: \$1,400.47

ROAD CONSTRUCTION SUMMARY

T.S. Contract Name: Steele 15 CT Sale Date: Road Number: Spur No. 2 C Road Name: Road Construction: 0.09 mi 12 ft Subgrade 0 ft ditch 6/30/2014	
200 Clearing and Grubbing: acres	\$0.00
300 Excavation:	\$1,510.94
400 Drainage: Culvert: 0 lf DownSpout: 0 lf PolyPipe: 0 lf	\$0.00
500 Renovation:	\$0.00
700-1200 Surfacing:	\$0.00
1300 Geotextiles:	\$0.00
1400 Slope Protection:	\$0.00
1800 Soil Stabilization: 0.2 acres	\$205.33
1900 Cattleguards:	\$0.00
2100 RoadSide Brushing: 0.0 acres	\$0.00
2300 Engineering: 0.00 sta	\$0.00
2400 Minor Concrete:	\$0.00
2500 Gabions:	\$0.00
8000 Miscellaneous:	\$0.00
Mobilization: Const. \$36.22 Surf. \$0.00	\$36.22
Quarry Development:	\$0.00
Total: Notes:	\$1,752.48
Ouantities shown are estimates only and not have items	

Quantities shown are estimates only and not pay items. Surfacing Quantities shown are loose cubic yards.

Road Construction Worksheet

Road Number: Spur No. 2 C Road Name:

Section 200 Clearing and Grubbing:

Subtotal: \$0.00

Section 300 Excavation:

Subgrade Compaction: 4 Sta/hr $$33.62/sta. \times 4.9 sta = 163.06 Blading without ditch: $$12.14/station \times 4.85 stations = 58.88

Subgrade Construction

Excavator - Large (2 CY) 10 hr x \$128.90/hr = \$1,289.00

Subtotal: \$1,510.94

Section 400 Drainage:

Subtotal: \$0.00

Section 500 Renovation:

Subtotal: \$0.00

Section 700-1200 Surfacing:

Surfacing:

Subtotal: \$0.00

Section 1300 Geotextiles:

Subtotal: \$0.00

Section 1400 Slope Protection:

Subtotal: \$0.00

Section 1800 Soil Stabilization:

Dry Method with Mulch: \$540.65/acre x 0.20 acres = \$108.13

Includes Small Quantity Factor of 1.42

+ Seed Cost: \$132.00/acre x 0.20 acres = \$26.40

+ Fertilizer Cost: \$34.00/acre x 0.20 acres = \$6.80

+ Mulch Cost: \$320.00/acre x 0.20 acres = \$64.00

Subtotal: \$205.33

Mobilization:

Construction - 0.69% of total Costs = \$36.22

Surfacing - 0.00% by rock volume = \$0.00

Subtotal: \$36.22

Quarry Development:

Based on 0.00% of total rock volume

Subtotal: \$0.00

Total: \$1,752.48

ROAD CONSTRUCTION SUMMARY

T.S. Contract Name: Steele 15 CT Sale Date: Road Number: Spur No. 4 C Road Name: Road Construction: 0.05 mi 12 ft Subgrade 0 ft ditch 6/30/2014	
200 Clearing and Grubbing: acres	\$0.00
300 Excavation:	\$770.34
400 Drainage: Culvert: 0 lf DownSpout: 0 lf PolyPipe: 0 lf	\$0.00
500 Renovation:	\$0.00
700-1200 Surfacing:	\$0.00
1300 Geotextiles:	\$0.00
1400 Slope Protection:	\$0.00
1800 Soil Stabilization: 0.2 acres	\$205.33
1900 Cattleguards:	\$0.00
2100 RoadSide Brushing: 0.0 acres	\$0.00
2300 Engineering: 0.00 sta	\$0.00
2400 Minor Concrete:	\$0.00
2500 Gabions:	\$0.00
8000 Miscellaneous:	\$0.00
Mobilization: Const. \$20.59 Surf. \$0.00	\$20.59
Quarry Development:	\$0.00
Total: Notes:	\$996.26

Quantities shown are estimates only and not pay items. Surfacing Quantities shown are loose cubic yards.

Road Construction Worksheet

Road Number: Spur No. 4 C Road Name:

Section 200 Clearing and Grubbing: Subtotal: \$0.00 Section 300 Excavation: Subgrade Compaction: 4 Sta/hr \$33.62/sta. x 2.8 sta = \$92.46 Blading without ditch: \$12.14/station x 2.75 stations = \$33.39Subgrade Construction Excavator - Large (2 CY) 5 hr x \$128.90/hr = \$644.50Subtotal: \$770.34 Section 400 Drainage: Subtotal: \$0.00 Section 500 Renovation: Subtotal: \$0.00 Section 700-1200 Surfacing: Surfacing: Subtotal: \$0.00 Section 1300 Geotextiles: Subtotal: \$0.00 Section 1400 Slope Protection: Subtotal: \$0.00 Section 1800 Soil Stabilization: Dry Method with Mulch: $$540.65/acre \times 0.20 acres = 108.13 Includes Small Quantity Factor of 1.42 + Seed Cost: \$132.00/acre x 0.20 acres = \$26.40 + Fertilizer Cost: \$34.00/acre x 0.20 acres = \$6.80 + Mulch Cost: \$320.00/acre x 0.20 acres = \$64.00 Subtotal: \$205.33 Section 1900 Cattleguards: Subtotal: \$0.00 Section 2100 Roadside Brushing: Subtotal: \$0.00 Mobilization: Construction - 0.39% of total Costs = \$20.59 Surfacing - 0.00% by rock volume = \$0.00 Subtotal: \$20.59 Quarry Development: Based on 0.00% of total rock volume

Subtotal:

Total: \$996.26

\$0.00

ROAD CONSTRUCTION SUMMARY

T.S. Contract Name: Steele 15 CT Sale Date: Road Number: Spur No. 5 C Road Name:	
Road Construction: 0.05 mi 16 ft Subgrade 0 ft ditch 6/30/2014	
200 Clearing and Grubbing: acres	\$0.00
300 Excavation:	\$1,021.28
400 Drainage: Culvert: 0 lf DownSpout: 0 lf PolyPipe: 0 lf	\$0.00
500 Renovation:	\$0.00
700-1200 Surfacing:	\$5,835.44
1300 Geotextiles:	\$0.00
1400 Slope Protection:	\$0.00
1800 Soil Stabilization: 0.2 acres	\$205.33
1900 Cattleguards:	\$0.00
2100 RoadSide Brushing: 0.0 acres	\$0.00
2300 Engineering: 0.00 sta	\$0.00
2400 Minor Concrete:	\$0.00
2500 Gabions:	\$0.00
8000 Miscellaneous:	\$0.00
Mobilization: Const. \$149.03 Surf. \$0.00	\$149.03
Quarry Development:	\$0.00
Total: Notes:	\$7,211.07
Ouantities shown are estimates only and not pay items.	

Quantities shown are estimates only and not pay items. Surfacing Quantities shown are loose cubic yards.

Road Number: Spur No. 5 C Road Name: Section 200 Clearing and Grubbing: Subtotal: \$0.00 Section 300 Excavation: Subgrade Compaction: 4 Sta/hr \$33.62/sta. x 2.6 sta = \$87.41 Blading without ditch: \$12.14/\$station x 2.60 stations = \$31.56Subgrade Construction Excavator - Large (2 CY) 7 hr x \$128.90/hr = \$902.30Subtotal: \$1,021.28 Section 400 Drainage: Subtotal: \$0.00 Section 500 Renovation: Subtotal: \$0.00 Section 700-1200 Surfacing: Cr. Aggregate Quarry Name: Jarvis 3" Base BotW 1 7 #TOs Width F.W.L Taper Length TopW Depth CWid Other 0.05mi 12ft 16ft 12in 5% Rock Volume = 188 lcy Purchase Price / Royalty: $$10.00/lcy \times 188 lcy = $1,880.00$ Processing: $$0.90/lcy \times 188 lcy = 169.20 Compaction: $$1.34/lcy \times 188 lcy = 251.92 Basic Rock Haul cost: \$0.74/lcy x 188 lcy = \$139.12 Rock Haul -15% grades: \$1.10/lcy-mi x 188 lcy x 0.90 mi= \$186.12 Rock Haul St& Co Roads: \$0.49/lcy-mi x 188 lcy x 18.00 mi= \$1,658.16 Basic Water Haul cost: $$0.60/lcy \times 188 lcy = 112.80 Water Haul -15% grades: $$0.14/lcy-mi \times 188 lcy \times 1.00 mi= 26.32 Cr Aggregate Quarry Name: Jarvis 3" Landing Comment: 0+00 "Y" Jct Length TopW BotW Depth CWid #TOs Width F.W.L Taper Other 10 lcv Rock Volume = 10 lcy Purchase Price / Royalty: \$10.00/lcy x 10 lcy = \$100.00 Processing: $$0.90/1cy \times 10 lcy = 9.00 Compaction: $$1.34/lcy \times 10 lcy = 13.40 Basic Rock Haul cost: $$0.74/lcy \times 10 lcy = 7.40 Rock Haul -15% grades: $$1.10/lcy-mi \times 10 lcy \times 0.90 mi= 9.90 Rock Haul St& Co Roads: \$0.49/lcy-mi x 10 lcy x 18.00 mi= \$88.20 Basic Water Haul cost: $$0.60/lcy \times 10 lcy = 6.00 Water Haul -15% grades: \$0.14/lcy-mi x 10 lcy x 1.00 mi= \$1.40 Cr Aggregate Quarry Name: Jarvis 3" Landing Comment: 2+60 End Landing Length TopW BotW Depth CWid #TOs Width F.W.L Taper Other 50 lcy Rock Volume = 50 lcyPurchase Price / Royalty: $$10.00/lcy \times 50 lcy = 500.00 Processing: $$0.90/1cv \times 50 1cv = 45.00 Compaction: $$1.34/lcy \times 50 lcy = 67.00 Basic Rock Haul cost: $$0.74/lcy \times 50 lcy = 37.00 Rock Haul -15% grades: \$1.10/lcy-mi x 50 lcy x 0.90 mi= \$49.50 Rock Haul St& Co Roads: \$0.49/lcy-mi x 50 lcy x 18.00 mi= \$441.00

Basic Water Haul cost: $$0.60/lcy \times 50 lcy = 30.00

Water Haul -15% grades: $\$0.14/lcy-mi \times 50 lcy \times 1.00 mi= \7.00

Subtotal: \$5,835.44

Road Number: Spur No. 5 C Continued

Section 1300 Geotextiles:

Subtotal: \$0.00

Section 1400 Slope Protection:

Subtotal: \$0.00

Section 1800 Soil Stabilization:

Dry Method with Mulch: $$540.65/acre \times 0.20 acres = 108.13

Includes Small Quantity Factor of 1.42

+ Seed Cost: \$132.00/acre x 0.20 acres = \$26.40

+ Fertilizer Cost: \$34.00/acre x 0.20 acres = \$6.80

+ Mulch Cost: \$320.00/acre x 0.20 acres = \$64.00

Subtotal: \$205.33

Section 1900 Cattleguards:

Subtotal: \$0.00

Section 2100 Roadside Brushing:

Subtotal: \$0.00

Section 2300 Engineering:

Subtotal: \$0.00

Section 2400 Minor Concrete:

Subtotal: \$0.00

Section 2500 Gabions:

Subtotal: \$0.00

Section 8000 Miscellaneous:

Subtotal: \$0.00

Mobilization:

Construction - 2.85% of total Costs = \$149.03

Surfacing - 3.03% by rock volume = \$0.00

Subtotal: \$149.03

Quarry Development:

Based on 3.03% of total rock volume

Subtotal: \$0.00

Total: \$7,211.07

UNITED STATES DEPARTMENT OF THE INTERIOR BUREAU OF LAND MANAGEMENT

Mobilization Costs - Construction and Surfacing

T.S. Contract Name: Steele 15 CT Sale Date:

Average Mobilization distance = 50 miles Factor = 1.00

Mobilization: Construction

Comment: LUMP SUM = VEHICLE WASH

Fire Equipment: 1 ea x (1.00 x \$65.00/ea + 0 mi x \$3.64/mi) = \$65.00Graders-all: 1 ea x (1.00 x \$483.00/ea + 0 mi x \$14.73/mi) = \$483.00

Brush Cutter: 1 ea x $(1.00 \times $483.00/ea) = 483.00

Rollers & Comp: 1 ea x $(1.00 \times $483.00/ea + 0 \text{ mi } \times $26.90/mi) = 483.00

Excavators: 1 ea x $(1.00 \times \$861.00/ea = \$861.00)$

Tractors <= D7: 1 ea x (1.00 x \$672.00/ea + 0 mi x \$32.67/mi) = \$672.00Dump Truck<=10cy: 1 ea x (1.00 x \$113.00/ea + 0 mi x \$4.69/mi) = \$113.00Water Truck: 1 ea x (1.00 x \$107.00/ea + 0 mi x \$4.48/mi) = \$107.00

Lump Sum: \$1,960.00

Subtotal: \$5,227.00

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

Summary of Construction Quantities

T.S. Contract Name: Steele 15 CT Sale Date:

Road Number 27-11-15.11 C	Const 2.40	Improv	Renov	Decomm	Temp
27-12-10.1 R	2.40		18.35		
27-12-15.0 R			23.76		
27-12-15.10 C	8.95				
27-12-15.11 I		3.00			
27-12-15.3 C	5.95				
27-12-15.3 I		25.55			
27-12-15.3 R			5.00		
27-12-15.4 C	16.80				
27-12-15.5 C	9.10				
27-12-15.6 C	8.35				
27-12-15.7 C	23.60				
27-12-15.8 C	9.30				
27-12-15.9 C	10.80				
27-12-3.1 R			17.50		
27-12-9.6 R			7.92		
Spur No. 1 C	2.95				
Spur No. 2 C	4.85				
Spur No. 4 C	2.75				
Spur No. 5 C	2.60				
Total Sta:	108.40	28.55	72.53		

200 Clearing and Grubbing**	Clearing
	acres
27-11-15.11 C	0.0
27-12-10.1 R	0.0
27-12-15.0 R	0.0
27-12-15.10 C	0.0
27-12-15.11 I	0.0
27-12-15.3 C	0.0
27-12-15.3 I	0.0
27-12-15.3 R	0.0
27-12-15.4 C	0.0
27-12-15.5 C	0.0
27-12-15.6 C	0.0
27-12-15.7 C	0.0
27-12-15.8 C	0.0
27-12-15.9 C	0.0
27-12-3.1 R	0.0
27-12-9.6 R	0.0
Spur No. 1 C	0.0
Spur No. 2 C	0.0
Spur No. 4 C	0.0
Spur No. 5 C	0.0
	•••

Totals: 0.0 **Included in Time and Equipment for Excavation if not listed.

300 Excavation		Exc. LCY			Haul a-yds		aul d-mi		
	Totals:		0		0		0		
Subgrade Construction	27-11-15.11	С							
Excavator - Large	,							 	10 hr
Subgrade Construction	Spur No. 5 (
Excavator - Large								 	7 hr
Subgrade Construction	Spur No. 4 (
Excavator - Large	(2 CY)							 	5 hr
Subgrade Construction	Spur No. 2 (
Excavator - Large	,							 	10 hr
Subgrade Construction	Spur No. 1 (
Excavator - Large								 	8 hr
Subgrade Construction									
Excavator - Large								 	20 hr
Subgrade Construction	27-12-15.9								
Excavator - Large								 	30 hr
Subgrade Construction	27-12-15.8								05.1
Excavator - Large				• •				 	25 hr
Subgrade Construction									F 0 1
Excavator - Large			• •	• •		• •		 • •	50 nr
Subgrade Construction	27-12-15.6 (_							0 5 1
Excavator - Large						• • •		 	25 nr
Subgrade Construction	27-12-15.5 (0 5 1
Excavator - Large			• •			• • •		 • •	∠5 nr
Subgrade Construction									10 hr
Excavator - Large	(2 C1)		• •			• •		 • •	40 111
Subgrade Excavation Excavator - Large									15 hm
Excavator - Large	(2 (1)		• •			• • •		 	10 111

Road Number	Culvert	Polypipe	Downspout			
Total Drainage:						
roour brainago.						
0+00 / Exist Ditc		:	No Quantiti	es		
0+00 / EXIST DITC	niine 2/-12-1 nized CMP	15.3 C			4	O T.F
12 A40 MIUMI	iiizea chi					ОШ
500 Renovation			es Slide	· =		
27-12-10.1 R		0.35		0		
27-12-15.0 R 27-12-15.11 I		0.45 0.06		0		
27-12-15.11 1 27-12-15.3 I		0.08		0		
27-12-13.3 T 27-12-3.1 R		0.33		0		
27-12-3.1 R 27-12-9.6 R		0.33		0		
27-12-9.0 K		0.13		O		
	Totals:	1.82		0		
"Old Subgrade" Rip	nan Barriar 2	7_12_15 11 T				
	ce				1	0 CY
18+35 End Landing	27-12-10.1 F	3				
	arge (2 CY)				3	hr
2+00 Borrow 27- Dump Truck 12	cy				2	hr
43+20 Tanktrap	27-12-15.3 R					
	all (1.5 CY)				2	hr
Gate Restoration	27-12-15.0 R				1	T.S
Old Subgrade Scar	ificationa 25	7-12-15.11 T				
Tractor: D7 w	ith rippers				1	hr
Subgrade Improvem Excavator - I	ent 27-12-15. arge (2 CY)	,11 I			1	0 hr
Subgrade Improvem	ent 27-12-15.	.3 I				
Excavator - L	arge (2 CY)				3	0 hr
Subgrade Renovati	on 27-12-3.1 arge (2 CY)	R			2	∩ hr
Subgrade Renovati					2	O III
Excavator - L	arge (2 CY)				8	hr
Waterline removal	/ disposal 2 ipment				1	LS
Waterline removal						по
	ipment				1	LS
Surfacing (Loose Cu	hia Varda)					
Note: Due to slight		erences hetwe	en total I.CV	we subt	otaled I.CV	
Totals shown here m						
TOCATO SHOWN HOLD IN	ay not be enace	signation of the signature of the signat	in one road	o anuna 100	ana wornon	
Quarry Name: Jarvis	3" Base					
Cr. Aggregate		Roadway	Turnouts	Other		
27-12-15.3 I		1,850	148	0	1,998	
27-12-15.3 C		431	49	0	480	
27-12-15.4 C		1,217	99	0	1,316	
27-12-15.6 C		605	0	0	605	
27-12-15.7 C		1,709	99	0	1,808	
27-12-15.9 C		782	0	0	782	
27-12-15.11 I		221	0	0	221	
27-11-15.11 C		166	0	0	166	
Spur No. 5 C		188	0	0	188	
	m - ± - 1	7 100	205		7 5 6 4	
	Totals:	7,169	395	0	7,564	

_	ding				
Cr Aggregate		Roadway	Turnouts	Other	
27-12-15.4 C 27-12-15.4 C		0	0	10 100	10 100
27-12-13.4 C 27-12-15.4 C		0	0	50	50
27-12-15.6 C		0	0	10	10
27-12-15.6 C		0	0	70	70
27-12-15.6 C		0	0	50	50
27-12-15.7 C 27-12-15.7 C		0	0	10 50	10 50
27-12-15.7 C 27-12-15.9 C		0	0	10	10
27-12-15.9 C		0	0	50	50
Spur No. 5 C		0	0	10	10
Spur No. 5 C 27-11-15.11 C		0	0	50 10	50 10
27-11-15.11 C 27-11-15.11 C		0	0	50	50
27-11-15.11 C		0	0	50	50
27-12-15.6 C		0	0	10	10
	Totals:	0	0	590	590
Quarry Name: Jarvis 3" Spo	t.				
Cr Aggregate		Roadway	Turnouts	Other	
27-12-9.6 R		0	0	20	20
27-12-15.0 R		0	0	20	20
	Totals:	0	0	40	40
Quarry Name: Jarvis 1-1/2"	Spot				
Cr Aggregate		Roadway	Turnouts	Other	
	Totals:	0	0	0	0
Quarry Name: Jarvis Riprap					
Quarry Name: Jarvis Riprap		Roadway	Turnouts	Other	
-	Totals:	Roadway	Turnouts	Other	0
Riprap					0
-			0		0
Riprap	Totals:	0	0		0
Riprap 1300 Geotextiles	Totals:	0	0		0
Riprap 1300 Geotextiles 1400 Slope Protection	Totals: Totals:		0 ties	0	0
Riprap 1300 Geotextiles	Totals: Totals:		0 ties Dry/with	0 -	0
Riprap 1300 Geotextiles 1400 Slope Protection	Totals: Totals:		0 ties	0	0
Riprap 1300 Geotextiles 1400 Slope Protection 1800 Soil stabilization - 27-11-15.11 C 27-12-10.1 R	Totals: Totals:	No Quanti O Dry W/O Mulch 0.0 0.0	Dry/with Mulch 0.2 0.1	0 -	0
Riprap 1300 Geotextiles 1400 Slope Protection 1800 Soil stabilization - 27-11-15.11 C 27-12-10.1 R 27-12-15.10 C	Totals: Totals:	No Quanti O Dry W/O Mulch 0.0 0.0 0.0	Dry/with Mulch 0.2 0.1 0.3	0 -	0
Riprap 1300 Geotextiles 1400 Slope Protection 1800 Soil stabilization - 27-11-15.11 C 27-12-10.1 R 27-12-15.10 C 27-12-15.11 I	Totals: Totals:	0 No Quanti 0 Dry W/O Mulch 0.0 0.0 0.0 0.0	Dry/with Mulch 0.2 0.1 0.3 0.2	0 -	0
Riprap 1300 Geotextiles 1400 Slope Protection 1800 Soil stabilization - 27-11-15.11 C 27-12-10.1 R 27-12-15.10 C	Totals: Totals:	No Quanti O Dry W/O Mulch 0.0 0.0 0.0	Dry/with Mulch 0.2 0.1 0.3	0 -	0
Riprap 1300 Geotextiles 1400 Slope Protection 1800 Soil stabilization - 27-11-15.11 C 27-12-10.1 R 27-12-15.10 C 27-12-15.11 I 27-12-15.3 C 27-12-15.3 I 27-12-15.3 R	Totals: Totals:	Dry W/O Mulch 0.0 0.0 0.0 0.0 0.0	Dry/with Mulch 0.2 0.1 0.3 0.2 0.1 0.6 0.2	0 -	0
Riprap 1300 Geotextiles 1400 Slope Protection 1800 Soil stabilization - 27-11-15.11 C 27-12-10.1 R 27-12-15.10 C 27-12-15.11 I 27-12-15.3 C 27-12-15.3 I 27-12-15.3 R 27-12-15.4 C	Totals: Totals:	Dry W/O Mulch 0.0 0.0 0.0 0.0 0.0 0.0	Dry/with Mulch 0.2 0.1 0.3 0.2 0.1 0.6 0.2 0.6	0 -	0
Riprap 1300 Geotextiles 1400 Slope Protection 1800 Soil stabilization - 27-11-15.11 C 27-12-10.1 R 27-12-15.10 C 27-12-15.11 I 27-12-15.3 C 27-12-15.3 I 27-12-15.3 R 27-12-15.4 C 27-12-15.5 C	Totals: Totals:	Dry W/O Mulch 0.0 0.0 0.0 0.0 0.0 0.0 0.0	Dry/with Mulch 0.2 0.1 0.3 0.2 0.1 0.6 0.2 0.6 0.2	0 -	0
Riprap 1300 Geotextiles 1400 Slope Protection 1800 Soil stabilization - 27-11-15.11 C 27-12-10.1 R 27-12-15.10 C 27-12-15.31 C 27-12-15.3 R 27-12-15.3 R 27-12-15.4 C 27-12-15.5 C 27-12-15.6 C	Totals: Totals:	Dry W/O Mulch 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0	Dry/with Mulch 0.2 0.1 0.3 0.2 0.1 0.6 0.2 0.6 0.2 0.3	0 -	0
Riprap 1300 Geotextiles 1400 Slope Protection 1800 Soil stabilization - 27-11-15.11 C 27-12-10.1 R 27-12-15.10 C 27-12-15.11 I 27-12-15.3 C 27-12-15.3 I 27-12-15.3 R 27-12-15.4 C 27-12-15.5 C	Totals: Totals:	Dry W/O Mulch 0.0 0.0 0.0 0.0 0.0 0.0 0.0	Dry/with Mulch 0.2 0.1 0.3 0.2 0.1 0.6 0.2 0.6 0.2	0 -	0
Riprap 1300 Geotextiles 1400 Slope Protection 1800 Soil stabilization - 27-11-15.11 C 27-12-10.1 R 27-12-15.10 C 27-12-15.11 I 27-12-15.3 C 27-12-15.3 R 27-12-15.4 C 27-12-15.5 C 27-12-15.6 C 27-12-15.7 C	Totals: Totals:	Dry W/O Mulch 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.	Dry/with Mulch 0.2 0.1 0.3 0.2 0.1 0.6 0.2 0.6 0.2 0.3 0.7	0 -	0

Continuation of Construction Quantities

Spur No. 1 C		0.0	0.2
Spur No. 2 C		0.0	0.2
Spur No. 4 C		0.0	0.2
Spur No. 5 C		0.0	0.2
	Totals:	0.0	5.3 0.0
	Small Quantity	Factor of	1.42 used

1900 Cattleguards

Totals: No Quantities

2100 RoadSide Brushing acres
27-12-10.1 R
27-12-15.0 R
27-12-9.6 R

Totals: 2.3

Totals: 0.00

2400 Minor Concrete

2300 Engineering

Totals: No Quantities


stations


2500 Gabions


Totals: No Quantities

8000 Miscellaneous


Totals: No Quantities







WATER DIP



(NOT TO SCALE)


Road Surface Shoulder

NOTES

- 1. ALL BARRIERS, WATER BARS, AND WATER DIPS AS REQUIRED SHALL BE CONSTRUCTED AS SHOWN.
- 2. LOCATIONS WILL BE AS DIRECTED BY THE AUTHORIZED OFFICER PRIOR TO CONSTRUCTION.
- 3. ALL WATER BARS SHALL BE SKEWED 30° 40°.
- 4. ALL WATER DIPS SHALL BE SKEWED 60° 70°.
- 5. ALL WATER BARS AND WATER DIPS SHALL BE CUT INTO THE ROADBED FROM THE DITCHLINE.
- 6. DITCHLINES SHALL BE BLOCKED WITH EXCAVATED MATERIAL (DITCH DAM) DOWNGRADE FROM ALL WATER BARS AND WATER DIPS.
- 7. EXCAVATED MATERIAL FROM BARRIER TRENCH (TANK TRAP) SHALL BE PLACED ON THE SIDE NEAREST THE BEGINNING OF THE ROAD.

- 8. OUTLETS OF WATER DIPS MUST BE ROCKED ON FILL SLOPE.
- 9. RIPRAP BARRIERS SHALL BE AT LEAST 3' HIGH, 3' DEEP, AND OF SUFFICIENT WIDTH TO COMPLETELY BLOCK THE ROADWAY AND ANY ADJACENT SHOULDERS THAT CAN BE TRAVELED WITH A VEHICLE. RIPRAP SHALL BE KEYED IN PLACE TO PREVENT ANY MOVEMENT.
- 10. ALL BERMS INCLUDING WATER BARS. WATER DIPS, AND EARTHEN BARRIERS SHALL BE COMPACTED TO 85% OF MAXIMUM DENSITY.





WATER DIP/BAR SPACING

ROAD GRADE	MAXIMUM SPACING
*	FEET
0-4	500
5-6	400
7-9	300
10-14	100
15-20	50

U. S. DEPARTMENT OF THE INTERIOR BUREAU OF LAND MANAGEMENT COOS BAY DISTRICT OREGON

BARRIER AND EROSION CONTROL DETAIL

ALWAYS THINK SAFETY

DESIGN	IED	J.	COUNTS			
REVIEW	/ED	J.	MENGUITA	4		
APPRO		т.	BUCHHOL	Z		
DRAWN	JC		SCALE	NC	NE	
DATE	08/15		SHEET	2	OF	9
DRAWING	NO.					

"EXHIBIT D" ESTIMATE OF QUANTITIES*

		SURF	ACING			OTHER		SOIL STA	BILIZATION	OTHER
ROAD NUMBER	SPOT ROCK **	AGG. MAINT. ROCK **	AGG. MAINT. ROCK **	AGG. MAINT. ROCK **	RIPRAP BARRIER **	RIPRAP ARMOR **	PITRUN **	DRY	HYDRO- MULCH	
SPEC. NO.	1200	1200	1000		1400			1800	1800	
UNITS	C.Y.	C.Y.	C.Y.	C.Y.	C.Y.	C.Y.	C.Y.	ACRES	ACRES	
	(C)	(A)	(A)	(A)	(A)	B	(A)			
Fairview-Sumner County Road	O	A	(A)	(A)	(A)	B	(A)			
	O	(A)	(A)	(A)	(A)	B	(A)			
27-12-3.1	0	(A)	(A)	(A)	(A)	B	(A)	0.2		
27-12-10.1	0	(A)	lack	(A)	A	B	(A)	0.2		
27-12-15.3	0	(A)	A	(A)	10 (A)	B	(A)	0.3		
27-12-15.4	0	(A)	(A)	(A)	(A)	B	(A)			
27-12-15.5	O	A	(A)	(A)	A	B	(A)	0.5		
27-12-15.6	O	A	A	(A)	A	B	A			İ
27-12-15.7	0	A	(A)	(A)	A	B	(A)			
27-12-15.8	O	(A)	(A)	(A)	A	B	(A)	0.3		
27-12-15.9	O	(A)	Ā	(A)	A	B	(A)			
27-12-15.10	© ©	(A)	A	(A)	10 (A)	B	A	0.2		
27-12-15.11	O	A	A	(A)	10 A	B	A			
	0	(A)	(A)	A	A	B	A	0.1		
SPUR NO. 1	O	(A)	A	(A)	A	B	A	0.1		
SPUR NO. 2	000	(A)	(A)	A	10 🙆	B	A	0.1		
SPUR NO. 4	O	A	A	A	A	B	A			
SPUR NO. 5	0	A	A	A	A	B	A			
	(C)	(A)	A	(A)	A	B	A			Ì
	© ©	A	A	A	A	B	A			
	(C)	A	A	A	A	B	A			
	(C)	A	A	A	A	B	A			
	0	A	A	Ā	Ā	B	A			
		A	A	A	A	B	A			
	O	A	Ã	Ã	A	B	A			
	Ö	Ā	A	A	A	B	A			1
TOTALS	O	230 A	100 A	A	40 A	B	A	2.0		

ITEM	SIZE	GRADE
700 (PITRUN)		A
1000 (Base)	3"	A
	4"	В
1100	4"	В
1200 (Top)	1 ½ "	A
	21/2"	С
1400 (RIPRAP)	CLASS 6	A
		В
CHIP SEAL ROCK	3/4"	S

GRADE INDICATED IN CIRCLE



U. S. DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT
COOS BAY DISTRICT OREGON
"EXHIBIT D"
ESTIMATE OF QUANTITIES
DESIGNED J. COUNTS
REVIEWED J. MENGUITA
APPROVED T. BUCHHOLZ
DRAWN JC SCALE NONE

- * FOR INFORMATIONAL USE ONLY. QUANTITIES SHOWN ARE NOT PAY ITEMS.
- ** ROCK QUANTITES ARE TRUCK MEASUREMENT.

SALE NO. ORC00-TS 2016.0002 STEELE 15 CT EXHIBIT D Sheet 4 of 9 Sheets

ROAD MAINTENANCE SPECIFICATIONS

General road maintenance specifications are designated by numeric symbols according to the type of road work to be performed, as follows:

<u>Section</u>	
3000 3100	GENERAL OPERATIONAL MAINTENANCE
3200	SEASONAL MAINTENANCE
3300	FINAL MAINTENANCE
3400	OTHER MAINTENANCE

SALE NO. ORC00-TS 2016.0002 STEELE 15 CT EXHIBIT D Sheet 5 of 9 Sheets

GENERAL - 3000

3001	The Purchaser shall be required to maintain all roads as shown on the Exhibit D map of this contract in accordance with Sections 3000, 3100, 3200, 3300, and 3400 of this exhibit.
3002	The Purchaser shall maintain the cross section of existing dirt or graveled roads to the existing geometric standards. Any roads required to be constructed, improved, or renovated under terms of this contract shall be maintained to the standards required in Exhibit C of this contract.
3003	The minimum required maintenance on any roads shall include the provisions specified in Subsections 3101, 3104, and 3105.
3004	The Purchaser shall be responsible for providing timely maintenance and cleanup on any road(s) with logging units substantially completed prior to moving operations to other roads. Release of maintenance requirements may be granted, upon written request, when the conditions specified in Sections 3300 and 3400 are met satisfactorily.
	OPERATIONAL MAINTENANCE - 3100
3101	The Purchaser shall blade and shape the road surface and shoulders with a motor patrol grader. Banks shall not be undercut. Back blading with tractors or similar equipment will be allowed only around landings and other areas when approved by the Authorized Officer.
3102	The Purchaser shall place 230 yds³ of crushed aggregate, conforming to the requirements in Section 1200 of Exhibit C of this contract, and 100 yds³ of crushed aggregate, conforming to the requirements in Section 1000 of this contract, on the roadway at locations and in the amounts designated by the Authorized Officer.
	This crushed aggregate shall be used to repair surface failures, and areas of depleted surface depth, excluding damages covered by Section 12 of this contract. The aggregate shall be furnished, hauled, placed, spread, and compacted by use of dump trucks, water trucks, and motor patrol grader.
3103	The Purchaser shall maintain established berms and place additional berms using adjacent material where needed to protect fills as directed by the Authorized Officer.
3104	The Purchaser shall perform other road cleanup including removal of debris, fallen timber, bank slough, and slides which can practicably be accomplished by a motor patrol grader, rubber-tired front-end bucket loader, rubber-tired backhoe or comparable equipment, and by the use of hand tools.
3104a	Removal of bank slough and slide material includes placement of material at the nearest suitable turnout or disposal site where material cannot erode into streams, lakes, or reservoirs or cause undue damage to road fill slopes which have been planted or mulched to control soil erosion.
3104b	The Purchaser shall be responsible for removal of all slides or slough, up to fifteen (15) station yards in quantity, at any one site. This work includes unlimited multiple sites on all roads required to be maintained by the Purchaser.
	Prior to removal of any slough or slide material exceeding fifteen (15) station yards at any one site, the Purchaser and the Authorized Officer or their Authorized Representatives shall agree in writing, in the field, to the quantity of material, method of disposal, and the disposal site. Work may commence

Upon completion of agreed upon work, a reduction in timber sale purchase price will be made to offset the cost of work, based on current BLM Timber Appraisal Production Cost Schedules. Adjustments in purchase price for completed work shall be made as necessary and no less than once per year when

immediately after agreement.

actual work is ongoing.

SALE NO. ORC00-TS 2016.0002 STEELE 15 CT EXHIBIT D Sheet 6 of 9 Sheets

3105

The Purchaser shall be responsible for maintaining normal flow in drainage structures. This includes cleaning out drainage ditches, catch basins, clearing pipe inverts of sediment and other debris lodged in the barrel of the pipe and maintaining water dips and waterbars using equipment specified in Subsection 3104 and other culvert cleaning and flushing equipment.

3106

The Purchaser shall be responsible for repair and replacement of all materials eroded from road shoulders and fill slopes, up to fifteen (15) station yards in quantity, at any one site. The work includes unlimited multiple sites on all roads required to be maintained by the Purchaser. Prior to repair and replacement of eroded material exceeding fifteen (15) station yards at any one site, the Purchaser and the Authorized Officer or their Authorized Representatives shall agree in writing, in the field, to the quantity of material, borrow source, and method of repair. Work may commence immediately after agreement.

Upon completion of agreed upon work, a reduction in timber sale purchase price will be made to offset the cost of the work, based upon current BLM Timber Sale Appraisal Production Cost Schedules. Adjustments in purchase price for completed work shall be made as necessary, and no less than once per year when actual work is ongoing.

3107

The Purchaser shall cut or trim trees and brush which obstructs vision or prevents the safe passage of traffic along the traveled way, when directed by the Authorized Officer.

The Purchaser shall also cut trees or brush encroaching on the road prism that are a result of his activities or winter damage during the contract period. Disposal of such vegetative material shall be by scattering below the road.

3108

The Purchaser shall avoid fouling gravel or bituminous surfaces through covering with earth and debris from side ditches, slides, or other sources. The Purchaser shall also avoid blading surfacing material off the running surface of the roadway. Skidding of logs on the roadway in or outside designated logging units is not authorized without prior written approval by the Authorized Officer. Repair required by such skidding activity is not considered maintenance and shall be performed at the Purchaser's expense.

3108a

The Purchaser shall perform logging operations on gravel and/or bituminous roadways only where the locations have been marked on the ground and/or approved by the Authorized Officer.

SEASONAL MAINTENANCE - 3200

3201

The Purchaser shall perform preventive maintenance at the end of Purchaser's hauling each season and during nonhauling periods which occur between other operations on the contract area. This includes cross ditching, blockage, removing ruts or other surface irregularities, and all other requirements specified in Section 3100.

3202

The Purchaser shall perform and complete maintenance, specified in Sections 3000, 3100, and 3200, on all roads maintained by him, prior to October 1 each year, except as specified in Subsection 3203, after initial commencement of construction or logging operations. Thereafter all roads shall have continuous preventive maintenance and road cleanup until suspension of seasonal operations. This includes all roads used and not used during the preceding operating seasons.

3203

The Purchaser shall complete road cleanup and maintenance, as specified in Section 3100, at the completion of logging operations on any road(s) located in an area separate from the area where logging activities will resume.

3204

The Purchaser shall be responsible for performing post storm inspections and maintenance during the winter season to minimize erosion and potential road or watershed damage.

SALE NO. ORC00-TS 2016.0002 STEELE 15 CT EXHIBIT D Sheet 7 of 9 Sheets

FINAL MAINTENANCE - 3300

3301

The Purchaser shall complete final maintenance and/or damage repairs on all roads used under terms of their contract within 30 calendar days following the expiration of Purchaser's right to cut and remove timber (Sec. 4) and in accordance with Sec. 16(b) of this contract. This work shall include any maintenance and/or damage repairs specified in Sections 3000, 3100, and 3200 necessary to meet the conditions specified in Subsection 3002 and shall be executed in accordance with Subsection 3302 of this section.

The Authorized Officer may grant acceptance of Purchaser's maintenance responsibility in part where certain individual roads or road segments are no longer of any use to the Purchaser's remaining removal operations, providing that all contract requirements as specified under Section 16(b), Special Provisions Sections 3000, 3100, 3200, and 3300 of the maintenance specifications have been completed and a relinquishment of cutting and removal rights on cutting units tributary to these roads is signed by the Purchaser. Request for partial acceptance must be submitted in writing by the Purchaser.

3302

The Purchaser shall perform final road maintenance only when weather or soil moisture conditions are suitable for normal maintenance equipment operations as determined by the Authorized Officer.

If final maintenance is delayed after the date required in Subsection 3301 of this contract by adverse soil moisture or unsuitable equipment operating conditions, the Purchaser will be notified by the Authorized Officer when soil moisture and equipment operating conditions are suitable. The Purchaser shall then be required to complete final maintenance within 30 days.

OTHER MAINTENANCE - 3400

3401

The Purchaser shall repair any damage to road surfaces that was specified under Subsections 3108 and 3108a. This repair includes restoring the roadway to the designed standard and replacement of surfacing with approved surface material. This repair is not limited to use of equipment specified in Subsection 3104.

3402

The Purchaser shall be permitted to remove ice and snow from roads authorized for use under this contract only when prior written approval has been secured from the Authorized Officer. The Purchaser shall submit a written request for permission to remove ice and snow in advance of the date operations are to begin.

3420

The Purchaser shall perform the following work:

Road No.

Work

27-12-3.1

Construct water bars in accordance with Sheet No. 2 of the Exhibit D and as directed by the Authorized Officer.

Seed, fertilize, and mulch all water bars in accordance with Section 1800 of the Exhibit C.

Re-establish tanktrap at Sta. 1+70.

Seed, fertilize, and mulch tanktrap in accordance with Section 1800 of the Exhibit C.

27-12-10.1

Construct water bars from MP 0.00 to Sta. 18+35 in accordance with Sheet No. 2 of the Exhibit D and as directed by the Authorized Officer.

Seed, fertilize, and mulch all water bars in accordance with Section 1800 of the Exhibit C.

27-12-15.3

Construct water bars from Sta. 0+00 to Sta. 31+50 in accordance with Sheet No. 2 of the Exhibit D and as directed by the Authorized Officer.

. Scarify fu

Scarify full width of subgrade to a depth of 12" and pullback any bermed excavation from Sta. 31+50 to Sta. 43+20.

Seed, fertilize, and mulch all scarified and disturbed areas in accordance with Section 1800 of the Exhibit C.

Road No.	
	Construct riprap barrier at the junction with Fairview-Sumner Lane in accordance with Sheet No. 2 of the Exhibit D and as directed by the Authorized Officer. Riprap shall be keyed in place per Note No. 9 of Sheet No. 2, and meet the gradation requirements listed in Section 1403 of the specifications.
27-12-15.4	Construct water bars in accordance with Sheet No. 2 of the Exhibit D and as directed by the Authorized Officer.
27-12-15.5	Scarify full width of subgrade to a depth of 12" and pullback any bermed excavation. Seed, fertilize, and mulch all scarified and disturbed areas in accordance with Section 1800 of the Exhibit C.
27-12-15.6	Construct water bars in accordance with Sheet No. 2 of the Exhibit D and as directed by the Authorized Officer.
27-12-15.7	Construct water bars in accordance with Sheet No. 2 of the Exhibit D and as directed by the Authorized Officer.
27-12-15.8	Scarify full width of subgrade to a depth of 12" and pullback any bermed excavation. Seed, fertilize, and mulch all scarified and disturbed areas in accordance with Section 1800 of the Exhibit C.
. 27-12-15.9	Construct water bars in accordance with Sheet No. 2 of the Exhibit D and as directed by the Authorized Officer.
27-12-15.10	Scarify full width of subgrade to a depth of 12" and pullback any bermed excavation. Seed, fertilize, and mulch all scarified and disturbed areas in accordance with Section 1800 of the Exhibit C.
	Construct riprap barrier at the junction with Road No. 27-12-3.1 in accordance with Sheet No. 2 of the Exhibit D and as directed by the Authorized Officer. Riprap shall be keyed in place per Note No. 9 of Sheet No. 2, and meet the gradation requirements listed in Section 1403 of the specifications.
27-12-15.11	Construct water bars in accordance with Sheet No. 2 of the Exhibit D and as directed by the Authorized Officer. Construct riprap barrier at the junction with Fairview-Sumner Lane in accordance with Sheet No. 2 of the Exhibit D and as directed by the Authorized Officer. Riprap shall be keyed in place per Note No. 9 of Sheet No. 2, and meet the gradation requirements listed in Section 1403 of the specifications.
Spur No. 1	Scarify full width of subgrade to a depth of 12" and pullback any bermed excavation. Seed, fertilize, and mulch all scarified and disturbed areas in accordance with Section 1800 of the Exhibit C.
Spur No. 2	Scarify full width of subgrade to a depth of 12" and pullback any bermed excavation. Seed, fertilize, and mulch all scarified and disturbed areas in accordance with Section 1800 of the Exhibit C.
	Construct riprap barrier at the junction with Fairview-Sumner Lane in accordance with Sheet No. 2 of the Exhibit D and as directed by the Authorized Officer. Riprap shall be keyed in place per Note No. 9 of Sheet No. 2, and meet the gradation requirements listed in Section 1403 of the specifications.

SALE NO. ORC00-TS 2016.0002 STEELE 15 CT EXHIBIT D Sheet 9 of 9 Sheets

Road No.	Work
Spur No. 4	Scarify full width of subgrade to a depth of 12" and pullback any bermed excavation. Seed, fertilize, and mulch all scarified and disturbed areas in accordance with Section 1800 of the Exhibit C.
Spur No. 5	Construct water bars in accordance with Sheet No. 2 of the Exhibit D and as directed by the Authorized Officer.

\$20,034.60

ROAD MAINTENANCE APPRAISAL

SALE NO. ORC00-TS-2016.0002 SALE NAME: Steele 15 CT

ROAD NUMBERS	MILES
Fairview-Sumner Lane	1.2
27-12-3.1 27-12-9.6 27-12-10.1 27-12-15.0 27-12-15.3 27-12-15.4 27-12-15.5 27-12-15.6 27-12-15.7 27-12-15.8 27-12-15.9 27-12-15.10 27-12-15.11	0.3 0.2 0.3 0.5 0.7 0.3 0.2 0.2 0.5 0.2 0.2
Spur No. 1 Spur No. 2 Spur No. 4 Spur No. 5	0.1 0.1 0.1 0.1

5.5

-SUMMARY-

1.	MOVE IN:	\$1,079.00
2.	CULVERTS, SLOUGH, SLUMPS, & MISC	\$3,344.00
3.	GRADING FOR TIMBER HAUL	\$3,212.00
4.	GRADING FOR AGGREGATE HAUL	\$0.00
5.	MAINTENANCE ROCK	\$6,529.60
6.	OTHER MAINTENANCE	\$5,870.00

TOTAL MAINTENANCE:

ROAD MAINTENANCE APPRAISAL

SALE NO. ORC00-TS-2016.0002

SALE NAME: Steele 15 CT

-APPRAISAL WORKSHEET-

1.	MOVE-IN: EQUIPMENT		MOVE-INS	COST/MOVE	
	GRADER BACKHOE W/ FE LOAD DUMP TRUCK	DER	1 1 1	\$483.00	\$483.00 \$483.00 \$113.00
				TOTAL =	\$1,079.00
2.	CULVERT MAINT., SLC	OUGH REMOVAL	., SLUMP REPA	IRS, ETC.	
	MAINT. OBLIGATION 5.50	MILES @	AVE. COST \$608.00	/ MILE =	\$3,344.00
3.	GRADING FOR TIMBER UNIT #	R HAUL GRADINGS 1	5.5	S ACC. MILES 5.5	
	5.5	MILES @	TOTAL MILES \$584.00	5.5 / MILE =	\$3,212.00
4.	GRADING FOR AGGRE	EGATE HAUL: MILES @		/ MILE =	
5.	MAINTENANCE ROCKS	1-1/2"	APPR FROM	Jarvis MILES	
ROYALTY PROCESSING SLOW HAUL MED. HAUL	230	CU. YDS. @ CU. YDS. @ CU. YDS. @ CU. YDS. @	\$10.00 \$0.90 \$2.21 \$1.10	25	\$2,300.00 \$207.00 \$0.00 \$0.00
FAST HAUL		CU. YDS. @	\$0.49	18.0 TOTAL =	\$2,028.60 \$4,535.60
	SIZE	3-0"	APPR FROM	Jarvis	
ROYALTY PROCESSING SLOW HAUL MED. HAUL FAST HAUL	100 - - 100	CU. YDS. @ CU. YDS. @ CU. YDS. @ CU. YDS. @ CU. YDS. @	\$10.00 \$0.90 \$2.21 \$1.10 \$0.49		\$1,000.00 \$90.00 \$0.00 \$22.00 \$882.00 \$1,994.00
				IOIAL	Ψ1,337.00

ROAD MAINTENANCE APPRAISAL

		0.122.1.1.1.2.0100.0.10.0.1	
6.	OTHER MAINTENANCE:		
	27 12 2 1		
	<u>27-12-3.1</u> Waterbars	\$300.00	
	Soil Stabilization	\$200.00	
	Tanktrap	\$100.0 <u>0</u>	
	Tariktap	<u>\$150.00</u>	\$600.00
	<u>27-12-10.1</u>		*
	Waterbars	\$300.00	
	Soil Stabilization	<u>\$100.00</u>	
			\$400.00
	<u>27-12-15.3</u>		
	Waterbars	\$500.00	
	Scarification	\$360.00	
	Soil Stabilization	\$200.00	
	Riprap Barrier	<u>\$250.00</u>	# 4.040.00
	07.40.45.4		\$1,310.00
	<u>27-12-15.4</u>	\$0.40.00	
	Waterbars	<u>\$240.00</u>	\$240.00
	<u>27-12-15.5</u>		Φ240.00
	Scarification	\$270.00	
	Soil Stabilization	\$300.00	
	Con Clabinzation	<u>Φ000.00</u>	\$570.00
	<u>27-12-15.6</u>		ψο10.00
	Waterbars	<u>\$100.00</u>	
		<u> </u>	\$100.00
	<u>27-12-15.7</u>		·
	Waterbars	<u>\$300.00</u>	
			\$300.00
	<u>27-12-15.8</u>		
	Scarification	\$280.00	
	Soil Stabilization	<u>\$200.00</u>	
	07.40.47.0		\$480.00
	<u>27-12-15.9</u>	# 400.00	
	Waterbars	<u>\$120.00</u>	¢400.00
	<u>27-12-15.10</u>		\$120.00
	Scarification	\$270.00	
	Soil Stabilization	\$110.00	
	Riprap Barrier	\$250.00	
	Tapiap Barrior	<u>φ230.00</u>	\$630.00
	<u>27-12-15.11</u>		φοσοίσο
	Waterbars	\$60.00	
	Riprap Barrier	\$250.0 <u>0</u>	
			\$310.00
	Spur No. 1		
	Scarification	\$90.00	
	Soil Stabilization	<u>\$60.00</u>	
			\$150.00
	Spur No. 2	A	
	Scarification	\$150.00	
	Soil Stabilization	\$60.00	¢400.00
	Riprap Barrier	<u>\$250.00</u>	\$460.00
	Spur No. 4		
	Scarification	\$80.00	
	Soil Stabilization	\$60.00 \$60.00	
	Con Clabinzation	<u>ψου.υυ</u>	\$140.00
	Spur No. 5		ψ170.00
	Waterbars	<u>\$60.00</u>	
		<u> </u>	\$60.00
		TOTAL :	\$5,870.00
			45,510.00

EXHIBIT E

Steel 15 SALE NAME

NET MBF

6996

OR00-TS- ORC00-TS-2016.0002

A. ROAD USE FEES - Payable to Private Company:

	AGREEMENT	ROAD	NET	USE FEE	TOTAL
COMPANY NAME:	NUMBER:	NUMBER	MBF	per MBF	FEES:
CCSC	C-957	27-12-3.1	375	\$2.00	\$750.00
CCSC	C-957	27-12-9.6	375	\$0.00	\$0.00
CCSC	C-957	27-12-10.1	409	\$2.00	\$818.00
			TOTAL USE FEE:		\$1,568.00

B. MAINTENANCE FEES:

- 1. Maintenance and Rockwear Fees Payable to the U.S. (BLM Maintained Roads):
 - a. Timber Haul:

				SURFACE		REGULAR		
Surface		NET	,ROAD	REPLACEMENT	M	1AINTENANC	Е	TOTAL
Туре	ROAD NUMBER:	MBF	MILES:	/MBF/Mile	Subtotal	/MBF/Mile	Subtotal	FEE:
			0		\$0.00		\$0.00	\$0.00

2. ROCKWEAR Fees Payable to the U.S. (OPERATOR Maintained Roads):

	a. Timber Haul:			SURFACE	
Surface		NET	ROAD	REPLACEMENT	ROCKWEAR
Туре	ROAD NUMBER:	MBF	MILES:	/MBF/Mile	Subtotal
Dirt	27-12-15.10	153	0.1	\$0.00	\$0.00
Dirt	27-12-15.10	324	0.07	\$0.00	\$0.00
Rock	27-12-9.6-A	375	0.08	\$0.49	\$14.70
Rock	27-12-15.11	68	0.03	\$0.49	\$1.00
Rock	27-12-15.11	476	0.06	\$0.49	\$13.99
Dirt	Spur 2	102	0.09	\$0.00	\$0.00
Rock	27-12-15.7	238	0.1	\$0.49	\$11.66
Rock	27-12-15.7	527	0.1	\$0.49	\$25.82
Rock	27-12-15.9	204	0.08	\$0.49	\$8.00
Rock	Spur 5	153	0.05	\$0.49	\$3.75
Rock	27-12-15.9	357	0.13	\$0.49	\$22.74
Rock	27-12-15.7	1190	0.11	\$0.49	\$64.14
Dirt	27-12-15.8	171	0.18	\$0.00	\$0.00
Rock	27-12-15.7	1702	0.12	\$0.49	\$100.08
Dirt	27-12-15.3	306	0.09	\$0.00	\$0.00
Rock	27-12-15.3	2008	0.12	\$0.49	\$118.07
Rock	27-12-15.3	2365	0.12	\$0.49	\$139.06
Rock	27-12-15.6	561	0.12	\$0.49	\$32.99
Dirt	Spur 4	85	0.05	\$0.00	\$0.00
Rock	27-12-15.6	936	0.04	\$0.49	\$18.35
Rock	27-12-15.3	3301	0.19	\$0.49	\$307.32
Dirt	27-12-15.5	137	0.03	\$0.00	\$0.00
Dirt	27-12-15.5	274	0.07	\$0.00	\$0.00
Dirt	27-12-15.5	564	0.07	\$0.00	\$0.00
Rock	27-12-15.4	544	0.06	\$0.49	\$15.99
Rock	27-12-15.4	731	0.13	\$0.49	\$46.56
Rock	27-12-15.4	1089	0.13	\$0.49	\$69.37
Rock	27-12-15.3	4954	0.17	\$0.49	\$412.67
Dirt	Spur 1	188	0.06	\$0.00	\$0.00
Rock	27-12-15.0	409	0.45	\$0.49	\$90.18
Rock	27-12-9.6B	375	0.06	\$0.49	\$11.03
		Ţ 1	3.3		\$1,527.47

3. ROAD MAINTENANCE AND/OR ROCKWEAR FEES - Payable to Private Company:

MAINTENANCE AND/OR

Surface Type	COMPANY NAME:	AGREEMENT NUMBER:	ROAD NUMBER	NET MBF	ROAD MILES:	ROCKWEAR FEE /MBF/MILE	TOTALS:
Dirt	ccsc	C-957	27-12-3.1-C	51	0.3	\$0.00	\$0.00
Rock	CCSC	C-957	27-12-9.6-B	375	0.06	\$0.00	\$0.00
Dirt	ccsc	C-957	27-12-10.1	85	0.10	\$0.00	\$0.00
Dirt	CCSC	C-957	27-12-10.1	221	0.10	\$0.00	\$0.00
Dirt	CCSC	C-957	27-12-10.1	221	0.15	\$0.00	\$0.00
	<u> </u>	<u> </u>	<u> </u>		0.7	I	\$0.00

4. OPERATOR MAINTENANCE WILL BE REQUIRED ON APPROX. 4.9 MILES OF ROAD. (SEE EXHIBIT D)

	SALE VOLUME:	6996	MBF.		ROCKV	VEAR	MAINTE	NANCE
			RO	AD USE FEES:	FE)	ES .	FEI	ES
SUMMARY	OF ROAD USE & ROAD N	AINTENA	N TOTAL:	\$ /MBF	TOTAL:	\$/MBF	TOTAL:	\$/MBF:
1. COMPAN	NY-OWNED ROADS:		\$1,568.00	\$0.22	\$0.00	\$0.00		\$0.00
2. BLM-MA	INTAINED ROADS:				\$0.00	\$0.00	\$0.00	\$0.00
3. OPERAT	OR-MAINTAINED ROADS	:			\$1,527.47	\$0.22		\$0.00
			\$1,568.00	\$0.22	\$1,527.47	\$0.22	\$0.00	\$0.00

MAINTENANCE OBLIGATION PAYABLE TO BLM \$1,527.47

0.2183348

Exhibit F
Sheet 1 of 1

SPECIAL PROVISIONS TO CONTROL THE SPREAD OF NOXIOUS WEEDS

Vehicle and Equipment Cleaning

- 1. Cleaning shall consist of the removal of soil and debris by washing with a high pressure hose or steam cleaning. Cleaning and inspection sites will be agreed to by Purchaser and BLM. All petroleum product residues shall be contained at wash sites and dealt with in accordance to DEQ standards. Contractor shall provide an approved plan for the cleaning station that demonstrates that the station meets all DEQ and water quality regulations. All necessary permits shall be obtained by the contractor.
- 2. All equipment parts shall be cleaned as designated by the Authorized Officer, including removal of tractor belly plates, in accordance with Sec. 1 above.

All construction, logging and slash disposal equipment shall be cleaned prior to entering the contract area. The Authorized Officer will determine if log trucks and vehicles used for transportation of personnel shall be cleaned, based upon the location of use immediately prior to current timber sale. If the vehicles have been in a weed-infested area, they shall be washed before entering Contract Area, as shown on Exhibit A.

Bid, offer, or contract number or other identification

UNITED STATES DEPARTMENT OF THE INTERIOR BUREAU OF LAND MANAGEMENT

EQUAL OPPORTUNITY IN EMPLOYMENT CERTIFICATION OF NONSEGREGATED FACILITIES

By the submission of this bid or offer and/or by entering into this contract, the bidder, offeror, lessee, subcontractor, or applicant certifies that he does not maintain or provide for his employees any segregated facilities at any of his establishments, and that he does not permit his employees to perform their services at any location, under his control, where segregated facilities are maintained. He certifies further that he will not maintain or provide for his employees any segregated facilities at any of his establishments, and that he will not permit his employees to perform their services at any location, under his control, where segregated facilities are maintained. The bidder, offeror, applicant, or subcontractor agrees that a breach of this certification is a violation of the Equal Opportunity clause in this contract. As used in this certification, the term "segregated facilities" means, but is not limited to, any waiting rooms, work areas, rest rooms and wash rooms, restaurants and

other eating areas, time clocks, locker rooms and other storage or dressing areas, parking lots, drinking fountains, recreation or entertainment areas, transportation, and housing facilities provided for employees which are segregated by explicit directive or are in fact segregated on the basis of race, color, religion, sex, or national origin, because of habit, local custom, or otherwise. He further agrees that (except where he has obtained identical certifications from proposed subcontractors for specific time periods) he will obtain identical certifications from proposed subcontractors prior to the award of subcontracts exceeding \$10,000 which are not exempt from the provisions of the Equal Opportunity clause; that he will retain such certifications in his files; and that he will forward the following notice to such proposed subcontractors (except where the proposed subcontractors have submitted identical certifications for specific time periods):

NOTICE TO PROSPECTIVE SUBCONTRACTORS OF REQUIREMENT FOR CERTIFICATIONS OF NONSEGREGATED FACILITIES

A Certification of Nonsegregated Facilities, as required by the May 9, 1967, order (32 F.R. 7439, May 19, 1967) on Elimination of Segregated Facilities, by the Secretary of Labor, must be submitted prior to the award of a subcontract exceeding \$10,000 which is not exempt from the provisions of the Equal Opportunity clause. The certification may be submitted either for each subcontract or for all subcontracts during a period (i.e., quarterly, semiannually, or annually).

In accordance with 41 CFR 60, as amended May 19, 1967, and Executive Order No. 11246 of September 24, 1965, as amended, this certification is applicable to all bids, offers, contracts and subcontracts as well as agreements with applicants who are themselves performing federally assisted contracts, which may exceed \$10,000 and are not exempt from the provisions of the Equal Opportunity clause of the Order.

- 1. AUTHORITY Timber located on the revested Oregon and California Railroad Grant Lands and on the reconveyed Coos Bay Wagon Road Grant Lands is administered and sold pursuant to authority of the Act of August 28, 1937 (50 Stat. 874; 43 U.S.C. 1181a); timber located on other lands and other vegetative resources on all public lands of the United States under jurisdiction of the Bureau of Land Management are administered and sold pursuant to authority of the Act of July 31, 1947 (61 Stat. 681), as amended, by the Act of July 23, 1955 (69 Stat. 367; 30 U.S.C. 601 et. seq.). Regulations of the Secretary of the Interior governing sale of timber are codified in 43 CFR Group 5400.
- 2. QUALIFICATIONS OF BIDDERS—A bidder for sale of timber/vegetative resources must be either (a) a citizen of the United States, (b) a partnership composed wholly of such citizens, (c) an unincorporated association composed wholly of such citizens, or (d) a corporation authorized to transact business in the State in which the timber/vegetative resource is located.
- 3. INSPECTION OF TIMBER/VEGETATIVE RESOURCES—Bidder is invited, urged, and cautioned to inspect the timber/vegetative resource prior to submitting a bid. By executing the timber/vegetative resource sale contract, bidder warrants that the contract is accepted on the basis of his examination and inspection of the timber/vegetative resource and his opinion of its value.
- 4. DISCLAIMER OF WARRANTY—Government expressly disclaims any warranty of the fitness of the designated timber/vegetative resource for any purpose of the bidder; all timber/vegetative resources are to be sold "As Is" without any warranty of merchantability by Government. Any warranty as to the quantity or quality of timber/vegetative resource to be sold is expressly disclaimed by Government.
- 5. *BIDS* Sealed or written bids for not less than the advertised appraised price, per timber/vegetative resource must be submitted in duplicate to the District Manager who issued *Timber/Vegetative Resource Sale Notice*.
- (a) Sealed Bid Sales Bids will be received until time for opening which is set out in the Notice. Enclose both copies of bid with required bid deposit in a sealed envelope marked on the outside Bid for Timber/Vegetative Resources, time bid is to be opened, tract number, and legal description of land on which timber/vegetative resource is located. In event of a tie, the high bidder shall be determined by lot from among those who submitted the tie bids.
- (b) Auction Sales Submission of the required bid deposit and a written bid is required to qualify for oral bidding. Oral bidding shall begin from the highest written bid. No oral bid will be considered which is not higher than the preceding bid. In the event there is a tie in high written bids, and no oral bidding occurs, the bidder who was the first to submit his bid deposit and written bid shall be declared the high bidder. If the officer conducting the sale cannot determine who made the first submission of high tie written bids, the high bidder shall be determined by lot. High bidder must confirm his bid, in writing, immediately upon being declared high bidder.
- (c) Except as otherwise provided in 43 CFR 5442.2, bids will not be considered in resale of timber/vegetative resource remaining from an uncompleted contract from any person or affiliate of such person who failed to complete the original contract because of (1) cancellation for the purchaser's breach or (2) through failure to complete payment by expiration date.
- (d) When it is in the interest of the Government to do so, it may reject any and all bids and may waive minor deficiencies in bids or in sale advertisement.
- 6. BID FORMS—All sealed, written bids, and confirmation of oral bids shall be submitted on forms provided by Government.
- (a) Lump Sum Sales Bids shall specify (1) Bureau of Land Management estimated volume, (2) price per unit, and (3) total purchase price. Estimated volume and price per unit are to be used for administrative and appraisal purposes only. Upon award of contract, high bidder shall be liable for total purchase price, including any adjustment which may be made as a result of reappraisal if an extension of time is granted, even though quantity of timber/vegetative resource actually cut, removed, or designated for taking is more or less than the estimated volume or quantity listed.
- (b) Timber Scale Sales Bids must state price per thousand board feet that will be paid for each species. High bidder will be determined by multiplying bid price per thousand board feet per species by Bureau of Land Management

- estimate of volume of each species. Purchaser shall be liable for purchase price of all merchantable timber sold under contract even though all such timber is not actually cut and removed prior to expiration of time for cutting and removal as specified in contract.*
- 7. BID DEPOSIT—All bidders must make a deposit of not less than the amount specified in the Timber/Vegetative Resource Notice. Deposit may be in the form of cash, money orders, bank drafts, cashiers or certified checks made payable to the Department of the Interior—BLM, bid bonds of a corporate surety shown on the approved list of the United States Treasury Department*, or any approved guaranteed remittance approved by the Contracting Officer. Upon conclusion of bidding, the bid deposit of all bidders, except high bidder, will be returned. The cash deposit of the successful bidder may be applied toward the required sale deposit and/or the purchase price. Cash not applied to the sale deposit or the purchase price, or a corporate surety bid bond, will be returned at the time the contract is signed by the Government.
- 8. AWARD OF CONTRACT Government may require high bidder to furnish such information as is necessary to determine the ability of bidder to perform the obligation of contract. Contract will be awarded to high bidder, unless he is not qualified or responsible or unless all bids are rejected. If high bidder is not qualified or responsible or fails to sign and return the contract together with required performance bond and any required payment, contract may be offered and awarded to the highest bidders qualified, responsible, and willing to accept the contract.
- 9. TIMBER/VEGETATIVE RESOURCE SALE CONTRACT To be executed by purchaser, has been prepared by Government, and may be examined in the District Manager's office.

10. PERFORMANCE BOND-

- (a) A performance bond in an amount of not less than 20 percent of total purchase price is required, but the amount of the bond shall not be in excess of \$500,000, except when the purchaser opts to increase the minimum bond to permit cutting prior to payment as provided in 43 CFR 5451.2, or in the event the purchaser is a holder of an unresolved default the bond may be increased as provided in 43 CFR 5450.1(b). Performance bond may be (1) bond of a corporate surety shown on approval list issued by the United States Treasury Department and executed on an approved standard form, (2) personal surety bond executed on an approved standard form if Government determines principals and bondsman are capable of carrying out the terms of the contract, (3) cash bonds, (4) negotiable securities of the United States, or (5) any guaranteed remittance approved by the Contracting Officer.
- (b) If purchaser elects to cut timber without skidding or yarding it to a loading point or removing it prior to the payment of the second or subsequent installments, Government shall require an increase in amount of performance bond initially required by an amount equal to the value of timber to be cut. Such increase must be on a bond rider form supplied by Government and be approved, in writing, by Government prior to cutting timber covered by the bond increase. This increased amount of bond shall be used to assure payment for timber cut in advance of payment.*
- 11. PAYMENT BOND—If purchaser elects to (a) cut and remove timber, or (b) remove timber already cut which has been secured by an increased performance bond as provided in paragraph 10(b) above, before payment of the second or subsequent installments, Government shall require a payment bond on a form supplied by Government. Purchaser shall obtain written approval from Government of payment bond prior to cutting and/or removal of timber covered by the bond. Payment bond shall be used to assure payment for timber cut and/or removed in advance of payment.*
- 12. PAYMENT OF PURCHASE PRICE—For sales of \$500 or more, Government may allow payment by installments. Except as discussed in paragraphs 10 and 11 above, no part of any timber/vegetative resource sold may be severed, cut, or removed unless advance payment has been made as provided in contract.
- 13. LIQUIDATED DAMAGES Within thirty (30) days from receipt of *Timber/Vegetative Resources Sale Contract*, the successful bidder shall sign contract and return it to Government, together with required bond and any required payment. If successful bidder fails to comply within the stipulated time, his bid deposit shall be retained by Government as liquidated damages.

- 14. NINETY-DAY SALES If no bid is received within time specified in the advertisement of sale and if Government determines that there has been no significant rise in the market value of timber/vegetative resource, it may, in its discretion, keep the sale open, not to exceed ninety (90) days.
- 15. UNAUTHORIZED USE OF GOVERNMENT PROPERTY—A sale may be refused to high bidder who has been notified that he has failed to make satisfactory arrangements for payment of damages resulting from unauthorized use of, or injury to, property of the United States.
- 16. EQUAL OPPORTUNITY CLAUSE—This contract is subject to the provisions of Executive Order No. 11246 of September 24, 1965, as amended, which sets forth the nondiscrimination clauses. Copies of this order may be obtained from the District Manager. 43 CFR 60-1.7(b) requires that the Equal Opportunity Compliance Report Certification will be completed by prospective contractors. Certification may be obtained from District Manager.
- 17. LOG EXPORT All timber offered for sale except as noted in the *Timber Sale Notice* is restricted from export from the United States in the form of unprocessed timber and cannot be used as a substitute for exported private timber. For the purpose of this contract, unprocessed timber is defined as: (1) any logs except those of utility grade or below, such as sawlogs, peeler logs, and pulp logs; (2)
- cants or squares to be subsequently remanufactured exceeding eight and three quarters (8-3/4) inches in thickness; (3) split or round bolts or other roundwood not processed to standards and specifications suitable for end product use; or (4) western red cedar lumber which does not meet lumber of American Lumber Standards Grades of Number 3 dimensions or better, or Pacific Lumber Inspection Bureau R-List Grades of Number 3 common or better. Timber manufactured into the following will be considered processed: (1) lumber and construction timbers, regardless of size, manufactured to standards and specifications suitable for end product uses; (2) chips, pulp and pulp products; (3) green or dry veneer and plywood; (4) poles and piling cut or treated for use as such; (5) cants, squares, and lumber cut for remanufacture of eight and three quarters (8-3/4) inches in thickness or less; or (6) shakes and shingles. In event purchaser wishes to sell any or all of timber restricted from export in the form of unprocessed timber, the buyer, exchanges, or recipient shall be required to comply with contractual provisions relating to "unprocessed timber". Special reporting, branding and painting of logs may be included in contract provisions.*
- 18. DETAILED INFORMATION Detailed information concerning contract provisions, bid, performance bond forms, tract location maps, and access conditions may be obtained from the District Manager. All persons interested in bidding on the products listed are encouraged to familiarize themselves with all such detailed information.

Form 5440-9 (November 2011)

UNITED STATES DEPARTMENT OF THE INTERIOR BUREAU OF LAND MANAGEMENT

☑ TIMBER or TIMBER AND OTHER WOOD PRODUCTS

DEPOSIT AND BID FOR

 □ VEGETATIVE RESOURCES (Other Than Timber)

Name of Bidder	
Tract Number 16-02	
Sale Name Steele 15 CT	
Sale Notice (dated)	
November 19, 2015	
BLM District	

7	(Other 1	nan minber			Coos Bay Distri	ict
☐ Sealed Bid for Sealed	Bid Sale		☑ Writte	n Bid for Oral	Auction Sale	
Time for opening sealed b	ids 🔲 a.m.	☐ p.m.	Sale comm	nences 10:00	🗹 a.m.	□ p.m.
On (date)	Place		On (date)	12/18/2015	Place	Conf Rm A
In response to the above timber/vegetative resource			it and bid an	e hereby sub	mitted for the p	ourchase of designated
Required bid deposit is \$154,400.00 and is enclosed in the form of: cash money order cashier's check certified check bank draft						
bid bond of corporate sur				anteed remittane	ce approved by the	e authorized officer.

IT IS AGREED That the bid deposit shall be retained by the United States as liquidated damages if the bid is accepted and the undersigned fails to execute and return the contract, together with any required performance bond and any required payment within 30 days after the contract is received by the successful bidder. It is understood that no bid for less than the appraised price on a unit basis per species will be considered. If the bid is rejected the deposit will be returned.

BID SCHEDULE - LUMP SUM SALE

NOTE: Bidders should carefully check computations in completing the Bid Schedule

	В	ID SUBMITTED			ORAL	ORAL BID MADE	
PRODUCT SPECIES	UNIT	ESTIMATED VOLUME OR QUANITY	UNIT PRICE	TOTAL VALUE	UNIT PRICE	TOTAL VALUE	
Douglas-fir	MBF	6,452	х	≣(х	=	
Red alder	MBF	494	х	=	х	¥	
Western redcedar	MBF	28	х	= 1	х	/E	
Grandfir	MBF	15	х	see /	·x	=	
Western hemlock	MBF	7	х	as a	х	· #	
			х	A	х	N=	
			х	#	х	=	
			х	==	х	=	
			х	#	х	=	
			х	=	х	=:	
			х	*	х	#1	
			х	=	X	m)	
			х	=	Х	=	
			х	=	X	#	
			Х	=	х	#	
			х	=	Х	в.	
		TOTAL PURC	HASE PRICE				

If sale contract is executed, undersigned is liable for total purchase price even though the quantity cut, removed, or designated for taking is more or less than the total estimated volume or quantity shown above. Undersigned certifies bid was arrived at by bidder or offeror independently, and was tendered without collusion with any other bidder or offeror. In submitting or confirming this bid, undersigned agrees to the foregoing provisions, applicable regulations, and certifies that he is authorized to act as, or on behalf of, the bidder.

ink, and complete the following)
ina, una complete ine following)
Name of firm (type or print)
Business address, include zip code (type or print)
(To be completed following oral bidding) I HEREBY confirm the above oral bid
By (signature)
Date
Sealed Bid – Send to District Manager, who issued the sale notice, in a sealed envelope marked on the outside: (1) "Bid for Timber" or (1a) "Vegetative Resources Other Than Timber" (2) Time bids are to be opened (3) Legal description
_

NOTICES

The Privacy Act and 43 CFR 2.48(d) require that you be furnished with the following information in connection with the information required by this form.

AUTHORITY: 38 FR 6280 and 43 CFR 5442.1

PRINCIPAL PURPOSE: To qualify an oral auction bidder, and then if successful, to bind bidder to certain contract conditions.

ROUTINE USES: To determine that an individual is qualified to participate in oral auction bidding, and, as surety that bidder will fulfill contract requirements.

EFFECT OF NOT PROVIDING INFORMATION: Filing this deposit and bid information is necessary only when an individual wishes to participate in a sealed or auction bid sale for timber or vegetative resources.

(Continued on page 3)

(Form 5440-9, page 2)

Form 5440-9 (November 2011)

UNITED STATES DEPARTMENT OF THE INTERIOR BUREAU OF LAND MANAGEMENT

☑ TIMBER or TIMBER AND OTHER WOOD PRODUCTS

DEPOSIT AND BID FOR

□ VEGETATIVE RESOURCES (Other Than Timber)

Name of Bidder	
Tract Number 16-02	
Sale Name Steele 15 CT	
Sale Notice (dated) November 19, 2015	
BLM District Coos Bay District	

Sealed Bid for	Sealed Bid Sale			☑ Written Bid for Oral Auction Sale				
Time for opening s	sealed bids	☐ a.m.	□ p.m.	Sale comm	nences 10:00	🗹 a.m.	□ p.m.	
On (date)	Place			On (date)	12/18/2015	Place	Conf Rm A	
	e above dated Sale resource on the trac			it and bid ar	e hereby sub	mitted for the p	ourchase of designated	
	it is \$154 order ashier's chorate surety on approv		check bank	draft	in the form of:	e approved by the	authorized officer.	

IT IS AGREED That the bid deposit shall be retained by the United States as liquidated damages if the bid is accepted and the undersigned fails to execute and return the contract, together with any required performance bond and any required payment within 30 days after the contract is received by the successful bidder. It is understood that no bid for less than the appraised price on a unit basis per species will be considered. If the bid is rejected the deposit will be returned.

BID SCHEDULE - LUMP SUM SALE

NOTE: Bidders should carefully check computations in completing the Bid Schedule

	ORAL	BID MADE				
PRODUCT SPECIES	UNIT	ESTIMATED VOLUME OR QUANITY	UNIT PRICE	TOTAL VALUE	UNIT PRICE	TOTAL VALUE
Douglas-fir	MBF	6,452	х	500	X	.=:
Red alder	MBF	494	х	=	х	¥
Western redcedar	MBF	28	х	18	Х	in .
Grandfir	MBF	15	х	=	·X	¥
Western hemlock	MBF	7	х	18	Х	F
			х		х	=
			х	=	Х	=
			х	=	х	=
			х	=	Х	, E.
			х	20	Х	=
			Х	==	х	E
			х	## ()	X	E
			х	3	Х	/ H
			х	*	Χ -	tt
			Х	1 11	Х	=
			х	==	Х	=
		TOTAL PURC	HASE PRICE			

If sale contract is executed, undersigned is liable for total purchase price even though the quantity cut, removed, or designated for taking is more or less than the total estimated volume or quantity shown above. Undersigned certifies bid was arrived at by bidder or offeror independently, and was tendered without collusion with any other bidder or offeror. In submitting or confirming this bid, undersigned agrees to the foregoing provisions, applicable regulations, and certifies that he is authorized to act as, or on behalf of, the bidder.

Bid submitted on (date)	
(Check appropriate box, sign in	ink, and complete the following)
☐ Signature, if firm is individually owned	Name of firm (type or print)
☐ Signatures, if firm is a partnership or L.L.C.	Business address, include zip code (type or print)
Corporation organized under the state laws of	(To be completed following oral bidding) I HEREBY confirm the above oral bid
Signature of Authorized Corporate Signing Officer	By (signature)
Title	Date
Submit bid, in <i>duplicate</i> , to qualify for either an oral auction or sealed bid sale together with the required bid deposit made payable to the Department of the Interior – BLM. Oral Auction – Submit to Sales Supervisor prior to closing of qualifying period for tract.	Sealed Bid – Send to District Manager, who issued the sale notice, in a sealed envelope marked on the outside: (1) "Bid for Timber" or (1a) "Vegetative Resources Other Than Timber" (2) Time bids are to be opened (3) Legal description

NOTICES

The Privacy Act and 43 CFR 2.48(d) require that you be furnished with the following information in connection with the information required by this form.

AUTHORITY: 38 FR 6280 and 43 CFR 5442.1

PRINCIPAL PURPOSE: To qualify an oral auction bidder, and then if successful, to bind bidder to certain contract conditions.

ROUTINE USES: To determine that an individual is qualified to participate in oral auction bidding, and, as surety that bidder will fulfill contract requirements.

EFFECT OF NOT PROVIDING INFORMATION: Filing this deposit and bid information is necessary only when an individual wishes to participate in a sealed or auction bid sale for timber or vegetative resources.

(Continued on page 3)

(Form 5440-9, page 2)

Partial

ROW

Total

Regen

UNITED STATES DEPARTMENT OF THE INTERIOR BUREAU OF LAND MANAGEMENT

Timber - Sale - Summary

Legal Description

Forest Type	Township	Range	Section	Subdivision
CBWR	27S	12W	15	N1/2,E1/2SW1/4,SE1/4

Cutting Volume (16' MBF)

1 1		1		l	ľ	1				
1	4,850	400	22	12	6		5,290	0	311	
2	717	59	3	2	1		782	0	46	
3	327	27	2	1			357	0	21	
RW	558	8	1				567	0	0	1
Totals	6,452	494	28	15	7		6,996	0	378	1
	Logging Cost	s per 16' MB	F				Profit & Ri	sk		
C+		-	\$	193,38		Total Profit & Ri	sk		11 %	6
Stump to True			\$	24.03		Basic Profit & Ri	isk 11 % + Additiona	ıl Risk	0 %	
Transportation Road Constru			\$	36.15		Back Off			0 9	%
Road Amortiz			\$	0.22			Tract Featur	res		
Road Mainter			\$	3.08		Avg Log	Douglas-fir: 50 bf	A1	11 : 49 bf	
Other Allowa						Recovery	Douglas-fir : 96 %		11 : 95 %	
			+	0.42		Salvage	Douglas-fir: 0 %		11:0%	
	pullback					.,	.,			0
Misc				4.37		Avg Volume (Avg Yarding Slop	16' MBF per Acre)			8 10 %
Slash Di	sposal			3.08		Avg Yarding Dist			35	
Vehicle '	Washing		\$	0.28		Avg Age	ance (rect)			60
Tot	al Other Allowanc	es:		\$ 8.15		Volume Cable			6	59 %
						Volume Ground			3	31 %
						Volume Aerial				0 %
						Road Construction	on Stations		108.4	10
						Road Improvement	ent Stations		28.5	15
						Road Renovation	Stations		72.5	3
						Road Decomission	on Stations		156.5	0
							Cruise			
						Cruised By			Kirkland, Davi	is
						Date			03/01/201	.5
Total Loggin	ig Costs per 16' M	/RE	ſs	265.02		Type of Cruise			VP, 3P, 1009	%
Total Loggin					,	County, State			Coos, O	R
Center #1 : C		ilization Cen	ters	13 Miles			NI -4 N/-1			
Center #1 : N				9 Miles		Green (16' MBF)	Net Volun	ae	6,99	06
	tance to Utilizati	on Centers		13	3	Salvage (16' MB'			•	0
	Ler	igth of Conti	ract			Sarvage (10 1411)	•)			
Cutting and I	Removal Time			36 Months	3	Douglas-fir Peele	er			0
	perty Removal Ti	ime		1 Months		Export Volume				0
i Cisonai Fior	perty Removal 11					Scaling Allowane	ce (\$0.75 per 16' MBF)		\$5,247.0	00

\$5,247.00

Scaling Allowance (\$0.75 per 16' MBF)

WRC

GF

WH

Unit

DF

RA

UNITED STATES DEPARTMENT OF THE INTERIOR BUREAU OF LAND MANAGEMENT

Coos Bay Steele 15 CT ORC00-TS-2016.0002

Stumpage Summary

Stumpage Computation

Species	Trees	Net Volume	Pond Value	(-) Profit & Risk	(-) Logging Cost	(+) Marginal Log Value	(-) Back Off	Appraised Price	Appraised Value
DF	26,669	6,452	\$ 554.79	\$ 61.03	\$ 265.02			\$ 228.70	\$ 1,475,572.40
RA	3,557	494	\$ 427.99	\$ 47.08	\$ 265.02			\$ 115.90	\$ 57,254.60
WRC	482	28	\$ 642.83	\$ 70.71	\$ 265.02			\$ 307.10	\$ 8,598.80
GF	33	15	\$ 409.00	\$ 44.99	\$ 265,02		_	\$ 99.00	\$ 1,485.00
WH	177	7	\$ 290.68	\$ 31.97	\$ 265.02			\$ 29,10	\$ 203.70
Totals	30,918	6,996							\$ 1,543,114.50

(16' MBF)

Log Code by Percent

Species	Code #1	Code #2	Code #3	Code #4	Code #5	Code #6
Douglas-fir				42.0	50.0	8.0
Red Alder		38.0	31.0	31.0		
Western red-cedar			71.0	29.0		
Grand Fir				75.0	25.0	
Western Hemlock					57.0	43.0

Marginal Log Volume

Species	Grade #7	Grade #8
Douglas-fir		
Red Alder		
Western red-cedar		
Grand Fir		
Western Hemlock		

Appraised By: Kirkland, Travis

Date: 10/05/2015

Area Approval By:

Date:

District Approval By: Davis, Brian

Date: 11/10/2015

Printed: 11/10/2015

UNITED STATES DEPARTMENT OF THE INTERIOR BUREAU OF LAND MANAGEMENT

Prospectus

Appraisal Method: (16' MBF)

Species	Trees	Net Volume 16' MBF	Net Volume 32' MBF	Net Volume CCF
Douglas-fir	26,669	6,452	5,676	
Red Alder	3,557	494	394	
Western red-cedar	482	28	24	
Grand Fir	33	. 15	12	
Western Hemlock	177	7	5	
Total	30,918	6,996	6,111	

All Species

Gross Volume	Number Trees	Avg bf Volume Per Tree	DBH	Gross Merch Volume	Merch Logs	Avg bf Gross Merch Log
7,343	30,918	237	13.7	7,268	149,413	49

Merch	Cull	Total	Logs per	Net	Gross	Recovery
Logs	Logs	Logs	Tree	Volume	Volume	
149,413	5,824	155,237	5.0	6,996	7,343	95 %

Douglas-fir

Gross Volume	Number Trees	Avg bf Volume Per Tree	DBH	Gross Merch Volume	Merch Logs	Avg bf Gross Merch Log
6,725	26,669	252	13.9	6,657	134,292	50

Merch	Cull	Total	Logs per	Net	Gross	Recovery
Logs	Logs	Logs	Tree	Volume	Volume	
134,292	5,413	139,705	5.2	6,452	6,725	96 %

Cutting Areas

	Regen	Partial Cut	Right Of Way	Total
Unit	Acres	Acres	Acres	Acres
1		311		311
2		46		46
3		21		21
RW			11	11
Totals :		378	11	389

Printed: 11/10/2015 9:18:50AM Page 2 of 2