

# PROSPECTUS

## SCALE SALE

### \*SEALED BID AUCTION\*

GRANTS PASS FIELD OFFICE  
JOSEPHINE MASTER UNIT

Medford Sale # ORM07-TS-2020.0004  
January 28, 2021 (SQF)

#1 Blown Fortune Timber Sale, Douglas County, O&C, PD BID DEPOSIT REQUIRED: \$44,900.00

All timber designated for cutting in Lot 11, Lot 14, Lot 15, Lot 17, Lot 18, Lot 19 Sec 3; SE¼SE¼ Sec 4, W½SW¼, SE¼SE¼ Sec 5; N½SW¼, SW¼SW¼ Sec 8; N½NE¼, SE¼NE¼, E½NW¼, N½SE¼ Sec 9; SE¼SW¼ Sec 10; W½NE¼, SE¼NE¼, NW¼, N½SW¼, SE¼SW¼, SE¼ Sec 17; SE¼NE¼, E½SE¼ Sec 18; NE¼, N½NW¼, SE¼NW¼ Sec 31; T. 32 S., R. 5 W.; Willamette Meridian.

Approx. Number Merch. Trees	Est. Volume MBF 32' Log	Species	Est. Volume MBF 16' Log	Appr. Price Per MBF*	Est. Volume Times Appraised Price
28,695	3,705	Douglas-fir	4,432	\$91.50	\$405,528.00
4,134	528	White Fir	608	\$48.50+	\$29,488.00
2,740	186	Incense-cedar	238	\$50.80+	\$12,090.40
583	21	Ponderosa Pine	28	\$28.50+	\$798.00
21	5	Western Hemlock	6	\$47.30+	\$283.80
<b>36,173</b>	<b>4,445</b>	<b>Totals</b>	<b>5,325</b>		<b>\$448,188.20</b>

\*Stumpage values have been determined by market value estimates and analytical appraisal methods were used to compute the appraised price. Additional information concerning the appraised price is available at the Medford District Office.

+Minimum Stumpage values were used to compute the Appraised Price/MBF (10% of Pond Value). Reduced Douglas fir appraised value by \$92,495.84 to pay for deficit species white fir, incense-cedar, ponderosa pine, and western hemlock.

**TIMBER AUCTION LOCATION – SEALED BIDS will be received by the District Manager, or his representative, at the Bureau of Land Management Medford Interagency Office, 3040 Biddle Rd., Medford, Oregon 97504, between 8:00 am and 10:00 am, PACIFIC TIME, on Thursday, January 28th, 2021. Bid proposals should be clearly marked, “ATTN: Sealed bid Blown Fortune Timber Sale”.**

**Bidders must submit A WRITTEN BID on Form 5440-9 on a price per unit (MBF) of the Douglas-fir volume. The bid must not be less than the appraised price of \$91.50/mbf. All other species will be sold at appraised price per unit (MBF).**

CRUISE INFORMATION – Blown Fortune timber sale units were cruised using the PCMTRE method. 514 plots were cruised across 429 acres using a 40 BAF and a 1 in 5 sampling frequency. Roadside units were cruised using the 3P and BLM100% cruise method.

Approximately 0 trees which are considered to be nonmerchantable are designated for cutting. Approximately 0% of the sale volume is salvage material. With respect to merchantable trees of all conifer species: the average tree is 13.8 inches DBHOB; the average gross merchantable log contains 50 bd. ft.; the total gross volume is approximately 5,981 M bd. ft; and 89% recovery is

expected. Average DF is 13.7 inches DBHOB; average gross merchantable log DF contains 51 bd. ft. Cruise plot maps showing the location of these sample tree plots are available at the Medford District Office.

LOG EXPORT AND SUBSTITUTION RESTRICTIONS – All timber sold to the Purchaser under the terms of the contract, except exempted species, is restricted from export under the United States in the form of unprocessed timber and is prohibited from use as a substitute for exported private timber.

The BLM has revised the log export restrictions special provision to reduce the log branding and painting requirements. The new requirements include branding of one end of all logs with a scaling diameter of over 10 inches. All loads of 11 logs or more, regardless of the diameter of the logs, will have a minimum of 10 logs branded on one end. All logs will be branded on loads of 10 logs or less. One end of all branded logs will be marked with yellow paint. At the discretion of the Contracting Officer, the Purchaser may be required to brand and paint all logs. The Purchaser shall bear any increased costs for log branding and painting.

CUTTING AREA – The sale contains a total of Twenty-two (22) units containing four hundred thirty-seven (437) acres. Eighteen (18) units containing four hundred twenty-five (425) acres must be partial cut and one (1) unit containing four (4) acres must be group selection harvested. This includes seven (7) right-of-ways that must be clear-cut. Three (3) units containing eight (8) acres must be treated for roadside management.

CUTTING TIME – Contract duration will be thirty-six (36) months for cutting and removal of timber.

ACCESS – Access to the sale area is available via: a public road system through the contract area; existing BLM roads; Right-of-Way and Road Use Agreement 1960 Memorandum Of Understanding with Oregon Department of Forestry; and Right-of-Way and Road Use Agreement M-824 with Silver Butte Timber Company.

Among other conditions, **Right-of-Way and Road Use Agreement 1960 Memorandum Of Understanding with Oregon Department of Forestry** requires, but is not limited to:

1. Completion of an agreement between the Purchaser and the Permittee.
2. Road maintenance to be completed by the Purchaser.
3. Arbitration of conditions of road use. The Permittee has indicated they require a rockwear obligation of \$432.83, based upon the cruised estimated volume listed in the license agreement. The final rockwear obligation will be based on a \$0.73 per thousand board feet log scale per mile for the use of said rockered roads.

Among other conditions, **Right-of-Way and Road Use Agreement M-824 with Silver Butte Timber Company** requires, but is not limited to:

1. Completion of an agreement between the Purchaser and the Permittee.
2. Road maintenance to be completed by the Purchaser.
3. Prior to cutting or removing any timber from the road right-of-way between Stations 0+00 and 0+35.55 on Road No. 32-5-10.1B, the Purchaser shall pay the total value of that timber as agreed upon.
4. Arbitration of conditions of road use. The Permittee has indicated they require a road use obligation of \$4,533.41, based upon the cruised estimated volume listed in the license agreement. The final road use obligation will be based on a \$22.07 per thousand board feet log scale for the use of Road No. 32-5-10.2B, \$2.00 per thousand board feet log scale for the use of Road No. 32-5-10.2A, and \$2.00 per thousand board feet log scale

for the use of Road No. 32-5-10.1A.

ROAD MAINTENANCE – The Purchaser will be required to maintain all the roads that they construct, plus 22.18 miles of existing BLM and Third Party (Industry) roads listed in Section 3000 of Exhibit D1. An allowance in the amount of \$30,476.54 has been made for the maintenance of these roads. The Purchaser will be required to pay a rockwear fee of \$0.73 per thousand board feet log scale per mile for the use of these rocked roads. BLM will maintain the 0.62 miles of existing bituminous surface road listed in Section 3000 of Exhibit D1. The Purchaser will be required to pay a maintenance fee of \$0.92 per thousand board feet log scale per mile for the use of the bituminous surface road.

ROAD CONSTRUCTION – The Purchaser will be required to construct 11+19 stations of permanent road and 1.43 miles of temporary road.

DECOMMISSIONING – An allowance in the amount of \$10,011.93 has been made for decommissioning. Decommissioning work to be performed is described in Section 3500 of Exhibit D1.

SOIL DAMAGE PREVENTION – Pursuant to Section 26 of Form 5450-4, Timber Sale Contract, mechanical ground based harvesting, ground based yarding, skid trail and landing rehabilitation, machine piling, temporary route construction, temporary route reconstruction, or temporary route decommissioning shall be restricted to periods of low moisture (dry conditions). Low soil moisture varies by texture and is based on site-specific considerations. Generally, low soil moisture is determined by the inability of a soil sample taken at four (4) to six (6) inches to maintain form when compressed and by the inability of soil moisture at the surface to be readily displaced, causing ribbons and ruts along equipment tracks. Low soil moisture limits will be determined by the Authorized Officer.

Pursuant to Section 26 of Form 5450-4, Timber Sale Contract, log haul shall not be conducted on all natural surface roads that receive one-half (½) inch or more precipitation within a twenty-four (24) hour period. Haul shall not resume for a minimum of forty-eight (48) hours following any storm event, or until road surface is sufficiently dry, as approved by the Authorized Officer. The Purchaser may elect, at their own expense, to apply rock surfacing to these roads to bring them up to wet weather haul standards, as approved by the Authorized Officer.

Pursuant to Section 26 of Form 5450-4, Timber Sale Contract, log haul shall not be conducted on hydrologically connected natural surface roads during conditions that would result in any of the following: surface displacement such as rutting or ribbons, continuous mud splash or tire slides, fines being pumped through road surfacing from the subgrade resulting in a layer of surface sludge, as directed by the Authorized Officer.

Pursuant to Section 26 of Form 5450-4, Timber Sale Contract, the Purchaser shall, prior to October 15 of the same operating season, winterize and rehabilitate temporary routes, landings, hydrologically connected corridors and skidtrails and other areas of exposed soils by properly installing and/or using water bars, berms, sediment basins, gravel pads, hay bales, small dense woody debris, seeding and/or mulching, to reduce sediment runoff and divert runoff water away from stream channels, headwalls, slide areas, high landslide hazard locations or steep erodible fill slopes as directed by the Authorized Officer.

In addition to the requirement set forth in Sec. 26 of this contract, the Purchaser shall, prior to October 15 of the same operating season, perform all non-emergency road maintenance as directed by the Authorized Officer.

EQUIPMENT REQUIREMENTS – A yarding tractor equipped with an integral arch capable of one-end log suspension and a winch for lining logs seventy-five (75) feet. A skyline yarder with a medium (40-50 foot) tower; capable of one-end log suspension with a minimum lateral yarding capability of seventy-five (75) feet while maintaining a fixed position during inhaul; capable of multi-span; and capable of an external yarding distance of one thousand six hundred (1,600) feet slope distance. A piece of equipment capable of sub-soiling to a depth of twelve (12) inches will

be required for fully decommissioning: temporary routes TR 3-14, TR 5-8, TR 9-5, TR 17-2, TR 17-15, and TR 31-2; all tractor swing routes; and any landings or skid roads within ground based units as necessary to achieve no more than twenty (20) percent detrimental soil compaction within the unit. A fire engine of three hundred (300) gallons or more capacity with five hundred (500) feet of 1½ inch hose (must be adequate length to reach two hundred (200) feet beyond active work sites), six (6) 1½ inch wyes, six (6) 1½ inch to 1 inch reducers, three (3) 1½ inch nozzles and three (3) 1 inch nozzles will be required for fire prevention and control. Each fire engine shall be equipped with a pump capable of delivering a minimum of forty (40) gallons per minute (gpm) water flow at one hundred fifty (150) pounds per square inch (psi) engine pressure through fifty (50) feet of 1½ inch fire hose. The pump may be either power take off driven or truck-mounted auxiliary engine driven, or portable.

SLASH DISPOSAL – Slash disposal will consist of a combination of lop and scatter, machine pile, cover, and burn machine piles, selective slashing, hand pile, cover, and burn hand piles, pile, cover, and burn landing decks, and underburn as described in SD-1, SD-2, and SD-4 of the Special Provisions. A post logging assessment shall be conducted to determine treatment needs in all units. The initial slash disposal appraisal described in SD-5 prescribed forty nine (49) acres of lop and scatter, two hundred fifteen (215) acres of selective slashing, hand pile, cover, and burn hand piles, one hundred seventy three (173) acres of machine pile, cover, and burn machine piles, and thirty five and one-half (35.5) acres of cover and burn landing decks.

Additionally, there is an option to provide payment in lieu of constructing forty-six thousand six hundred twenty-five (46,625) feet of fireline and perform underburning on five hundred twenty six (526) acres.

OPTIONAL CONTRIBUTION – The purchaser will have the option of performing fireline construction and underburning slash disposal requirements or contributing forty-one thousand, one hundred fifty three and no/100 dollars (\$41,153.00) in lieu thereof. The option must be declared upon execution of the contract. The optional contribution must be paid in installments payable in the same manner as and together with payments required in Section 3 of the contract.

CONTRACT TERMINATION – A Special Provision has been added to the contract which enables the Contracting Officer to suspend the contract to facilitate protection of certain plant or animal species, and/or to modify or terminate the contract when necessary to comply with the Endangered Species Act, or comply with a court order, in accordance with the Standards and Guidelines of the Medford District Record of Decision (ROD) and Resource Management Plan (RMP). This contract provision limits the liability of the Government to the actual costs incurred by the Purchaser which have not been amortized by timber removed from the contract area.

PERFORMANCE BOND – A performance bond in the amount of 20% of the total purchase price will be required.

OTHER –

1. No extension of time beyond the normal 30 days will be granted for completing bonding and contract signing requirements.
2. A revised Special Provision has been added to the contract which enables the Contracting Officer to suspend the contract to facilitate protection of certain plant or animal species, and/or to modify or terminate the contract when necessary to: (1) Comply with the Endangered Species Act or to prevent incidental take of northern spotted owls in accordance with management direction in the Record of Decision (ROD) and Resource Management Plan (RMP), or; (2) Comply with a stay or remedy issued by the Interior Board of Land Appeals or a court order, or; (3) Protect species which were identified for protection in accordance with management direction established in the ROD and RMP.
3. No operations, including burning, within units 3-11, 9-5, 9-14, 9-18, 32-5-9.0 and/or road construction associated with these units as shown on Exhibit A shall be conducted between March 1 and April 15 of the same calendar year, both days inclusive, or until northern spotted owl spot check surveys are complete. If northern spotted owls are

observed within or adjacent to the units, this restriction would be extended during the year of harvest until June 30 or until two (2) weeks after the fledging period, unless protocol surveys determine the owls are not nesting. This restriction may be extended to September 30 during the year of harvest if site specific information indicates a late nesting attempt and harvesting would cause a nesting northern spotted owl to flush.

4. The Purchaser shall notify the Authorized Officer in writing by February 1 of each calendar year in which operations are expected to take place on the contract area between March 1 and September 30, both days inclusive. If notification is not received by the Authorized Officer by February 1, felling, bucking, yarding, road construction, or any other activity with the potential to disturb nesting northern spotted owls may not be allowed between March 1 and September 30, both days inclusive.

Upon receipt of a notice that the Purchaser expects to perform such operations during this time period, the Government will conduct surveys to determine whether owls have moved into harvest units. If northern spotted owls are detected in or adjacent to the units, operations would be restricted until northern spotted owl occupancy and nesting status has been determined. If it is determined owls are not nesting or that no young have been produced, the Authorized Officer may lift the seasonal restriction on such operations in writing. Without this approval, such operations are prohibited from March 1 through June 30 of each year.

5. No work in the stream channel shall be conducted between September 15 of one calendar year and July 1 of the following calendar year, both days inclusive. Purchaser may request in writing, a waiver of this restriction.
6. No non-emergency road maintenance shall be conducted from October 15 of one calendar year and May 15 of the following calendar year, both days inclusive. Purchaser may request in writing, a waiver of this restriction.
7. A harvester, feller-processor, or feller-buncher with purpose built carriers with boom-mounted felling heads and a boom with a minimum lateral reach of twenty (20) feet may be used in the ground based portion of harvest units. Mechanized equipment as stated above with self-leveling cabs may be used on slopes up to fifty (50) percent, as approved by the Authorized Officer.
8. In the Riparian Reserve and Late-Successional Reserve portion of units 3-7, 3-11, 3-14, 5-6, 5-8, 9-5, 9-14, 9-18, 17-1, 17-2, 17-15, 17-16, 17-17, 31-1, 31-2, and 31-3 as shown on Exhibit E, the Purchaser shall create a total of three hundred fifty six (356) snags via girdling. See Special Provision L-32 and Exhibit E for more details.
9. The construction of Road 32-5-10 will require tree removal and construction across lands owned by Silver Butte Co. This construction will result in the removal of six hundred (600) board feet of merchantable timber, as described below.

Species	Est. Volume MBF 16' Log	Appr. Price Per MBF	Est. Volume Times Appraised Price
Douglas fir	0.5	\$434.56	\$217.28
Incense-cedar	0.1	\$260.32	\$26.03
<b>Totals</b>	<b>0.6</b>		<b>\$243.31</b>

The Purchaser shall purchase this timber from Silver Butte Co. at an Independently Appraised Total Purchase Price of two hundred forty-three and 31/100 dollars (\$243.31). Additionally, landings, artificial guyline anchors, and cable corridors will be needed on

Silver Butte Co. land to access units 3-11 and 10-1. The use of landings, felling, yarding, and purchasing of trees, and construction of Road 32-5-10.1 shall adhere to the terms and conditions of the crossing plat with Silver Butte Co.

10. Artificial guyline anchors (equipment or deadmen) may be needed for units 3-7, 5-8, 8-9G, and 9-5.
11. In units 3-11 and 31-3 it is acceptable to have yarding corridors outside of unit boundaries, as approved by the Authorized Officer.
12. In unit 5-6, much of the unit can be logged with ground-based equipment. However, due to long adverse skidding distances, the unit was appraised as cable yard.
13. In the ground based portion of unit 10-1 and much of unit 17-17, logs will need to be directionally felled and bull-lined toward skid trails.
14. In portions of units 3-11, 3-14, and 17-1, a cable-tractor swing yarding system may need to be utilized in order to access all of the unit.
15. The 32-5-8.0 and 32-5-8.1 roads also access BLM Oh Windy Timber Sale.

NARRATIVE DESCRIPTION OF HOW TO GET TO THE TIMBER SALE AREA –

**To access units 3-7, 3-11, 3-14, 5-8, 8-9G, 9-5, 9-14, 9-18, 10-1, 17-1, 17-2, 17-15, 17-15G, 17-16, 17-17, 32-5-8.0, 32-5-8.2, and 32-5-9.0:** Take I-5 to Exit 80 for Glendale. At the four-way stop proceed straight onto Junction Road for 0.7 miles. Turn right onto Azalea-Glen Road, travel 2.5 miles. Turn left onto Fortune Branch Rd. and proceed until the junction of BLM Roads 32-5-20.0 and 32-5-17.0. Units can be accessed from both BLM Rd # 32-5-20.0 and BLM Rd # 32-5-17.0. **A BLM lock key will be needed to access units 9-5 and 10-1 past a gate.**

**To access unit 5-6:** From I-5, take Exit 80 to Glendale. At the four-way stop proceed straight onto Junction Road for 0.7 miles. Turn left onto Azalea-Glen Road, travel 1.4 miles. Turn right onto Windy Creek Rd, travel approximately 6.3 miles. Turn right onto BLM Road # 32-5-7.0 and proceed to unit.

**To access units 31-1, 31-2, 31-3:** From I-5 North, take Exit 83 for Barton Road. Turn right at the stop sign onto Barton Rd. Continue straight onto Swamp Creek Rd., BLM Road # 32-5-30.0. **A BLM lock key will be needed to access units 31-1, 31-2, and 31-3 past a gate.**

ENVIRONMENTAL ASSESSMENT – An environmental assessment (DOI-BLM-ORWA-M070-2018-0010-EA) was prepared for this sale, and a Finding of No Significant Impact has been documented. This document is available for inspection as background for this sale at the Medford District Office.

OR110-5422-11 (03/2019)

## BLOWN FORTUNE TIMBER SALE

### SPECIAL PROVISIONS

THIS IS A SALE PROSPECTUS ONLY. THESE ARE THE SPECIAL PROVISIONS AS THEY WILL BE WRITTEN IN THE CONTRACT. ATTACHMENTS MAY NOT INCLUDE ALL EXHIBITS REFERRED TO IN THE CONTRACT PROVISIONS. THE COMPLETE CONTRACT, INCLUDING ALL EXHIBITS, IS AVAILABLE FOR INSPECTION AT THE MEDFORD INTERAGENCY OFFICE.

Sec. 41. TIMBER RESERVED FROM CUTTING - The following timber on the contract area is hereby reserved from cutting and removal under the terms of this contract and is retained as the property of Government.

- (A) AR-1 All timber on the Reserve Areas as shown on Exhibit A and all trees marked with a combination of orange paint, orange flagging, and/or posters which are on or mark the boundaries of the Reserve Areas.
- (B) AR-2 All timber on the Reserve Areas shown on Exhibit A and all blazed, painted, or posted trees which are on or mark the boundaries of the Reserve Areas, except approximately four hundred eighty one (481) Douglas-fir, fifteen (15) ponderosa pine, and fifty eight (58) incense-cedar trees marked for cutting heretofore by the Government with blue paint above and below stump height in roadside management units 32-5-8.0, 32-5-8.2, and 32-5-9.0 shown on Exhibit A.
- (C) IR-1 Approximately three thousand four hundred sixty seven (3,467) Douglas-fir, twelve (12) ponderosa pine, fifteen (15) sugar pine, one hundred forty six (146) incense-cedar, two hundred four (204) fir, and thirty nine (39) hardwood trees marked with orange paint above and below stump height in units 5-6, 5-8, 9-5, 9-14, 31-1, and 31-3 as on Exhibit A.
- (D) IR-1 Approximately fourteen thousand nine hundred twenty five (14,925) Douglas-fir, eight hundred fifteen (815) ponderosa pine, one thousand three hundred fifty four (1,354) sugar pine, three thousand forty seven (3,047) incense-cedar, two thousand one hundred ninety eight (2,198) white fir, one thousand one hundred five (1,105) oak, and nine hundred eighteen (918) hardwood trees marked with pink paint above and below stump height in units 3-7, 3-11, 3-14, 8-9G, 9-18, 10-1, 17-1, 17-2, 17-15, 17-15G, 17-16, 17-17, and 31-2 as on Exhibit A.
- (E) IR-6 All Pacific yew trees in the Contract Area shown on Exhibit A.
- (F) IR-13 All trees greater than thirty six (36) inches D.B.H.O.B and were established prior to 1850 in the contract as shown on Exhibit A that are cut for safety or operational purposes shall be retained on site as directed by the Authorized Officer.
- (G) IR-13 All existing snags and coarse woody debris in all units shown on Exhibit A which do not present a safety hazard as determined by the Authorized Officer. All snags that are felled for safety reasons, and do not present a safety hazard on the ground, shall be retained on site.

**BLOWN FORTUNE TIMBER SALE**  
**SPECIAL PROVISIONS**

Section 42

(A) **LOGGING**

- (1) L-1 Before beginning operations on the contract area for the first time or after a shutdown of seven (7) or more days, the Purchaser shall notify the Authorized Officer in writing of the date they plan to begin operations. The Purchaser shall also notify the Authorized Officer in writing if he intends to cease operations for any period of seven (7) or more days.
  
- (2) L-2 Prior to the commencement of operations the Purchaser shall obtain from the Authorized Officer written approval of a written operations and logging plan commensurate with the terms and conditions of the contract, which shall include measures needed to ensure protection of the environment and watershed. A pre-work conference between the Purchaser's authorized representative and the Authorized Officer must be held at a location designated by the Authorized Officer before the logging plan will be approved. All logging shall be done in accordance with the plan.
  
- (3) L-4 All trees designated for cutting shall be cut so that the resulting stumps shall not be higher than twelve (12) inches measured from the ground on the uphill side of the trees unless otherwise approved by the Authorized Officer.

Designated Area	Yarding Requirements or Limitations
<u>Roadside Management Units</u> 32-5-8.0, 32-5-8.2, 32-5-9.0	<p>Mechanical felling required with a single-grip felling head (a head that can hold and fully suspend the tree after it is cut). Only purpose built carriers with boom-mounted felling heads may be approved. The boom must have a lateral reach of twenty (20) feet or more, and the machine's lateral reach must be utilized as much as possible. The purpose-built carrier may be of the articulated, rubber-tired design, or the zero-clearance tail swing leveling track-mounted design.</p> <p>Yarding shall be done with a system which will fully suspend both ends of the log clear of the ground during inhaul.</p> <p>Landing size shall not exceed one-quarter (1/4) acre, shall be located along existing roads, and shall be approved by the Authorized Officer. No landing creation or expansion shall occur without prior approval from the Authorized Officer. Design landings with adequate drainage.</p> <p>Conifer tops and limbs, hardwoods, brush, and other cut vegetation created from the roadway clearing treatment shall be machine piled concurrently with felling operations and shall be treated according to the roadway clearing prescriptions found in Exhibit C13 and according to the machine pile and</p>

**BLOWN FORTUNE TIMBER SALE**  
**SPECIAL PROVISIONS**

<p style="text-align: center;"><u>Roadside Management Units</u> <u>Continued</u> 32-5-8.0, 32-5-8.2, 32-5-9.0</p>	<p>cover slash disposal stipulations found in Sec. 42(E)(1)(b)(SD-1b).</p> <p>All mechanized equipment shall only operate on existing road surfaces.</p> <p>Mechanized felling operations are subject to seasonal operating restrictions as described in Section 42(A)(11)(L-19) of this contract.</p> <p>See Exhibits C6B and C13 in the Engineering package for more details on the roadside management requirements.</p>
Designated Area	Yarding Requirements or Limitations
<p style="text-align: center;"><u>Ground Based Harvest &amp; Ground Based (Tractor) Yard Units</u> 3-11, 3-14, 5-6, 9-14, 10-1, 17-1, 17-2, 17-15, 17-15G, 17-16, 17-17, 31-2</p>	<p>Mechanized harvesting operations are optional. All ground-based harvest units may be manually felled.</p> <p>The harvester, feller-processor, or feller-buncher shall be approved by the Authorized Officer prior to the start of mechanized felling operations. Only purpose built carriers with boom-mounted felling heads may be approved. The boom must have a lateral reach of twenty (20) feet or more, and the machine's lateral reach must be utilized as much as possible. The purpose-built carrier may be of the articulated, rubber-tired design, or the zero-clearance tail swing leveling track-mounted design.</p> <p>Directional falling to lead and away from streams, unit boundaries, and resource buffers shown on Exhibit A will be required.</p> <p>The harvest equipment shall walk on existing or created slash as directed by the Authorized Officer. If Purchaser is required to create slash to walk on, then Purchaser shall not be required to whole-tree-yard.</p> <p>Non-specialized ground-based equipment (without a self-leveling cab) shall be limited to slopes of thirty-five (35) percent or less. Specialized ground-based equipment (with a self-leveling cab) shall be limited to slopes fifty (50) percent or less. This equipment can operate on steeper ground if it is operating on previously constructed skid trails or accessing isolated ground-based harvest areas requiring short distances over steeper pitches.</p> <p>Mechanized ground-based felling and yarding operations are subject to dry condition operating restrictions as described in Section 42(A)(11)(L-19) of this contract.</p>

**BLOWN FORTUNE TIMBER SALE**  
**SPECIAL PROVISIONS**

<p style="text-align: center;"><u>Ground Based Harvest &amp; Ground Based (Tractor) Yard Units</u></p> <p style="text-align: center;"><u>Continued</u></p> <p>3-11, 3-14, 5-6, 9-14, 10-1, 17-1, 17-2, 17-15, 17-15g, 17-16, 17-17, 31-2</p>	<p>Yarding tractor shall be equipped with an integral arch and yard with one-end log suspension.</p> <p>Existing skid roads shall be used when possible. Skid roads shall not exceed a width of twelve (12) feet on average per unit and new skid roads shall be placed at least one hundred fifty (150) feet apart where topography will allow, unless the Purchaser proposes an alternate logging plan that limits soil compaction from skids trails to less than fifteen (15) percent over the harvest unit and is approved by the Authorized Officer.</p> <p>Designate skid trails in locations that do not channel water into waterbodies, floodplains, and wetlands, or unstable areas.</p> <p>Rehabilitate utilized skid roads, landings, cable-tractor swing routes, and/or temporary routes as necessary to achieve no more than twenty (20) percent detrimental soil conditions in the ground-based harvest unit, as specified in Sec. 42(C)(12)(E-1).</p> <p>Block skid trails following use.</p> <p>Landing size shall generally not exceed one-quarter (1/4) acre, shall be located along existing roads, temporary routes, and/or cable-tractor swing routes within unit boundaries, and shall be approved by the Authorized Officer. Design landings with adequate drainage so that they are not hydrologically connected to draws or the ditchline of roads.</p> <p>Minimize disturbance to existing coarse woody debris. Where skid trails encounter large coarse woody debris, the Purchaser shall buck out a portion for equipment access.</p> <p>The use of blades while tractor yarding will be limited, equipment shall walk over as much ground litter as possible.</p>
<p><b>Designated Area</b></p>	<p><b>Yarding Requirements or Limitations</b></p>
<p style="text-align: center;"><u>Cable Yard Units</u></p> <p>3-7, 3-11, 3-14, 5-6, 5-8, 8-9G, 9-5, 9-18, 10-1, 17-1, 17-2, 31-1, 31-2, 31-3</p>	<p>Yarding will be done with a cable yarding system which will suspend one end of the log clear of the ground during inhaul on the yarding corridor. The cable yarding system shall be capable of yarding one thousand six hundred (1,600) feet slope distance.</p> <p>Skyline equipment shall be capable of yarding in a multispan configuration.</p>

**BLOWN FORTUNE TIMBER SALE**  
**SPECIAL PROVISIONS**

<p><u>Cable Yard Units</u> <u>Continued</u> 3-7, 3-11, 3-14, 5-6, 5-8, 8-9G, 9-5, 9-18, 10-1, 17-1, 17-2, 31- 1, 31-2, 31-3</p>	<p>A carriage is required which will maintain a fixed position on the skyline during lateral yarding and has a minimum lateral yarding capability of seventy-five (75) feet.</p> <p>Yarding corridors will be perpendicular to the contours.</p> <p>Prior to falling any timber in the unit, all tail/lift trees and/or intermediate support trees shall be pre-designated by the Purchaser and approved by the Authorized Officer.</p> <p>Existing cable corridors shall be used whenever possible. Yarding corridors shall be approximately one hundred fifty (150) feet apart, measured at the tailholds.</p> <p>Yarding corridor widths shall not exceed six (6) feet either side of the skyline centerline.</p> <p>Landing size shall not exceed one-quarter (<math>\frac{1}{4}</math>) acre, shall be located along existing roads, temporary routes, and/or cable-tractor swing routes within unit boundaries where possible, and shall be approved by the Authorized Officer. Short purchaser spurs into units may be necessary to achieve one-end log suspension. Design landings with adequate drainage so that they are not hydrologically connected to draws or the ditchline of roads.</p> <p>Corridors may be needed outside of unit boundaries in units 3-11, and 31-3. These corridors shall not be located in any of the buffers shown on Exhibit A and shall be approved by the Authorized Officer prior to use.</p> <p>Yarding over streams shall be avoided unless it is the only viable option. If yarding is needed over streams shown on Exhibit A, it shall be done with full suspension within fifty (50) feet of and over streams and shall be approved by the Authorized Officer. Any trees cut for the yarding corridor outside of unit boundaries within one hundred ninety-five (195) feet of streams shown on Exhibit A shall be retained on site as coarse woody debris.</p> <p>Directional falling to the lead and away from streams, and unit boundaries shown on Exhibit A will be required.</p> <p>Cable corridors that are hydrologically connected to streams shown on Exhibit A shall be water-barred and shall have slash placed over them prior to winter rain events to protect water quality.</p>
---	--

**BLOWN FORTUNE TIMBER SALE**  
**SPECIAL PROVISIONS**

<p style="text-align: center;"><u>Cable Yard Units</u> <u>Continued</u></p> <p>3-7, 3-11, 3-14, 5-6, 5-8, 8-9G, 9-5, 9-18, 10-1, 17-1, 17-2, 31- 1, 31-2, 31-3</p>	<p>In units 3-11, 3-14, and 17-1 the Purchaser shall be allowed to walk a yarder into the unit utilizing a tractor-swing system as approved by the Authorized Officer.</p>
--	--

- (4) L-5 All conifer trees eight (8) inches or larger D.B.H.O.B., which are not reserved shall be felled in all units shown on Exhibit A.
- (5) L-8 In all units as shown on Exhibit A, all trees designated for cutting shall be felled and whole tree yarded or yarded with tops attached except when excessive stand damage occurs as determined by the Authorized Officer. If excessive stand damage occurs, all trees shall be bucked into log lengths not to exceed forty-one (41) feet prior to being yarded.
- (6) L-11 No trees may be felled into the stream, or other resource buffers designated on Exhibit A.
- (7) L-12 In the Units shown on Exhibit A, yarding/felling shall be done in accordance with the requirements for the designated area listed below.
- (8) L-14 No falling, yarding or loading is permitted in or through the stream buffers as shown on Exhibit A.
- (9) L-19 No work in the stream channel shall be conducted between September 15 of one calendar year and July 1 of the following calendar year, both days inclusive. Purchaser may request in writing, a waiver of this restriction.
- (10) L-19 No non-emergency road maintenance shall be conducted from October 15 of one calendar year and May 15 of the following calendar year, both days inclusive. Purchaser may request in writing, a waiver of this restriction.
- (11) L-19 No mechanical ground based harvesting, ground based yarding, skid trail and landing rehabilitation, machine piling, road and temporary route construction, road and temporary route reconstruction, temporary route decommissioning, or non-emergency road maintenance shall be conducted in units 3-11, 3-14, 5-6, 9-14, 10-1, 17-1, 17-2, 17-15, 17-15g, 17-16, 17-17, and 31-2 between October 15 of one calendar year and May 15 of the following calendar year both days inclusive. Purchaser may request in writing, a conditional waiver of this restriction. If soil moisture conditions are dry, as determined by the inability of a soil sample taken at four (4) to six (6) inches to maintain form when compressed and by the inability of soil moisture at the surface to be readily displaced, causing ribbons and ruts along equipment tracks, the Contracting Officer may approve a conditional waiver. If impacts to soil resulting from said conditional waiver are not acceptable as determined by the Authorized Officer, the waiver will be revoked.

**BLOWN FORTUNE TIMBER SALE**  
**SPECIAL PROVISIONS**

- (12) L-19 No haul on natural surface shall be conducted on the Contract Area between October 15 of one calendar year and May 15 of the following calendar year, both days inclusive. Purchaser may request in writing, a conditional waiver of this restriction. If the Authorized Officer determines that hauling would not result in road damage or the transport of sediment to nearby stream channels based on soil moisture conditions or rain events, Contracting Officer may approve a conditional waiver for hauling. If soil moisture conditions or rain events are anticipated to cause impacts to roads or stream water quality resulting from said conditional waiver are not acceptable as determined by the Authorized Officer, the waiver will be revoked.
- (13) L-20 No operations, including burning, within units 3-11, 9-5, 9-14, 9-18, 32-5-9.0 and/or road construction associated with these units as shown on Exhibit A shall be conducted between March 1 and April 15 of the same calendar year, both days inclusive, or until northern spotted owl spot check surveys are complete. If northern spotted owls are observed within or adjacent to the units, this restriction would be extended during the year of harvest until June 30 or until two (2) weeks after the fledging period, unless protocol surveys determine the owls are not nesting. This restriction may be extended to September 30 during the year of harvest if site specific information indicates a late nesting attempt and harvesting would cause a nesting northern spotted owl to flush.
- (14) L-22 During logging operations, the Purchaser shall keep the 32-5-3.2, 32-5-8.0, 32-5-8.1, 32-5-9.0, 32-5-17.0, 32-5-20.0, 32-5-30.0, and 32-5-30.1 Roads, where the road passes through the contract area, clear of trees, rock, dirt, and other debris so far as is practicable. The road shall not be blocked by such operations for more than thirty (30) minutes.
- (15) L-24 Before cutting and removing any trees necessary to facilitate logging in the harvest units shown on Exhibit A, the Purchaser shall identify the location of the skid roads, cable yarding roads, and tailhold, tieback, guyline, lift, intermediate support, and danger trees on the ground in a manner approved by the Authorized Officer at the pre-work conference and documented in the Logging Plan. Said Purchaser identification of trees to be cut and removed does not constitute authority to proceed with cutting and removal. In addition, before proceeding with cutting the following conditions must be met:
- (a) All skid roads and/or cable yarding roads upon which timber is identified by the Purchaser to be cut and removed in accordance with this special provision must be necessary for the safe and expeditious removal of timber sold under this contract and shall be limited to the minimum width necessary for yarding of logs with a minimum of damage to reserve trees, however, unless otherwise approved in writing by the Contracting Officer, the width of each skid road, and/or cable yarding road shall be limited to twelve (12) feet.
  - (b) The Purchaser may immediately cut and remove additional timber to clear skid roads and cable yarding roads; and provide tailhold, tieback, guyline, lift and intermediate support trees; and clear danger trees when the trees have been marked with paint (color to be determined at pre-work) above and below stump height by the Authorized Officer and thereby approved for cutting and removal

**BLOWN FORTUNE TIMBER SALE**  
**SPECIAL PROVISIONS**

by the Authorized Officer. The volume of the timber to be sold will be determined by the Authorized Officer in accordance with Bureau of Land Management prescribed procedures. No timber may be cut or removed under terms of this provision unless sufficient installment payments have been made in accordance with Section 3(b) of the contract or sufficient bonding has been provided in accordance with Section 3(d) of the contract.

- (c) The Purchaser agrees that sale of this additional timber shall be accomplished by a unilateral modification of the contract executed by the Contracting Officer and that such timber shall be sold at the unit prices shown in Exhibit B of this contract unless: the value of the timber must be reappraised subject to the terms for contract extension set forth in Section 9 of the contract; or, the Authorized Officer determines that the species of trees are not listed in Exhibit B of this contract shall be appraised and sold by bilateral modification of the contract at current fair market value in accordance with Section 8 of the contract.
- (d) This authorization for the Purchaser to cut and remove additional timber prior to the execution of a modification may be withdrawn by the Contracting Officer if the Authorized Officer determines that the Purchaser has cut and removed any tree not previously marked and approved for cutting by the Authorized Officer, which under Section 10 of the contract constitutes a violation of the contract and under Section 13 of the contract may constitute a trespass rendering the Purchaser liable for damages under applicable law.
- (e) If authorization is withdrawn, the Contracting Officer shall issue a written notice to the Purchaser that the sale of additional timber under this special provision is no longer approved. In this case, the Purchaser shall inform the Authorized Officer at least one (1) working day prior to the need for cutting and removing any additional timber, and execute a bilateral modification prior to cutting for such additional approved timber at the unit prices shown in Exhibit B of the contract or in accordance with Section 8 or Section 9 of the contract as determined by the Authorized Officer in accordance with this provision. The Contracting Officer may issue a written order to the Purchaser to suspend, delay, or interrupt any or all contract work for the period of time deemed necessary and appropriate for the Government to safely measure and mark additional timber.
- (f) The Government may reserve trees previously designated for cutting and removal by blacking out blue paint, and/or applying orange or pink paint as replacements for additional trees cut and removed for skid roads and/or cable yarding roads when the Authorized Officer determines such reservation is necessary to maintain stand densities consistent with objectives set forth in the management prescriptions. This may include the replacement of trees damaged by storm events, or insects or disease. The volume of this timber to be reserved will be determined by the Authorized Officer in accordance with Bureau of Land Management prescribed procedures and the value shall be based on the unit prices shown in Exhibit B of the contract. The Purchaser agrees that the Total Purchase

**BLOWN FORTUNE TIMBER SALE**  
**SPECIAL PROVISIONS**

Price shall be reduced accordingly through a unilateral modification to the contract executed by the Contracting Officer.

- (16) L-32 In harvest units 3-7, 3-11, 5-6, 5-8, 9-5, 9-14, 9-18, 17-1, 17-2, 17-15, 17-16, 17-17, 31-1, 31-2, and 31-3 the Purchaser shall create snags via girdling, or other method as approved by the Authorized Officer, within one hundred ninety five (195) feet of streams (the Riparian Reserve land use allocation) as shown on Exhibit E. The total number of snags to create in the Riparian Reserve per unit is as follows: 3-7 (4 snags), 3-11 (26 snags), 5-6 (12 snags), 5-8 (2 snags), 9-5 (6 snags), 9-14 (2 snags), 9-18 (2 snags), 17-1 (8 snags), 17-2 (18 snags), 17-15 (10 snags), 17-16 (2 snags), 17-17 (6 snags), 31-1 (10 snags), 31-2 (16 snags), 31-3 (2 snags). A total of total of one hundred twenty-six (126) snags shall be created in the Riparian Reserve land use allocation portion of units. Of this total, one-half (½) of the snags required in each unit shall be greater than ten (10) inches diameter at breast height outside bark and one-half (½) of the snags required in each unit shall be greater than twenty (20) inches diameter at breast height outside bark. All snags created shall come from reserve marked trees as described in Section 41(C)(IR-1), Section 41(D)(IR-1), or Section 41 (F)(IR-13) and shall be distributed in a variety of spatial patterns including aggregated groups and individual trees. No adjustments of volume or value shall be made to meet these requirements. The Purchaser shall tally all girdled trees by diameter class and species per unit. At the end of girdling operations, a completed tree tally shall be submitted to the Authorized Officer. Any species of tree available could be used to meet this requirement. The Purchaser shall not create snags in locations that may be hazardous to roads or powerlines.
- (17) L-32 In harvest units 3-7, 3-11, 3-14, 5-6, 5-8, 9-5, 9-14, 9-18, 17-2, 17-15, 17-16, and 17-17 the Purchaser shall create snags via girdling, or other method as approved by the Authorized Officer, within the Late-Successional Reserve (LSR) land use allocation as shown on Exhibit E. The total number of snags to create in the LSR per unit is as follows: 3-7 (16 snags), 3-11 (56 snags), 3-14 (22 snags), 5-6 (28 snags), 5-8 (18 snags), 9-5 (10 snags), 9-14 (2 snags), 9-18 (50 snags), 17-2 (14 snags), 17-15 (6 snags), 17-16 (2 snags), and 17-17 (6 snags). A total of total of two hundred thirty (230) snags shall be created in the LSR portion of units. Of this total, one-half (½) of the snags required in each unit shall be greater than ten (10) inches diameter at breast height outside bark and one-half (½) of the snags required in each unit shall be greater than twenty (20) inches diameter at breast height outside bark. All snags created shall come from reserve marked trees as described in Section 41(C)(IR-1), Section 41(D)(IR-1), or Section 41 (F)(IR-13) and shall be distributed in a variety of spatial patterns including aggregated groups and individual trees. No adjustments of volume or value shall be made to meet these requirements. The Purchaser shall tally all girdled trees by diameter class and species per unit. At the end of girdling operations, a completed tree tally shall be submitted to the Authorized Officer. Any species of tree available could be used to meet this requirement. The Purchaser shall not create snags in locations that may be hazardous to roads or powerlines.
- (18) L-33 Purchaser's operations shall facilitate BLM's safe and practical inspection of Purchaser's operations and BLM's conduct of other official duties on Contract Area.

**BLOWN FORTUNE TIMBER SALE**  
**SPECIAL PROVISIONS**

Purchaser has all responsibility for compliance with safety requirements for Purchaser's employees, contractors and subcontractors.

In the event that the Authorized Officer identifies a conflict between the requirements of this contract or agreed upon methods of proceeding hereunder and State or Federal safety requirements, the contract may be modified. If the cost of such contract modification is of a substantial nature (\$2,000.00 or more), the Purchaser may request, in writing, an adjustment in the Total Purchase Price specified in Section 2 of the timber sale contract, as amended, to compensate for the changed conditions.

Unless otherwise specified in writing, when operations are in progress adjacent to or on roads and/or trails in the harvest unit area, Purchaser shall furnish, install, and maintain all temporary traffic controls that provide the road or trail user with adequate warning of and protection from hazardous or potentially hazardous conditions associated with its operations. Purchaser shall prepare a Traffic Control Plan, which the Purchaser has determined is compliant with state and local OSHA and Transportation standards no later than the pre-work meeting and prior to commencing operations. Traffic control devices shall be appropriate to current operating and/or weather conditions and shall be covered or removed when not needed., Flagmen and devices shall be as specified in state OSHA and Transportation standards for logging roads or the "Manual on Uniform Traffic Control Devices for Streets and Highways" (MUTCD) published by the U.S. Department of Transportation - Federal Highway Administration. Included in the Traffic Control Plan, Purchaser shall note traffic control device locations on a Purchaser produced copy of the contract Exhibit "A" Map.

**(B) ROAD CONSTRUCTION, MAINTENANCE, AND USE**

- (1) R-1 The Purchaser shall construct, improve, renovate, and/or decommission all roads, structures, and temporary routes listed for use under this contract in accordance with the plans and specifications shown on Exhibits C and D, which is attached hereto and made a part hereof.
- (2) R-1a Any required construction, improvement, or renovation of roads and structures shall be completed and accepted, in accordance with Section 18, prior to the removal of any timber, except right-of-way timber, over that road.
- (3) R-1b The Purchaser shall construct, use, and decommission temporary routes TR 03-14, TR 05-08, TR 09-05, TR 17-02, TR 17-15, and TR 31-02 by October 15<sup>th</sup> of the same respective operating season. If a temporary route needs to be used over multiple operating seasons, winterize the route prior to October 15th.
- (4) R-1c The Purchaser shall not commence work on road renovation, construction, and reconstruction until receipt of written notice to do so from the Authorized Officer. Work shall commence no later than 5 days after such notice, and shall be completed within 1 year after such notice.

**BLOWN FORTUNE TIMBER SALE  
SPECIAL PROVISIONS**

- (5) R-1d Prior to completion and approval of sub-grade construction from all proposed road construction and reconstruction, as well as all temporary route construction and reconstruction, as shown on Exhibit C, all logs shall be removed from the designated right-of-way.
- (6) R-2 The Purchaser is authorized to use the roads listed below and shown on Exhibits C and D for the removal of Government timber sold under the terms of this contract, provided that the Purchaser pay the required maintenance and rockwear obligations described in Section 42(B)(8)(R-2d), Section 42(B)(9)(R-2e), Section 42(B)(11)(R-3), and Section 42(B)(12)(R-3). Any road listed on Exhibit C and D and requiring construction, improvement, or renovation in Exhibit C of this contract, shall be maintained by the Purchaser until receiving written acceptance of the construction, improvement, or renovation from the Contracting Officer. The Purchaser shall pay current Bureau of Land Management maintenance and rockwear fees for the sale of additional timber under modification to the contract.

Road No. and Segment	Length Miles Used	Ownership	Road Surface Type	Maintenance Responsibility
32-5-3.01	0.49	BLM	Aggregate	Purchaser
32-5-3.02	0.53	BLM	Aggregate	Purchaser
32-5-3.06	0.10	BLM	Natural	Purchaser
32-5-5.01	0.33	BLM	Aggregate	Purchaser
32-5-7.00 A	0.59	Private	Aggregate	Purchaser
32-5-7.01	0.21	BLM	Aggregate	Purchaser
32-5-8.00	2.09	BLM	Aggregate	Purchaser
32-5-8.01	1.05	BLM	Aggregate	Purchaser
32-5-8.02	0.18	BLM	Aggregate	Purchaser
32-5-8.04	0.17	BLM	Natural	Purchaser
32-5-9.00	2.49	BLM	Aggregate	Purchaser
32-5-9.01	0.62	BLM	Aggregate	Purchaser
32-5-10.00 A	0.73	BLM	Aggregate	Purchaser
32-5-10.01 A	0.70	Private	Natural	Purchaser
32-5-10.01 B	0.21	BLM	Natural	Purchaser
32-5-10.02 A	0.38	Private	Natural	Purchaser
32-5-10.02 B	0.47	Private	Natural	Purchaser
32-5-17.00 A	1.74	BLM	Aggregate	Purchaser
32-5-17.00 B	0.56	BLM	Aggregate	Purchaser
32-5-17.01	0.32	BLM	Aggregate	Purchaser
32-5-17.02	0.22	BLM	Aggregate	Purchaser
32-5-20.00 A	0.62	BLM	Bituminous	BLM
32-5-20.00 B	1.94	BLM	Aggregate	Purchaser
32-5-20.00 C	1.40	BLM	Aggregate	Purchaser
32-5-30.00 A	0.66	BLM	Aggregate	Purchaser
32-5-30.00 B	0.33	BLM	Aggregate	Purchaser
32-5-30.01	0.84	BLM	Aggregate	Purchaser
32-5-30.02	0.64	BLM	Aggregate	Purchaser

**BLOWN FORTUNE TIMBER SALE**  
**SPECIAL PROVISIONS**

Road No. and Segment	Length Miles Used	Ownership	Road Surface Type	Maintenance Responsibility
32-5-31.04	0.35	BLM	Aggregate	Purchaser
Windy Creek Rd	1.84	Private	Aggregate	Purchaser
<b>TOTAL</b>	<b>22.80</b>			

- (7) R-2a With the prior written approval of the Authorized Officer, the Purchaser may arrange for cooperative maintenance with other users of roads included in Section 42(B)(6)(R-2) of this contract; provided, that such cooperative arrangement shall not relieve the Purchaser of his liability for the maintenance and repair of such roads resulting from wear or damage, in accordance with this contract. The Purchaser shall furnish the Authorized Officer a copy of any cooperative maintenance agreements entered into with other users on these roads.
- (8) R-2d The Purchaser shall pay a road maintenance fee of **\$0.92** per thousand board feet log scale per mile for the use of said BLM road: 32-5-20.0(A) and the Purchaser shall pay a rockwear fee of **\$0.73** per thousand board feet log scale per mile for the use of all remaining BLM rocked roads listed for use under this contract. The total maintenance fee due shall be based upon volumes determined pursuant to Exhibit B of this contract and mileage of roads used as determined by the Authorized Officer. Prior to the use of such roads, the Purchaser shall give written notice to the Authorized Officer of the roads intended for use in the removal of timber purchased under this contract, together with an estimate of the volume to be hauled over such roads. **The Purchaser will be required to label, with a permanent ink marker, each load ticket with the corresponding unit number as directed by the Authorized Officer.** The Authorized Officer shall establish an installment schedule of payment of the maintenance obligation. If it is determined by the Authorized Officer, after all merchantable timber has been cut and scaled, that the total maintenance payments made under this contract exceed the total maintenance and rockwear payment due, such excess shall be returned to the Purchaser after such determination is made.
- (9) R-2e The Contracting Officer may at any time, by written notice, terminate the Purchaser's operator road maintenance obligations and require instead payment of current Bureau of Land Management road maintenance and rockwear fees for the particular surface type of the roads involved. These fees will be applied to the remaining contract volume on the sale area, as determined by the Authorized Officer, to be transported over the roads listed in Section 42(B)(6)(R-2). If the total road maintenance and rockwear fee does not exceed five hundred and no/100 dollars (\$500.00), the Purchaser shall pay such amount in full prior to use of such roads. If the total road maintenance and rockwear fee exceeds five hundred and no/100 dollars (\$500.00), the Authorized Officer shall establish an installment schedule of payments of the maintenance and rockwear obligations.
- (10) R-2f The Purchaser shall perform any required road repair and maintenance work on roads used by them, under the terms of Exhibit D, Road Maintenance Specifications, of this contract, which is attached hereto and made a part hereof.

BLOWN FORTUNE TIMBER SALE  
SPECIAL PROVISIONS

- (11) R-3 In the use of Roads 32-5-7.00 A and Windy Creek Rd, the Purchaser shall comply with the conditions of Cooperative Right-of-Way Agreement dated January 6, 1960, between the United States of America and **Oregon Department of Forestry**. This document is available for inspection at the Medford District Office.

These conditions include:

- (a) Payment of a road rockwear obligation of **four hundred thirty two and 83/100 dollars (\$432.83)**, based upon the cruised estimated volume, to Oregon Department of Forestry, payable at the time indicated in the License Agreement.
- (b) Prior to the use of said roads, the Purchaser shall furnish the Authorized Officer a properly signed copy of the executed License Agreement.
- (c) Default by the Purchaser of said Cooperative Right-of-Way Agreement, or any License Agreement executed pursuant thereto, for failure to pay appropriate road use fees shall be considered a violation of this contract. The amount of unpaid fees shall be considered as the amount of damage suffered by the Government as a result of the violation of this provision.

- (12) R-3 In the use of Roads 32-5-10.01 and 32-5-10.02, the Purchaser shall comply with the conditions of Right-of-Way and Road Use Agreement No. M-824, between the United States of America and **Silver Butte Timber Co.** This document is available for inspection at the Medford District Office.

These conditions include:

- (a) Payment of a road use obligation of **four thousand five hundred thirty three and 41/100 dollars (\$4,533.41)** to Silver Butte Timber Co., based upon the cruised estimated volume, payable at the time indicated in the License Agreement.
- (b) In construction of the 32-5-10.01 road, as shown in Exhibit C, the Purchaser shall comply with the conditions of the Right-of-Way and Road Use Agreement No. M-824 between the United States of America and Silver Butte Timber Co.
- (c) Prior to the use of said roads, the Purchaser shall furnish the Authorized Officer a properly signed copy of the executed License Agreement.
- (d) Prior to cutting or removing any timber from the road right-of-way between Stations 0+00 and 0+35.5 on Road No. 32-5-10.01, the Purchaser shall pay to Silver Butte Timber Co., the owner of the right-of-way timber, the total value of that timber as shown below based upon the indicated estimated volume and species price per unit used in the Government's contract as set forth on the Exhibit B.

**BLOWN FORTUNE TIMBER SALE  
SPECIAL PROVISIONS**

<b>Road Number</b>	<b>Species</b>	<b>Est. Volume MBF 16' Log</b>	<b>Appr. Price Per MBF</b>	<b>Est. Volume Times Appraised Price</b>
32-5-10.01	Douglas-fir	0.5	\$434.56	\$217.28
32-5-10.01	Incense-cedar	0.1	\$260.32	\$26.03
	<b>Totals</b>	<b>0.6</b>		<b>\$243.31</b>

- (e) Default by the Purchaser of said Right-of-Way and Road Use Agreement, or any License Agreement executed pursuant thereto, for failure to pay appropriate road use fees shall be considered a violation of this contract. The amount of unpaid fees shall be considered as the amount of damage suffered by the Government as a result of the violation of this provision.
- (13) R-3c The Purchaser agrees that if they elect to use any other private roads, which is the subject of a right-of-way agreement with the Government for the removal of Government timber sold under the terms of this contract, the Purchaser shall request and agree to the modification of this contract to provide for such use and for allowances for amortization of the Government's share of the capital investment of any such road.
- (14) R-4 The Purchaser shall be required to secure written approval to use vehicles or haul forest products and equipment over Government owned or controlled roads when such vehicles or equipment exceeds the maximum allowable weights or dimensions established by the State for vehicles operating without a permit or if vehicles meet allowable non-permitted State vehicle weights, but the haul route crosses a structure or segment of road that is posted for reduced weights. The Purchaser agrees to abide by any special requirements included in said written approval.

Details of such equipment shall be furnished to the Authorized Officer for evaluation of load characteristics at least fifteen (15) days prior to proposed move in.

Details shall include:

- A. Axle weights when fully loaded.
- B. Axle spacing.
- C. Transverse wheel spacing.
- D. Tire size.
- E. Outside width of vehicle.
- F. Operating speed.
- G. Frequency of use.
- H. Special features (e.g., running tracks, overhang loads, etc.).

The Purchaser shall be responsible for repair of any damage to roads or structures caused by the use of overweight or over-dimension vehicles or equipment: (1) without written approval; (2) in violation of the conditions of a written approval; or, (3) in a negligent

BLOWN FORTUNE TIMBER SALE  
SPECIAL PROVISIONS

manner.

The amount of actual damage shall be determined by the Authorized Officer following a technical inspection and evaluation.

- (15) **R-5 Tracked type equipment shall not be allowed to cross over concrete bridge decks, other concrete surfaced structures, or asphalt surfaced roads without the proper protection of that surface.** Prior approval shall be obtained from the Authorized Officer when crossing with protective devices.

The Purchaser shall be responsible for the repair of any damage to roads or structures caused by the use tracked vehicles or equipment: (1) without written approval; (2) in violation of the conditions of a written approval; or, (3) in a negligent manner. The amount of actual damage shall be determined by the Authorized Officer following a technical inspection and evaluation.

(C) ENVIRONMENTAL PROTECTION

- (1) E-1 In addition to the requirements set forth in Sec. 26 of this contract, the Purchaser shall restrict non-road, in unit, ground-based equipment used for harvesting, yarding, machine piling, and rehabilitation operations (including temporary routes, tractor swing routes, and landings) to periods of low soil moisture (dry conditions). Low soil moisture varies by texture and is based on site-specific considerations. Generally, low soil moisture is determined by the inability of a soil sample taken at four (4) to six (6) inches to maintain form when compressed and the inability of soil moisture at the surface to be readily displaced, causing ribbons and ruts along equipment tracks. Low soil moisture limits will be determined by the Authorized Officer. Ground-based equipment shall be allowed to operate when the ground is frozen or adequate snow exists to prevent soil compaction and displacement, as determined by the Authorized Officer.
- (2) E-1 In addition to the requirements set forth in Sec. 26 of this contract, the Purchaser shall not haul on hydrologically connected natural surface or rocked roads during conditions that would result in any of the following: surface displacement such as rutting or ribbons, continuous mud splash or tire slide, fines being pumped through road surfacing from the subgrade resulting in a layer of surface sludge, as directed by the Authorized Officer.
- (3) E-1 In addition to the requirements set forth in Sec. 26 of this contract, the Purchaser shall not haul on all natural surface roads that receive one-half (½) inch or more precipitation within a twenty four (24) hour period. Haul shall not resume for a minimum of forty-eight (48) hours following any storm event, or until road surface is sufficiently dry, as approved by the Authorized Officer. The Purchaser may elect, at their own expense, to apply rock surfacing to these roads to bring them up to wet weather haul standards, as approved by the Authorized Officer.
- (4) E-1 In addition to the requirement set forth in Section 26 of this contract, the Purchaser shall implement the following noxious weed control measures:

BLOWN FORTUNE TIMBER SALE  
SPECIAL PROVISIONS

- (a) In order to prevent the potential spread of noxious weeds into the Medford District BLM, the operator would be required to clean all logging, construction, chipping, grinding, shredding, rock crushing, and transportation equipment prior to entry on BLM lands.
  - (b) Cleaning shall be defined as removal of dirt, grease, plant parts, and material that may carry noxious weed seeds into BLM lands. Cleaning prior to entry onto BLM lands may be accomplished by using a pressure hose.
  - (c) Only equipment inspected by the BLM would be allowed to operate within the Analysis Area. All subsequent move-ins of equipment as described above shall be treated the same as the initial move-in.
  - (d) Prior to initial move-in of any equipment, and all subsequent move-ins, the operator shall make the equipment available for BLM inspection at an agreed upon location off Federal lands.
  - (e) Equipment would be visually inspected by the Authorized Officer to verify that the equipment has been reasonably cleaned.
- (5) E-1 In addition to the requirements set forth in Section 26 of this contract, the Purchaser shall implement the following noxious weed control measures:

Upon decommissioning and prior to fall rains, the Purchaser shall scarify landings (outside of the driving surface), tractor swing routes, and temporary routes to provide for adequate drainage, then stabilize and revegetate all bare soil with certified weed free straw mulch and a native seed mixture approved by the Authorized Officer. Landings on roads and rocky areas that lack soil for seed germination need not be scarified, seeded or mulched, as determined by the Authorized Officer. The BLM may provide the seed mixture and straw mulch if the purchaser is unable to locate and buy the approved materials from a commercial source. The Purchaser shall reimburse the government for the cost of seed and straw, if provided by the government. The Purchaser shall furnish the specific seed mixture prescribed by the Authorized Officer, which will include up to 3 grasses and 2 forbs from the following list, but may include substitutions approved by the Authorized Officer:

Grasses: *Achnatherum lemmonii*, *Bromus carinatus*, *Brumus vulgaris*, *Elymus glaucus*, *Festuca californica*, *Festuca roemerii*, *Koeleria macrantha*, *Poa secunda*, *Vulpia microstachys*

Forbs: *Achillea millefolium*, *Clarkia purpurea*, *Clarkia homboidea*, *Collinsia grandiflora*, *Eriophyllum lanatum*, *Lupinus bicolor*, *Madia elegans*, *Madia gracilis*

The proportion of each species in the mixture shall be prescribed by the Authorized Officer. The Purchaser shall apply prescribed seed and straw mulch to acres designated

**BLOWN FORTUNE TIMBER SALE**  
**SPECIAL PROVISIONS**

for treatment, as directed by the Authorized Officer, at the following rates of application:

Grass seed	20 to 25 lbs/acre (cumulative, all species)
Forb seed	0.5 to 2 lbs/acre (cumulative, all species)
Straw mulch	1000 lbs/acre

The Purchaser shall apply seed and straw mulch between September 1 of one calendar year and March 31 of the following year. Deviations from that timing must be approved by the Authorized Officer. The Purchaser shall notify the Authorized Officer at least 5 days in advance of the date that he/she intends to commence revegetation and soil stabilization work.

If the Purchaser furnishes seed from any source other than the BLM, that seed shall meet the following minimum test standards:

<u>Test</u>	<u>Grasses (%)</u>	<u>Forbs (%)</u>
Purity:	95	80
Germination:	85	70
Other species/weed content (max):	0.2	0.2
Noxious weed content:	Prohibited	Prohibited

Furnished seed shall meet the minimum requirements for either Yellow Tag Source Identified Seed or Blue Tag Certified Class Seed, as defined by the Association of Official Seed Certifying Agencies. Seed source shall be approved by the Authorized Officer and shall be from the EPA Level III Ecoregion in which the project occurs. For each lot of seed, the Purchaser shall furnish the Authorized Officer a Seed Test result from a certified seed testing lab (e.g., Oregon State University), which shall include: test date; lot number; seed source; and results of test for purity, germination, and weed content. All seed lots must have been tested within the previous 12 months to be accepted. Seed that has become wet, moldy, or otherwise damaged shall not be accepted. Seed must be available to the Authorized Officer for inspection at least 5 days in advance of commencing revegetation work. If the Purchaser furnishes straw mulch from any source other than the BLM, the material must be from native grass or other approved sterile grain crops that are certified weed free and free of mold or other objectionable materials. Straw mulch shall be in an air-dry condition and suitable for spreading in a uniform manner. Straw mulch must be available to the Authorized Officer for inspection at least 5 days in advance of commencing revegetation work.

- (6) E-1 In addition to the requirement set forth in Sec. 26 of this contract, the Purchaser shall prepare a Spill Prevention, Control, and Countermeasure Plan (SPCC) for all hazardous substances to be used in the contract area, as directed by the Authorized Officer. Such plan shall include identification of Purchaser's representatives responsible for supervising initial containment action for releases and subsequent cleanup. Such plans must comply with the State of Oregon DEQ OAR 340-142, Oil and Hazardous Materials Emergency Response Requirements. All operators shall have a Spill Containment Kit (SCK) as described in the SPCC plan on-site during any operation with potential for run-off to adjacent waterbodies. The SCK shall be appropriate in size and type for the oil or hazardous material carried by the Purchaser.

BLOWN FORTUNE TIMBER SALE  
SPECIAL PROVISIONS

- (7) E-1 In addition to the requirement set forth in Sec. 26 of this contract, the Purchaser shall not store any fuel or other petroleum products or refuel heavy mechanized equipment within one hundred fifty (150) feet of all riparian management or wet areas. The Purchaser shall not refuel or maintain handheld equipment such as drip torches and chainsaw within one hundred (100) feet of waterbodies. Portable pumps may be refueled onsite within a spill containment system. All Petroleum products shall be stored in durable containers and located so that any accidental releases will be contained and not drain into any stream system. Hydraulic fluid and fuel lines on heavy mechanized equipment would be in proper working condition in order to minimize potential for leakage into streams. Absorbent materials shall be onsite to allow for immediate containment of any accidental spills. Spilled fuel and oil shall be cleaned up and disposed of at an approved disposal site.
- (8) E-1 In addition to the requirements set forth in Sec. 26 of this contract, the Purchaser shall prevent the delivery of chemical retardant foam or additives to waterbodies, and wetlands. Ignition devices/materials shall be stored and disposed of at least one hundred fifty (150) feet away from streams and wetlands.
- (9) E-1 In addition to the requirement set forth in Sec. 26 of this contract, the Purchaser shall not locate new landings in areas that contribute eroded fines to streams, wet areas, dry draws and swales. If these landing locations cannot be avoided, ensure that properly installed sediment control measures are placed and maintained, as needed, to keep eroded material onsite.
- (10) E-1 In addition to the requirement set forth in Sec. 26 of this contract, the Purchaser shall ensure that silt fencing or other sediment control measures are properly placed and maintained during use and periods of non-use when utilizing landings, skid trails, temp routes, or haul routes that have the potential to release eroded fines into a stream or wet area, directly or via draws or ditchlines. Any project-related activity would be suspended if conditions develop that cause a potential for sediment laden runoff to enter a wetland, floodplain or waters of the state. Operations can resume when sediment control devices are in place and conditions allow turbidity standards to be met.
- (11) E-1 In addition to the requirement set forth in Sec. 26 of this contract, the Purchaser shall, prior to October 15 of the same operating season, winterize and rehabilitate temporary routes, landings, hydrologically connected corridors and skidtrails and other areas of exposed soils by properly installing and/or using water bars, berms, sediment basins, gravel pads, hay bales, small dense woody debris, seeding and/or mulching, to reduce sediment runoff and divert runoff water away from stream channels, headwalls, slide areas, high landslide hazard locations or steep erodible fill slopes as directed by the Authorized Officer.
- (12) E-1 In addition to the requirement set forth in Section 26 of this contract, the Purchaser shall fully decommission: temporary routes TR 3-14, TR 5-8, TR 9-5, TR 17-2, TR 17-15, and TR 31-2, and all tractor swing routes, and rehabilitate ground based skid trails, and landings outside of the road prism, within ground-based yarding areas **as needed to**

**BLOWN FORTUNE TIMBER SALE**  
**SPECIAL PROVISIONS**

**achieve no more than twenty (20) percent detrimental soil compaction within the unit**, as directed by the Authorized Officer, by one of the following methods:

- (a) If the Authorized Officer deems subsoiling will not cause unacceptable damage to the root systems of residual trees the Purchaser shall discontinuously subsoil, simultaneously water bar, seed, mulch, and barricade. Subsoil to a depth of twelve (12) inches, and no further than thirty-six (36) inches apart. If the Authorized Officer deems subsoiling to this depth will cause an unacceptable amount of damage to the root system of residual trees, the Purchaser shall scarify to a depth of up to six (6) inches and simultaneously water bar, seed, mulch, and barricade.
- (b) All rehabilitation shall occur within eighteen (18) months of harvest, during dry conditions, and after pile burning is complete.
- (13) E-1 In addition to the requirement set forth in Sec. 26 of this contract, the Purchaser shall place material removed during excavation in locations where it cannot enter streams or other water bodies.
- (14) E-2 The water bars to be constructed as required by Sec. 26(c) shall be constructed in accordance with the spacing described in the table below and to the specifications shown on Exhibit C-11-1 which is attached hereto and made a part hereof.

Gradient (Percent)	Water Bar Spacing by Erosion Class	
	High Units 3-11, 3-14, 9-14, 17-2, 17-15, 17-16, 17-17, 31-2	Moderate Units 17-1, 17-15G
2-5%	200 feet	300 feet
6-10%	150 feet	200 feet
11-15%	100 feet	150 feet
16-20%	75 feet	100 feet
21-35%	50 feet	75 feet
36+%	50 feet	50 feet

- (15) E-3 The Purchaser shall immediately discontinue specified construction or timber harvesting operations upon written notice from the Contracting Officer that:
  - (a) threatened or endangered plants or animals protected under the Endangered Species Act of 1973, as amended, may be affected by the operation, and a determination is made that consultation or reinitiation of consultation is required concerning the species prior to continuing operation, or;
  - (b) when, in order to comply with the Endangered Species Act, or to prevent incidental take of northern spotted owls in accordance with management direction in the Record of Decision (ROD) and Resource Management Plan (RMP), the Contracting Officer determines it may be necessary to modify or terminate the contract, or;

BLOWN FORTUNE TIMBER SALE  
SPECIAL PROVISIONS

- (c) Federal proposed, Federal candidate, Bureau sensitive or State listed species protected under BLM Manual 6840 - Special Status Species Management - have been identified, and a determination is made that continued operations would affect the species or its habitat, or;
- (d) when, in order to comply with a court order, which enjoins operations on the sale or otherwise requires the Bureau of Land Management to suspend operations, or;
- (e) when, in order to comply with a court order, the Contracting Officer determines it may be necessary to modify or terminate the contract, or;
- (f) when, in order to comply with a stay or other remedy issued by the Interior Board of Land Appeals (IBLA) the Contracting Officer determines it may be necessary to modify or terminate the contract, or;
- (g) species have been discovered which were identified for protection in accordance with management direction established in the ROD and RMP, and the Contracting Officer determines that continued operations would affect the species or its habitat, or;
- (h) when, in order to protect species which were identified for protection in accordance with management direction established in the ROD and RMP, the Contracting Officer determines it may be necessary to modify or terminate the contract.

Those operations necessary for a safe removal of personnel and equipment from the contract area and those directed by the Contracting Officer, which are required in order to leave the contract area in an acceptable condition will be permitted. Discontinued operations may be resumed upon receipt of written instructions and authorization by the Contracting Officer.

During any period of suspension, the Purchaser may withdraw performance and payment bond coverage aside from that deemed necessary by the Authorized Officer to secure cut and/or removed timber for which the Bureau of Land Management has not received payment, and/or unfulfilled contract requirements associated with harvest operations that have already occurred and associated post-harvest requirements.

In the event of a suspension period or a combination of suspension periods that exceed a total of 30 days, the First Installment held on deposit may be temporarily reduced upon the written request of the Purchaser. For the period of suspension extending beyond 30 days, the First Installment on deposit may be reduced to five (5) percent of the First Installment amount listed in Section 3.a. of the contract. Any First Installment amount temporarily reduced may be refunded or transferred to another BLM contract at the request of the Purchaser. However, if the Purchaser has outstanding debt owing the United States, the Contracting Officer must first apply the amount of First Installment that could be refunded to the debt owed in accordance with the Debt Collection

**BLOWN FORTUNE TIMBER SALE**  
**SPECIAL PROVISIONS**

Improvement Act, as amended (31 USC 3710, et seq.). Upon Purchaser's receipt of a bill for collection and written notice from the Contracting Officer lifting the suspension, the Purchaser shall restore the First Installment to the full amount shown in Section 3.a. of the contract within 15 days after the bill for collection is issued, subject to Section 3.i. of the contract. The Purchaser shall not resume contract operations until the First Installment amount is fully restored.

In the event of a suspension period or a combination of suspension periods that exceed a total of 30 days, the unamortized Out-of-Pocket Expenses for road or other construction required pursuant to Exhibit C of the contract shall be refunded or transferred to another BLM contract at the request of the Purchaser. Upon written notice from the Contracting Officer lifting the suspension, the Purchaser shall reimburse the Government the amounts refunded or transferred. The Purchaser may choose to pay this reimbursement at once or in installments payable at the same time as payments are due for the timber under the contract and in amounts approximately equal to the expenses associated with the timber for which payment is due.

In the event that operating time is lost as a result of the incorporation of additional contract requirements, or delays due to Endangered Species Act consultation with the U.S. Fish and Wildlife Service or U.S. National Marine Fisheries Service, court-ordered injunctions, or an IBLA issued stay or remedy, the Purchaser agrees that an extension of time, without reappraisal, will constitute a full and complete remedy for any claim that delays due to the suspension hindered performance of the contract or resulted in damages of any kind to the Purchaser.

The Contracting Officer may determine that it is necessary to modify the contract or terminate the cutting and removal rights under the contract in order to comply with the Endangered Species Act, prevent incidental take of northern spotted owls in accordance with the ROD and RMP, protect species that have been discovered which were identified for protection in accordance with management direction established in the ROD and RMP, or comply with a court order or an IBLA issued stay or remedy. Following the issuance of a written notice that cutting and removal rights will be terminated, the Purchaser will be permitted to remove timber cut under the contract, if allowed by the Endangered Species Act, if able to proceed without causing incidental take of northern spotted owls in accordance with the ROD and RMP, if consistent with species protection in accordance with management direction established in the ROD and RMP, or if consistent with a court order or an IBLA issued stay or remedy.

In the event the contract is modified or cutting and removal rights are terminated under this subsection, the Purchaser agrees that the liability of the United States shall be limited to the actual costs incurred by the Purchaser which have not been amortized by timber removed from the contract area. This calculation of liability shall utilize actual Purchaser costs and Government estimates of timber volumes. At the Authorized Officer's request, the Purchaser agrees to provide documentation of the actual costs incurred in the performance of the contract. In addition, the Purchaser shall be released from the obligation to pay the contract price for any timber which is not authorized to be removed from the contract area.

BLOWN FORTUNE TIMBER SALE  
SPECIAL PROVISIONS

The Purchaser specifically and expressly waives any right to claim damages, other than those described in the preceding paragraphs, based on an alleged breach of any duty to the Purchaser, whether express or implied, in regard to the manner in which the Government defended the litigation which resulted in the court order affecting the operation of the contract. This waiver also extends to any claims based on effects on the operation of the contract that arise from litigation against another agency. Furthermore, the Purchaser specifically acknowledges and agrees that a court ruling that the Government violated the Administrative Procedures Act cannot be interpreted, in itself, to mean that the Government had not acted reasonably in regard to its duties to the Purchaser under this contract.

- (16) E-5 The Purchaser shall notify the Authorized Officer in writing by February 1 of each calendar year in which operations are expected to take place on the contract area between March 1 and September 30, both days inclusive. If notification is not received by the Authorized Officer by February 1, felling, bucking, yarding, road construction, or any other activity with the potential to disturb nesting northern spotted owls may not be allowed between March 1 and September 30, both days inclusive.

Upon receipt of a notice that the Purchaser expects to perform such operations during this time period, the Government will conduct surveys to determine whether owls have moved into harvest units. If northern spotted owls are detected in or adjacent to the units, operations would be restricted until northern spotted owl occupancy and nesting status has been determined. If it is determined owls are not nesting or that no young have been produced, the Authorized Officer may lift the seasonal restriction on such operations in writing. Without this approval, such operations are prohibited from March 1 through June 30 of each year.

(D) FIRE PREVENTION

- (1) F-1 Fire Prevention and Control. Primarily for purposes of fire prevention and control, the Purchaser shall, prior to the operation of power driven equipment in construction or logging operations under this contract during the closed fire season or periods of fire danger, prepare a fire prevention and control plan to the satisfaction of the of the Authorized Officer.
- (2) F-1a Fire Prevention and Control. Primarily for purposes of fire prevention and control, the Purchaser shall comply with the following provisions:
- (a) At least three (3) days prior to the operation of power-driven equipment during any operations under this contract during the closed fire season or periods of fire danger, prepare a fire prevention and control plan to the satisfaction of the Authorized Officer, the State of Oregon Department of Forestry, and the State of Oregon Douglas Forest Protection Agency.

**BLOWN FORTUNE TIMBER SALE**  
**SPECIAL PROVISIONS**

- (b) Provide and maintain on the contract area in good working order, and immediately available, the following equipment for use during closed fire season or periods of fire danger:
1. F-2a Fire fighting tools shall be kept at each landing or at such other place as the Authorized Officer shall designate whenever employees are working on the contract area. All fire fighting tools shall be kept in a sturdily constructed box which shall be painted red and lettered on the front or top in large letters, "For Fire Only." The box shall have a hinged lid and a hasp by which the lid can be sealed. One box may serve two landings not over six hundred (600) feet apart. When filled, the box shall not weigh over two hundred (200) pounds. The fire tools shall be in good condition, be tight on strong handles, and have sharp cutting edges. There shall be not less than four (4) tools in each box nor less than one (1) tool for each employee working on the contract area. Three-fourths (3/4) of all fire tools shall be shovels, hazel hoes, or other scraping tools. The fire tools shall be used only for fighting fire.
  2. F-2b At each landing or such other place as the Authorized Officer shall designate during periods of operation one (1) tank truck of three hundred (300) gallons or more capacity with a minimum of five hundred (500) feet of 1½ inch hose (must be adequate length to reach 200 feet beyond active work sites), six (6) 1½ inch wyes, six (6) 1½ inch to 1 inch reducers, three (3) 1½ inch nozzles and three (3) 1 inch nozzles. One (1) three hundred (300) gallon fire engine may be substituted for each required 300-gallon tank truck, provided that the total capability to pump and deliver water remains unchanged. Each fire engine / tank truck shall be equipped with a pump capable of delivering a minimum of forty (40) gallons per minute (gpm) water flow at one hundred fifty (150) pounds per square inch (psi) engine pressure through fifty (50) feet of 1½ inch fire hose. The pump may be either power take off driven or truck-mounted auxiliary engine driven, or portable. All equipment shall be acceptable to and approved by the Authorized Officer and shall conform to the standards set forth in Oregon Revised Statutes 477.645 through 477.670. All hose couplings shall have the standard thread adopted by the BLM (1 ½ inches National Hose Thread (NH), 1 inch National Pipe Straight Hose Thread (NPSH) or be provided with suitable adapters. At the close of each working day, all bulldozers and fire/tank trucks shall be filled with fuel and made ready for immediate use. All fire/tank trucks shall be filled with water and made available for immediate use.
  3. F-2c Serviceable cell phone or radio equipment able to provide prompt and reliable communication between the contract area, Medford BLM District Office, Oregon Department of Forestry, and Douglas Forest Protection Agency. Such communication shall be available during periods of operation including the time watchman service is required.

**BLOWN FORTUNE TIMBER SALE**  
**SPECIAL PROVISIONS**

4. F-2d A pair of headlights capable of being quickly attached to each bulldozer used on the contract area. The headlights shall be adequate to provide illumination sufficient to allow use of the bulldozers for fire fighting and construction of fire lines at night.
5. F-2f A headlamp for each employee in the woods crew adequate to provide sufficient illumination for night firefighting. A headlight shall be of the type that can be fastened to the head so as to allow independent use of the hands. At least one extra set of batteries shall be provided for each such headlight.
6. F-2f Two (2) back-pack pumps at each landing and one (1) at each tail block, all to be kept full of water and in good operating condition.
7. F-2g A chemical fire extinguisher of at least eight (8) ounces minimum capacity of a type approved by the Authorized Officer and a size 0 or larger shovel shall be carried during the closed fire season or periods of fire danger by each falling crew and each buckner using a power saw on the contract area. Such fire extinguisher shall be filled and in effective operating condition and shall at all times be immediately available to the operator when the saw is being fueled or the motor of the saw is running. Any fueling of a power saw shall be done in an area which has first been cleared of all flammable material. Power saws shall be moved at least twenty (20) feet from the place of fueling before the engine is started. Each power saw shall be equipped with an exhaust system and a spark arresting device which are of types approved by the Authorized Officer.

(c) F-5 Where blocks and cables are used on the contract area during periods of fire danger, the Purchaser shall remove all flammable material at least ten (10) feet from the place where the tail or any other block will hang when the cable is tight. Such clearings shall be inspected periodically by the Purchaser and shall be kept free of flammable material.

(3) F-9 During Oregon Department of Forestry regulated use closure, no smoking shall be permitted outside of closed vehicles.

(E) **SLASH DISPOSAL**

(1) SD-1 Fire Hazard Reduction. In addition to the requirements of Sec. 15 of this contract, and notwithstanding the Purchaser's satisfactory compliance with State laws and regulations regarding offsetting or abating the additional fire hazard created by this operation and the State's willingness to release the Purchaser from liability for such hazard, the Purchaser shall remain responsible to the Government for performance of the following hazard reduction measures required by this contract:

(a) SD-1a Lop and scatter all slash outside of the machine pile and burn and/or handpile and burn portions of units 3-11, 17-17, 31-1, and 31-3 as shown on

**BLOWN FORTUNE TIMBER SALE**  
**SPECIAL PROVISIONS**

Exhibit S. All top and side branches must be free of the central stem so that such stem is reduced to the extent that it is within eighteen (18) inches of the ground at all points. Slash includes all woody material (brush, limbs, tops, unmerchantable stems, or chunks) severed, uprooted, or broken from live plants as a result of Purchaser's operations under the terms of this contract. Lop and scatter shall be completed in accordance with Exhibit S as directed by the Authorized Officer.

1. All slash shall be arranged in a discontinuous pattern across the forest floor.
  2. All slash shall be loped to no more than eight (8) feet in length.
- (b) SD-1b Machine pile, cover, and burn all slash in the ground based portion of units 3-11, 3-14, 9-14, 17-1, 17-2, 17-15, 17-15G, 17-16, 17-17, 31-2, 32-5-8.0, 32-5-8.2, and 32-5-9.0, and within the clearing limits of all permanent roads and temporary routes as shown on Exhibit S. Slash shall be piled by machine. Piling shall be completed in accordance with Exhibit S as directed by the Authorized Officer. Finished piles shall be tight and free of earth.
1. The BLM will prepare a fire burn plan. Smoke clearance shall be obtained by the BLM the day prior to planned ignition for all burn units.
  2. Slash includes all woody material (brush, limbs, tops, unmerchantable stems, or chunks) severed, uprooted, or broken from live plants as a result of Purchaser's operations under the terms of this contract. Do not pile pieces of slash with a diameter greater than twelve (12) inches.
  3. All equipment shall be approved by the Authorized Officer. Piling shall be accomplished using a track mounted hydraulic excavator or equivalent with at least a five (5) tooth brush rake. The excavator shall have a minimum reach of twenty (20) feet. The excavator shall be equipped with a hydraulic thumb or rotating controllable grapple head. Finished piles shall be tight and free of dirt and other non-woody debris.
  4. Piles shall be less than sixteen (16) feet in height and width.
  5. Machine piling operations are limited to slopes less than thirty five (35) percent slope when using non-specialized equipment (without a self-leveling cab) or to slopes less than fifty (50) percent slope when using specialized equipment (with a self-leveling cab); and to seasonal restrictions as described in Sec. 42(A)(11)(L-19) and dry conditions as described in Sec. 42(C)(1)(E-1). All areas that are identified in Exhibit A as ground based yarding that cannot be machine piled would be hand piled, except three (3) acres in unit 17-17 that shall be lopped and scattered as shown on Exhibit S.

**BLOWN FORTUNE TIMBER SALE**  
**SPECIAL PROVISIONS**

6. Machine piles shall be constructed as compactly as possible. There should be an adequate supply of fine fuels located within and under the covered area of the pile to ensure ignition of the larger fuels. Completed piles shall be free of projecting limbs or slash which would interfere with adequate covering of the piles.
  7. Machine piles shall be adequately covered with a cap of ten (10) feet by ten (10) feet of four (4) millimeter black polyethylene plastic. The plastic shall be held in place with woody debris or tied with rope or twine to ensure coverage. Coverage shall be completed when piles are constructed, or as directed by the Authorized Officer.
  8. Machine piles shall not be placed within fifteen (15) feet of snags, stumps, reserve trees or large woody debris.
  9. Machine piles will be burned in the fall to spring season after one (1) or more inches of precipitation have occurred.
  10. The Purchaser is required to furnish the fuel and equipment for machine pile burning.
- (c) SD-1c Hand pile, cover, and burn all slash situated in units 3-7, 5-6, 5-8, 8-9G, 9-5, 9-18, and 10-1; hand pile, cover, and burn all slash within one hundred (100) feet of existing roads, where the unit coincides with the road, in units 3-11, 31-1, and 31-3; and hand pile, cover, and burn all slash within the cable yard portion of units 3-14, 17-1, 17-2, and 31-2 as shown on Exhibit S. Slash shall be piled by hand. Finished piles shall be tight and free of earth.
1. The BLM will prepare a fire burn plan. Smoke clearance shall be obtained by the BLM the day prior to planned ignition for all burn units.
  2. Slash includes woody material (brush, limbs, tops, unmerchantable stems, or chunks severed, uprooted, or broken from live plants as a result of Purchaser's operations under the terms of this contract.
  3. Hand pile all slash which is between one (1) and six (6) inches in diameter on the large end and exceeds two (2) feet in length, or as directed by the Authorized Officer.
  4. Hand piles shall be covered with a large enough piece of four (4) millimeter thick black plastic to ensure a dry ignition spot, generally five (5) feet by five (5) feet or large enough to cover eighty (80) percent of the pile.
  5. Hand piles shall not be placed adjacent to or within ten (10) feet of leave trees or large woody debris.

BLOWN FORTUNE TIMBER SALE  
SPECIAL PROVISIONS

6. Hand piles shall not be located on roadways, turnouts, shoulders, or cut banks, unless authorized by the Authorized Officer.
  7. Burning of hand piles would occur after a sufficient period of curing (generally over a year) and adequate seasonal moisture.
- (d) SD-1f Within twenty (20) feet of the edge of each landing pile, all tops, broken pieces, limbs and debris more than one (1) inch in diameter at the large end and longer than two (2) feet in length shall be piled within fourteen (14) days of completion of hauling logs from that landing. Landing piles shall be kept free of dirt and located off of the driving surface of roads and at least fifteen feet (15) from any Reserve Tree and/or as directed by the Authorized Officer.

Upon completion of landing piling, the Purchaser shall prepare the landing piles for burning by constructing a fireline by hand or machine approximately eighteen (18) inches wide and down to mineral soil around each pile to prevent escaped fire. Landing piles shall be less than sixteen (16) feet in height and width. Cover piles with large enough piece of four (4) millimeter thick black plastic to ensure a dry ignition spot, generally ten (10) foot by ten (10) foot. The Purchaser is required to furnish the covering materials. The timing of this covering work shall be in accordance with instructions from the Authorized Officer. If the structure of the landing piles will not permit adequate consumption of piled debris by burning, the Purchaser shall re-pile them at the direction of the Authorized Officer.

1. The BLM will prepare a fire burn plan. Smoke clearance shall be obtained by the BLM the day prior to planned ignition for all burn units.
  2. Landing piles will be burned in the fall to spring season after one (1) or more inches of precipitation have occurred.
  3. Landing piles will be burned within twenty-four (24) months of harvest completion.
  4. If purchaser elects to set aside pole/firewood decks and not put the material in landing piles, the purchaser will be required to remove decks before the expiration of cutting rights. Material will be hauled off site for processing. The Authorized Officer will determine location of pole/hardwood decks.
- (2) SD-2 Notwithstanding the provisions of Sec. 15 of this contract, the Government shall assume all obligations for disposal or reduction of fire hazards created by Purchaser's operations on Government lands, except for burning and mop up assistance as required herein, and measures required in Sections 42(E)(1)(SD-1) and 42(E)(3)(SD-4). In accordance with written instruction to be issued by the Authorized Officer at least ten (10) days in advance of earliest date of required performance, the Purchaser shall, under supervision of the Authorized Officer or his designated representative, assist in preparing units for burning, mop-up, and patrol by furnishing, at his own expense, the services of personnel and equipment on each unit as shown below.

**BLOWN FORTUNE TIMBER SALE**  
**SPECIAL PROVISIONS**

All crews shall arrive on the project area with radios capable of inter-crew communications and communication with a BLM representative at a ratio of one (1) radio per every five (5) crew members.

(a) For igniting and burning machine piles in units 3-11, 3-14, 9-14, 17-1, 17-2, 17-15, 17-15G, 17-16, 17-17, 31-2, 32-5-8.0, 32-5-8.2, and 32-5-9.0 and within the clearing limits of all permanent roads and temporary routes as shown on Exhibit S:

1. One (1) person to supervise crew and equipment operators who is Burn Boss Qualified at the complexity level of the burn, and to serve as Purchaser's representative.
2. One (1) crew with six (6) members per crew, including a designated crew foreman. Each crew shall be equipped with fuel, drip torches, shovels, pulaskis, one (1) power saw and one (1) backpack pump; one (1) tool for each crew member.
3. One (1) Wildland Fire Engine Boss.
4. One (1) Wildland Fire Engine. Each engine shall have three hundred (300) gallons or more capacity with one thousand (1,000) feet of one and one half (1½) inch hose and nozzle(s) acceptable to the Authorized Officer. All hose couplings shall have the standard thread adopted by the State Fire Marshall pursuant to ORS 476.610 as amended. Each engine shall be equipped with a mounted pump conforming to the standards set forth in the National Wildfire Coordinating Group (NWCG) Wildland Fire Qualification System requirements. Engine and tank shall be in good working order and shall be filled with water.
5. Six (6) drip torches.
6. Hand ignition with drip torches is required in machine pile units.
7. All ignition personnel will be directly supervised by a BLM representative.

(b) For mop-up of machine piles in units 3-11, 3-14, 9-14, 17-1, 17-2, 17-15, 17-15G, 17-16, 17-17, 31-2, 32-5-8.0, 32-5-8.2, and 32-5-9.0 and within the clearing limits of all permanent roads and temporary routes as shown on Exhibit S:

1. One (1) person to supervise crew and equipment operators who is Burn Boss Qualified at the complexity level of the burn, and to serve as Purchaser's representative.

**BLOWN FORTUNE TIMBER SALE**  
**SPECIAL PROVISIONS**

2. One (1) crew with six (6) members per crew, including a designated crew foreman. Each crew shall be equipped with shovels, pulaskis, or scraping tool, one (1) power saw and one (1) backpack pump; one (1) tool for each crew member.
  3. One (1) Wildland Fire Engine Boss.
  4. One (1) Wildland Fire Engine. Each engine shall have three hundred (300) gallons or more capacity with one thousand (1,000) feet of one and one half (1½) inch hose and nozzle(s) acceptable to the Authorized Officer. All hose couplings shall have the standard thread adopted by the State Fire Marshall pursuant to ORS 476.610 as amended. Each engine shall be equipped with a mounted pump conforming to the standards set forth in the National Wildfire Coordinating Group (NWCG) Wildland Fire Qualification System requirements. Engine and tank shall be in good working order and shall be filled with water.
- (c) For igniting and burning hand piles in units 3-7, 3-11, 3-14, 5-6, 5-8, 8-9G, 9-5, 9-18, 10-1, 17-1, 17-2, 31-1, 31-2, and 31-3:
1. One (1) person to supervise crew and equipment operators who is Burn Boss Qualified at the complexity level of the burn, and to serve as Purchaser's representative.
  2. One (1) crew with ten (10) members per crew, including a designated crew foreman. Each crew shall be equipped with fuel, drip torches, shovels, pulaskis, one (1) power saw and one (1) backpack pump; one (1) tool for each crew member.
  3. One (1) Wildland Fire Engine Boss.
  4. One (1) Wildland Fire Engine. Each engine shall have three hundred (300) gallons or more capacity with one thousand (1,000) feet of one and one half (1½) inch hose and nozzles acceptable to the Authorized Officer. All hose couplings shall have the standard thread adopted by the State Fire Marshall pursuant to ORS 476.610 as amended. Each engine shall be equipped with a mounted pump conforming to the standards set forth in the National Wildfire Coordinating Group (NWCG) Wildland Fire Qualification System requirements. Engine and tank shall be in good working order and shall be filled with water.
  5. Ten (10) drip torches.
  6. Hand ignition with drip torches is required in pile burn units.
  7. All ignition personnel will be directly supervised by a BLM representative.

BLOWN FORTUNE TIMBER SALE  
SPECIAL PROVISIONS

- (d) For mop up of hand piles in units 3-7, 3-11, 3-14, 5-6, 5-8, 8-9G, 9-5, 9-18, 10-1, 17-1, 17-2, 31-1, 31-2, and 31-3:
1. One (1) person to supervise crew and equipment operators who is Burn Boss Qualified at the complexity level of the burn, and to serve as Purchaser's representative.
  2. One (1) crew with six (6) members per crew, including a designated crew foreman. Each crew shall be equipped with shovels, pulaskis, or scraping tool, one (1) power saw and one (1) backpack pump; one (1) tool for each crew member.
  3. One (1) Wildland Fire Engine Boss.
  4. One (1) Wildland Fire Engine. Each engine shall have three hundred (300) gallons or more capacity with one thousand (1,000) feet of one and one half (1½) inch hose and nozzle(s) acceptable to the Authorized Officer. All hose couplings shall have the standard thread adopted by the State Fire Marshall pursuant to ORS 476.610 as amended. Each engine shall be equipped with a mounted pump conforming to the standards set forth in the National Wildfire Coordinating Group (NWCG) Wildland Fire Qualification System requirements. Engine and tank shall be in good working order and shall be filled with water.
- (e) For igniting and burning landing piles:
1. One (1) person to supervise crew and equipment operators who is Burn Boss Qualified at the complexity level of the burn, and to serve as Purchaser's representative.
  2. One (1) crew with six (6) members per crew, including a designated crew foreman. Each crew shall be equipped with shovels, pulaskis, or scraping tool, one (1) power saw and one (1) backpack pump; one (1) tool for each crew member.
  3. One (1) Wildland Fire Engine Boss.
  4. One (1) Wildland Fire Engine. Each engine shall have three hundred (300) gallons or more capacity with one thousand (1,000) feet of one and one half (1½) inch hose and nozzles acceptable to the Authorized Officer. All hose couplings shall have the standard thread adopted by the State Fire Marshall pursuant to ORS 476.610 as amended. Each engine shall be equipped with a mounted pump conforming to the standards set forth in the National Wildfire Coordinating Group (NWCG) Wildland Fire Qualification System requirements. Engine and tank shall be in good working order and shall be filled with water.

BLOWN FORTUNE TIMBER SALE  
SPECIAL PROVISIONS

(f) For mop-up landing piles:

1. One (1) person to supervise crew and equipment operators who is Burn Boss Qualified at the complexity level of the burn, and to serve as Purchaser's representative.
2. One (1) crew with six (6) members per crew, including a designated crew foreman. Each crew shall be equipped with shovels, pulaskis, or scraping tool, one (1) power saw and one (1) backpack pump; one (1) tool for each crew member.
3. One (1) Wildland Fire Engine Boss.
4. One (1) Wildland Fire Engine. Each engine shall have three hundred (300) gallons or more capacity with one thousand (1,000) feet of one and one half (1½) inch hose and nozzle(s) acceptable to the Authorized Officer. All hose couplings shall have the standard thread adopted by the State Fire Marshall pursuant to ORS 476.610 as amended. Each engine shall be equipped with a mounted pump conforming to the standards set forth in the National Wildfire Coordinating Group (NWCG) Wildland Fire Qualification System requirements. Engine and tank shall be in good working order and shall be filled with water.

Aircraft and pilots used for Logging Residue Reduction or the suppression of escaped fires from Logging Residue Reduction operations, shall be acquired from a list of aircraft and pilots approved (i.e., carded for these specific activities) by the Office of Aircraft Services or the U.S. Forest Service. This list is available from BLM District Offices upon request.

All listed personnel shall be physically fit, experienced and fully capable of functioning as required. All personnel shall arrive at the project area(s) with the following personal safety equipment: long sleeve natural fabric shirt, full length natural fabric trousers, minimum eight (8)-inch top leather boots, hardhat, and leather gloves. All personnel shall wear long pants and long sleeve shirts, lug-soled leather boots with minimum eight (8)-inch tall uppers that provide ankle support, approved hardhat, and leather gloves. On the day of ignition, clothing shall be of approved aramid fabric, Nomex™ or equivalent, and all personnel shall carry an approved fire shelter. Clothing shall be free of diesel fuel oil.

All listed tools and equipment shall be in good usable condition. All power driven equipment shall be fully fueled and available for immediate use. During periods of use under this subsection, the Purchaser shall provide fuel and maintenance for all such power- driven equipment.

Except as provided hereafter for fire escapement, the Purchaser shall continue the required assistance in mop up on each hand/machine piled unit and landing decks, four hundred fifty (450) hours as directed by the Authorized Officer within a 10 days

**BLOWN FORTUNE TIMBER SALE**  
**SPECIAL PROVISIONS**

beginning 8:00 a.m. the day following completion of ignition in that unit or until released from such services by the Authorized Officer, whichever occurs first.

In the event of a fire escapement, Purchaser's personnel and equipment shall, under supervision of the Authorized Officer, take action to suppress, including control and mop-up, the escaped fire until released from such service by the Government. If it becomes necessary to suppress a fire which escapes from the prescribed fire area for a period beyond midnight of ignition day, then the Government shall, at its option:

- (a) reimburse Purchaser for such additional use of personnel and equipment at wage rates shown in the current Administratively Determined Pay Rates for Western Area and at equipment rates shown in current Oregon-Washington Interagency Fire Fighting Equipment Rental Rates schedule, until the Purchaser is released from such service by the Government, or+
- (b) release the Purchaser from additional suppression work and assume responsibility for suppressing the escaped fire.

In situations where an escaped fire is controlled and contained by an adequate fire break (e.g., trail, road, stream, rock formation), the Government may permit the Purchaser to remove personnel for that day; provided that, all mop up work on the escaped fire area is included with mop up work on the prescribed fire area. In such an event, the Purchaser must sign a statement of agreement to complete mop up work on all escaped fire areas concurrently with mop up work on the prescribed fire area.

In case of injury to personnel or damage to equipment furnished by the Purchaser as required by this subsection, liability shall be borne by the Purchaser, unless such injury or damage is caused by Government negligence.

Time is of the essence in complying with this provision. In the event the Purchaser fails to provide personnel and equipment required herein, the Purchaser shall be responsible for all additional costs incurred by the Government in disposing of slash, including but not limited to the wages and other costs of providing federal employees and others as substitute labor force, the cost of providing substitute equipment, and appropriate additional overhead expenses. If the Purchaser's failure results in deferral of burning and new conditions necessitate additional site preparation work and/or use of additional personnel and equipment to accomplish planned burning, the Purchaser also shall be responsible for such additional costs.

- (3) SD-4 Logging Residue Reduction. In addition to the requirements of Secs. 15 and 25 of this contract, and notwithstanding the Purchaser's satisfactory compliance with State laws and regulations regarding offsetting or abating the additional fire hazard created by this operation and the State's willingness to release Purchaser from liability for such hazard, the Purchaser shall remain responsible to the Government for performance of the following logging residue reduction and site preparation measures required by this contract:

**BLOWN FORTUNE TIMBER SALE**  
**SPECIAL PROVISIONS**

- (a) L-4 Selective Slashing: All trees between one (1) inch and eight (8) inches D.B.H.O.B. shall be felled and spaced following logging as directed by the Authorized Officer in units 3-7, 5-6, 5-8, 8-9G, 9-5, 9-18, and 10-1 and the hand pile portions of units 3-11, 3-14, 17-1, 17-2, 31-1, 31-2, and 31-3 as shown on Exhibit S. Space live conifers twelve (12) feet by twelve (12) feet, and space hardwoods and shrubs forty (40) feet by forty (40) feet.

Acceptable leave trees shall:

1. Demonstrate good form and vigor.
2. Have a minimum four (4) inch terminal leader with thirty (30) percent live crown ratio.
3. Be non-chlorotic; be light or dark green with very little or no yellowish tint.
4. Have an un-damaged top.
5. Be free of visible disease, cankers, fire damage, or blister rust.
6. Not have multiple tops.

In absence of trees that meet the above definition for an acceptable leave tree, include any live conifer seedling, natural or planted that has a two (2) inch terminal leader with a twenty-five (25) percent crown ratio.

- (b) Perform fireline construction for underburning in units 5-6, 9-18, and 17-1 as shown on Exhibit S:

Notwithstanding the provisions of Sec. 15 of this contract, the Government shall assume all obligations for disposal or reduction of fire hazards created by Purchaser's operations on Government lands, except for burning and mop up assistance as required herein, and measures required in Sections 42(E)(1)(SD-1) and 42(E)(3)(SD-4). In accordance with written instruction to be issued by the Authorized Officer at least ten (10) days in advance of earliest date of required performance, the Purchaser shall, under supervision of the Authorized Officer or his designated representative, assist in preparing units for burning, mop-up, and patrol by furnishing, at his own expense, the services of personnel and equipment on each unit as shown below.

All crews shall arrive on the project area with radios capable of inter-crew communications and communication with a BLM representative at a ratio of one (1) radio per every five (5) crew members.

1. Underburn units shall follow the Resource, Prescribed Fire Objectives and Constraints (Element 5 Objectives) for each underburn unit as outlined in Prescribed Fire Burn Plan and as directed by the Authorized Officer or BLM representative.
2. The BLM will prepare a fire burn plan. Smoke clearance shall be obtained the day prior to planned ignition for all burn units by the BLM.

BLOWN FORTUNE TIMBER SALE  
SPECIAL PROVISIONS

3. Prescribed burning shall be conducted in a manner that will minimize damage to reserve trees, duff, soil, and to avoid loss of large/coarse woody debris and will be consistent with ecosystem management objectives outlined in the burn plan.
  4. Firelines will be constructed by hand to mineral soil to a minimum of eighteen (18) inches wide and a maximum of three (3) feet wide.
  5. Create a minimum fuel break of ten (10) feet on the underburn side of the fire line and six (6) feet on the unburned side of the fire line by removing logging slash or live vegetation under eight (8) inches diameter at the large end or at eight (8) inch diameter at breast height.
  6. Slash shall be dispersed in a discontinuous pattern a minimum of fifteen (15) feet away from the fire line within or outside the unit boundary as directed by the Authorized Officer or BLM representative.
  7. Limit fire lines inside Riparian Reserves (areas within one hundred ninety-five (195) feet of streams shown on Exhibit S). On very steep ground where runoff could enter waterways incorporate water bars as directed by the Authorized Officer. Locate fire lines so that open meadows associated with streams do not burn, unless prescribed for restoration.
  8. Fire lines shall be constructed within thirty (30) days of notification by the Authorized Officer. Water bars shall be constructed and maintained on the fire lines to the satisfaction of the Authorized Officer.
- (c) For igniting and holding underburning in units 5-6, 9-18, and 17-1 as shown on Exhibit S:
1. One (1) person to supervise crew and equipment operators who is Burn Boss Qualified at the complexity level of the burn, and to serve as Purchaser's representative.
  2. Two (2) crews with ten (10) members per crew, including a designated crew foreman. Each crew shall be equipped with fuel, drip torches, shovels, pulaskis, one (1) power saw and one (1) backpack pump; one (1) tool for each crew member.
  3. One (1) tractor/dozer operator.
  4. Three (3) Wildland Fire Engine Bosses.
  5. One (1) tractor (Caterpillar D6 or equivalent) equipped with straight solid blade.

BLOWN FORTUNE TIMBER SALE  
SPECIAL PROVISIONS

6. Three (3) Wildland Fire Engines. Each engine shall have three hundred (300) gallons or more capacity with one thousand (1,000) feet of one and one half (1½) inch hose and nozzles acceptable to the Authorized Officer. All hose couplings shall have the standard thread adopted by the State Fire Marshall pursuant to ORS 476.610 as amended. Each engine shall be equipped with a mounted pump conforming to the standards set forth in the National Wildfire Coordinating Group (NWCG) Wildland Fire Qualification System requirements. Engine and tank shall be in good working order and shall be filled with water.
  7. Sixteen (16) drip torches.
  8. Hand ignition with drip torches is required in underburn units. Ignition shall occur at least twenty-five (25) feet from intermittent streams and at least sixty (60) feet from perennial streams shown on Exhibit S.
  9. All ignition personnel will be directly supervised by a BLM representative.
  10. The Purchaser is required to furnish the fuel and equipment for underburning.
- (d) For mop-up of underburning in units 15-6, 9-18, and 17-1 as shown on Exhibit S:
1. One (1) person to supervise crew and equipment operators who is Burn Boss Qualified at the complexity level of the burn, and to serve as Purchaser's representative.
  2. One (1) crew with six (6) members per crew, including a designated crew foreman. Each crew shall be equipped with shovels, pulaskis, or scraping tool, one (1) power saw and one (1) backpack pump; one (1) tool for each crew member.
  3. One (1) Wildland Fire Engine Boss.
  4. One (1) Wildland Fire Engine. Each engine shall have three hundred (300) gallons or more capacity with one thousand (1,000) feet of one and one half (1½) inch hose and nozzle(s) acceptable to the Authorized Officer. All hose couplings shall have the standard thread adopted by the State Fire Marshall pursuant to ORS 476.610 as amended. Each engine shall be equipped with a mounted pump conforming to the standards set forth in the National Wildfire Coordinating Group (NWCG) Wildland Fire Qualification System requirements. Engine and tank shall be in good working order and shall be filled with water.

**BLOWN FORTUNE TIMBER SALE**  
**SPECIAL PROVISIONS**

Aircraft and pilots used for Logging Residue Reduction or the suppression of escaped fires from Logging Residue Reduction operations, shall be acquired from a list of aircraft and pilots approved (i.e., carded for these specific activities) by the Office of Aircraft Services or the U.S. Forest Service. This list is available from BLM District Offices upon request.

All listed personnel shall be physically fit, experienced and fully capable of functioning as required. All personnel shall arrive at the project area(s) with the following personal safety equipment: long sleeve natural fabric shirt, full length natural fabric trousers, minimum eight (8)-inch top leather boots, hardhat, and leather gloves. All personnel shall wear long pants and long sleeve shirts, lug-soled leather boots with minimum eight (8)-inch tall uppers that provide ankle support, approved hardhat, and leather gloves. On the day of ignition, clothing shall be of approved aramid fabric, Nomex™ or equivalent, and all personnel shall carry an approved fire shelter. Clothing shall be free of diesel fuel oil.

All listed tools and equipment shall be in good usable condition. All power driven equipment shall be fully fueled and available for immediate use. During periods of use under this subsection, the Purchaser shall provide fuel and maintenance for all such power- driven equipment.

Except as provided hereafter for fire escapement, the Purchaser shall continue the required assistance in mop up on each underburn unit shown on Exhibit S for six hundred forty (640) hours as directed by the Authorized Officer within a 10 days beginning 8:00 a.m. the day following completion of ignition in that unit or until released from such services by the Authorized Officer, whichever occurs first.

In the event of a fire escapement, Purchaser's personnel and equipment shall, under supervision of the Authorized Officer, take action to suppress, including control and mop-up, the escaped fire until released from such service by the Government. If it becomes necessary to suppress a fire which escapes from the prescribed fire area for a period beyond midnight of ignition day, then the Government shall, at its option:

- (a) reimburse Purchaser for such additional use of personnel and equipment at wage rates shown in the current Administratively Determined Pay Rates for Western Area and at equipment rates shown in current Oregon-Washington Interagency Fire Fighting Equipment Rental Rates schedule, until the Purchaser is released from such service by the Government, or
- (b) release the Purchaser from additional suppression work and assume responsibility for suppressing the escaped fire.

In situations where an escaped fire is controlled and contained by an adequate fire break (e.g., trail, road, stream, rock formation), the Government may permit the Purchaser to remove personnel for that day; provided that, all mop up work on the escaped fire area is included with mop up work on the prescribed fire area. In such an event, the

**BLOWN FORTUNE TIMBER SALE**  
**SPECIAL PROVISIONS**

Purchaser must sign a statement of agreement to complete mop up work on all escaped fire areas concurrently with mop up work on the prescribed fire area.

In case of injury to personnel or damage to equipment furnished by the Purchaser as required by this subsection, liability shall be borne by the Purchaser, unless such injury or damage is caused by Government negligence.

Time is of the essence in complying with this provision. In the event the Purchaser fails to provide personnel and equipment required herein, the Purchaser shall be responsible for all additional costs incurred by the Government in disposing of slash, including but not limited to the wages and other costs of providing federal employees and others as substitute labor force, the cost of providing substitute equipment, and appropriate additional overhead expenses. If the Purchaser's failure results in deferral of burning and new conditions necessitate additional site preparation work and/or use of additional personnel and equipment to accomplish planned burning, the Purchaser also shall be responsible for such additional costs.

- (4) SD-5 The Purchaser shall perform logging residue reduction and site preparation work on approximately four hundred thirty-eight (438) acres of harvest area located in all units as shown on Exhibit A.
- (a) The required work shall consist of any treatment or combination of treatments listed in the table below, as determined by the Authorized Officer and specified in writing by the Contracting Officer. The number of acres of each treatment shall be determined by the Authorized Officer.

Treatment	Treatment Description	Cost/Acre
Lop and Scatter	0-12 tons/acre	\$42.00
Selective Slashing	≤ 60% cover (cut)	\$300.00
Hand Pile and Cover	0-25 piles/acre	\$325.00
Hand Pile Burn and Mop-up	0-25 piles/acre	\$42.00
Machine Pile and Cover	Cost per acre	\$375.00
Machine Pile Burn and Mop-up	0-20 piles/acre	\$28.00
Cover and Burn Landing Decks	Cost per acre	\$56.00

- (b) The following treatments were assumed for appraisal purposes on this contract:

Appraised Treatment	Acres	Cost/Acre	Total Cost Per Treatment
Lop and Scatter	49	\$42.00	\$2,058.00
Selective Slashing	215	\$300.00	\$64,500.00

**BLOWN FORTUNE TIMBER SALE**  
**SPECIAL PROVISIONS**

Hand Pile and Cover	215	\$325.00	\$69,875.00
Hand Pile Burn and Mop-up	215	\$42.00	\$9,030.00
Machine Pile and Cover	173	\$375.00	\$64,875.00
Machine Pile Burn and Mop-up	173	\$28.00	\$4,844.00
Cover and Burn Landing Decks	35.5	\$56.00	\$1,988.00
<b>Total Appraised Cost</b>	<b>437</b>		<b>\$258,323.00</b>

- (c) The Total Purchase Price set forth in Section 2 shall be adjusted in a unilateral modification executed by the Contracting Officer by the amount that the total cost of the site preparation treatments designated pursuant to Section 42(E)(4)(SD-5)(a) differs from two hundred fifty eight thousand three hundred twenty three and no/100 dollars (\$258,323.00), as calculated by using the estimated acres determined by the Authorized Officer and the per acre costs listed in Section 42(E)(4)(SD-5)(a).
- (d) Lop and scatter shall be done in accordance with Section 42(E)(1)(SD-1)(a)(SD-1a); Selective slashing shall be done in accordance with Section 42(E)(3)(SD-4)(a)(L-4); Hand piling and burning shall be done in accordance with Section 42(E)(1)(SD-1)(c)(SD-1c) and Section 42(E)(2)(SD-2)(c&d); Machine piling and burning shall be done in accordance with Section 42(E)(1)(SD-1)(b)(SD-1b) and Section 42(E)(2)(SD-2)(a&b); Pile and burn landing decks shall be done in accordance with Section 42(E)(1)(SD-1)(d)(SD-1f) and Section 42(E)(2)(SD-2)(e&f).

(F) **CONTRIBUTIONS**

- (1) **C-1** The Purchaser shall perform fireline construction in accordance with Section 42(E)(3)(SD-4)(b) and perform underburning in accordance with Section 42(E)(3)(SD-4)(c&d). The Purchaser shall have the option of completing this work, or in lieu thereof, may make a contribution to the Bureau of Land Management in the amount of forty one thousand one hundred fifty three and no/100 dollars (\$41,153.00), and upon making such contribution, the Purchaser shall be relieved of the obligations set out in this subsection. The Purchaser shall notify the Authorized Officer of their intention to make this contribution prior to the date of execution of this contract. If the total contribution does not exceed five hundred and no/100 dollars (\$500.00), the Purchaser shall pay such amount in full prior to the commencement of operations. If the total contribution exceeds five hundred and no/100 dollars (\$500.00), the Authorized Officer shall establish an installment schedule of payments.

(G) **LOG EXPORTS**

- (1) **LE-1** All timber sold to the Purchaser under the terms of the contract, except exempted species, is restricted from export from the United States in the form of unprocessed timber, and is prohibited from being used as a substitute for exported private timber. For the purpose of this contract, unprocessed timber is defined as: (1) any logs except those

**BLOWN FORTUNE TIMBER SALE**  
**SPECIAL PROVISIONS**

of utility grade or below, such as sawlogs, peeler logs and pulp logs; (2) cants or squares to be subsequently remanufactured exceeding eight and three-quarters (8¾) inches in thickness; (3) split or round bolts or other roundwood not processed to standards and specifications suitable for end-product uses; or (4) western red cedar lumber which does not meet lumber of American Lumber Standards Grades of Number 3 dimension or better, or Pacific Lumber Inspection Bureau R-List Grades of Number 3 Common or better. Thus, timber manufactured into the following will be considered processed: (1) lumber and construction timber, regardless of size, manufactured to standards and specifications suitable for end-product uses; (2) chips, pulp, and pulp products; (3) green or dry veneer and plywood; (4) poles and piling cut or treated for use as such; (5) cants, squares, and lumber cut for remanufacturing of eight and three quarters (8¾) inches in thickness or less; (6) shakes and shingles.

Substitution will be determined under the definition found in 43 CFR 5400.0-5(n).

The Purchaser is required to maintain and upon request to furnish the following information:

- (a) Date of last export sale.
- (b) Volume of timber contained in last export sale.
- (c) Volume of timber exported in the past twelve (12) months from the date of last export sale.
- (d) Volume of Federal timber purchased in the past twelve (12) months from the date of last export sale.
- (e) Volume of timber exported in succeeding twelve (12) months from date of last export sale.
- (f) Volume of Federal timber purchased in succeeding twelve (12) months from date of last export sale.

In the event the Purchaser elects to sell any or all of the timber sold under this contract in the form of unprocessed timber, the Purchaser shall require each party buying, exchanging, or receiving such timber to execute a Form 5460-16 (Certificate as to Nonsubstitution and the Domestic Processing of Timber). The original of such certification shall be filed with the Authorized Officer. Additionally, when the other party is an affiliate of the Purchaser, the Purchaser will be required to update information under item (2) of Form 5450-17 (Export Determination) and file the form with the Authorized Officer.

In the event an affiliate of the Purchaser has exported private timber within twelve (12) months prior to purchasing or otherwise acquiring Federal timber sold under this contract, the Purchaser shall, upon request, obtain from the affiliate information in a form specified by the Authorized Officer and furnish the information to the Authorized Officer.

BLOWN FORTUNE TIMBER SALE  
SPECIAL PROVISIONS

Prior to the termination of this contract, the Purchaser shall submit to the Authorized Officer Form 5460-15 (Log Scale and Disposition of Timber Removed Report) which shall be executed by the Purchaser. In addition, the Purchaser is required under the terms of this contract to retain for a three-year period from the date of termination of the contract the records of all sales or transfer of logs involving timber from the sale for inspection and use of the Bureau of Land Management.

Unless otherwise authorized in writing by the Contracting Officer, the Purchaser shall brand clearly and legibly one end of all logs with a scaling diameter (small end inside bark) of over 10 inches, prior to the removal of timber from the contract area. All loads of 11 logs or more will have a minimum of 10 logs clearly and legibly branded on one end regardless of the diameter of the logs. All logs will be branded on loads of 10 logs or less. One end of all branded logs to be processed domestically will be marked with a 3 square inch spot of highway yellow paint. The purchaser will stop trucks for accountability monitoring at mutually agreed upon locations when notified by the Authorized Officer.

If multiple trailers (mule trains) are used, each bunked load shall be considered an individual load, and these guidelines will apply to each bunked load. If a flatbed stake trailer is used, each bundle will be treated as a separate load.

At the discretion of the Contracting Officer, the Purchaser may be required to brand and paint all logs. Any increased costs for log branding and painting shall be the responsibility of the Purchaser.

**The Purchaser shall be required to label with a permanent ink marker, each load ticket with the corresponding unit number, as directed by the Authorized Officer.**

In the event of the Purchaser's noncompliance with this subsection of the contract, the Authorized Officer may take appropriate action as set forth in Section 10 of this contract. In addition, the Purchaser may be declared ineligible to receive future awards of Government timber for a period of one year.

**Blown Fortune Timber Sale Seasonal Restriction Matrix, Contract # ORM07-TS-20-4**

Unrestricted Period
Operations Restricted To Dry Conditions
Operations Restricted While BLM Performs Spotted Owl Spot Check Surveys
Operations <b>MAY</b> Be Restricted If Nesting Spotted Owls Found - See Sec. 42(A)(13)(L-20) for more details
Operations <b>MAY</b> Be Further Restricted If Nesting Spotted Owls Found & Operations Would Cause Owls to Flush-See Sec. 42(A)(13)(L-20) for more details

The Purchaser shall notify the Authorized Officer in writing by February 1 of each calendar year in which operations are expected to take place on the contract area between March 1 and September 30, both days inclusive. Upon receipt of this notice, the Government will conduct surveys to determine whether owls have moved into harvest units. If northern spotted owls are detected in or adjacent to the units, operations would be restricted until northern spotted owl occupancy and nesting status has been determined. See Sec. 42(C)(16)(E-5) for more details

\* Operations will be suspended if unacceptable damage to residual trees occur.

\*\* In-stream work periods for culvert cleaning are July 1st - September 15th.

\*\*\* **All road maintenance and improvements must be completed before wet season haul can occur on that road. Haul will be suspended if the road begins to show damage or conditions develop that could cause damage to the road as described in Sec. 42(C)(2)(E-1) & Sec. 42(C)(3)(E-1).**

Blasting- If blasting for road construction is deemed necessary, a seasonal restriction from March 1st through Sept 30th could apply depending on proximity to owls and amount of blasting needed.

Dry Condition Yarding and Temp. Route & Road Construction- Ground-based harvesting and yarding, road construction, temporary route work, and rehabilitation activities would not occur when soil moisture at a depth of 4-6 inches is wet enough to maintain form when compressed, or when soil moisture at the surface would readily displace, causing ribbons and ruts along equipment tracks. These conditions are generally found when soil moisture at a depth of 4-10 inches is between 15-25% depending on soil type.

Sale Area	Activity	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec
		1 15	1 15	1 15	1 15	1 15	1 15	1 15	1 15	1 15	1 15	1 15	1 15
<u>Cable Yard Units:</u> 3-7, 8-9G, 31-1, 31-3	Manual Felling and Bucking*												
	Cable Yarding*												
	Road Maintenance**												
	Loading, Hauling on Rocked Rd.***												
<u>Cable Yard Unit with Owl Seasonal Restrictions:</u> 9-18	Loading, Hauling Natural Surface Rd.***												
	Manual Felling and Bucking*												
	Cable Yarding*												
	Road Maintenance**												
	Loading, Hauling on Rocked Rd.***												
	Burning												

**Blown Fortune Timber Sale Seasonal Restriction Matrix, Contract # ORM07-TS-20-4**


Sale Area	Activity	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec
		1 15	1 15	1 15	1 15	1 15	1 15	1 15	1 15	1 15	1 15	1 15	1 15
<u>Cable Yard Unit with Temp. Route Construction:</u> 5-8	Manual Falling and Bucking*												
	Cable Yarding*												
	Temp. Route Construction and Rehab. Activities Involving Heavy Equipment												
	Road Maintenance**												
	Loading, Hauling on Rocked Rd.***												
	Hauling Natural Surface Rd.***												
	Manual Falling and Bucking*												
	Cable Yarding*												
<u>Cable Yard Unit with Temp. Route Construction &amp; Owl Seasonal Restrictions:</u> 9-5	Temp. Route Construction and Rehab. Activities Involving Heavy Equipment												
	Road Maintenance**												
	Loading, Hauling on Rocked Rd.***												
	Loading, Hauling Natural Surface Rd.***												
	Burning												
	Manual Falling and Bucking*												
	Mechanical Ground Based Harvesting & Yarding, Landing Construction, and Rehab. Activities Involving Heavy Equipment												
	Road Maintenance**												
<u>Ground Based Yard Units:</u> 17-15G, 17-16, 17-17, 32-5-8.0, 32-5-8.2, 32-5-9.0	Loading, Hauling on Rocked Rd.***												
	Manual Falling and Bucking*												
	Mechanical Ground Based Harvesting & Yarding; Road, Temp. Route & Landing Construction; and Rehab. Activities Involving Heavy Equipment												
	Road Maintenance**												
	Loading, Hauling on Rocked Rd.***												
	Manual Falling and Bucking*												
	Mechanical Ground Based Harvesting & Yarding; Road, Temp. Route & Landing Construction; and Rehab. Activities Involving Heavy Equipment												
	Road Maintenance**												
<u>Ground Based Yard Units with Temp. Route Construction:</u> 17-15	Loading, Hauling on Rocked Rd.***												
	Hauling Natural Surface Rd.***												

**Blown Fortune Timber Sale Seasonal Restriction Matrix, Contract # ORM07-TS-20-4**

Sale Area	Activity	Jan		Feb		Mar		Apr		May		Jun		Jul		Aug		Sep		Oct		Nov		Dec	
		1	15	1	15	1	15	1	15	1	15	1	15	1	15	1	15	1	15	1	15	1	15	1	15
<u>Ground Based Yard Units with Owl Seasonal Restrictions:</u> 9-14	Manual Felling and Bucking*																								
	Mechanical Ground Based Harvesting & Yarding, Landing Construction, and Rehab. Activities Involving Heavy Equipment																								
	Road Maintenance**																								
	Loading, Hauling on Rocked Rd.*** Burning																								
<u>Ground Based &amp; Cable Yard Units:</u> 5-6, 17-1	Manual Felling and Bucking*																								
	Cable Yarding*																								
	Mechanical Ground Based Harvesting & Yarding, Landing Construction, and Rehab. Activities Involving Heavy Equipment																								
	Road Maintenance**																								
<u>Ground Based &amp; Cable Yard Units with Road and/or Temp. Route Construction:</u> 3-14, 10-1, 17-2, 31-2	Loading, Hauling on Rocked Rd.***																								
	Hauling Natural Surface Rd.***																								
	Manual Felling and Bucking*																								
	Cable Yarding*																								
<u>Ground Based &amp; Cable Yard Unit with Road and/or Temp. Route Construction &amp; Owl Seasonal Restrictions:</u> 3-11	Mechanical Ground Based Harvesting & Yarding, Road, Temp. Route & Landing Construction, and Rehab. Activities Involving Heavy Equipment																								
	Road Maintenance**																								
	Loading, Hauling on Rocked Rd.***																								
	Hauling Natural Surface Rd.***																								



# SALE LOCATION MAP



### Legend

▲ Mountain Peaks

★ Cities

### Road Surface Type

#### SurfaceType

— Paved Road

— Rocked Road

— Natural Surface Road

▨ Blown Fortune Roadside Management Unit

■ Blown Fortune Timber Sale Unit

□ Bureau of Land Management

▒ Local Government, Private Individual or Company

■ Oregon Department of Forestry


United States Department of the Interior  
 Bureau of Land Management  
 Medford District Office  
 3040 Biddle Road  
 Medford, OR 97504  
 (541) 618-2200



0 0.75 1.5  
 Miles  
 1 inch = 8,333 feet

No warranty is made by the Bureau of Land Management as to the accuracy, reliability, or completeness of these data for individual or aggregate use with other data. Original data were compiled from various sources. This information may not meet National Map Accuracy Standards. This product was developed through digital means and may be updated without notification.





1 inch = 1,000 feet

40 FOOT CONTOUR INTERVAL


No warranty is made by the Bureau of Land Management as to the accuracy, reliability, or completeness of these data for individual or aggregate use with other data. Original data were compiled from various sources and may be updated without notification.

Map created by SDT  
 3/10/2020



United States Department of the Interior  
 Bureau of Land Management  
 Medford District Office  
 3040 Biddle Road  
 Medford, OR 97504  
 (541) 618-2200





1 inch = 1,000 feet

40 FOOT CONTOUR INTERVAL

CONSTRUCT 0.15 MILES  
TRACTOR SWING

CONSTRUCT 0.23 MILES  
TEMP ROUTE TR 5-8


United States Department of the Interior  
 Bureau of Land Management  
 Medford District Office  
 3040 Biddle Road  
 Medford, OR 97504  
 (541) 618-2200

No warranty is made by the Bureau of Land Management as to the accuracy, reliability, or completeness of these data for individual or aggregate use with other data. Original data were compiled from various sources and may be updated without notification.

Map created by SDT  
 3/10/2020







1 inch = 1,000 feet

40 FOOT CONTOUR INTERVAL


No warranty is made by the Bureau of Land Management as to the accuracy, reliability, or completeness of these data for individual or aggregate use with other data. Original data were compiled from various sources and may be updated without notification.

United States Department of the Interior  
 Bureau of Land Management  
 Medford District Office  
 3040 Biddle Road  
 Medford, OR 97504  
 (541) 618-2200

Map created by SDT  
 3/10/2020







1 inch = 1,000 feet

40 FOOT CONTOUR INTERVAL


No warranty is made by the Bureau of Land Management as to the accuracy, reliability, or completeness of these data for individual or aggregate use with other data. Original data were compiled from various sources and may be updated without notification.

United States Department of the Interior  
 Bureau of Land Management  
 Medford District Office  
 3040 Biddle Road  
 Medford, OR 97504  
 (541) 618-2200

Map created by SDT  
 3/10/2020







1 inch = 1,000 feet

40 FOOT CONTOUR INTERVAL


No warranty is made by the Bureau of Land Management as to the accuracy, reliability, or completeness of these data for individual or aggregate use with other data. Original data were compiled from various sources and may be updated without notification.

United States Department of the Interior  
 Bureau of Land Management  
 Medford District Office  
 3040 Biddle Road  
 Medford, OR 97504  
 (541) 618-2200

Map created by SDT  
 3/10/2020







United States Department of the Interior  
 Bureau of Land Management  
 Medford District Office  
 3040 Biddle Road  
 Medford, OR 97504  
 (541) 618-2200



1 inch = 1,000 feet


40 FOOT CONTOUR INTERVAL

No warranty is made by the Bureau of Land Management as to the accuracy, reliability, or completeness of these data for individual or aggregate use with other data. Original data were compiled from various sources and may be updated without notification.

Map created by SDT  
 3/10/2020







1 inch = 1,000 feet

40 FOOT CONTOUR INTERVAL


No warranty is made by the Bureau of Land Management as to the accuracy, reliability, or completeness of these data for individual or aggregate use with other data. Original data were compiled from various sources and may be updated without notification.

United States Department of the Interior  
 Bureau of Land Management  
 Medford District Office  
 3040 Biddle Road  
 Medford, OR 97504  
 (541) 618-2200

Map created by SDT  
 3/10/2020







1 inch = 1,000 feet

40 FOOT CONTOUR INTERVAL

No warranty is made by the Bureau of Land Management as to the accuracy, reliability, or completeness of these data for individual or aggregate use with other data. Original data were compiled from various sources and may be updated without notification.

United States Department of the Interior  
 Bureau of Land Management  
 Medford District Office  
 3040 Biddle Road  
 Medford, OR 97504  
 (541) 618-2200

Map created by SDT  
 3/10/2020





## LEGEND

UNIT	UNIT ACRES	PRESCRIPTION-PAINT COLOR-LOGGING SYSTEM
3-7	10	SH-P-C
3-11	41	SH-P-GB/C
3-14	11	SH-P-GB/C
5-6	20	SH-O-GB/C
5-8	10	SH-O-C
8-9G	3	GS-P-C
9-5	8	SH-O-C
9-14	2	SH-O-GB
9-18	26	SH-P-C
10-1	25	SH-P-GB/C
17-1	75	SH-P-GB/C
17-2	75	CT/SH-P-GB/C
17-15	35	SH-P-GB
17-15G	4	GS-P-GB
17-16	6	SH-P-GB
17-17	23	SH-P-GB
31-1	18	SH-O-C
31-2	28	SH-P-GB/C
31-3	9	SH-O-C
32-5-8.0	5	RSM-B-GB
32-5-8.2	1	RSM-B-GB
32-5-9.0	2	RSM-B-GB
<b>TOTAL</b>	<b>437</b>	

\* BOUNDARIES OF HARVEST UNITS ARE POSTED AND PAINTED IN ORANGE

SH = SELECTION HARVEST  
CT = COMMERCIAL THIN  
GS = GROUP SELECTION HARVEST  
RSM = ROADSIDE MANAGEMENT  
GB = GROUND BASE YARD  
C = CABLE YARD  
P = PINK MARK LEAVE TREE  
O = ORANGE MARK LEAVE TREE  
B = BLUE MARK CUT TREE

0 750 1,500 3,000  
 Feet

1 inch = 1,000 feet

40 FOOT CONTOUR INTERVAL

No warranty is made by the Bureau of Land Management as to the accuracy, reliability, or completeness of these data for individual or aggregate use with other data. Original data were compiled from various sources and may be updated without notification.

United States Department of the Interior  
Bureau of Land Management  
Medford District Office  
3040 Biddle Road  
Medford, OR 97504  
(541) 618-2200

Map created by SDT  
3/10/2020



**Legend**

- ▲ Mountain Peaks
- Gates
- Ⓢ Skips
- Blown Fortune Road Construction**
- ▬ Permanent Road Construction
- ▬▬ Temporary Route Construction
- ▬▬▬ Temporary Route Reconstruction
- Cable Tractor Swing Route
- ▬ Blown Fortune Roadside Management Units
- Roads**
- Surface Type**
- ▬ Paved
- ▬▬ Rocked
- ▬▬▬ Natural
- Intermediate 40-ft contour
- Index 200-ft contour
- - - - Intermittent Stream
- - - - Perennial Stream
- Blown Fortune Timber Sale Units**
- Logging System**
- ▭ Cable Yard
- ▨ Ground Base Yard
- ▣ Blown Fortune Contract Area Boundary
- BlownFortune Reserve Area
- ▭ Township and Range
- ▭ Section
- ▭ Lot
- Ownership**
- & C BLM O&C Lands
- PD BLM PD Lands
- ODF State Lands
- PVT Private Lands

**SUMMARY**

CT/SH-P-GB/C	COMMERCIAL THIN & SELECTION HARVEST - PINK MARK LEAVE TREE - GROUND BASE & CABLE YARD (UNIT 17-2)	75 ACRES
SH-P-GB	SELECTION HARVEST - PINK MARK LEAVE TREE - GROUND BASE YARD (UNITS 17-15, 17-16, 17-17)	64 ACRES
SH-P-GB/C	SELECTION HARVEST - PINK MARK LEAVE TREE - GROUND BASE & CABLE YARD (UNITS 3-11, 3-14, 10-1, 17-1, 31-2)	180 ACRES
SH-P-C	SELECTION HARVEST - PINK MARK LEAVE TREE - CABLE YARD (UNITS 3-7, 9-18)	36 ACRES
GS-P-GB	GROUP SELECTION HARVEST - PINK MARK LEAVE TREE - GROUND BASE YARD (UNIT 17-15G)	4 ACRES
GS-P-C	GROUP SELECTION HARVEST - PINK MARK LEAVE TREE - CABLE YARD (UNIT 8-9G)	3 ACRES
SH-O-GB	SELECTION HARVEST - ORANGE MARK LEAVE TREE - GROUND BASE YARD (UNIT 9-14)	2 ACRES
SH-O-C	SELECTION HARVEST - ORANGE MARK LEAVE TREE - CABLE YARD (UNITS 5-8, 9-5, 31-1, 31-3)	45 ACRES
SH-O-GB/C	SELECTION HARVEST - ORANGE MARK LEAVE TREE - GROUND BASE & CABLE YARD (UNIT 5-6)	20 ACRES
RSM-B-GB	ROADSIDE MANAGEMENT - BLUE MARK CUT TREE - GROUND BASE YARD (UNITS 32-5-8.0, 32-5-8.2, 32-5-9.0)	8 ACRES
	TOTAL TIMBER SALE UNIT AREA	437 ACRES
	RESERVE AREA	1,366.90 ACRES
	TOTAL CONTRACT AREA	1,803.90 ACRES



1 inch = 1,000 feet

40 FOOT CONTOUR INTERVAL

No warranty is made by the Bureau of Land Management as to the accuracy, reliability, or completeness of these data for individual or aggregate use with other data. Original data were compiled from various sources and may be updated without notification.

United States Department of the Interior  
Bureau of Land Management  
Medford District Office  
3040 Biddle Road  
Medford, OR 97504  
(541) 618-2200

Map created by SDT  
3/10/2020







**United States  
Department of the Interior  
Bureau of Land Management**

**Timber Appraisal**

---

<b>Sale Name:</b> Blown Fortune Reoffer 2021	<b>Sale Date:</b> Thursday, January 28, 2021
<b>BLM District:</b> Medford DO	<b>Unit of Measure:</b> 16' MBF
<b>Contract #:</b> ORM07-TS-2020.0004	<b>Contract Term:</b> 36 months
<b>Sale Type:</b> Advertised	<b>Contract Mechanism:</b> 5450-4 Sale of Timber - Scale Sale

---

**Content**

**Timber Appraisal Summary**  
**Stumpage Summary**  
**Unit Summary**  
**Stump to Truck**  
**Transportation**  
**Engineering Allowances**  
**Other Allowances**

**Prepared By:** Caulfield, David J - 12/10/2020

**Approved By:** Rentz, George C - 12/10/2020

## Legal Description of Contract Area

Land Status	County	Township	Range	Section	Subdivision	Meridian
O&C	Douglas	32S	5W	3	Lot 11, 14, 15, 17, 18, 19	Willamette
O&C	Douglas	32S	5W	4	SE1/4SE1/4,	Willamette
O&C	Douglas	32S	5W	5	W1/2SW1/4, SE1/4SE1/4	Willamette
O&C	Douglas	32S	5W	8	N1/2SW1/4, SW1/4SW1/4	Willamette
O&C	Douglas	32S	5W	9	N1/2NE1/4, SE1/4NE1/4, E1/2NW1/4, N1/2SE1/4	Willamette
PD	Douglas	32S	5W	10	SE1/4SW1/4	Willamette
O&C	Douglas	32S	5W	17	W1/2NE1/4, SE1/4NE1/4, NW1/4, N1/2SW1/4, SE1/4SW1/4, SE1/4	Willamette
O&C	Douglas	32S	5W	18	SE1/4NE1/4, E1/2SE1/4	Willamette
O&C	Douglas	32S	5W	31	NE1/4, N1/2NW1/4, SE1/4NW1/4	Willamette

## Species Totals

Species	Net	Gross Merch	Gross	# of Merch Logs	# of Cull Logs	# of Trees
Douglas Fir	4,432.0	4,872.0	4,972.0	96,208	1,914	28,671
White Fir	608.0	656.0	666.0	13,445	410	4,134
Incense-cedar	238.0	270.0	279.0	6,823	235	2,740
Ponderosa Pine	28.0	32.0	41.0	853	127	583
Western Hemlock	6.0	7.0	7.0	129	0	21
<b>Totals</b>	<b>5,312.0</b>	<b>5,837.0</b>	<b>5,965.0</b>	<b>117,458</b>	<b>2,686</b>	<b>36,149</b>

## Cutting Area Acres

Regeneration Harvest Acres	Partial Cut Acres	Right of Way Acres	Total Acres	Net Volume per Acre
7.0	422.0	8.0	437.0	12.2

**Comments:**

\*\*\*\*\* See Deficit Surplus Worksheet for updated pricing\*\*\*\*\*

Updated engineering costs, logging cost, pond values.

**Logging Costs**

Stump to Truck	\$1,411,790.24
Transportation	\$257,586.81
Road Construction	\$462,898.09
Maintenance/Rockwear	\$51,542.32
Road Use	\$4,533.41
Other Allowances	\$301,471.40
<b>Total:</b>	<b>\$2,489,822.27</b>
<b>Total Logging Cost per MBF:</b>	<b>\$468.72</b>

**Utilization Centers**

<u>Location</u>	<u>Distance</u>	<u>% of Net Volume</u>
Average of 3 mills	31.7 miles	100 %

**Profit & Risk**

Profit	10 %
Risk	5 %
<b>Total Profit &amp; Risk</b>	<b>15 %</b>

**Tract Features**

<b>Quadratic Mean DBH</b>	13.8 in
<b>Average GM Log</b>	50 bf
<b>Average Volume per Acre</b>	12.2 mbf
<b>Recovery</b>	89 %
<b><u>Net MBF volume:</u></b>	
<b>Green</b>	5,312.0 mbf
<b>Salvage</b>	0 mbf
<b>Export</b>	0 mbf
<b><u>Ground Base Logging:</u></b>	
<b>Percent of Sale Volume</b>	39 %
<b>Average Yarding Slope</b>	0 %
<b>Average Yarding Distance</b>	0 ft
<b><u>Cable Logging:</u></b>	
<b>Percent of Sale Volume</b>	61 %
<b>Average Yarding Slope</b>	0 %
<b>Average Yarding Distance</b>	0 ft
<b><u>Aerial Logging:</u></b>	
<b>Percent of Sale Volume</b>	0 %
<b>Average Yarding Slope</b>	0 %
<b>Average Yarding Distance</b>	0 ft

**Cruise**

<b>Cruise Completed</b>	July 2019
<b>Cruised By</b>	Caulfield, Cannon, Northwest District Cruisers

**Cruise Method**

Timber units in this sale were cruised using the PCMTRE cruise method. 514 plots were cruised across 429 acres using a 40 BAF and a 1 in 5 sampling frequency. Road side units were cruised using the 3P and BLM100% cruise method. New road construction unit 32-5-10.2 was cruise with the BLM100% cruise method.

## Stumpage Computation

Species	# of Trees	Net Volume	Pond Value	(-) Profit & Risk	(-) Logging Costs	(+) Marginal Log Value	Appraised Price/MBF	Appraised Value
<del>Douglas Fir</del>	<del>28,671</del>	<del>4,432.0</del>	<del>\$683.05</del>	<del>\$102.46</del>	<del>\$468.72</del>	<del>\$0.00</del>	<del>\$111.90</del>	<del>\$495,940.80</del>
White Fir	4,134	608.0	\$484.17	\$72.63	\$468.72	\$0.00	\$48.50 *	\$29,488.00
Incense-cedar	2,740	238.0	\$507.98	\$76.20	\$468.72	\$0.00	\$50.80 *	\$12,090.40
Ponderosa Pine	583	28.0	\$285.00	\$42.75	\$468.72	\$0.00	\$28.50 *	\$798.00
Western Hemlock	21	6.0	\$472.14	\$70.82	\$468.72	\$0.00	\$47.30 *	\$283.80
<b>Totals</b>	<b>36,149</b>	<b>5,312.0</b>						<del>\$538,601.00</del>

\* Minimum Stumpage values were used to compute the Appraised Price/MBF (10% of Pond Value)

\*\*\*\*\* See Deficit Surplus Worksheet for updated pricing\*\*\*\*\*

**Percent of Volume By Log Grade**

Species	No. 1 & 2 Peeler	No. 3 Peeler	Special Mill	No. 2 Sawmill	No. 3 Sawmill	No. 4 Sawmill	Camp Run
Douglas Fir			4.0 %	41.0 %	47.0 %	8.0 %	

**Comments:** \*\*\*\*\* See Deficit Surplus Worksheet for Updated Pricing\*\*\*\*\* Reduced Douglas Fir total value \$92,495.84 to pay for deficit species white fir, incense-cedar, ponderosa pine, western hemlock.

Species	Peeler	No. 1 Sawmill	Special Mill	No. 2 Sawmill	No. 3 Sawmill	No. 4 Sawmill	Camp Run
White Fir				46.0 %	44.0 %	10.0 %	

Species	No. 1 Sawmill	No. 2 Sawmill	No. 3 Sawmill	No. 4 Sawmill	No. 5 Sawmill	No. 6 Sawmill	Camp Run
Incense-cedar				15.0 %	73.0 %	12.0 %	

Species	No. 1 Sawmill	No. 2 Sawmill	No. 3 Sawmill	No. 4 Sawmill	No. 5 Sawmill	No. 6 Sawmill	Camp Run
Ponderosa Pine				31.0 %	22.0 %	47.0 %	

Species	Peeler	No. 1 Sawmill	Special Mill	No. 2 Sawmill	No. 3 Sawmill	No. 4 Sawmill	Camp Run
Western Hemlock				55.0 %	42.0 %	3.0 %	

## Unit: 3-7

Species	Net	Gross Merch	Gross	# of Trees
Douglas Fir	102.0	112.0	114.0	657
White Fir	14.0	15.0	16.0	96
Incense-cedar	5.0	6.0	6.0	62
Ponderosa Pine	1.0	1.0	1.0	13
<b>Totals:</b>	<b>122.0</b>	<b>134.0</b>	<b>137.0</b>	<b>828</b>

## Net Volume/Acre: 12.2 MBF

Regeneration Harvest	0.0
Partial Cut	10.0
Right of Way	0.0
<b>Total Acres:</b>	<b>10.0</b>

## Unit: 3-11

Species	Net	Gross Merch	Gross	# of Trees
Douglas Fir	417.0	459.0	469.0	2,694
White Fir	58.0	63.0	64.0	395
Incense-cedar	22.0	26.0	26.0	256
Ponderosa Pine	2.0	3.0	4.0	54
Western Hemlock	1.0	1.0	1.0	2
<b>Totals:</b>	<b>500.0</b>	<b>552.0</b>	<b>564.0</b>	<b>3,401</b>

## Net Volume/Acre: 12.2 MBF

Regeneration Harvest	0.0
Partial Cut	41.0
Right of Way	0.0
<b>Total Acres:</b>	<b>41.0</b>

## Unit: 3-14

Species	Net	Gross Merch	Gross	# of Trees
Douglas Fir	116.0	126.0	129.0	730
White Fir	16.0	17.0	17.0	106
Incense-cedar	6.0	7.0	7.0	69
Ponderosa Pine	1.0	1.0	1.0	15
<b>Totals:</b>	<b>139.0</b>	<b>151.0</b>	<b>154.0</b>	<b>920</b>

## Net Volume/Acre: 12.6 MBF

Regeneration Harvest	0.0
Partial Cut	11.0
Right of Way	0.0
<b>Total Acres:</b>	<b>11.0</b>

**Unit: 5-6**

Species	Net	Gross Merch	Gross	# of Trees
Douglas Fir	204.0	224.0	229.0	1,314
White Fir	28.0	31.0	31.0	193
Incense-cedar	11.0	12.0	13.0	125
Ponderosa Pine	1.0	1.0	2.0	26
<b>Totals:</b>	<b>244.0</b>	<b>268.0</b>	<b>275.0</b>	<b>1,658</b>

**Net Volume/Acre: 12.2 MBF**

Regeneration Harvest	0.0
Partial Cut	20.0
Right of Way	0.0
<b>Total Acres:</b>	<b>20.0</b>

**Unit: 5-8**

Species	Net	Gross Merch	Gross	# of Trees
Douglas Fir	102.0	112.0	114.0	657
White Fir	14.0	15.0	16.0	96
Incense-cedar	5.0	6.0	6.0	62
Ponderosa Pine	1.0	1.0	1.0	13
<b>Totals:</b>	<b>122.0</b>	<b>134.0</b>	<b>137.0</b>	<b>828</b>

**Net Volume/Acre: 12.2 MBF**

Regeneration Harvest	0.0
Partial Cut	10.0
Right of Way	0.0
<b>Total Acres:</b>	<b>10.0</b>

**Unit: 8-9G**

Species	Net	Gross Merch	Gross	# of Trees
Douglas Fir	31.0	34.0	34.0	197
White Fir	4.0	5.0	5.0	29
Incense-cedar	2.0	2.0	2.0	19
<b>Totals:</b>	<b>37.0</b>	<b>41.0</b>	<b>41.0</b>	<b>245</b>

**Net Volume/Acre: 12.3 MBF**

Regeneration Harvest	3.0
Partial Cut	0.0
Right of Way	0.0
<b>Total Acres:</b>	<b>3.0</b>

**Unit: 9-5**

Species	Net	Gross Merch	Gross	# of Trees
Douglas Fir	81.0	90.0	91.0	526
White Fir	11.0	12.0	12.0	77
Incense-cedar	4.0	5.0	5.0	50
<b>Totals:</b>	<b>96.0</b>	<b>107.0</b>	<b>108.0</b>	<b>653</b>

**Net Volume/Acre: 12.0 MBF**

Regeneration Harvest	0.0
Partial Cut	8.0
Right of Way	0.0
<b>Total Acres:</b>	<b>8.0</b>

**Unit: 9-14**

Species	Net	Gross Merch	Gross	# of Trees
Douglas Fir	20.0	22.0	23.0	131
White Fir	3.0	3.0	3.0	19
Incense-cedar	1.0	1.0	1.0	12
<b>Totals:</b>	<b>24.0</b>	<b>26.0</b>	<b>27.0</b>	<b>162</b>

**Net Volume/Acre: 12.0 MBF**

Regeneration Harvest	0.0
Partial Cut	2.0
Right of Way	0.0
<b>Total Acres:</b>	<b>2.0</b>

**Unit: 9-18**

Species	Net	Gross Merch	Gross	# of Trees
Douglas Fir	265.0	291.0	297.0	1,709
White Fir	37.0	38.0	40.0	250
Incense-cedar	14.0	16.0	17.0	162
Ponderosa Pine	2.0	2.0	2.0	34
<b>Totals:</b>	<b>318.0</b>	<b>347.0</b>	<b>356.0</b>	<b>2,155</b>

**Net Volume/Acre: 12.2 MBF**

Regeneration Harvest	0.0
Partial Cut	26.0
Right of Way	0.0
<b>Total Acres:</b>	<b>26.0</b>

**Unit: 10-1**

Species	Net	Gross Merch	Gross	# of Trees
Douglas Fir	254.0	280.0	286.0	1,643
White Fir	35.0	38.0	39.0	241
Incense-cedar	14.0	16.0	16.0	156
Ponderosa Pine	2.0	2.0	2.0	33
<b>Totals:</b>	<b>305.0</b>	<b>336.0</b>	<b>343.0</b>	<b>2,073</b>

**Net Volume/Acre: 12.2 MBF**

Regeneration Harvest	0.0
Partial Cut	25.0
Right of Way	0.0
<b>Total Acres:</b>	<b>25.0</b>

**Unit: 17-1**

Species	Net	Gross Merch	Gross	# of Trees
Douglas Fir	763.0	839.0	857.0	4,922
White Fir	105.0	116.0	116.0	725
Incense-cedar	43.0	47.0	48.0	472
Ponderosa Pine	4.0	6.0	8.0	132
Western Hemlock	3.0	4.0	4.0	13
<b>Totals:</b>	<b>918.0</b>	<b>1,012.0</b>	<b>1,033.0</b>	<b>6,264</b>

**Net Volume/Acre: 12.2 MBF**

Regeneration Harvest	0.0
Partial Cut	75.0
Right of Way	0.0
<b>Total Acres:</b>	<b>75.0</b>

**Unit: 17-2**

Species	Net	Gross Merch	Gross	# of Trees
Douglas Fir	763.0	840.0	857.0	4,928
White Fir	106.0	115.0	116.0	722
Incense-cedar	41.0	47.0	48.0	469
Ponderosa Pine	5.0	5.0	7.0	99
Western Hemlock	1.0	1.0	1.0	4
<b>Totals:</b>	<b>916.0</b>	<b>1,008.0</b>	<b>1,029.0</b>	<b>6,222</b>

**Net Volume/Acre: 12.2 MBF**

Regeneration Harvest	0.0
Partial Cut	75.0
Right of Way	0.0
<b>Total Acres:</b>	<b>75.0</b>

**Unit: 17-15**

Species	Net	Gross Merch	Gross	# of Trees
Douglas Fir	356.0	392.0	400.0	2,300
White Fir	50.0	53.0	54.0	337
Incense-cedar	19.0	22.0	23.0	219
Ponderosa Pine	2.0	2.0	3.0	46
Western Hemlock	1.0	1.0	1.0	2
<b>Totals:</b>	<b>428.0</b>	<b>470.0</b>	<b>481.0</b>	<b>2,904</b>

**Net Volume/Acre: 12.2 MBF**

Regeneration Harvest	0.0
Partial Cut	35.0
Right of Way	0.0
<b>Total Acres:</b>	<b>35.0</b>

**Unit: 17-15G**

Species	Net	Gross Merch	Gross	# of Trees
Douglas Fir	40.0	45.0	46.0	263
White Fir	6.0	6.0	6.0	39
Incense-cedar	2.0	2.0	3.0	25
<b>Totals:</b>	<b>48.0</b>	<b>53.0</b>	<b>55.0</b>	<b>327</b>

**Net Volume/Acre: 12.0 MBF**

Regeneration Harvest	4.0
Partial Cut	0.0
Right of Way	0.0
<b>Total Acres:</b>	<b>4.0</b>

**Unit: 17-16**

Species	Net	Gross Merch	Gross	# of Trees
Douglas Fir	61.0	67.0	69.0	394
White Fir	9.0	9.0	9.0	58
Incense-cedar	3.0	4.0	4.0	37
<b>Totals:</b>	<b>73.0</b>	<b>80.0</b>	<b>82.0</b>	<b>489</b>

**Net Volume/Acre: 12.2 MBF**

Regeneration Harvest	0.0
Partial Cut	6.0
Right of Way	0.0
<b>Total Acres:</b>	<b>6.0</b>

**Unit: 17-17**

Species	Net	Gross Merch	Gross	# of Trees
Douglas Fir	234.0	258.0	263.0	1,511
White Fir	33.0	35.0	37.0	221
Incense-cedar	13.0	14.0	15.0	144
Ponderosa Pine	1.0	2.0	2.0	30
<b>Totals:</b>	<b>281.0</b>	<b>309.0</b>	<b>317.0</b>	<b>1,906</b>

**Net Volume/Acre: 12.2 MBF**

Regeneration Harvest	0.0
Partial Cut	23.0
Right of Way	0.0
<b>Total Acres:</b>	<b>23.0</b>

**Unit: 31-1**

Species	Net	Gross Merch	Gross	# of Trees
Douglas Fir	183.0	202.0	206.0	1,183
White Fir	26.0	28.0	28.0	173
Incense-cedar	10.0	11.0	12.0	112
Ponderosa Pine	1.0	1.0	2.0	24
<b>Totals:</b>	<b>220.0</b>	<b>242.0</b>	<b>248.0</b>	<b>1,492</b>

**Net Volume/Acre: 12.2 MBF**

Regeneration Harvest	0.0
Partial Cut	18.0
Right of Way	0.0
<b>Total Acres:</b>	<b>18.0</b>

**Unit: 31-2**

Species	Net	Gross Merch	Gross	# of Trees
Douglas Fir	285.0	313.0	320.0	1,840
White Fir	40.0	43.0	43.0	270
Incense-cedar	15.0	17.0	18.0	175
Ponderosa Pine	2.0	2.0	3.0	37
<b>Totals:</b>	<b>342.0</b>	<b>375.0</b>	<b>384.0</b>	<b>2,322</b>

**Net Volume/Acre: 12.2 MBF**

Regeneration Harvest	0.0
Partial Cut	28.0
Right of Way	0.0
<b>Total Acres:</b>	<b>28.0</b>

**Unit: 31-3**

Species	Net	Gross Merch	Gross	# of Trees
Douglas Fir	92.0	101.0	103.0	591
White Fir	13.0	14.0	14.0	87
Incense-cedar	5.0	6.0	6.0	56
Ponderosa Pine	1.0	1.0	1.0	12
<b>Totals:</b>	<b>111.0</b>	<b>122.0</b>	<b>124.0</b>	<b>746</b>

**Net Volume/Acre: 12.3 MBF**

Regeneration Harvest	0.0
Partial Cut	9.0
Right of Way	0.0
<b>Total Acres:</b>	<b>9.0</b>

**Unit: 32-5-8.0**

Species	Net	Gross Merch	Gross	# of Trees
Douglas Fir	49.0	51.0	51.0	391
Incense-cedar	2.0	2.0	2.0	38
Ponderosa Pine	2.0	2.0	2.0	15
<b>Totals:</b>	<b>53.0</b>	<b>55.0</b>	<b>55.0</b>	<b>444</b>

**Net Volume/Acre: 10.6 MBF**

Regeneration Harvest	0.0
Partial Cut	0.0
Right of Way	5.0
<b>Total Acres:</b>	<b>5.0</b>

**Unit: 32-5-8.2**

Species	Net	Gross Merch	Gross	# of Trees
Douglas Fir	3.0	3.0	3.0	22
<b>Totals:</b>	<b>3.0</b>	<b>3.0</b>	<b>3.0</b>	<b>22</b>

**Net Volume/Acre: 3.0 MBF**

Regeneration Harvest	0.0
Partial Cut	0.0
Right of Way	1.0
<b>Total Acres:</b>	<b>1.0</b>

**Unit: 32-5-9.0**

<b>Species</b>	<b>Net</b>	<b>Gross Merch</b>	<b>Gross</b>	<b># of Trees</b>
Douglas Fir	11.0	11.0	11.0	68
Incense-cedar	1.0	1.0	1.0	20
<b>Totals:</b>	<b>12.0</b>	<b>12.0</b>	<b>12.0</b>	<b>88</b>

**Net Volume/Acre: 6.0 MBF**

Regeneration Harvest	0.0
Partial Cut	0.0
Right of Way	2.0
<b>Total Acres:</b>	<b>2.0</b>

Total Stump To Truck	Net Volume	\$/MBF
\$1,411,790.24	5,312.0	\$265.77

**Stump to Truck: Falling, Bucking, Yarding, & Loading**

Yarding System	Unit of Measure	# of Units of Measure	\$/Unit of Measure	Total Cost	Remarks
Tractor Swing	GM MBF	270.0	\$300.78	\$81,210.60	Units 3-11 (8ac.), 3-14 (3ac.), 17-1 (9ac.)
Cable: Medium Yarder	GM MBF	3,292.0	\$263.36	\$866,981.12	
Track Skidder	GM MBF	2,275.0	\$190.90	\$434,297.50	
<b>Subtotal</b>				<b>\$1,382,489.22</b>	

**Additional Costs**

Item	Unit of Measure	# of Units of Measure	\$/Unit of Measure	Total Cost	Remarks
Deadman Anchor	Each	41.0	\$450.00	\$18,450.00	Units 3-7, 3-11, 3-14, 5-8, 8-9G, 9-5
Lift Tree	Each	3.0	\$150.00	\$450.00	Unit 10-1 (3 over 30')
Directional Falling	MBF	598.0	\$10.49	\$6,273.02	
<b>Subtotal</b>				<b>\$25,173.02</b>	

**Additional Moves**

<b>Equipment</b>	<b>Unit of Measure</b>	<b># of Units of Measure</b>	<b>\$/Unit of Measure</b>	<b>Total Cost</b>	<b>Remarks</b>
Track Skidder Side	Total	1.0	\$1,808.00	\$1,808.00	1 Move - Loader, 2 Skidders, harvester
Cable Side	Total	1.0	\$1,584.00	\$1,584.00	1 Move - Yarder, Loader, Tractor, Delimber
Ripping Tractor	Hour	8.0	\$92.00	\$736.00	Ripping Units 3-11, 3-14, 5-8, 8-9G, 9-5, 9-14, 17-1, 17-2, 17-15, 31-2
<b>Subtotal</b>				<b>\$4,128.00</b>	

Total	Net Volume	\$/MBF
\$257,586.81	5,312.0	\$48.49

Utilization Center	One Way Mileage	Description	Unit of Measure	# of Units	\$/Unit of Measure	Total Cost	% of Sale Volume
Average of 3 mills	31.7	All Species	GM MBF	5,837.0	\$44.13	\$257,586.81	100 %

**Comments:**

Mileage was averaged between 3 closest mills.

### Engineering Allowances

Total	Net Volume	\$/MBF
\$518,973.82	5,312.0	\$97.70

Cost Item	Total Cost
Road Construction:	\$462,898.09
Road Maintenance/Rockwear:	\$51,542.32
Road Use Fees:	\$4,533.41

**Comments:**

Updated to reflect use of Silver Butte constructed road.

Total	Net Volume	\$/MBF
\$301,471.40	5,312.0	\$56.75

### Environmental Protection

Cost item	Total Cost
Snag Creation	\$7,415.48
Waterbar Corridors	\$660.72
Equipment Washing	\$1,600.00
Block Skids	\$1,200.00
Seed and Mulch	\$4,104.00
Ripping	\$12,630.00
<b>Subtotal</b>	<b>\$27,610.20</b>

### Logging

Cost item	Total Cost
Skid Location	\$1,101.20
Waterbar Skids	\$3,000.00
landing Construction	\$7,100.00
<b>Subtotal</b>	<b>\$11,201.20</b>

### Road Construction, Maintenance, Use, & Decommissioning

Cost item	Total Cost
Stream and Culvert Cleaning	\$432.00
<b>Subtotal</b>	<b>\$432.00</b>

### Slash Disposal & Site Prep

Cost item	Total Cost
Fire Line Construction	\$13,928.00
Machine Pile Burn	\$4,844.00
Lop and Scatter	\$2,058.00
Hand Pile Burn	\$9,030.00

Landing Clean Up	\$3,905.00
Cover and Burn Landing Piles	\$1,988.00
Underburning	\$27,225.00
Selective Slashing	\$64,500.00
Hand Pile and Cover	\$69,875.00
Machine Pile	\$64,875.00
<b>Subtotal</b>	<b>\$262,228.00</b>

---



UNITED STATES  
DEPARTMENT OF THE INTERIOR  
BUREAU OF LAND MANAGEMENT

Sale: Blown Fortune Sale  
Date: Jan. 2021  
Prep. By : MRV  
Tract No: ORM07-TS-20.04

ROAD MAINTENANCE AND ROAD USE APPRAISAL WORK SHEET

Summary of Costs

1.1) Road Use - Amortization: \$4,533.41/5325 MBF = \$0.85/MBF

---

Road Maintenance Obligation:

(2.1) BLM Maintenance . . . . .	\$2,898.20
(2.2) BLM Rockwear . . . . .	\$0.00
(5.1) Purchaser Maintenance Rockwear . . . . .	<u>\$7,722.82</u>
Total Rockwear Payable to BLM . . . . .	<u>\$7,722.82</u>
(3.1) 3rd Party Maintenance . . . . .	\$0.00
(3.2) 3rd Party Rockwear . . . . .	\$432.83
(4.1) Other Maintenance Payments . . . . .	\$0.00
Total Maintenance Fee Obligation (2.1-5.1)	<u>\$11,053.85</u>

Purchaser Maintenance Allowances:

(5.2A) Move In . . . . .	\$6,726.00
(5.2B) Culverts, Catch Basins, Downspouts . . . . .	\$3,833.40
(5.2C) Grading, Ditching . . . . .	\$6,536.70
(5.2D) Slide Removal and Slump Repair . . . . .	\$2,763.84
(5.2E) Dust Palliative (Water) . . . . .	\$2,394.60
(5.2F) Surface Repair (Aggregate) . . . . .	\$8,222.00
(5.2G) Other . . . . .	\$0.00
Total Purchaser Maintenance Allowances (5.2A-5.2G)	<u>\$30,476.54</u>

(2.1-5.2G) Cost (\$11,053.85 + \$30,476.54) = \$41,530.39  
 Cost/MBF \$41,530.39 / 5325 MBF = \$7.80/MBF \$7.80/MBF

(5.2H) Decommissioning . . . . . \$10,011.93

(5.2H) Cost/MBF \$10,011.93/5325 MBF = \$1.88/MBF

(2.1-5.2H) Cost (\$11,053.85 + \$30,476.54 + \$10,011.93) = \$51,542.32

Total Cost/MBF (Excluding Road Use) \$51,542.32/5325 MBF = \$9.68/MBF

**1) Road Use Fees - Amortization**

Details		*INTERIM FEES ASSESSED			
R/W		Rd Use	Vol	Road Use	
Number	Road Number	Fee x	MBF =	Obligation	
M-824	32-5-10.1 A*	2.00	305	\$610.00	
M-824	32-5-10.2 A*	2.00	163	\$326.00	
M-824	32-5-10.2 B	22.07	163	\$3,597.41	
Subtotal by agreement number					
M-824				\$4,533.41	

(1.1) Subtotal \$4,533.41

**2) BLM Maintenance - Timber Haul**

MAINTENANCE (2.1)					ROCKWEAR (2.2)		
Road Number	A Surf	Maint	Vol		Maint	Fee x MBF =	Rkwear
and Segment	N Type	Mi x Fee x	MBF =				
32-5W-20.00 A	A BST	0.62 0.92	5081		\$2,898.20	0.00 5081	\$0.00
(2.1) Subtotal					<u>\$2,898.20</u>	(2.2) Subtotal	<u>\$0.00</u>

**3) Third Party Maintenance and Rockwear**

				MAINTENANCE (3.1)		ROCKWEAR (3.2)		
Agmnt	Surface	Road		Mi x	Fee x MBF =	Maint	Fee x MBF =	Rkwear
Number	Type	Number						
M-824	NAT	32-5-10.2 B		0.47			0.00 163	\$0.00
M-824	NAT	32-5-10.2 A		0.38			0.00 163	\$0.00
M-824	NAT	32-5-10.1 A		0.70			0.00 305	\$0.00
MOU ODF	AGG	32-5-7.0 A		0.59			0.73 244	\$105.09
MOU ODF	AGG	Windy Crk Rd		1.84			0.73 244	\$327.74
Subtotal of maintenance fees by agreement number:								
Subtotal of rockwear fees by agreement number:								
M-824								\$0.00
MOU ODF								\$432.83
(3.1) Subtotal								<u>\$0.00</u>
(3.2) Subtotal								<u>\$432.83</u>

**4) Other Maintenance Payments - USFS or Others Perform Maintenance**

Agency	Road Number	Miles (Log)	Vol (mbf)	Fee x MBF/MI =	Cost
(4.1) Subtotal					<u>\$0.00</u>

5) Purchaser Maintenance - Rock Wear

TIMBER HAUL (5.1)

Road No and Segment	A N	Mi	x	RkWear Fee x	Vol MBF	Total = RkWear
32-5-3.1 (1)	A	0.49	0.73	53	\$18.96	
32-5-3.1 (2)	A	0.31	0.73	261	\$59.06	
32-5-3.2	A	0.29	0.73	139	\$29.43	
32-5-3.6	A	0.10	0.00	69	\$0.00	
32-5-5.1	A	0.33	0.73	244	\$58.78	
32-5-7.1	A	0.21	0.73	244	\$37.41	
32-5-8.0 (1)	A	0.60	0.73	1009	\$441.94	
32-5-8.0 (2)	A	0.49	0.73	555	\$198.52	
32-5-8.0 (3)	A	0.36	0.73	545	\$143.23	
32-5-8.0 (4)	A	0.57	0.73	16	\$6.66	
32-5-8.1 (1)	A	0.84	0.73	362	\$221.98	
32-5-8.1 (2)	A	0.21	0.73	40	\$6.13	
32-5-8.2	A	0.18	0.73	40	\$5.26	
32-5-8.4	A	0.16	0.00	37	\$0.00	
32-5-9.0 (1)	A	0.21	0.73	1211	\$185.65	
32-5-9.0 (2)	A	0.54	0.73	1187	\$467.92	
32-5-9.0 (3)	A	0.38	0.73	610	\$169.21	
32-5-9.0 (4)	A	0.63	0.73	494	\$227.19	
32-5-9.0 (5)	A	0.18	0.73	263	\$34.56	
32-5-9.0 (6)	A	0.55	0.73	261	\$104.79	
32-5-9.1	A	0.54	0.73	318	\$125.36	
32-5-10.0 A (1)	N	0.29	0.73	577	\$122.15	
32-5-10.0 A (2)	N	0.73	0.73	96	\$51.16	
32-5-10.1 B	N	0.21	0.00	305	\$0.00	
32-5-17.0 A (1)	A	0.39	0.73	1988	\$565.98	
32-5-17.0 A (2)	A	1.35	0.73	1529	\$1,506.83	
32-5-17.0 B	A	0.56	0.73	318	\$130.00	
32-5-17.1	A	0.27	0.73	218	\$42.97	
32-5-17.2	A	0.22	0.73	468	\$75.16	
32-5-20.0 B (1)	A	0.20	0.73	1961	\$286.31	
32-5-20.0 B (2)	A	0.18	0.73	1892	\$248.61	
32-5-20.0 B (3)	A	0.41	0.73	1485	\$444.46	
32-5-20.0 B (4)	A	0.33	0.73	1204	\$290.04	
32-5-20.0 B (5)	A	0.82	0.73	1131	\$677.02	
32-5-20.0 C	A	1.35	0.73	122	\$120.23	
32-5-30.0 A	A	0.50	0.73	673	\$245.65	
32-5-30.0 B1	A	0.48	0.73	100	\$35.04	
32-5-30.1 A (1)	A	0.35	0.73	331	\$84.57	
32-5-30.1 A (2)	A	0.86	0.73	220	\$138.12	
32-5-30.2	A	0.64	0.73	242	\$113.06	
32-5-31.4	A	0.07	0.73	67	\$3.42	

(5.1) Subtotal \$7,722.82

**Purchaser Operational Maintenance**

**Move In**

Equipment	No Move	Cost/ Units x	Dist in x	Sub- Factor	total
Motor Grader:	1	3	\$414.00	1.00	\$1,242.00
Back Hoe:	1	3	\$308.00	1.00	\$924.00
Loader:	1	3	\$414.00	1.00	\$1,242.00
Water Truck:	1	3	\$96.00	1.00	\$288.00
Dump Truck:	2	3	\$91.00	1.00	\$546.00
Excavator:	1	3	\$414.00	1.00	\$1,242.00
Roller:	1	3	\$414.00	1.00	\$1,242.00

(5.2A) Total \$6,726.00



**Other**

Fallen Timber Cutting:	0.0 Hours x \$0.00/Hour	= \$0.00
Brush Cutting/Tree Trimming:	0.0 Hours x \$0.00/Hour	= \$0.00
Oil/Asphalt Materials:	Lump Sum	= \$0.00
Signing for Dust Palliatives:	Lump Sum	= \$0.00
	Lump Sum	= \$0.00

(5.2G) Total \$0.00

**Decommissioning****Ripping**

Road Number	Ripping Cost	x	(NumSta or CuYds)	=	Total
TR 03-14	\$30.70	x	6.92	=	\$212.44
TR 05-08	\$30.70	x	12.15	=	\$373.01
TR 09-05	\$30.70	x	13.2	=	\$405.24
TR 17-02	\$30.70	x	17.42	=	\$534.79
TR 17-15	\$30.70	x	11.62	=	\$356.73
TR 31-02	\$30.70	x	14.26	=	\$437.78

(Ripping) Total \$2,320.00

**Other Costs**

Road Number	Cubic Yds Pullback Material	+	Qty Waterbars	+	Qty Earthen Barriers	=	Total
32-5-03.06	(0x\$1.80)	+	(3x\$55.93)	+	(1x\$167.80)	=	\$335.59
32-5-17.02	(0x\$1.80)	+	(8x\$55.93)	+	(1x\$167.80)	=	\$615.24
TR 03-14	(0x\$1.80)	+	(4x\$55.93)	+	(1x\$167.80)	=	\$391.52
TR 05-08	(0x\$1.80)	+	(5x\$55.93)	+	(1x\$167.80)	=	\$447.45
TR 09-05	(0x\$1.80)	+	(7x\$55.93)	+	(1x\$167.80)	=	\$559.31
TR 17-02	(0x\$1.80)	+	(9x\$55.93)	+	(1x\$167.80)	=	\$671.17
TR 17-15	(0x\$1.80)	+	(6x\$55.93)	+	(1x\$167.80)	=	\$503.38
TR 31-02	(0x\$1.80)	+	(9x\$55.93)	+	(1x\$167.80)	=	\$671.17

(Other Cost) Total \$4,194.83

**Time & Equipment**

32-5-03.06	General Laborer:	2 hr @ \$37.57/hr	=\$75.14
32-5-03.06	Chainsaw:	1 hr @ \$47.37/hr	=\$47.37
32-5-17.02	General Laborer:	2 hr @ \$37.57/hr	=\$75.14
32-5-17.02	Chainsaw:	1 hr @ \$47.37/hr	=\$47.37
TR 03-14	General Laborer:	2 hr @ \$37.57/hr	=\$75.14
TR 03-14	Chainsaw:	1 hr @ \$47.37/hr	=\$47.37
TR 03-14	Seed and Mulch:	0.22 ac @ \$875.00/ac	=\$192.50
TR 05-08	General Laborer:	2 hr @ \$37.57/hr	=\$75.14
TR 05-08	Chainsaw:	1 hr @ \$47.37/hr	=\$47.37
TR 05-08	Seed and Mulch:	0.39 ac @ \$875.00/ac	=\$341.25
TR 09-05	General Laborer:	2 hr @ \$37.57/hr	=\$75.14
TR 09-05	Chainsaw:	1 hr @ \$47.37/hr	=\$47.37
TR 09-05	Seed and Mulch:	0.42 ac @ \$875.00/ac	=\$367.50
TR 17-02	General Laborer:	2 hr @ \$37.57/hr	=\$75.14
TR 17-02	Chainsaw:	1 hr @ \$47.37/hr	=\$47.37
TR 17-02	Seed and Mulch:	0.56 ac @ \$875.00/ac	=\$490.00
TR 17-15	Excavator-Small(1.5CY)- Temp Culvert Removal:	4 hr @ \$99.88/hr	=\$399.52
TR 17-15	General Laborer:	2 hr @ \$37.57/hr	=\$75.14
TR 17-15	Chainsaw:	1 hr @ \$47.37/hr	=\$47.37
TR 17-15	Seed and Mulch:	0.37 ac @ \$875.00/ac	=\$323.75
TR 31-02	General Laborer:	2 hr @ \$37.57/hr	=\$75.14
TR 31-02	Chainsaw:	1 hr @ \$47.37/hr	=\$47.37
TR 31-02	Seed and Mulch:	0.46 ac @ \$875.00/ac	=\$402.50
(5.2H) Decommissioning Total			<u>\$10,011.93</u>

**UNITED STATES  
DEPARTMENT OF THE INTERIOR  
BUREAU OF LAND MANAGEMENT (BLM)**

<b>Contract No.: ORM07-TS-2020.0004</b>
<b>Sale Name: Blown Fortune Timber Sale</b>
<b>Issuing Office: Medford District</b>

**EXHIBIT B  
SCALE SALE  
PURCHASE PRICE SCHEDULE AND MEASUREMENT SPECIFICATIONS**

I. **Total Actual Purchase Price** - In accordance with Section 2 and 3 of the contract, the Purchaser agrees to pay the Government for the timber sold under the contract in accordance with the following schedule and measurement requirements. Timber sold is comprised of Merchantable Timber, Merchantable Timber Remaining, and Other Timber as defined below. In the event an Extension of Time is approved, the prices per measurement unit are subject to readjustment (refer to Section 9 of the contract).

<b>Schedule of Species/Products, Measurement Units, and Prices</b>		
<b>Species/Products</b>	<b>Measurement Unit</b>	<b>Price Per Measurement Unit</b>
Merchantable logs - Douglas-fir	MBF	
White Fir	MBF	\$48.50
Incense-cedar	MBF	\$50.80
Ponderosa Pine	MBF	\$28.50
Western Hemlock	MBF	\$47.30
Utility logs	MBF	Not Applicable

II. **Merchantable Timber** - All timber which can be cut into logs, which equal or exceed the following specifications, shall be considered merchantable timber required to be removed from the contract area. Purchaser shall pay for same in accordance with Section 3 of the contract at the unit prices shown in Section I of this Exhibit.

<b>Schedule of Material Specifications</b>			
<b>Species/Product</b>	<b>Length (feet)</b>	<b>Diameter (inches inside bark at small end)</b>	<b>Net Scale (% of gross volume of any log segment)</b>
All Species	8 feet	6 inches	33 1/3% of gross volume of any log segment or 10 bf.

If Purchaser elects to remove any logs which do not meet the above minimum material specifications and which have not been reserved to Government in Sec. 41 of the contract, such logs shall be scaled in accordance with section V of this Exhibit herein and be paid for in accordance with Section 2 and 3 of the contract and the value in Section I of this Exhibit.

III. **Merchantable Timber Remaining - Measurement Requirements** - The remaining volume of any merchantable sold timber on the contract area shall be determined as provided in Section 3. (g). of the contract. Purchaser shall pay for same in accordance with Section 3 of the contract at the unit prices shown in Section I of this Exhibit.

IV. **Other Timber** - If any timber is of a species not listed in Section I of this Exhibit the Authorized Officer shall establish volumes and values in accord with Standard BLM methods.

V. **Scaling**

A. **Log Rule and Measurement** - All logs shall be scaled in Eastside Scribner according to the Northwest Log Rules Eastside and Westside Log Scaling Handbook, as amended, or supplemented by BLM before the first advertisement date of the sale.

B. **Scaling Service** - A Scaling Authorization Form must be completed and approved by the Authorized Officer prior to beginning of hauling operations. All sites on the Scaling Authorization are required to have a Log Yard Agreement with the BLM. Log scaling services shall be provided and performed by BLM personnel or third party scaling organizations under agreement with BLM.

1. All logs shall be scaled and volumes determined by BLM or a certified contract scaler.
2. The BLM scaler or contract scaler is designated to collect Eastside MBF scale data from all loads.
3. All logs shall be scaled using an authorized BLM scaling method approved by the Authorized Officer in accordance with BLM prescribed procedures.

C. **Defect Caused by Abnormal Delay** - Scaling deductions made for rot, check or other defect resulting from abnormal delay in scaling caused by Purchaser shall be recorded separately and charged to the Purchaser in accordance with Section 3 of the contract.

D. **Log Presentation** - Purchaser shall present logs so that they may be scaled in an economical and safe manner in accordance with the Log Yard Authorization required in Section V. B. of this Exhibit.

E. **Check Scale**

The BLM will conduct check scales using the following standards.

Gross Scale. A variance of one and ½ percent (1.5%) in gross scale is the standard unless otherwise justified.

Net scale. The allowable variance is as follows:

Check scaler's percent defect in logs	Scalers allowable variance
0-10 percent	2 percent
over 10 percent	0.2 * percent defect to a maximum of 5 percent

Determinations as to volume of timber made by a BLM check scaler in conformance with the standards as set forth herein shall be final. When such checks show a variance in scale in excess of acceptable standards, in two or more consecutive check scales, an adjustment to the volume reported as scaled will be made by BLM. Such adjustments will be made based on the difference between available BLM check scales and the original scale during the period covered by the unsatisfactory check scales. Unless otherwise approved in writing by the Authorized Officer, the volume to which this difference will be applied will be 50 percent of the volume scaled between the last satisfactory check and the first unsatisfactory check, 100 percent of the volume scaled during the unsatisfactory check, and 50 percent of the volume between the last unsatisfactory check scale and the next satisfactory check scale.

**F. Accountability**

1. Purchaser shall notify the Authorized Officer seven (7) days prior to starting or stopping of hauling operations performed under the contract.
2. All logs will be painted and branded at the landing and accounted for in accordance with Section 42 of the contract. If Sale Area is within a State that maintains a log brand register, brands shall be registered with the State. Purchaser shall use assigned brand(s) exclusively on logs from this sale until the Authorized Officer releases the brand(s).
3. Each truck driver shall obtain a load receipt and a BLM scaler receipt from the Log Truck Ticket Book issued by the Authorized Officer and comply with the instructions specified on the cover of said book. All load tickets will be marked with the cutting area number using a permanent marker or as directed by the Authorized Officer. While products are in transit, the truck driver shall display the load receipt and BLM scaler receipt on the bunk or wing log at the front of the load on the driver's side. All logs on each load shall be delivered to the destination listed on the woods receipt. The BLM scaler receipt shall be surrendered at the location of BLM scaling, the unloading location, or as requested by BLM. A designated area shall be identified at the yard scaling location for logs arriving during off hours. Logs arriving during off hours shall be left on the truck or may be off loaded to the designated area.
4. The Purchaser shall not haul logs from the contract area on weekends; Memorial Day, Fourth of July, Labor Day, Thanksgiving, Christmas, and New Year's holidays; or outside the hours of 8:00 a.m. to 5:00 p.m. daily, unless otherwise approved in writing by the Authorized Officer or designated in the Approved Logging Plan. (Refer to Section 42 of the contract).
5. The Purchaser shall furnish BLM a map showing the route which shall be used to haul logs

from the timber sale area to the scaling location. Such route shall be the most direct haul route between the two points, unless another route is approved by BLM. The route of haul may be changed only with advance notice to and approval by BLM. The haul route map shall be attached to the Approved Logging Plan.

6. All loads will be scaled at locations listed on the Scaling Authorization as approved by the Authorized Officer. Purchaser shall notify the Authorized Officer three (3) days in advance to request additional scale site locations for approval on the Scaling Authorization.
7. Any removal of logs from loaded trucks before being accounted for and/or scaled as required by the contract shall be considered a willful trespass and render the Purchaser liable for damages under applicable law. Any payment made for purchase of such logs shall be deducted from amount due because of trespass.

G. **Scaling Lost Products** - The value of lost loads shall be equal to the highest value load for the month in which the lost load is hauled regardless of where the highest value load is scaled. If no loads have been scaled in that month, value will be determined from the closest month in which loads were scaled.

VI. **Estimated Volumes and Values** - The following volume estimates and calculations of value of timber sold are made solely as an administrative aid for determining payment amounts, when payments are due, the value of timber subject to any special bonding provisions, and other purposes specified in various portions of the contract. The cutting areas are shown on Exhibit A of the contract.

A. **Merchantable Timber Volume Removed from Contract Area** - The total volume of removed timber shall be determined using the Government's records of scaled volumes of timber skidded or yarded monthly, or a shorter period if agreed to by the Purchaser and Government, to loading points or removed from the contract area.

B. **Merchantable Timber Not Yet Removed from Contract Area** - The value of merchantable timber which has not been removed will be determined by multiplying the value per acre as shown below times the amount of acreage subject to the purpose of the value determination, as determined by the Authorized Officer:

<b>Total Estimated Purchase Price And/or Schedule of Volumes and Values for Merchantable Timber Not Yet Removed from Contract Area</b>					
<b>Cutting Area</b>		<b>Total Estimated Volume (MBF)</b>		<b>Total Estimated Purchase Price</b>	
<b>Cutting Area Number</b>	<b>Approximate Number of Acres</b>	<b>Volume per Acre</b>	<b>Total Volume</b>	<b>Value per Acre</b>	<b>Total Value</b>
3-7	10	12.2	122		
3-11	41	12.2	500		

3-14	11	12.6	139		
5-6	20	12.2	244		
5-8	10	12.2	122		
8-9G	3	12.3	37		
9-5	8	12.0	96		
9-14	2	12.0	24		
9-18	26	12.2	318		
10-1	25	12.2	305		
17-1	75	12.2	918		
17-2	75	12.2	916		
17-15	35	12.2	428		
17-15G	4	12	48		
17-16	6	12.2	73		
17-17	23	12.2	281		
31-1	18	12.2	220		
31-2	28	12.2	342		
31-3	9	12.3	111		
32-5-8.0	5	10.6	53		
32-5-8.2	1	3	3		
32-5-9.0	2	6	12		
<b>Sale Total</b>	<b>437</b>	<b>12.2</b>	<b>5312</b>		

OVERNIGHT LOAD CONTROL RECORD	
Log Delivery Location	
Timber Sale	
1	Time and Date Load Delivered
2	Truck Name
3	Load Receipt No.
4	Number of Logs
5	Signature of Person Receiving the Load
6	Date and Time Load Released
7	Signature of Person Releasing the Load

Instructions:

1. Designated individual fills out the heading and lines 1 through 5 (including FULL SIGNATURE in ink on line 5.)
2. Contractor or BLM scaler will fill out lines 6 and 7 (including FULL SIGNATURE in ink) when loads are released for scaling, otherwise the BLM and/or yard owner will be required to sign.
3. Unless otherwise agreed, scaler will attach this form to the Load Receipt.

OVERNIGHT LOAD CONTROL RECORD	
Log Delivery Location	
Timber Sale	
1	Time and Date Load Delivered
2	Truck Name
3	Load Receipt No.
4	Number of Logs
5	Signature of Person Receiving the Load
6	Date and Time Load Released
7	Signature of Person Releasing the Load

Instructions:

1. Designated individual fills out the heading and lines 1 through 5 (including FULL SIGNATURE in ink on line 5.)
2. Contractor or BLM scaler will fill out lines 6 and 7 (including FULL SIGNATURE in ink) when loads are released for scaling, otherwise the BLM and/or yard owner will be required to sign.
3. Unless otherwise agreed, scaler will attach this form to the Load Receipt.



# EXHIBIT C2-1

## LEGEND

### Land Ownership

-  BLM
-  Non-BLM
-  Timber Units
-  Roadside Management

### Roads - Surface Type


-  Bituminous
-  Aggregate
-  Natural
-  Unknown

### Road Construction


-  Road Construction
-  Temp Construction
-  Temp Reconstruction
-  Tractor Swing

### Timber Sale Haul Roads

-  BLM Maintenance
-  Purchaser Renovation
-  Third Party Maintenance



**ALWAYS  
THINK  
SAFETY**



Rev No.	Description	Date	Approval
UNITED STATES DEPARTMENT OF THE INTERIOR BUREAU OF LAND MANAGEMENT MEDFORD DISTRICT - MEDFORD, OREGON			
<b>BLOWN FORTUNE TIMBER SALE ROAD RENOVATION MAP</b>			
DRAFTED BY: BLM			
DATE: FEB 2020		SHEET: 1 OF 11	

# EXHIBIT C2-2

## LEGEND

### Land Ownership

- BLM
- Non-BLM
- Timber Units

XXXXXX Roadside Management

### Roads - Surface Type

- Bituminous
- Aggregate
- Natural
- Unknown

### Road Construction

- Road Construction
- Temp Construction
- Temp Reconstruction
- Tractor Swing


### Timber Sale Haul Roads

- BLM Maintenance
- Purchaser Renovation
- Third Party Maintenance

### Road Closures

- Gate
- Barricade (trees/dirt)

Rev No.	Description	Date	Approval
UNITED STATES DEPARTMENT OF THE INTERIOR BUREAU OF LAND MANAGEMENT MEDFORD DISTRICT - MEDFORD, OREGON			
<b>BLOWN FORTUNE TIMBER SALE</b> <b>ROAD RENOVATION MAP</b>			



**ALWAYS**  
**THINK**  
**SAFETY**



# EXHIBIT C2-3

## LEGEND

### Land Ownership

-  BLM
-  Non-BLM
-  Timber Units
-  Roadside Management

### Roads - Surface Type

-  Bituminous
-  Aggregate
-  Natural
-  Unknown

### Road Construction

-  Road Construction
-  Temp Construction
-  Temp Reconstruction
-  Tractor Swing

### Timber Sale Haul Roads

-  Purchaser Renovation
-  BLM Maintenance

### Road Closures


-  Gate
-  Barricade (trees/dirt)

Rev No.	Description	Date	Approval

UNITED STATES DEPARTMENT OF THE INTERIOR  
 BUREAU OF LAND MANAGEMENT  
 MEDFORD DISTRICT - MEDFORD, OREGON

## BLOWN FORTUNE TIMBER SALE ROAD RENOVATION MAP

DRAFTED BY: BLM	
DATE: FEB 2020	SHEET: 3 OF 11



**ALWAYS  
 THINK  
 SAFETY**

# EXHIBIT C2-4

## LEGEND

### Land Ownership

-  BLM
-  Non-BLM
-  Timber Units
-  Roadside Management

### Roads - Surface Type

-  Bituminous
-  Aggregate
-  Natural
-  Unknown

### Road Construction

-  Road Construction
-  Temp Construction
-  Temp Reconstruction
-  Tractor Swing

### Timber Sale Haul Roads

-  Purchaser Renovation
-  BLM Maintenance

### Road Closures

-  Gate
-  Barricade (trees/dirt)

Rev No.	Description	Date	Approval


UNITED STATES DEPARTMENT OF THE INTERIOR  
 BUREAU OF LAND MANAGEMENT  
 MEDFORD DISTRICT - MEDFORD, OREGON

## BLOWN FORTUNE TIMBER SALE ROAD RENOVATION MAP

DRAFTED BY: BLM

DATE: FEB 2020

SHEET: 4 OF 11



ALWAYS  
**THINK**  
 SAFETY





# EXHIBIT C2-6

## LEGEND

### Land Ownership

-  BLM
-  Non-BLM
-  Timber Units
-  Roadside Management

### Roads - Surface Type

-  Bituminous
-  Aggregate
-  Natural
-  Unknown

### Road Construction

-  Road Construction
-  Temp Construction
-  Temp Reconstruction
-  Tractor Swing

### Timber Sale Haul Roads

-  Purchaser Renovation
-  BLM Maintenance

### Road Closures


-  Gate
-  Barricade (trees/dirt)

Rev No.	Description	Date	Approval


UNITED STATES DEPARTMENT OF THE INTERIOR  
BUREAU OF LAND MANAGEMENT  
MEDFORD DISTRICT - MEDFORD, OREGON

## BLOWN FORTUNE TIMBER SALE

### ROAD RENOVATION MAP



**ALWAYS  
THINK  
SAFETY**





# EXHIBIT C2-8

## LEGEND

### Land Ownership

-  BLM
-  Non-BLM
-  Timber Units
-  Roadside Management

### Roads - Surface Type

-  Bituminous
-  Aggregate
-  Natural
-  Unknown

### Road Construction

-  Road Construction
-  Temp Construction
-  Temp Reconstruction
-  Tractor Swing



### Timber Sale Haul Roads

-  Purchaser Renovation
-  BLM Maintenance

### Road Closures

-  Gate
-  Barricade (trees/dirt)

Rev No.	Description	Date	Approval
UNITED STATES DEPARTMENT OF THE INTERIOR BUREAU OF LAND MANAGEMENT MEDFORD DISTRICT - MEDFORD, OREGON			
<b>BLOWN FORTUNE TIMBER SALE</b> <b>ROAD RENOVATION MAP</b>			
DRAFTED BY: BLM			SHEET: 8 OF 11
DATE: FEB 2020			



**ALWAYS**  
**THINK**  
**SAFETY**

# EXHIBIT C2-9

## LEGEND

### Land Ownership

-  BLM
-  Non-BLM
-  Timber Units
-  Roadside Management

### Roads - Surface Type

-  Bituminous
-  Aggregate
-  Natural
-  Unknown

### Road Construction

-  Road Construction
-  Temp Construction
-  Temp Reconstruction
-  Tractor Swing

### Timber Sale Haul Roads

-  Purchaser Renovation
-  BLM Maintenance

### Road Closures



-  Gate
-  Barricade (trees/dirt)

Rev No.	Description	Date	Approval

UNITED STATES DEPARTMENT OF THE INTERIOR  
 BUREAU OF LAND MANAGEMENT  
 MEDFORD DISTRICT - MEDFORD, OREGON

## BLOWN FORTUNE TIMBER SALE ROAD RENOVATION MAP

DRAFTED BY: BLM  
 DATE: FEB 2020  
 SHEET: 9 OF 11



**ALWAYS  
 THINK  
 SAFETY**

# EXHIBIT C2-10

## LEGEND

### Land Ownership

-  BLM
-  Non-BLM
-  Timber Units
-  Roadside Management

### Roads - Surface Type

-  Bituminous
-  Aggregate
-  Natural
-  Unknown

### Road Construction

-  Road Construction
-  Temp Construction
-  Temp Reconstruction
-  Tractor Swing

### Timber Sale Haul Roads

-  Purchaser Renovation
-  BLM Maintenance

### Road Closures


-  Gate
-  Barricade (trees/dirt)

Rev No.	Description	Date	Approval

UNITED STATES DEPARTMENT OF THE INTERIOR  
 BUREAU OF LAND MANAGEMENT  
 MEDFORD DISTRICT - MEDFORD, OREGON

**BLOWN FORTUNE TIMBER SALE**  
**ROAD RENOVATION MAP**

DRAFTED BY: BLM  
 DATE: FEB 2020  
 SHEET: 10 OF 11



**ALWAYS**  
**THINK**  
**SAFETY**



# EXHIBIT C2-11

## LEGEND

### Land Ownership

-  BLM
-  Non-BLM
-  Timber Units

-  Roadside Management

### Roads - Surface Type

-  Bituminous
-  Aggregate
-  Natural
-  Unknown

### Road Construction

-  Road Construction
-  Temp Construction
-  Temp Reconstruction
-  Tractor Swing

### Timber Sale Haul Roads

-  Purchaser Renovation
-  BLM Maintenance

### Road Closures


-  Gate
-  Barricade (trees/dirt)

Rev No.	Description	Date	Approval

UNITED STATES DEPARTMENT OF THE INTERIOR  
BUREAU OF LAND MANAGEMENT  
MEDFORD DISTRICT - MEDFORD, OREGON

## BLOWN FORTUNE TIMBER SALE

### ROAD RENOVATION MAP



**ALWAYS  
THINK  
SAFETY**









# EXHIBIT C4-2

ROAD NUMBER	FROM (STA)	TO (STA)	LENGTH (MILES)	TYPICAL STATION TYPE	ALIGNMENT		ROAD WIDTH 1-3		GRADIENT		CLEARING WIDTH			SURFACING 4						REMARKS
					MAXIMUM DEGREE OF CURVE	SUBGRADE	DITCH	MAXIMUM FAVORABLE	MAXIMUM ADVERSE	BEYOND	EXISTING ROAD(S)		BASE COURSE			SURFACE COURSE				
											MINIMUM	WIDTH	COMPACTION	DEPTH	TYPE 2	GRADING	MINIMUM	WIDTH	COMPACTION	
New Construction																				
32-5-10.1 B	0+00	11+19	0.21	3			15'		-17.5%	6.2%	3'	0'								
Temporary Routes																				
Temp Route 03-14	0+00	6+92	0.13	3			14'				3'	0'						Temp Road to be constructed. Fully decommission upon haul completion		
Temp Route 05-08	0+00	12+15	0.23	3			14'				3'	0'						Temp Road to be constructed. Fully decommission upon haul completion		
Temp Route 09-05	0+00	13+20	0.25	3			14'				3'	0'						Temp Road to be constructed. Fully decommission upon haul completion		
Temp Route 17-02	0+00	17+42	0.33	3			14'				3'	0'						Temp Road to be constructed. Fully decommission upon haul completion		
Temp Route 17-15	0+00	11+62	0.22	3			14'				3'	0'						Temp Road to be constructed. Fully decommission upon haul completion		
Temp Route 31-02	0+00	14+26	0.27	3			14'				3'	0'						Temp Road to be constructed. Fully decommission upon haul completion		

## NOTES


1. EXTRA SUB-GRADE WIDTHS TO EACH FILL SHOULDER, ADD 1 FOOT FOR FILLS OF 1-6 FEET AND 2 FEET FOR FILLS OVER 6 FEET. WIDEN THE INSIDE SHOULDER OF ALL CURVES AS FOLLOWS WHEN THE DEGREE OF CURVE EQUALS:
  - 7-21 ADD 1 FT.
  - 22-35 ADD 2 FT.
  - 36-48 ADD 3 FT.
  - 49-64 ADD 4 FT.
  - 65-96 ADD 5 FT.
2. SURFACING TYPES
  - A. PIT RUN ROCK
  - B. GRID ROLLED ROCK MATERIAL
  - C. SCREENED ROCK MATERIAL
  - D. CRUSHED ROCK MATERIAL
3. TURNOUTS
  - A. WIDTH 10 FT. IN ADDITION TO SUB-GRADE WIDTH, OR AS SHOWN ON THE PLANS.
  - B. LOCATED APPROXIMATELY, AS SHOWN ON THE ROAD PLANS.
  - C. INVISIBLE AND NOT MORE THAN 750 FT. APART.
4. SURFACING TURNOUTS, CURVE WIDENING, AND ROAD APPROACH APRONS SHALL BE SURFACED.
  - 5. CLEARING WIDTH SEE SUBSECTION 2100

REV. NO.	DESCRIPTION	DATE	APPROV.
UNITED STATES DEPARTMENT OF THE INTERIOR BUREAU OF LAND MANAGEMENT MEDFORD DISTRICT - MEDFORD, OREGON			
<b>BLOWN FORTUNE                  TIMBER SALE                  SPECIFICATION SHEET</b>			
DRAFTED BY: BLM		SCALE: NONE	
DATE: FEB 2020		SHEET: 2 OF 3	
DRAWING NO.: OR-11-9113.4-1			

**ALWAYS  
 THINK  
 SAFETY**




# EXHIBIT C5



## ROAD RENOVATION

### NOTES:


1. RECONSTRUCTION ROADS AS SHOWN AND IN ACCORDANCE WITH SECTION 500 OF THE SPECIFICATIONS. REQUIRED RECONSTRUCTION INCLUDES CURVE WIDENING AND TURNOUTS. DITCH RECONSTRUCTION INCLUDES CLEANING CULVERT INLETS AND OUTLETS.
2. WHERE RUTTING, EROSION AND POTHOLES EXIST, SCARIFY TO DEPTH OF RUT/EROSION/POTHOLE, BLADE, SHAPE AND COMPACT EXISTING AGGREGATE OR NATIVE SURFACE MATERIAL.
3. REMOVE AND DISPOSE OF SLIDE, DITCH, AND CATCH BASIN MATERIAL. DISPOSAL SITE LOCATIONS AS STAKED ON THE GROUND. DISPOSAL/WASTE SITES SHALL BE APPROVED BY THE AUTHORIZED OFFICER PRIOR TO USE. SEE VICINITY MAP FOR DISPOSAL SITE LOCATIONS/ OR AS STAKED ON GROUND.
4. MATCH EXISTING TRAVEL WAY CROSS SLOPE. THE TRAVELED WAY SHALL BE SHAPED TO THE EXISTING CROSS SLOPE. EXISTING ROADS WHICH ARE CROWNED SHALL BE AT 3% FROM CENTERLINE ROAD, INSLOPED AS IS, OUTSLOPED AS IS.



## CROSS DRAIN CULVERT PLAN VIEW

### CLEARING NOTES:

1. NO GRUBBING OR ROOT DISTURBANCE UNLESS NOTED
2. REMOVE VEGETATION BY CUTTING OR MOWING
3. RECONSTRUCTION CULVERT CATCH BASIN A MINIMUM OF 4' FROM CULVERT INLET




## DRAW CULVERT PLAN VIEW

### CLEARING NOTES:

1. NO GRUBBING OR ROOT DISTURBANCE UNLESS NOTED
2. REMOVE VEGETATION BY CUTTING OR MOWING
3. RECONSTRUCTION INLET CHANNEL, REMOVE ALL DEBRIS AND OBSTRUCTION A MINIMUM OF 2 X CULVERT DIAMETER & 10 FEET LONG

CULVERT OUTLET AT FILL SLOPE: REMOVE ALL TREES, BRUSH AND DEBRIS FROM SHOULDER OF ROAD TO TOE OF FILL STUMPS MAY REMAIN IN PLACE, FLUSH CUT WITHIN 6-INCHES PARALLEL TO THE SLOPE




## DRAW CULVERT PROFILE

ALWAYS  
**THINK**  
SAFETY

REV. NO.	DESCRIPTION	DATE	APPROV.
UNITED STATES DEPARTMENT OF THE INTERIOR BUREAU OF LAND MANAGEMENT MEDFORD DISTRICT - MEDFORD, OREGON			
<b>BLOWN FORTUNE TIMBER SALE TYPICAL ROAD RENOVATION</b>			
DRAFTED BY: BLM	SCALE: NONE		
DATE: FEB 2020	SHEET: 1 OF 1		
DRAWING NO.: OR-11-9113.4-4			

# EXHIBIT C6A



**Brushing Diagram**

Cutting Limit = C + D + B + F

B = Road Bed Subgrade (includes turnouts)

Cut all vegetation to maximum height of 1" flush with the running surface.


C = 4 ft - Distance to be brushed on cut slope beyond centerline of ditch. Cut all vegetation to maximum height of 4".

D = Centerline of ditch to inside shoulder. Cut all vegetation to maximum height of 1".

F = 4 ft - Distance to be brushed on fill slope beyond outside shoulder. Cut all vegetation to maximum height of 4".

V = 14 ft - Height of vertical cutting limit

**Inside Corner**



**Sight Distance Diagram**


Thin, space and prune trees through curved sections of road for visibility as shown. Thinning and spacing of trees shall be a minimum (10) feet apart. A minimum (1/3) tree crown shall be maintained on any pruned tree.

Clear 4 ft radius around all culvert inlets and outlets. Tie ribbon at outlet.

ALWAYS  
**THINK**  
SAFETY

REV. NO.	DESCRIPTION	DATE	APPROV.
UNITED STATES DEPARTMENT OF THE INTERIOR BUREAU OF LAND MANAGEMENT MEDFORD DISTRICT - MEDFORD, OREGON			
<b>BLOWN FORTUNE TYPICAL ROADSIDE BRUSHING DETAIL</b>			
DRAFTED BY: BLM	SCALE: NONE		
DATE: FEB 2020	SHEET: 1 OF 1		
DRAWING NO.: OR-11-9113.4.4			

# EXHIBIT C6B



Roadside Management Unit Cutting Limits = C + D + B + E

- C = 10-15 ft - Distance to remove all trees on cut slope beyond centerline of ditch. Variable slope distance as specified in timber sale specifications. Cut all trees. Remove all tree stumps from centerline of ditch to 4 ft slope distance up the cut bank (grind/pop).
- D = Centerline of ditch to inside shoulder hinge point. Cut all trees. Remove all tree stumps from inside shoulder hinge point to centerline of ditch (grind/pop).
- B = Road Running Surface (includes turnouts). Cut all trees. Remove all tree stumps from road running surface and turnouts.
- E = 10-15 ft - Distance to remove all trees on fill slope beyond outside shoulder hinge point. Variable slope distance as specified in timber sale specifications. Cut all trees. Remove all tree stumps from outside shoulder hinge point to 4 ft slope distance down the fill slope (grind/pop).

**NOTES:**

1. All stumps shall be grubbed and disposed of at a waste disposal site or other approved locations. Stump holes shall be filled (if needed) with suitable material and compacted.
2. Any stumps along cut banks and fill slopes that will impede road maintenance equipment shall be removed (grind/pop).
3. Seed and mulch disturbed areas along cut banks and fill slopes in accordance with the Soil Stabilization Specifications (1800).





REV. NO.	DESCRIPTION	DATE	APPROV.
UNITED STATES DEPARTMENT OF THE INTERIOR BUREAU OF LAND MANAGEMENT MEDFORD DISTRICT - MEDFORD, OREGON			
<b>BLOWN FORTUNE            ROADSIDE MANAGEMENT            UNIT DETAIL</b>			
DRAFTED BY: BLM	SCALE: NONE		
DATE: FEB 2020	SHEET: 1 OF 1		
DRAWING NO.: OR-11-9113.4.4			

**ALWAYS  
 THINK  
 SAFETY**





# EXHIBIT C8-1


## CULVERT INSTALLATION TYPES



## CATCH BASIN




CATCH BASIN BACK SLOPES SHALL BE CONSTRUCTED TO THE SAME RATIO AS ADJOINING ROAD SECTION BACK SLOPE.



CROSS SECTION AT CATCH BASIN

ALWAYS  
**THINK**  
SAFETY




THE GRADE OF CROSSDRAINS SHALL BE AT LEAST 2% GREATER THAN THE GRADE OF THE DITCH.

REV. NO.	DESCRIPTION	DATE	APPROV.
UNITED STATES DEPARTMENT OF THE INTERIOR BUREAU OF LAND MANAGEMENT MEDFORD DISTRICT - MEDFORD, OREGON			
<b>BLOW FORTUNE CULVERT INSTALLATION DETAILS</b>			
DRAFTED BY: BLIM	SCALE: NONE		
DATE: FEB 2020	SHEET: 1 OF 2		
DRAWING NO.: OR-11-9113.4-4			



# EXHIBIT C9

## CSP "HUGGER" COUPLER BANDS



STANDARD CONSTRUCTION IS A ONE PIECE BAND FOR 12" THRU 48" PIPES AND A TWO PIECE BAND FOR 54" PIPES AND ABOVE


THE HUGGER COUPLER BAND OR AN APPROVED EQUIVALENT COUPLER BAND SHALL BE MADE OF THE SAME MATERIAL AND FINISH AS THE PIPES JOINED. THE COUPLER BANDS SHALL BE A MINIMUM OF 10-1/2 INCHES WIDE AND BE 16 GAUGE OR HEAVIER. THE BAND SHALL BE DESIGNED TO BE DRAWN TOGETHER WITH A MINIMUM OF TWO (2) 1/2 INCH BOLTS THROUGH USE OF A BAR AND STRAP SUITABLY WELDED TO THE BAND. THE BAND SHALL ENGAGE AND MESH WITH THE SECOND ANNULAR CORRUGATION INWARD FROM THE END OF EACH OF THE CONDUIT SECTIONS JOINED.

WHEN DESIGNATED ON THE PLANS OR IN THE SPECIAL PROVISIONS, GASKETS SHALL BE INSTALLED WHEN THE "HUGGER" TYPE, OR AN APPROVED EQUIVALENT COUPLER BAND IS INSTALLED ON SPILLWAY, OVERSIDE OR DOWN DRAINS.


*ALWAYS*  
**THINK**  
*SAFETY*

REV. NO.	DESCRIPTION	DATE	APPROV.
UNITED STATES DEPARTMENT OF THE INTERIOR BUREAU OF LAND MANAGEMENT MEDFORD DISTRICT - MEDFORD, OREGON			
<b>BLOWN FORTUNE TIMBER SALE CULVERT BAND DETAIL</b>			
DRAFTED BY: BLM		SCALE: NONE	
DATE: FEB 2020		SHEET: 1 OF 1	
DRAWING NO.: OR-11-9113.4-4			

# EXHIBIT C10




CONVENTIONAL TYPE ELBOW



FULL ROUND DOWNSPOUT

- NOTE:
1. THE ELBOW AND SPILLWAY SECTION SHALL BE OF THE SAME DIAMETER, MATERIAL AND COATING AS THE CULVERT IT IS ATTACHED TO.
  2. THE SPILLWAY SECTION SHALL BE FABRICATED FROM 16 GAUGE METAL WITH 2 2/3" X 1/2" CORRUGATIONS.
  3. SUPPORTS MAY BE COMMERCIAL STEEL FENCE POSTS, STEEL BAR, ANGLE IRON OR EQUIVALENT METAL POSTS.
  4. CONNECTION BETWEEN HELICALLY CORRUGATED AND ANNUAL PIPE SHALL REQUIRE A SPECIAL ADAPTER COUPLING BAND.




RECTANGULAR FLUME

- NOTE:
1. THE FLUME SHALL BE FABRICATED FROM 16 GAUGE CULVERT STOCK WITH 2 2/3" X 1/2" CORRUGATIONS.
  2. THE STARTER SECTION SHALL BE FABRICATED FROM 16 GAUGE NON-CORRUGATE CULVERT STOCK
  3. ADJUSTABLE WIDTH FLUMES ARE AVAILABLE FOR APPLICATIONS OVER 24" WIDE. INSTALL ACCORDING TO MANUFACTURER.
  4. SUPPORTS MAY BE STEEL BAR, ANGLE IRON OR APPROVED EQUIVALENT POSTS.


### GENERAL NOTES

1. THE LENGTH OF THE DOWNSPOUT SHALL BE DETERMINED AT THE TIME OF INSTALLATION.
2. FABRICATION AND INSTALLATION OF ALL GALVANIZED STEEL DOWNSPOUTS SHALL CONFORM TO ASHTO M36, M218; ALUMINUM ALLOY TO ASHTO M196; ALUMINIZED TYPE II TO ASHTO 36, M196.
3. ALL STEEL NUTS, BOLTS AND WASHERS SHALL BE GALVANIZED. (ASTM A307, A153)
4. SLOPE PROTECTION SPLASH PADS, WHEN REQUIRED, SHALL BE A MIN. 2' WIDE X 5' LONG X 2' DEEP. INDIVIDUAL ROCKS SHALL BE 10" - 14" IN SIZE.
5. SLOPE PROTECTION SPLASH PADS SHALL EXTEND TO UNDISTURBED GROUND.



HALF ROUND DOWNSPOUT

- NOTE:
1. THE HALF ROUND SHALL BE ONE DIAMETER SIZE LARGER AND OF THE SAME MATERIAL AND COATING AS THE CULVERT IT IS ATTACHED TO.
  2. THE HALF ROUND SHALL BE FABRICATED FROM 16 GAUGE METAL WITH 2 2/3" X 1/2" CORRUGATIONS.
  3. SUPPORTS MAY BE STEEL BAR, ANGLE IRON OR APPROVED EQUIVALENT METAL POSTS.




METAL SUPPORT DETAIL

- 1 1/2" X 1 1/2" X 1/4" ANGLE IRON SUPPORT
- 1 1/2" X 1/4" STEEL BAR SUPPORT


REV.	NO.	DESCRIPTION	DATE	APPROV.
UNITED STATES DEPARTMENT OF THE INTERIOR BUREAU OF LAND MANAGEMENT MEDFORD DISTRICT - MEDFORD, OREGON				
DOWNSPOUT INSTALLATION DETAILS		BLM	SCALE	NONE
DATE	FEB 2020	SHEET	1 OF 1	
DRAWING NO.	ORM07-TS2020-04-C10			

ALWAYS  
**THINK**  
SAFETY

# EXHIBIT C11-1



**LOG BARRICADE**




1. Log barricade shall be constructed as shown above.
2. Exact location is listed in Roads Work List.
3. All barricades shall be skewed 30 degrees.
4. The log length shall extend from the cut bank to the fill slope.
5. The minimum small end diameter of the log barricade shall be 24".

**WATER BAR SPACING\* BY EROSION CLASS<sup>a</sup>**


ROAD GRADE	HIGH	MODERATE	LOW
%	FEET	FEET	FEET
2-5	200	300	400
6-10	150	200	300
11-15	100	150	200
16-20	75	100	150
21-35	50	75	100
35+	50	50	50

\* Spacing is determined by slope distance and is the maximum allowed for the grade.

<sup>a</sup> The erosion classes include the following rock types:  
**High:** Granite, sandstone, andesite porphyry, glacial or alluvial deposits, soft matrix conglomerate, volcanic ash, and pyroclastics.  
**Moderate:** Basalt, andesite, quartzite, hard matrix conglomerate, and rhyolite.  
**Low:** Metasediments, metavolcanics, and hard shale.




**WATER BAR**




1. Water bars shall be constructed as shown above.
2. Exact location will be flagged by the Authorized Officer prior to construction.
3. All water bars shall be skewed 30 degrees.
4. Upon completion of skidding logs, for the logging season, each skid road will have cross drainage constructed as shown above.


**SKREW DIAGRAM**



ALWAYS  
**THINK**  
 SAFETY



**WATER DIP**



1. Water dips shall be constructed as shown above.
2. Exact location is listed in Exhibit C Roads Work List.
3. All water dips shall be skewed 30 degrees.
4. The width shall extend across entire road running surface, from the cut bank to the fill slope.
5. Armor outlet of water dip on fill slope. Riprap material will be securely placed at outlet a minimum of 10 LF wide by 8 LF down fill slope by 1 FT in depth. Key-in toe of Riprap apron for stability. See Slope Protection specifications (1400).
6. Seed and mulch fill slope upon completion to stabilize side-cast material. See Soil Stabilization specifications (1800).

REV. NO.	DESCRIPTION	DATE	APPROV.


UNITED STATES DEPARTMENT OF THE INTERIOR  
 BUREAU OF LAND MANAGEMENT  
 MEDFORD DISTRICT - MEDFORD, OREGON

**BLOWN FORTUNE  
 TIMBER SALE  
 DRAINAGE & EROSION  
 CONTROL DETAILS**

DRAFTED BY: BLM	SCALE: NONE
DATE: FEB 2020	SHEET: 1 OF 2
DRAWING NO.: OR-11-9113.4-4	

# EXHIBIT C11-2

## STRAW BALE CHECK DAM ASSEMBLY



### PLAN

#### NOTES:


1. All straw bales will be from a weed free certified source.
2. Hydrologic Points of Concern (HPOC) are natural drainage features (ie. streams, creeks, draws) that intersect with existing or proposed roads.
3. If the HPOC is a bridge spanning across a noted or listed critical fish habitat (Coho) waterway, install check dam assembly, or other approved BMP, in road ditch line 150 LF up-grade from top of creek bank or edge of bridge.
4. If the HPOC is a draw culvert, install check dam assembly, or other approved BMP, in road ditch line 100 LF up-grade from inlet of culvert.

#### INSTALLATION NOTES:

1. Do not construct the check dam assembly more than one bale high.
2. Bales shall be placed tightly together and snug to the ground to ensure no gaps between bales or underneath the assembly.
3. Securely anchor the bales in place with two wooden or rebar stakes driven through the bales. Drive the stakes in the second bale toward the previously laid bale to force the bales tightly together. Ensure stakes are driven 12 inches minimum into the ground.
4. The assemblies do not need to be anchored if the terrain is relatively flat, less than 2% ditch line grade.

#### INSPECTION/MAINTENANCE NOTES:

1. Inspect each assembly before, during, and after each rain event.
2. Repair and/or replace damaged assemblies or decomposed bales promptly. Replacement bales shall be in good condition to ensure sediment trapping.
3. Trapped sediment shall be removed when it reaches 6-8 inches in depth.
4. Sediment shall be removed and placed in a stable area outside of wetlands, riparian reserves, floodplains, and waters of the State.



### SECTION A-A

REV. NO.	DESCRIPTION	DATE	APPROV.

UNITED STATES DEPARTMENT OF THE INTERIOR  
BUREAU OF LAND MANAGEMENT  
MEDFORD DISTRICT - MEDFORD, OREGON


BLOWN FORTUNE  
TIMBER SALE  
DRAINAGE & EROSION  
CONTROL INSTALLATION

DRAFTED BY: BLM	SCALE: NONE
DATE: FEB 2020	SHEET: 2 OF 2
DRAWING NO.: OR-11-9113.4-4	

ALWAYS  
**THINK**  
SAFETY


Exhibit C12

Blown Fortune T.S.  
32-5-10.1 B  
Sheet 1 of 1



Construct 15' outsloped subgrade, no ditch. Seed and mulch fill slope for entire length of road.

End haul material can be used as fill at designated sites on BLM land along 32-5-10.2 B road. See Exhibit C13 for details.



Mass Haul (Cu. Yd.)



# Exhibit C13

Sale Name: Blown Fortune

Page 1 of 12

## Roads Work List

### Definitions:

AGG = Aggregate

BST = Bituminous

NAT = Natural or Native Surface

CMP = Corrugated Metal Pipe

Pvt = Private (Industry or Citizen)

Jct = Junction/Intersection

MP = Mile Post

STA = Station

CY = Cubic Yard

Seg = Segment

### Road Renovation/Construction

The road renovation/construction work list consists of road work to be performed by the Purchaser's Representative and/or Contractor **prior** to timber hauling per Section 42(B)(2) of the contract Special Provisions. This work includes, but not limited to, clearing and grubbing; excavation for road construction; compacting, watering, blading and/or rolling the road surface; clearing and reshaping ditch lines; cleaning or enlarging catch basins and outlets; cleaning the entire barrel of all culverts; furnishing and replacing corrugated metal pipes (culverts); maintaining and/or constructing water dips; surfacing or resurfacing roads with crushed rock aggregate; slide removal; seeding and mulching; constructing barricades; and removing all down trees from roadways. All road work shall comply with the contract Special Provisions, Specifications, and Exhibits.

### Roadside Brushing

This consists of work to be performed by the Purchaser's Representative and/or Contractor **prior** to timber hauling per Section 42(B)(2) of the contract Special Provisions. This work includes, but not limited to, brushing 4 feet up the cut bank slope from the centerline of ditch and 4 feet down the fill slope from the outside shoulder hinge point of the road; removing brush at the inlet and outlet of existing culverts; and removing brush, limbs, and small diameter trees along the roadway to improve sight distance. All vegetation to be cut and disposed of will be 6 inches in diameter at breast height or less ( $\leq 6''$  DBH). Disposal from roadside brushing will be lop and scatter unless otherwise noted as chipping in the work list. In areas where the road crosses through private (Industry or civilian) property, conifer trees shall be pruned rather than cut down. Brush shall be cut to meet regular specifications. All work shall comply with the contract Special Provisions, Specifications, and Exhibits.

### Roadside Vegetation Management Units

This work includes, but not limited to, removing merchantable and non-merchantable trees 15 feet up the cut bank slope from the centerline of ditch and 15 feet down the fill slope from the outside shoulder hinge point of the road as designated in the contract as **Roadside Management Units**. All vegetation to be cut and removed will be greater than 12 inches in height and less than 25 inches (*in general\**) in diameter at breast height (DBH). All roadside management units will be tagged and marked with beginning and ending locations. Merchantable trees in sections outside of identified timber sale units are marked with blue tracer paint. Sections within timber sale units will not be marked with paint, but will also have tags identifying beginning and ending locations.

*\*In general refers to any tree  $\geq 24''$  DBH hindering culvert replacements or road renovation/construction activities (typically within the 4' Roadside Brushing extents) can be cut and removed.*

All stumps left after removal of trees that may hinder road maintenance operations, including culvert replacements and road renovation/construction activities, will be removed. Any damage that occurs to the road subgrade during stump removal will be properly repaired. Any loose material that remains on site shall be compacted or disposed of at areas designated by the Authorized Officer. Stumps that will not hinder road maintenance operations can be left in place. All disturbed areas shall be seeded and mulched. All remaining brush and limbs from tree removal operations shall either be chipped, piled and burned in locations designated by the Authorized Officer, or lopped and scattered below the road in accordance with roadside brushing disposal methods in the Roadside Brushing Specifications (2100). All work shall comply with the contract Special Provisions, Specifications, and Exhibits.

## Exhibit C13

Sale Name: Blown Fortune

Page 2 of 12

### 32-5-3.1 Road – Fortune Br Adv Or – AGG – Sub: 16Ft – Ditch: 3Ft – X-Sect:

<u>MP</u>	<u>Description</u>
0.00	Jct w/ 32-5-9.0 road. Begin road renovation, which includes reshaping road surface (blading, watering, and rolling) to road specifications; clearing and reshaping ditch lines; clearing all culvert inlets and outlets; cleaning all debris or obstructions from inside culverts; and roadside brushing and chipping.
0.14	Existing CMP. Inlet buried.
0.28	Jct. w/ 32-5-3.2 road on right. Begin placing aggregate at 4 inch depth.
0.31	Jct. w/ 32-5-3.6 road on left
0.40	Existing CMP
0.45	Existing CMP
0.49	End road renovation. End placing aggregate. Reconstruct turnaround area.

### 32-5-3.2 Road – Fortune Fwy – AGG – Sub: 15Ft – Ditch: 0Ft – X-Sect: Outsloped

<u>MP</u>	<u>Description</u>
0.00	Jct w/ 32-5-3.1 road. Begin road renovation, which includes reshaping road surface (blading, watering, and rolling) to road specifications and roadside brushing and chipping.
0.05	Maintain existing water dip.
0.12	Maintain existing water dip.
0.29	Jct. w/ temporary road TR 03-14 on left. Begin placing aggregate at 4 inch depth.
0.53	End road renovation. End placing aggregate. Reconstruct turnaround area.

### 32-5-3.6 Road – Non System – NAT – Sub: 14Ft – Ditch: 0Ft – X-Sect: Outsloped

<u>MP</u>	<u>Description</u>
0.0	Jct w/ 32-5-3.1 road. Begin road renovation, which includes reshaping road surface (blading, watering, and rolling) to road specifications and roadside brushing and chipping.
0.01	End haul WDS locations on right and left.
0.10	End road renovation.

### 32-5-5.1 Road – Windy Ck Sp 2– NAT – Sub: 14Ft – Ditch: 0Ft – X-Sect: Outsloped

<u>MP</u>	<u>Description</u>
0.00	Jct. w/ 32-5-7.1 road. Begin road renovation, which includes reshaping road surface (blading, watering, and rolling) to road specifications; and roadside brushing and chipping. Begin placing aggregate at 4 inch depth.
0.06	Existing CMP to be removed and replaced with a 24" x 34' CMP per project details and specifications. Supply and properly place 2 CY of Class 2 riprap material from an approved weed-free commercial source at pipe outlet for fill-slope protection per contract specifications and drawings.
0.12	Existing CMP to be removed and replaced with a 24" x 40' CMP per project details and specifications. Supply and properly place 2 CY of Class 2 riprap material from an approved weed-free commercial source at pipe outlet for fill-slope protection per contract specifications and drawings.
0.17	Existing CMP to be removed and replaced with a 24" x 40' CMP per project details and specifications. Supply and properly place 2 CY of Class 2 riprap material from an approved weed-free commercial source at pipe outlet for fill-slope protection per contract specifications and drawings.
0.33	End road renovation. End placing aggregate.

## Exhibit C13

Sale Name: Blown Fortune

Page 3 of 12

### 32-5-7.0 Road – Windy Ck Sec 5– AGG – Sub: 16Ft – Ditch: 3Ft – X-Sect: Crowned

<u>MP</u>	<u>Description</u>
0.00	Jct. w/ Windy Creek Road. Begin road renovation, which includes reshaping road surface (blading, watering, and rolling) to road specifications; clearing and reshaping ditch lines; clearing all culvert inlets and outlets; cleaning all debris or obstructions from inside culverts; and roadside brushing and chipping.
0.08	Existing large CMP. Hydrologic Point of Concern: Install check dams, or other approved BMP's, per contract specifications and Exhibit C11.
0.10	Jct. w/ powerline road on left. Grade to direct runoff from powerline road to ditch on left.
0.20	Existing CMP
0.30	Existing CMP
0.39	Existing CMP
0.40	Jct. w/ spur road on left.
0.47	Existing CMP to be removed and replaced with a 24" x 40' CMP per project details and specifications. Supply and properly place 2 CY of Class 2 riprap material from an approved weed-free commercial source at pipe outlet for fill-slope protection per contract specifications and drawings. Replace aggregate surfacing upon written acceptance of subgrade after culvert replacement. Properly place, water, and roll a 50' long (centered over culvert) by 16' wide by 6" (20 CY) compacted-in-place depth of 1-1/2"-minus crushed rock material from an approved weed-free commercial source per contract specifications and drawings.
0.55	Existing CMP to be removed and replaced with a 24" x 34' CMP per project details and specifications. Dig out outlet ditch for 30' to drain water away from outlet. Supply and properly place 2 CY of Class 2 riprap material from an approved weed-free commercial source at pipe outlet for fill-slope protection per contract specifications and drawings. Replace aggregate surfacing upon written acceptance of subgrade after culvert replacement. Properly place, water, and roll a 50' long (centered over culvert) by 16' wide by 6" (20 CY) compacted-in-place depth of 1-1/2"-minus crushed rock material from an approved weed-free commercial source per contract specifications and drawings.
0.59	Jct. w/ 32-5-7.1 road on left. End road renovation

### 32-5-7.1 Road – Windy Creek S1 Spur – NAT – Sub: 15Ft – Ditch: 3Ft – X-Sect: Crowned

<u>MP</u>	<u>Description</u>
0.00	Jct. w/ 32-5-7.0 road. Begin road renovation, which includes reshaping road surface (blading, watering, and rolling) to road specifications; clearing and reshaping ditch lines; clearing all culvert inlets and outlets; cleaning all debris or obstructions from inside culverts; and roadside brushing and chipping. Begin placing aggregate at 4 inch depth.
0.01	Existing CMP to be removed and replaced with a 24" x 40' CMP per project details and specifications. Supply and properly place 2 CY of Class 2 riprap material from an approved weed-free commercial source at pipe outlet for fill-slope protection per contract specifications and drawings.
0.06	Existing CMP
0.09	Existing CMP to be removed and replaced with a 24" x 50' CMP per project details and specifications. Drop outlet 3'. Supply and properly place 2 CY of Class 2 riprap material from an approved weed-free commercial source at pipe outlet for fill-slope protection per contract specifications and drawings.
0.16	Jct. w/ 32-5-5.0 road on right.
0.18	Existing CMP to be removed and replaced with a 24" x 40' CMP per project details and specifications. Supply and properly place 2 CY of Class 2 riprap material from an approved weed-free commercial source at pipe outlet for fill-slope protection per contract specifications and drawings.
0.21	Road number changes to 32-5-5.1. End road renovation. End placing aggregate.

## Exhibit C13

Sale Name: Blown Fortune

Page 4 of 12

### 32-5-8.0 Road – Buckhorn Rdg– AGG– Sub: 15Ft – Ditch: 3Ft – X-Sect: Crowned

<u>MP</u>	<u>Description</u>
0.00	Jct. w/ 32-5-20.0 road. Begin road renovation, which includes reshaping road surface (blading, watering, and rolling) to road specifications; clearing and reshaping ditch lines; clearing all culvert inlets and outlets; cleaning all debris or obstructions from inside culverts; and roadside brushing and chipping. Begin placing aggregate at 4 inch depth.
0.15	Existing CMP
0.18	Property line into BLM. Begin roadside vegetation maintenance. (See Exhibit C-6; Roadside brushing and roadside vegetation maintenance details).
0.27	Existing CMP
0.34	Existing CMP
0.44	Existing CMP
0.56	Existing CMP
0.60	Jct. w/ 32-5-8.1 and 32-5-8.2 roads on right.
0.76	Existing CMP
0.82	Existing CMP
0.96	Existing CMP
0.98	Existing road stockpile on right.
1.09	Existing CMP.
1.20	Existing CMP
1.27	Existing CMP
1.36	Existing CMP
1.40	Existing CMP
1.48	Existing CMP
1.50	End placing aggregate.
1.53	Existing CMP
1.58	Existing CMP
1.66	Existing CMP
1.77	Existing CMP
1.86	Existing CMP
1.95	End of AGG surface. Beginning of NAT surface. End of roadside ditches. Beginning of outsloped road. Reconstruct turn-around. End of roadside vegetation maintenance.
2.09	End road renovation.

### 32-5-8.1 Road – East Windy Ridge Road – AGG – Sub: 17Ft – Ditch: 0Ft – X-Sect: Outsloped

<u>MP</u>	<u>Description</u>
0.00	Jct. w/ 32-5-8.0 and 32-5-8.2 roads. Begin road renovation, which includes reshaping road surface (blading, watering, and rolling) to road specifications and roadside brushing and chipping.
0.17	Maintain existing water dip.
0.30	Begin placing aggregate at 4 inch depth.
0.40	Existing CMP
0.45	Maintain existing water dip.
0.54	Maintain existing water dip.
0.59	Maintain existing water dip.
0.64	Maintain existing water dip.
0.68	Jct. w/ temporary road TR 17-02 on left.
0.82	Maintain existing water dip.
1.05	End road renovation. End placing aggregate. Reconstruct turnaround area. Waste disposal site at end of road. Place waste material on stable area well off of road surface and outside of turnaround/landing area so not to impede drivability of traffic.

## Exhibit C13

Sale Name: Blown Fortune

Page 5 of 12

### 32-5-8.2 Road – Windy Ridge Sp– AGG – Sub: 17Ft – Ditch: 0Ft – X-Sect: Outsloped

<u>MP</u>	<u>Description</u>
0.00	Jct. w/ 32-5-8.0 and 32-5-8.1 roads. Begin road renovation, which includes reshaping road surface (blading, watering, and rolling) to road specifications and roadside brushing and chipping.
0.05	Maintain existing water dip.
0.06	Begin roadside vegetation maintenance on fill-slope side only. (See Exhibit C-6; Roadside brushing and roadside vegetation maintenance details).
0.18	Jct. w/ 32-5-8.4 road on right. End road renovation. End of roadside vegetation maintenance.

### 32-5-8.4 Road – Windy Ridge State Sp– NAT – Sub: 14Ft – Ditch: 0Ft – X-Sect: Crowned

<u>MP</u>	<u>Description</u>
0.00	Jct. w/ 32-5-8.2 road. Begin road renovation, which includes reshaping road surface (blading, watering, and rolling) to road specifications and roadside brushing and chipping.
0.01	Existing water bar.
0.03	Existing water bar.
0.08	Existing water bar.
0.17	Property line into State. End road renovation.

### 32-5-9.0 Road – E Fork Fortune Br – AGG – Sub: 16Ft – Ditch: 3Ft – X-Sect: Crowned

<u>MP</u>	<u>Description</u>
0.00	Jct w/ 32-5-17.0 road. Begin road renovation, which includes reshaping road surface (blading, watering, and rolling) to road specifications; clearing and reshaping ditch lines; clearing all culvert inlets and outlets; cleaning all debris or obstructions from inside culverts; and roadside brushing and chipping.
0.01	Existing CMP
0.04	Existing Bridge. Hydrologic Point of Concern: Install check dams, or other approved BMP's, per contract specifications and Exhibit C11.
0.07	Existing CMP
0.16	Existing CMP
0.35	Existing CMP
0.40	Jct. w/ spur road on left
0.41	Existing CMP
0.52	Existing CMP
0.57	Existing CMP
0.59	Existing CMP
0.66	Existing CMP
0.73	Existing CMP
0.75	Jct. w/ 32-5-10.0 road on right
0.76	Existing CMP
0.77	Begin roadside vegetation maintenance. (See Exhibit C-6; Roadside brushing and roadside vegetation maintenance details).
0.83	Existing CMP
0.95	Existing CMP
1.02	Existing CMP
1.12	Existing CMP
1.35	Existing CMP
1.42	Existing CMP
1.48	Existing CMP
1.53	Existing CMP
1.56	Existing CMP
1.65	Existing CMP

## Exhibit C13

Sale Name: Blown Fortune

Page 6 of 12

1.79	Existing CMP
1.88	Existing CMP
1.97	Jct. w/ 32-5-3.3 road on left. End of roadside vegetation maintenance.
2.01	Existing CMP
2.07	Jct. w/ 32-5-3.0 road on left
2.17	Existing CMP
2.25	Existing CMP
2.49	Jct. w/ 32-5-3.1 road on right. End road renovation.
2.51	End haul WDS location on right.
3.25	Jct w/ 31-5-15.0 road on right. End haul WDS location on right.

### 32-5-9.1 Road – Fortune Branch Sp – AGG – Sub: 14Ft – Ditch: 3Ft – X-Sect: Crowned

<u>MP</u>	<u>Description</u>
0.00	Jct w/ 32-5-17.0 road. Begin road renovation which includes reshaping road surface (blading, watering, and rolling) to road specifications; clearing and reshaping ditch lines; clearing all culvert inlets and outlets; cleaning all debris or obstructions from inside culverts; and roadside brushing and chipping. Begin placing aggregate at 4 inch depth.
0.15	Existing CMP to be removed and replaced with a 18” x 40’ CMP per project details and specifications. Supply and properly place 2 CY of Class 2 riprap material from an approved weed-free commercial source at pipe outlet for fill-slope protection per contract specifications and drawings.
0.16	Remove tree from road.
0.19	Existing CMP to be removed and replaced with a 18” x 48’ CMP per project details and specifications. Supply and properly place 2 CY of Class 2 riprap material from an approved weed-free commercial source at pipe outlet for fill-slope protection per contract specifications and drawings.
0.27	Existing CMP to be removed and replaced with a 18” x 60’ CMP per project details and specifications. Supply and properly place 2 CY of Class 2 riprap material from an approved weed-free commercial source at pipe outlet for fill-slope protection per contract specifications and drawings.
0.62	End road renovation. End placing aggregate. Reconstruct turnaround area. Waste disposal site at end of road. Place waste material on stable area well off of road surface and outside of turnaround/landing area so not to impede drivability of traffic.

### 32-5-10.0 Road – Fortune Rdg – AGG – Sub: 17Ft – Ditch: 0Ft – X-Sect: Crowned

<u>MP</u>	<u>Description</u>
0.00	Jct w/ 32-5-9.0 road. Begin road renovation which includes reshaping road surface (blading, watering, and rolling) to road specifications; clearing all culvert inlets and outlets; cleaning all debris or obstructions from inside culverts; and roadside brushing and chipping.
0.01	Property line into private land.
0.02	Existing CMP
0.04	Existing gate
0.10	Maintain existing water dip.
0.14	Existing CMP
0.18	Existing CMP. Construct ditch on left side for 100’ to drain water off road to this culvert.
0.24	Maintain existing water dip.
0.29	Jct w/ 32-5-10.1, 32-5-10.2, and private spur roads, all on left.
0.49	Property line into BLM
0.60	Maintain existing water dip.
0.73	Jct. w/ temporary road TR 09-05 on right. End road renovation. Reconstruct turnaround area.
1.01	End haul WDS location on right.

## Exhibit C13

Sale Name: Blown Fortune

Page 7 of 12

### 32-5-10.1 Road – Non System – NAT – Sub: 14Ft – Ditch: 0Ft – X-Sect: Crowned

<u>MP</u>	<u>Description</u>
0.00	Jct w/ 32-5-10.0 road. Begin road renovation which includes reshaping road surface (blading, watering, and rolling) to road specifications; clearing and reshaping ditch lines; clearing all culvert inlets and outlets; cleaning all debris or obstructions from inside culverts; and roadside brushing and chipping.
0.07	Existing CMP
0.23	Existing CMP
0.33	Existing CMP
0.36	Place 5 CY of borrow material on small slide in fill slope.
0.44	Existing CMP
0.52	Existing CMP
0.55	Existing CMP
0.56	Jct. w/ private spur road on left
0.70	End road renovation. Begin construction of 32-5-10.1 road as per Plan and Profile Sheet Exhibit C12: 32-5-10.1 B, Sheet 1. End haul locations shown on Exhibits C2-2, C2-5, and C2-7 to be approved by Authorized Officer.

### 32-5-10.2 Road – Non System – NAT – Sub: 16Ft – Ditch: 0Ft – X-Sect: Outsloped

<u>MP</u>	<u>Description</u>
0.00	Jct w/ 32-5-10.1 road. Begin road renovation which includes reshaping road surface (blading, watering, and rolling) to road specifications; clearing all culvert inlets and outlets; cleaning all debris or obstructions from inside culverts; and roadside brushing and chipping.
0.09	Existing CMP
0.20	Existing CMP
0.23	Existing CMP
0.26	Existing CMP
0.29	Existing CMP
0.85	End road renovation.

### 32-5-17.0 Road – Fortune Branch Rd – AGG – Sub: 16Ft – Ditch: 3Ft – X-Sect: Crowned

<u>MP</u>	<u>Description</u>
0.00	Jct w/ 32-5-20.0 road. Begin road renovation which includes reshaping road surface (blading, watering, and rolling) to road specifications; clearing and reshaping ditch lines; clearing all culvert inlets and outlets; cleaning all debris or obstructions from inside culverts; and roadside brushing. Begin dust abatement, when necessary.
0.02	Existing CMP
0.10	Existing CMP. End dust abatement.
0.18	Existing CMP
0.37	Existing CMP
0.38	Jct. w/ 32-5-17.2 road on right
0.43	Existing CMP
0.63	End haul WDS location on right.
0.64	Begin dust abatement, when necessary.
0.72	Existing Bridge. Hydrologic Point of Concern: Install check dams, or other approved BMP's, per contract specifications and Exhibit C11.
0.77	Existing CMP
0.79	Jct. w/ spur road on left. End dust abatement.
0.83	Existing CMP
0.89	Existing CMP
0.99	Property line into private land.
1.05	Existing CMP

## Exhibit C13

Sale Name: Blown Fortune

Page 8 of 12

1.11	Jct. w/ private road on left
1.13	Existing CMP
1.14	Jct. w/ spur road on left
1.17	Property line into BLM.
1.22	Jct. w/ 32-5-9.3 road on left
1.23	Existing CMP
1.26	Existing CMP
1.37	Existing CMP
1.41	Existing CMP
1.47	Existing CMP
1.60	Existing CMP
1.74	Jct. w/32-5-9.0 road on right
1.75	Existing CMP
1.83	Existing CMP
1.99	Existing CMP
2.08	Existing CMP
2.12	Existing CMP
2.18	Existing CMP
2.25	Existing CMP
2.30	Existing CMP
2.30	Jct. w/ 32-5-9.1 road on left. End road renovation.

### 32-5-17.1 Road – Buckhorn Btm– AGG – Sub: 14Ft – Ditch: 3Ft – X-Sect: Crowned

<u>MP</u>	<u>Description</u>
0.00	Jct. w/ 32-5-20.0 road. Begin road renovation which includes reshaping road surface (blading, watering, and rolling) to road specifications; clearing and reshaping ditch lines; clearing all culvert inlets and outlets; cleaning all debris or obstructions from inside culverts; and roadside brushing and chipping.
0.12	Existing CMP
0.27	Jct. w/ spur road on right.
0.32	End road renovation.

### 32-5-17.2 Road – Fortune 17 Spur – NAT – Sub: 14Ft – Ditch: 0Ft – X-Sect: Outsloped

<u>MP</u>	<u>Description</u>
0.00	Jct w/ 32-5-17.0 road. Begin road renovation which includes reshaping road surface (blading, watering, and rolling) to road specifications; and roadside brushing and chipping.
0.02	Remove existing berm barricade.
0.22	End road renovation.

### 32-5-20.0 Road – Buckhorn Mtn Rd – BST/AGG – Sub: 16Ft – Ditch: 3Ft – X-Sect: Crowned

<u>MP</u>	<u>Description</u>
0.00	Jct w/ County Road (Azalea-Glendale Rd). Beginning of BST surface. Begin clearing all culvert inlets and outlets; cleaning all debris or obstructions from inside culverts.
0.18	Existing CMP
0.35	Existing Cattle Guard
0.45	Existing CMP
0.61	Existing CMP. Property line into BLM.
0.62	End of BST surface. Begin of AGG surface. Begin road renovation which includes reshaping road surface (blading, watering, and rolling) to road specifications; clearing and reshaping ditch lines; clearing all culvert inlets and outlets; cleaning all debris or obstructions from inside culverts; and roadside brushing. Begin dust abatement, when necessary.
0.65	First Jct. w/ 32-5-17.0 road on right

## Exhibit C13

Sale Name: Blown Fortune

Page 9 of 12

- 0.67 Existing CMP with buried inlet to be removed and replaced with a 18" x 42' CMP per project details and specifications. Supply and properly place 2 CY of Class 2 riprap material from an approved weed-free commercial source at pipe outlet for fill-slope protection per contract specifications and drawings. Replace aggregate surfacing upon written acceptance of subgrade after culvert replacement. Properly place, water, and roll a 50' long (centered over culvert) by 16' wide by 6" (20 CY) compacted-in-place depth of 1-1/2"-minus crushed rock material from an approved weed-free commercial source per contract specifications and drawings.
- 0.68 Second Jct. w/ 32-5-17.0 road on right
- 0.74 Existing bridge. Hydrologic Point of Concern: Install check dams, or other approved BMP's, per contract specifications and Exhibit C11.
- 0.79 Existing CMP
- 0.87 Jct. w/ temporary road TR 17-15 on left. End dust abatement.
- 0.90 Existing CMP
- 1.00 Existing CMP
- 1.06 Jct. w/ 32-5-17.1 road on left
- 1.07 Existing CMP
- 1.11 Existing CMP
- 1.14 Remove 2 CY of slide material on the left.
- 1.20 Existing CMP
- 1.25 Existing CMP
- 1.38 Existing CMP
- 1.46 Existing CMP
- 1.51 Existing CMP
- 1.59 Existing CMP
- 1.66 Existing CMP
- 1.77 Existing CMP
- 1.84 Existing CMP
- 1.90 Existing CMP
- 1.93 Existing CMP
- 2.08 Existing CMP
- 2.11 Jct. w/ spur road on right
- 2.19 Existing CMP
- 2.30 Existing CMP
- 2.41 Existing CMP
- 2.48 Property line into State lands.
- 2.50 Existing CMP
- 2.64 Jct. w/ 32-5-8.0 road on left
- 2.66 Jct. w/ 32-5-8.3 road on left
- 2.68 Property line into State land.
- 2.79 Jct. w/ private spur road on right
- 2.81 Jct. w/ private spur road on left
- 2.82 Existing CMP
- 3.03 Existing CMP
- 3.19 Existing CMP
- 3.38 Existing CMP
- 3.64 Existing CMP
- 3.82 Existing CMP
- 3.96 Jct. w/ temporary road TR 05-08 on left. End road renovation. Construct turnaround area.
- 4.58 Jct. w/ 32-5-5.2 road on left. End haul WDS location 0.17 miles down the 32-5-5.2 road on right.

## Exhibit C13

Sale Name: Blown Fortune

Page 10 of 12

### 32-5-30.0 Road – Swamp Creek – AGG – Sub: 16Ft – Ditch: 3Ft – X-Sect: Crowned

<u>MP</u>	<u>Description</u>
0.00	Begins at the end of Swamp Creek Road (County) Begin road renovation which includes reshaping road surface (blading, watering, and rolling) to road specifications; clearing and reshaping ditch lines; clearing all culvert inlets and outlets; cleaning all debris or obstructions from inside culverts; and roadside brushing and chipping.
0.04	Jct w/ spur road on right
0.08	Existing CMP
0.14	Existing CMP to be removed and replaced with a 18" x 34' CMP per project details and specifications. Install 20 L.F. of full round down spout. Supply and properly place 2 CY of Class 2 riprap material from an approved weed-free commercial source at pipe outlet for fill-slope protection per contract specifications and drawings. Replace aggregate surfacing upon written acceptance of subgrade after culvert replacement. Properly place, water, and roll a 50' long (centered over culvert) by 16' wide by 6" (20 CY) compacted-in-place depth of 1-1/2"-minus crushed rock material from an approved weed-free commercial source per contract specifications and drawings.
0.15	Jct w/ Pvt driveway on left
0.19	Existing CMP to be removed and replaced with a 18" x 36' CMP per project details and specifications. Supply and properly place 2 CY of Class 2 riprap material from an approved weed-free commercial source at pipe outlet for fill-slope protection per contract specifications and drawings. Replace aggregate surfacing upon written acceptance of subgrade after culvert replacement. Properly place, water, and roll a 50' long (centered over culvert) by 16' wide by 6" (20 CY) compacted-in-place depth of 1-1/2"-minus crushed rock material from an approved weed-free commercial source per contract specifications and drawings.
0.22	Existing gate
0.25	Existing CMP
0.32	Existing CMP to be removed and replaced with a 18" x 36' CMP per project details and specifications. Supply and properly place 2 CY of Class 2 riprap material from an approved weed-free commercial source at pipe outlet for fill-slope protection per contract specifications and drawings. Replace aggregate surfacing upon written acceptance of subgrade after culvert replacement. Properly place, water, and roll a 50' long (centered over culvert) by 16' wide by 6" (20 CY) compacted-in-place depth of 1-1/2"-minus crushed rock material from an approved weed-free commercial source per contract specifications and drawings.
0.42	Existing CMP
0.49	Jct w/ 32-5-30.2 road on right
0.52	Jct w/ 32-5-30.1 road on left
0.57	Non-BLM quarry stockpile on left
0.60	Remove 30 CY of quarry stockpile from roadway
0.62	Install 18"x36' of CMP culvert per project details and specifications. Install 20 L.F. of full round downspout. Supply and properly place 2 CY of Class 2 riprap material from an approved weed-free commercial source at pipe outlet for fill-slope protection per contract specifications and drawings. Replace aggregate surfacing upon written acceptance of subgrade after culvert replacement. Properly place, water, and roll a 50' long (centered over culvert) by 16' wide by 6" (20 CY) compacted-in-place depth of 1-1/2"-minus crushed rock material from an approved weed-free commercial source per contract specifications and drawings.
0.65	Existing CMP to be removed and replaced with a 18" x 34' CMP per project details and specifications. Install 20 L.F. of full round down spout. Supply and properly place 2 CY of Class 2 riprap material from an approved weed-free commercial source at pipe outlet for fill-slope protection per contract specifications and drawings. Replace aggregate surfacing upon written acceptance of subgrade after culvert replacement. Properly place, water, and roll a 50' long (centered over culvert) by 16' wide by 6" (20 CY) compacted-in-place depth of 1-1/2"-

## Exhibit C13

Sale Name: Blown Fortune

Page 11 of 12

- minus crushed rock material from an approved weed-free commercial source per contract specifications and drawings.
- 0.76 Existing CMP
- 0.85 Existing CMP to be removed and replaced with a 18" x 38' CMP per project details and specifications. Install 20 L.F. of full round down spout. Supply and properly place 2 CY of Class 2 riprap material from an approved weed-free commercial source at pipe outlet for fill-slope protection per contract specifications and drawings. Replace aggregate surfacing upon written acceptance of subgrade after culvert replacement. Properly place, water, and roll a 50' long (centered over culvert) by 16' wide by 6" (20 CY) compacted-in-place depth of 1-1/2"-minus crushed rock material from an approved weed-free commercial source per contract specifications and drawings.
- 0.96 Existing CMP to be removed and replaced with a 18" x 36' CMP per project details and specifications. Supply and properly place 2 CY of Class 2 riprap material from an approved weed-free commercial source at pipe outlet for fill-slope protection per contract specifications and drawings. Replace aggregate surfacing upon written acceptance of subgrade after culvert replacement. Properly place, water, and roll a 50' long (centered over culvert) by 16' wide by 6" (20 CY) compacted-in-place depth of 1-1/2"-minus crushed rock material from an approved weed-free commercial source per contract specifications and drawings.
- 0.99 End Renovation. Construct turnaround area.

### 32-5-30.1 Road – Mainline – AGG – Sub: 16Ft – Ditch: 3Ft – X-Sect: Crowned

<u>MP</u>	<u>Description</u>
0.00	Jct w/ 32-5-30.0 road. Begin road renovation which includes reshaping road surface (blading, watering, and rolling) to road specifications; clearing and reshaping ditch lines; clearing all culvert inlets and outlets; cleaning all debris or obstructions from inside culverts; and roadside brushing and chipping.
0.05	Remove 5 CY of slide material from ditch and road.
0.53	Existing CMP
0.55	Existing CMP
0.55	Existing CMP
0.62	Existing CMP
0.72	Existing CMP
0.81	Existing CMP
0.84	Jct. w/ 32-5-31.4 road on left. End road renovation.

### 32-5-30.2 Road – Swampford Knls– NAT – Sub: 14Ft – Ditch: 3Ft – X-Sect: Crowned

<u>MP</u>	<u>Description</u>
0.00	Jct w/ 32-5-30.0 road. Begin road renovation which includes reshaping road surface (blading, watering, and rolling) to road specifications; clearing and reshaping ditch lines; clearing all culvert inlets and outlets; cleaning all debris or obstructions from inside culverts; and roadside brushing and chipping.
0.03	Existing CMP
0.10	Existing CMP
0.13	Existing CMP
0.17	Existing CMP
0.22	Existing CMP
0.27	Existing CMP
0.30	Existing CMP
0.37	Existing CMP
0.54	Existing CMP
0.64	Jct. w/ temporary road TR 31-02. End road renovation.

## Exhibit C13

Sale Name: Blown Fortune

Page 12 of 12

### 32-5-31.4 Road – Low Sp – AGG – Sub: 14Ft – Ditch: 3Ft – X-Sect: Crowned

<u>MP</u>	<u>Description</u>
0.00	Jct w/ 32-5-30.1 road. Begin road renovation which includes reshaping road surface (blading, watering, and rolling) to road specifications; clearing and reshaping ditch lines; clearing all culvert inlets and outlets; cleaning all debris or obstructions from inside culverts; and roadside brushing and chipping.
0.18	Existing CMP
0.22	Existing CMP
0.35	End road renovation.

### TR 03-14 Temp Road – NAT – Sub: 14Ft – Ditch: 0Ft – X-Sect: Outsloped

<u>STA</u>	<u>Description</u>
0+00	Jct w/ 32-5-3.2 road. Begin construction.
6+92	Construct truck turnaround. End construction.

### TR 05-08 Temp Road – NAT – Sub: 14Ft – Ditch: 0Ft – X-Sect: Outsloped

<u>STA</u>	<u>Description</u>
0+00	Jct w/ 32-5-20.0 road. Begin construction.
12+15	Construct truck turnaround. End construction.

### TR 09-05 Temp Road – NAT – Sub: 14Ft – Ditch: 0Ft – X-Sect: Outsloped

<u>STA</u>	<u>Description</u>
0+00	Jct w/ 32-5-10.0 road. Begin construction.
13+20	Construct truck turnaround. End construction.

### TR 17-02 Temp Road – NAT – Sub: 14Ft – Ditch: 0Ft – X-Sect: Outsloped

<u>STA</u>	<u>Description</u>
0+00	Jct w/ 32-5-8.1 road. Begin construction.
17+42	Construct truck turnaround. End construction.

### TR 17-15 Temp Road – NAT – Sub: 14Ft – Ditch: 0Ft – X-Sect: Outsloped

<u>STA</u>	<u>Description</u>
0+00	Jct w/ 32-5-20.0 road. Begin construction.
8+45	Install temporary 36"x40' Polyethylene drainage pipe or its equivalent.
11+62	Construct truck turnaround. End construction.

### TR 31-02 Temp Road – NAT – Sub: 14Ft – Ditch: 0Ft – X-Sect: Outsloped

<u>STA</u>	<u>Description</u>
0+00	Jct w/ 32-5-30.2 road. Begin construction.
14+26	Construct truck turnaround. End construction.

SPECIAL PROVISIONS

1. Before the initial start of road renovation, construction, reconstruction, or surfacing operations, or after a shutdown of 7 or more days, the Purchaser, or the Purchasers Representative, shall notify the Authorized Officer 48 hours in advance of the date they plan to begin operations. The Purchaser shall also notify the Authorized Officer if they intend to cease operations for any period of 30 or more days.
2. DAMAGE:
  - The Purchasers Representative/Contractor shall protect, and is responsible for, any damage to existing telephone lines, transmission lines, fiber optic lines, fences, ditches, and other existing improvements as required in Section 14. Damage to utilities and existing improvements shall be promptly paid for or repaired to a condition which is, in the opinion of the Authorized Officer and the governing utility company, as good or better condition than just prior to such damage occurring.
3. PERMITS:
  - All permits required are the responsibility of the Purchaser.
4. SEASONAL RESTRICTION . - . Waivers may be granted if conditions are favorable.

<u>ACTIVITY</u>	<u>START DATE</u>	<u>END DATE</u>
Road renovation	May 15	Oct. 15
In stream	July 1	Sept. 15
5. STREAMS:
  - All stream channel culverts and inlets shall be cleared and cleaned between **July 1<sup>st</sup> and September 15<sup>th</sup>** in accordance with Oregon Department of Fish and Wildlife (ODFW) in-stream work period guidelines.
  - Construct silt fences 25 and 50 feet below culvert replacement sites (on live streams) to trap sediment and prevent it from entering nearby stream channels.
  - Live streams shall be diverted around or through the work area in a manner that will minimize sedimentation downstream. Keep excavation site dewatered so that installation of culverts can be carried out only under dry conditions. Dispose of excess water by using natural drainage ways or devices near the site to the extent of their natural capacity and in a manner that will avoid damage to adjacent property. Utilize dewatering methods such as temporary sediment traps and/or silt fences for areas to be excavated. Provide for downstream water flow without significant transport of excavated material or sediment during construction. At no time shall turbidity limits exceed DEQ's water quality standards.
  - Ensure that all large wood is retained in the stream channel during culvert cleaning activities by moving logs which had accumulated on the upstream side of a culvert to the downstream side of the culvert.
6. WATER SOURCE:
  - The Purchaser is responsible for obtaining water, water sources shall be approved by the Authorized Officer prior to use. The Purchaser is responsible for all permits and fees from water sources on private or commercial sources.

7. EQUIPMENT

- Construction equipment shall be washed prior to entering BLM lands. Removal of all dirt, grease, and plant parts that may carry noxious weed seeds or vegetative parts is required. Equipment shall be inspected the Authorized Officer prior to entering BLM lands. Provide 48 hours' notice of inspection to BLM prior to mobilization.

8. SOIL STABILIZATION:

- All disturbed soil shall be seeded and mulched. The Purchasers Representative/Contractor shall apply native grass seed and Certified Weed Free straw mulch for soil stabilization operations. BLM will furnish native grass seed, **if available**. Acquiring certified weed free straw mulch is the responsibility of the Purchasers Representative.

9. ROAD RENOVATION:

- Road renovation shall generally take place between May 15<sup>th</sup> and October 15<sup>th</sup> of the same year. Waivers may be granted from the Authorized Officer for working outside of this time period. Seasonal restrictions for stream work and wildlife may still apply.
- Loose material cleaned from ditch lines and/or slide material shall not be sidecast or placed where it can enter wetlands, riparian reserves, floodplains, and waters of the State.

10. ROADSIDE BRUSHING

- While roadside brushing, there shall be no scarring or any other damage of the tree trunk or bole allowed. All debris resulting from roadside brushing activities shall be scattered downslope. Use of Excavators for brush removal will be at the discretion of the Authorized Officer. **All culvert inlets and outlets shall be brushed for a radius of 4 feet.**
- While roadside brushing through private industry lands, conifer trees at the edges of the cleared area (see cutting limit, Exhibit C6) shall have the branches pruned rather than being felled.
- All stumps, designated by the Authorized Officer, which would interfere with normal blading and road renovation operations (including turnouts), shall be removed in such a way as to not cause damage to the drainage ditch or the road bed.

11. TEMPORARY ROUTES

- All temp routes and native surfaced roads (that were previously closed before timber sale activities began) shall be winterized if access is needed over two dry seasons by October 15<sup>th</sup>. Winterization includes water barring, seeding, mulching, and barricading. All temp routes shall be ripped, water barred, barricaded, seeded, and mulched after use unless otherwise specified.
- Clearing, grubbing, and excavation activities of temporary spur routes shown on Exhibit C shall be performed in accordance with Exhibit C15.
- Construction of temporary routes shall be to minimum necessary width.

12. COMMERCIAL AGGREGATE

- Aggregate furnished for this work shall be direct from an accredited weed free commercial source and can be stockpiled in the period between November 1<sup>st</sup> and June 15<sup>th</sup> immediately prior to application. Aggregate which has been stockpiled between June 16<sup>th</sup> and October 31<sup>st</sup> of prior years will not be accepted. Aggregate crushed between June 16<sup>th</sup> and October 31<sup>st</sup> of the same application year shall not be stockpiled for more than two weeks before application.

13. WILDLIFE RESTRICTIONS

- Seasonally restrict mechanical roadside brushing activities (including chainsaws) and heavy equipment use to avoid disturbance to nesting NSOs and raptors from March 1st through September 30th within 200 feet of known NSO and raptor nests. This seasonal restriction could be waived if non-nesting status is determined.

14. WET SEASON HAUL

- The Purchaser may wet season haul, with the Authorized Officer's approval, on roads with durable rock surfacing and sufficient rock depth to resist rutting or development of sediment on road surfaces that drain directly to wetlands, floodplains, and waters of the State.
- If hauling activities during the wet season causes or begins to cause road damage or the transport of sediment into streams, the Authorized Officer may suspend wet season haul or require additional erosion control devices to prevent damage or off-site transportation of sediment. Additional rock may be required at the Purchaser's expense to repair any damage that occurs to the road during wet season haul. Any costs for rocking and installation of additional drainage features will be at the Purchaser's expense and shall be completed in accordance with the plans and specifications shown in Exhibit C of this contract.
- No hauling shall occur on native surface roads during the wet season (generally Oct. 15 – May 15); exceptions may be made during dry conditions of the wet season pending approval from a BLM Authorized Officer.

## **TIMBER SALE ROAD SPECIFICATIONS**

---

### **TABLE OF CONTENTS**

SECTION	DESCRIPTION
100	General
200	Clearing and Grubbing
300	Excavation and Embankment
400	Pipe Culverts
500	Renovation and Improvement of Existing Roads
600	Watering
1200	Aggregate Surface Course - Crushed Rock
1400	Slope Protection
1700	Erosion Control
1800	Soil Stabilization
2100	Roadside Brushing

---

## TIMBER SALE ROAD SPECIFICATIONS

---

### GENERAL – 100

101 - Prewrite Conference(s):

A prework conference will be held prior to the start of new construction, improvement, and renovation operations. The Purchaser shall request the conference at least 72 hours prior to the time it is to be held. The conference will be attended by the Purchaser and/or his representative(s), subcontractor(s) and/or his or their representative(s) and the Authorized Officer and/or his representative(s).

The purpose of the prework conference will be to review the required work, exhibits and specifications, and to establish a work schedule and a list of the Purchaser's representatives and subcontractor(s).

102 - Definitions:

AASHTO - American Association of State Highway and Transportation Officials. Current editions of tests and specifications.

Abrasion Resistance - The ability of a fabric surface to resist wear by friction.

ACI - American Concrete Institute

Apparent Opening Size (AOS) - Number of the U.S. Bureau of Standard sieve (or its opening size in millimeters or inches) having openings closest in size to the diameter of uniform particles which will allow 5 percent by weight to pass through the geotextile material when shaken in a prescribed manner. This is also referred to as Equivalent Opening Size (EOS).

ASTM - American Society for Testing and Materials.

Base Course - Surfacing structure consisting of crushed gravel or stone, crushed sandstone, pitrun rock, bank or river-run gravels, etc., to provide support and, in the event no surface course is placed, the running surface for traffic load.

BLM - Bureau of Land Management

Borrow - Excavated material required for embankments and other portions of the work.

---

## TIMBER SALE ROAD SPECIFICATIONS

---

Burst Strength - The resistance of a geotextile material to rupture from pressure applied at right angles to the plane of the geotextile material under specified conditions, usually expressed as the amount of pressure causing failure. Rupture or burst results from tensile failure of the geotextile material.

Culvert - A pipe, pipe-arch, arch, or box structure constructed of metal, concrete, plastic or wood which provides an opening under the roadway primarily for the conveyance of liquids, pedestrians or livestock.

Curve Widening - Widening required on inside of curves to accommodate long log and equipment hauling trucks.

Embankment - A structure of soil, aggregate, or rock material placed on a prepared ground surface and constructed to subgrade.

End Haul - Excavated material moved, other than by dozer, to an embankment or waste area to prevent sidecasting material outside of the road prism.

Excess Excavation - Material from the roadway in excess of that needed for construction of the designed roadway (waste).

Grab Tensile Strength - A modified tensile strength of a geotextile material. The strength of a specific width of geotextile material together with the additional strength contributed by adjacent areas. Typically, grab strength is determined on a 12-inch-wide strip of geotextile material, with the tensile load applied at the midpoint of the geotextile material width through 1-inch-wide jaw faces.

Grading - Leveling to grade, shaping and smoothing of a road subgrade; the shaping of roadside ditches as to grade and contour. In some instances includes smoothing of the cut bank.

Nonwoven Geotextile Material - A textile structure produced by bonding or interlocking of fibers, or both, accomplished by mechanical or chemical means.

Overhaul - Distance excavated material is transported in excess of the distance included in the cost for excavation.

Penetration Resistance - The geotextile material property determined by the force required to penetrate a geotextile material with a sharp pointed object. Initial

---

## **TIMBER SALE ROAD SPECIFICATIONS**

---

penetration is by separating the fibers. Further penetration is essentially a tearing process.

Percent Open Area - The net area of a geotextile material that is not occupied by geotextile material filaments, normally determinable only for woven and nonwoven geotextile material having distinct, visible, and measurable openings that continue directly through the geotextile material.

Permeability - The geotextile material property which permits water to be transmitted in the longitudinal or transverse planes of the geotextile material.

Pioneer Road - Temporary construction access built along the route of the project.

Piping - The process by which soil particles are washed in or through pore spaces in drains and filters or poorly compacted fill/backfill material.

Plans - The approved drawings, or exact reproductions thereof which show the locations, character, dimensions, and details of the work to be done.

Pore Size - The size of an opening between geotextile material filaments; apparent opening size (AOS) is used to quantify this geotextile material property.

Puncture Resistance - The geotextile material property determined by the force required to penetrate a geotextile material with a blunt object. Failure results in a tearing of the geotextile material.

Purchaser - The individual, partnership, joint venture, or corporation contracting with the Government under the terms of a Timber Sale Contract and acting independently or through their, or its agents, employees, or contractors.

Reasonably Close Conformity - Compliance with reasonable and customary manufacturing and construction tolerances where working tolerances are not specified.

Reinforcement - Strengthening of concrete with iron bars or mesh; geotextile with geotextile material inclusion; subgrade with aggregate; etc.

Roadbed - The graded portion of the road within top and side slopes, prepared as a foundation for the pavement structure and shoulders.

## **TIMBER SALE ROAD SPECIFICATIONS**

---

Road Centerline - The longitudinal center of a roadbed.

Road Improvement - Work done to an existing road which improves it over its original design standard.

Road Renovation - Work done to an existing road which restores it to its original design.

Roadway - The portion of a road within limits of construction. Usually from the toe of the fill slope to a point where the cut slope intersects natural ground line.  
Synonym - road prism.

Scale - In quarrying, consists of the removal of loose or overhanging rock adhering to the solid face after a shot or a round of shots has been fired.

Scarification - The process of loosening or breaking up of the surface layer of soil or road, usually to a specified depth.

Separation - Function of geotextile material as a partition between adjacent materials to prevent mixing of those materials.

Shoulder - The portion of the roadbed contiguous with the traveled way designed for accommodation of stopped vehicles, safety, and lateral support of base and surface courses.

Spalls - Flakes or chips of stone.

Specifications - A general term applied to all directions, provisions, and requirements pertaining to performance of the work.

Specific Gravity - The ratio of the density of a material to the density of water obtained by weighing known volumes of both items in air. A specific gravity less than one implies that the material will float.

Structures - Bridges, culverts, catch basins, retaining walls, underdrains, flumes, splash pads, downspouts, and other project features which may be involved in the work and not otherwise classified in these specifications.

Subbase - Reinforcement of the subgrade with large particles of pitrun rock or

## **TIMBER SALE ROAD SPECIFICATIONS**

---

crushed stone. Usually confined to roads having wet subgrades or subgrades with weak support characteristics.

Surface Course - Top layer of a road structure consisting of finely crushed gravels or asphalt designed to provide a smooth running surface for traffic load.

Subgrade - The top surface of a roadbed upon which the traveled way and shoulders are constructed.

Tensile Strength - The strength shown by a geotextile material subjected to tension as distinct from torsion, compression, or shear.

Tensile Stress - Strain Modulus - A measure of the resistance to elongation under stress. The ratio of the change in tensile stress to the corresponding change in strain.

Tensile Test - A test which subjects geotextile material to tensile forces and measures resultant stresses and strains.

Timber - Standing trees, downed trees, or logs which can be measured in board feet.

Traveled Way - The portion of the roadbed used for the movement of vehicles, exclusive of shoulders.

Typical Cross Sections - Cross-sectional plane of a typical roadway; showing natural ground line and designed roadway in relation to cut and fill, through cut, and through fill.

Turnout - Extra widening of the roadbed at appropriate intervals on single-lane roads for passing purposes.

Ultraviolet (UV) Radiation Stability - The ability of geotextile material to resist deterioration from exposure to sunlight.

Unaged Cloth - Cloth in condition received from the manufacturer or distributor.

Woven Geotextile Material - A textile structure comprising two or more sets of filaments of yarns interlaced in such a way that the elements pass each other at essentially right angles with one set of elements parallel to the geotextile material axis.

---

## **TIMBER SALE ROAD SPECIFICATIONS**

---

102a - Tests Used in These Specifications:

AASHTO T 11 Quantity of rock finer than No. 200 sieve.

AASHTO T 27 Sieve analysis of fine and coarse aggregate using sieves with square openings; gradation.

AASHTO T 89 Liquid limit of material passing the No. 40 sieve. Water content at which the soil passes from a plastic to a liquid state.

AASHTO T 90 Plastic limits and plasticity index of soil.

- a. Plastic limit - lowest water content at which the soil remains plastic.
- b. Plasticity index - range of water content, within which the material is in a plastic state. Numerical difference between the liquid and plastic limits of the soil.

AASHTO T 96 Resistance to abrasion of small size coarse aggregate by use of the Los Angeles machine.

AASHTO T 99 Relationship between soil moisture and density of soil.

Method A - 4" mold, soil passing a No. 4 sieve

25 blows/layer & 3 layers.

Method C - 4" mold, soil passing a 3/4 inch sieve

25 blows/layer & 3 layers.

Method D - 6" mold, soil passing a 3/4 inch sieve. 56 blows/layer & 3 layers.

AASHTO T 119 Slump of hydraulic cement concrete.

AASHTO T 152 Air content of freshly mixed concrete.

AASHTO T 166 Specific Gravity of compacted Bituminous Mixtures.

AASHTO T 176 Shows relative portions of fine dust or claylike materials in soil or graded aggregate.

AASHTO T 180 (OSHD 106-71) moisture density relationship of soil same as AASHTO T 99 proctor but uses a 10-lb rammer & 18-in drop height.

AASHTO T 191 Sand Cone. Density of soil in place: For subgrade use 6-inch or 12-

## **TIMBER SALE ROAD SPECIFICATIONS**

---

inch cone. For rock surfacing for 1-1/2-inch minus to 3-inch minus use 12-inch cone.

AASHTO T 205 Rubber balloon. Density of soil in place. Use for compacted or firmly bonded soil.

AASHTO T 209 Maximum Specific Gravity of Bituminous Paving Mixtures.

AASHTO T 210 Durability of aggregates based on resistance to produce fines.

AASHTO T 224 Correction for coarse particles in the soil.

AASHTO T 238 Density of Soil and Soil-Aggregate in place by nuclear methods.

AASHTO T 248 Reducing field samples of aggregate to testing size by mechanical splitter, quartering, or miniature stockpile sampling.

ASTM D 4564 Determination of relative density of cohesionless soils.

DMSO (dimethyl sulfide) Determines volume of expanding clays in aggregates. Usually associated with marine basalts.

- 103 - Compaction equipment shall meet the following requirements:
- 103f - Vibratory roller. The drum diameter shall be not less than 48 inches, the drum width not less than 58 inches, and have a turning radius of 15 feet or less. Vibration frequency shall be regulated in steps to 1400, 1500, and 1600 vibrations per minute (VPM), corresponding to engine speeds of 1575, 1690, and 1800 RPM. The centrifugal force developed shall be 7 tons at 1600 RPM. It shall be activated by a power unit of not less than 25 horsepower. The vibratory roller shall be self-propelled or drawn by a vehicle of sufficient horsepower to enable the unit to travel through a loose layer of material at a speed ranging from 0.9 mile to 1.8 miles per hour, as directed by the Authorized Officer.

The towing vehicle and roller or self-propelled unit meeting the above requirements shall be considered a vibratory roller unit.

- 103g - Vibratory compactor. Vibratory compactors shall consist of multiple or gang-type compacting units or pads with a minimum variable width of 2 feet. It shall be self-contained and capable of compacting material as required.

## **TIMBER SALE ROAD SPECIFICATIONS**

---

- 103h - Drum drive self-propelled vibratory grid roller. The unit shall consist of one cylindrical drum with a drum diameter of not less than 56 inches, nor more than 66 inches and the drum width shall be 84 inches. Vibratory frequency shall be regulated in seeps from 1200 to 1800 vibrations per minute (VPM), and the centrifugal force developed shall be at least 40,000 pounds at 1800 RPM. The vibratory grid roller shall be self-propelled and have a power unit of not less than 112 horsepower. The "grid" design shall be a herringbone or z-bar pattern around the circumference of the drum. The grid bars shall be 1 inch in height and spaced not more than 8-1/2 inches apart.
  
- 103i - Other. Compaction equipment approved by the Authorized Officer.

### **CLEARING AND GRUBBING - 200**

- 201 - This work shall consist of clearing, grubbing, removing and disposing of vegetation, debris, surface objects, and protruding obstructions within the clearing limits in accordance with these specifications and conforming to the lines, grades, dimensions and typical cross sections shown on the plans and as staked on the ground.
  
- 202 - Where clearing limits have not been staked, established by these specifications or shown on the plans, the limits shall extend 10 feet back of the top of the cut slope and 5 feet out from the toe of the fill slope.
  
- 202b - Where clearing limits for roadside vegetation maintenance sections have not been staked or shown on the plans, the limits shall extend 6 horizontal feet back of the centerline of the ditch and 6 horizontal feet outside of the shoulder of the road.
  
- 203 - Clearing shall consist of the removal and disposal of trees, logs, rotten material, brush, and other vegetative materials and surface objects in accordance with these specifications and within the limits established for clearing as specified under Subsections 202 as shown on the plans and as posted.
  
- 203b - Standing trees and snags to be cleared shall be felled within the limits established for clearing unless otherwise authorized.
  
- 203c - Disposal of logs from private timber cleared within the limits established as staked on the ground shall consist of decking at a location designated by the Authorized Officer.

**TIMBER SALE ROAD SPECIFICATIONS**

---

- 204 - Grubbing shall consist of the removal and disposal of stumps, roots, and other wood material embedded in the ground and protruding obstacles remaining as a result of the clearing operation in accordance with Subsections 204a, 204c, and 204d between the top of the cut slope and the toe of the fill slope.
  
- 204a - Stumps including those overhanging cut banks, shall be removed within the required excavation limits.
  
- 204c - On excavated areas, roots and embedded wood shall be removed to a depth not less than 6 inches below the subgrade.
  
- 204d - On areas to be occupied by embankments having heights greater than 4 feet, no stump or portion thereof shall remain within 3 feet of embankment subgrades or slope surfaces after grubbing is completed.
  
- 205 - Clearing and grubbing debris shall not be placed or permitted to remain in or under road embankment sections.
  
- 206 - Clearing and grubbing debris shall be disposed of by chipping in accordance with Subsection 209 and/or scattering in accordance with Subsection 210 and/or piling in accordance with Subsection 211 at the following road locations.

Road No.	From M.P.	To M.P.	Disposal Method
32-5W-8.00	0.18	1.95	Pile
32-5W-8.02	0.06	0.18	Pile
32-5W-9.00	0.77	1.97	Pile
32-5-10.01 B	0.00	0.21	Pile
TR 03-14	0.00	0.13	Pile
TR 05-08	0.00	0.23	Pile
TR 09-05	0.00	0.25	Pile
TR 17-02	0.00	0.33	Pile
TR 17-15	0.00	0.22	Pile
TR 31-02	0.00	0.27	Pile

- 206a - Notwithstanding Subsections 204, 204a, 204d, and 205, clearing and grubbing debris resulting from landing construction shall be placed at disposal sites and shall not be covered with excavated material. Location of disposal sites will be determined by the Authorized Officer.

## **TIMBER SALE ROAD SPECIFICATIONS**

---

- 208b - Trees, firm logs, and other firm large pieces, 4 inches in diameter and 8 feet in length and larger and not removed from the contract area by the Purchaser, shall be piled at locations determined by the Authorized Officer.
- 209 - Clearing and grubbing debris shall be reduced to chips of an acceptable size and disposed of by scattering.
- 210 - Disposal of clearing and grubbing debris shall be by scattering over government owned lands outside of established clearing limits in a manner acceptable to the Authorized Officer. The areas for such scattering shall have the prior approval of the Authorized Officer.
- 210a - Disposal of clearing and grubbing debris on non-government property by scattering this material outside of clearing limits will be permitted provided the Purchaser obtains a written permit from the property owner on whose property the disposal is to be made. The Purchaser shall furnish the Authorized Officer a certified copy of the permit and a written release from the property owner absolving the Government from responsibilities in connection with the disposal of debris on said property.
- 210b - Clearing and grubbing debris and stumps and cull logs resulting from road construction on non-Government property shall be loaded and hauled to designated areas, as shown on the plan. Disposal shall be by scattering in accordance with Subsection 210 or piling in accordance with Subsection 211.
- 211 - Disposal of clearing and grubbing debris and stumps and cull logs shall be by piling on government lands outside of established clearing limits in an area and in a manner acceptable to the Authorized Officer.
- 212 - No grading will be permitted prior to completion and approval by the Authorized Officer of the required clearing and grubbing work, except that stump grubbing may proceed with the excavation of the road prism.
- 213 - No clearing or grubbing debris shall be left lodged against standing trees.

---

## **TIMBER SALE ROAD SPECIFICATIONS**

---

### **EXCAVATION AND EMBANKMENT - 300**

- 301 - This work shall consist of excavating, overhaul, placement of embankments, backfilling, borrowing, leveling, ditching, grading, insloping, outsloping, crowning and scarification of the subgrade, compaction, disposal of excess and unsuitable materials, and other earth-moving work in accordance with these specifications and conforming to the lines, grades, dimensions, and typical cross sections shown on the plans.
  
- 302 - Excavation shall also consist of the excavation of road and landing cut sections, borrow sites, backfilling, leveling, ditching, grading, compaction, and other earth moving work necessary for the construction of the roadway in accordance with these specifications and conforming to the lines, grades, dimensions, and typical cross sections shown on the plans and as marked on the ground with stakes.
  
- 303 - Suitable material removed from the excavation shall be used in the formation of embankment subgrade, shoulders, slopes, bedding, backfill for structures, and for other purposes as shown on the plans.
  
- 304 - Borrow shall consist of suitable material required for the construction of embankments or for other portions of the work; such material shall be obtained from sources selected by the Purchaser at his option and approved by the Authorized Officer.
  
- 305 - Embankment construction shall consist of the placement of excavated and borrowed materials, backfilling, leveling, grading, compaction, and other earth-moving work necessary for the construction of the roadway and landings in accordance with these specifications and conforming to the lines, grades, dimensions, and typical cross sections shown on the plans and as marked on the ground with stakes.
  
- 305a - Material used in the construction of embankment sections shall be free of stumps, cull logs, brush, muck, sod, roots, frozen material, and other deleterious materials and shall be placed and compacted as specified.
  
- 305b - Embankment materials shall be placed in successive parallel layers on areas cleared of stumps, cull logs, brush, sod, and other vegetative and deleterious materials, except as provided under Subsection 204. Roadway embankments of earth material shall be

## **TIMBER SALE ROAD SPECIFICATIONS**

---

- placed in horizontal layers not exceeding 8 inches in depth.
- 306 - Layers of embankment material as specified under Subsections 305a and 305b, shall be moistened or dried to a uniform optimum moisture content suitable for maximum density and compacted to full width with compacting equipment conforming to requirements of Subsections 103f, 103g, 103h, and 103i.
- 306e - The final subgrade shall be compacted to full width with compacting equipment conforming to the requirements of Subsections 103f, 103g, 103h, and 103i. Minimum compaction shall be 1 hour of continuous compacting for each 6 stations of road or a fraction of as measured along the center line of the constructed road.
- 306g - All fill slopes shall be compacted to 75 percent of maximum density, either by walking with cat/excavator or by pressing with excavator bucket, to prevent surface erosion and raveling.
- 308 - In the case of rock fills, placement of material in layers is not required and such material may be placed by end-dumping or other methods approved by the Authorized Officer provided that the rock be reasonably prevented from escaping beyond the embankment toe.
- 314 - When heavy clays, muck, clay shale, or other deleterious material for forming the roadbed is encountered in cuts at subgrade, it shall be excavated to a minimum depth of 2 feet below the subgrade elevation and the excavated area backfilled with a selected borrow material approved by the Authorized Officer. The backfill material shall be uniformly moistened or dried to the optimum moisture content suitable for maximum density in accordance with the requirements of Subsection 306. Unsuitable material shall be disposed of as directed by the Authorized Officer.
- 316 - Borrow material from sources selected at the Purchaser's option shall be inspected and approved in writing by the Authorized Officer prior to placement.
- 317 - Selected borrow shall consist of talus material, finely broken rock, gravel, or other material of granular or favorable characteristics from sources shown on the plans.
- 318 - Selected borrow or selected roadway excavation material shall be uniformly spread on the roadbed in lifts not to exceed 6 inches in depth until the required thickness

## **TIMBER SALE ROAD SPECIFICATIONS**

---

shown on the plans is attained.

Each layer shall be uniformly moistened or dried to the optimum moisture content suitable for maximum density and compacted to full width in accordance with the requirements of Subsection 306.

- 320 - Ditches shall conform to the slope, grade, dimensions, and shape of the required cross section shown on the plans. Roots, stumps, rocks, and other projections shall be removed to form smooth, even slopes.
- 321 - Excess excavated, unsuitable, or slide materials shall not be disposed of on areas where the material will encroach on a stream course or other body of water. Such materials shall be disposed of in accordance with Subsection 321c. Materials not disposed of in this manner shall be retrieved and disposed of at the Purchaser's expense and at the direction of the Authorized Officer.
- 321c - End-dumping will be permitted for the placement of excess materials under Subsection 321 in designated disposal areas or within areas approved by the Authorized Officer. Watering, rolling, and placement in layers are required. Materials placed shall be sloped, shaped, and otherwise brought to a visible condition acceptable to the Authorized Officer.
- 323 - In the construction of channel changes and stream-crossing embankment sections, natural stream flow shall be maintained unless otherwise provided.
- 324 - Excavated material shall not be allowed to cover boles of standing trees to a depth in excess of 2 feet on the uphill side.
- 327 - The finished grading shall be approved in writing by the Authorized Officer for the total project. The Purchaser shall give the Authorized Officer 3 days notice prior to final inspection of the grading operations.

---

## **TIMBER SALE ROAD SPECIFICATIONS**

---

### **PIPE CULVERTS - 400**

- 401 - This work shall consist of furnishing and installing pipe culverts and other erosion control devices in accordance with these specifications and conforming to the lines, grades, dimensions, and typical cross sections shown on the plans. Individual lengths and locations are approximate; final lengths and locations will be determined by the Authorized Officer from established construction stakes and upon installation of the appurtenance structures. Additional pipe and erosion control devices may be required at the option of the Authorized Officer, in which case a reduction in the total purchase price shall be made to offset the cost of furnishing and installing such items. Costs will be based upon the unit prices set forth in the current BLM Timber Appraisal Production Cost Schedule.
  
- 403 - Grade culverts shall have a gradient of from 2 percent to 4 percent greater than the adjacent road grade. Grade culverts shall be skewed down grade 30 degrees as measured from the perpendicular to the centerline unless otherwise specified on the plans.
  
- 404 - Damage to the spelter, or burn back in excess of 3/8 inch, shall be wire brushed and painted with two coats of zinc-rich paint on zinc-coated, steel pipe and aluminum-rich paint on aluminum or aluminum-coated pipe.
  
- 405a - Corrugated-(aluminized) steel-welded pipe culverts and pipe-arch culverts and special sections shall conform to the requirements of AASHTO M 36 and AASHTO M 218, AASHTO M 274, or AASHTO M 289 as specified on the plans.
  
- 406 - Coupling bands shall conform to the requirements of AASHTO M 36 and AASHTO M 218 or AASHTO M 274 with the exception of band widths and the "Hugger"-type band which shall conform to the details, dimensions, and typical diagram shown on the plans.
  
- 406a - "Hugger"-type coupling bands shall only be used with annular corrugated pipe and pipe-arch culverts, or helically corrugated pipe and pipe-arch culverts having annular reformed ends. Annular reformed ends shall consist of two annular corrugations.
  
- 408 - Pipe culverts and pipe-arch culverts shall be placed on the bed starting at the downstream end with the inside circumferential laps pointing downstream and with

---

## TIMBER SALE ROAD SPECIFICATIONS

---

- the longitudinal laps at the side or quarter points. Coupling bands of the type required under these specifications shall be installed so as to provide the circumferential and longitudinal strength necessary to preserve the pipe alignment, prevent separation of the pipe sections, and minimize infiltration of fill material.
- 410 - Pipe shall be unloaded and handled with reasonable care. If the Authorized Officer determines any structure is damaged to the extent that it is unsuitable for use in the road construction, it shall be replaced at the Purchaser's expense.
- 411 - Trenches necessary for the installation of pipe culverts shall conform to the lines, grades, dimensions, and typical diagram included in the plans and in Exhibit C 9, the Culvert Installation Detail Sheet.
- 412 - Where ledge rock, boulders, soft, or spongy soils are encountered, they shall be excavated a minimum of 24 inches below the invert grade for a width of at least one pipe diameter or span on each side of the pipe and shall be backfilled with selected granular or fine readily compactable soil material.
- 413 - Pipe culverts and pipe-arch culverts shall be bedded on a selected granular, crushed rock material from stockpiles shown on the plans, or fine readily compactable soil material having a depth of not less than 6 inches as shown on plans. Foundation material shall be of uniform density throughout the length of the structure and shall be shaped to fit the pipe.
- 416 - Side-fill material for pipe culverts shall be placed within 1 pipe diameter, or a minimum of 2 feet, of the sides of the pipe barrel, and to 1 foot over the pipe with fine, readily compactable soil, crushed rock material from stockpiles shown on the plans, or granular fill material free of excess moisture, muck, frozen material, roots, sod, or other deleterious or caustic material and devoid of rocks or stones of sizes which may impinge upon and damage the pipe or otherwise interfere with proper compaction.
- 417 - For pipe culvert, side-fill material conforming to the requirements of Subsection 416 shall be placed and compacted under the haunches of the pipe, and shall be brought up evenly and simultaneously on both sides of the pipe to 1 foot above the pipe, in layers not exceeding 6 inches in depth and 1 pipe diameter/span, or a minimum of 2 feet in width each side of, and adjacent to, the full length of the pipe barrel. Each

## **TIMBER SALE ROAD SPECIFICATIONS**

---

layer shall be moistened or dried to a uniform moisture content suitable for maximum compaction and immediately compacted by approved hand or pneumatic tampers until a uniform density of 85 percent of the maximum density, is attained as determined by AASHTO T 99, Method C.

- 419 - The pipe culverts after being bedded and backfilled as required by these specifications shall be protected by a 2-foot cover of fill before heavy equipment is permitted to cross the drainage structures. Removal of the protection fill shall be as directed by the Authorized Officer.
  
- 423 - Construction of catch basins and ditch dams conforming to lines, grades, dimensions and typical diagrams shown on the plans, shall be required for all culverts.
  
- 423 - Construction of catch basins and ditch dams conforming to lines, grades, dimensions and typical diagrams shown on the plans, shall be required for all culverts.
  
- 427 - Record culvert sizes, lengths and location actually installed on a copy of the culvert list. This culvert list shall be furnished to the Authorized Officer.
  
- 428 - Remove and dispose of old culverts in a legal manner, and for any fees required. The Purchaser shall remove the old culverts from the work site within 3 working days of completion of the culvert replacement work for each road.
  
- 429 - Keep the excavation site dewatered so that the installation of culverts is completed under dry conditions. Dispose of excess water by using pumping or natural drainage ways near the site in a manner that will avoid damage to adjacent property. Provide for downstream waterflow with no more that 10% increase in natural stream turbidity due to transport of excavated material or sediment during construction. Diversion streams shall not be returned to the natural channel until all in-stream work has been completed.

### **RENOVATION AND IMPROVEMENT OF EXISTING ROADS - 500**

- 501 - This work shall consist of reconditioning and preparing the roadbed and shoulders, minor excavation and/or embankment, cleaning and shaping drainage ditches, trimming vegetation from cut and embankment slopes, and cleaning and repairing drainage structures of existing roads in accordance with these specifications, as

## **TIMBER SALE ROAD SPECIFICATIONS**

---

shown on the plans, and as marked on the ground with stakes.

- 502 - The existing road surface shall be bladed and shaped to the lines, grades, dimensions, and typical cross sections shown on the plans and as marked on the ground with stakes and as specified in the worklist.
- 502b - Drainage ditches shall be bladed and shaped in accordance with the lines, grades, dimensions, and typical cross sections shown on the plans.
- 504 - Existing road surface shall be uniformly moistened or dried to the optimum moisture content suitable for maximum density and compacted to full width with equipment conforming to requirements of Subsections 103f, 103g, 103h, and 103i and as specified in the worklist.
- 504a - Minimum compaction required shall be 1 hour of continuous rolling for each 3 stations of road, or fraction thereof, as measured along the centerline per layer of material.
- 506 - The inlet end of existing drainage structures shall be cleared of vegetative debris and boulders that are of sufficient size to obstruct normal stream flow. Pipe inverts shall be cleared of sediment and other debris lodged in the barrel of the pipe. The outflow area of pipe structures shall be cleared of rock and vegetative obstructions which will impede the structure's designed outflow configuration. Catch basins shall conform to the lines, grade, dimensions, and typical diagram shown on the plans.
- 508 - Vegetation encroaching on the roadbed and the drainage ditches of existing roads shall be removed by cutting and disposed of in accordance with Subsection 2100 of these specifications.
- 509 - The finished grading shall be approved in writing by the Authorized Officer 3 days prior to surfacing operations. The Purchaser shall give the Authorized Officer 3 days notice prior to final inspection of the grading operations.

### **WATERING - 600**

- 601 - This work shall consist of furnishing and applying water required for the compaction of embankments, roadbeds, backfills, base courses, surface courses, finishing and reconditioning of existing roadbeds, laying dust, or for other uses in accordance with

## **TIMBER SALE ROAD SPECIFICATIONS**

---

these specifications.

- 602 - Water, when needed for compaction or laying dust, shall be applied at the locations, in the amounts, and during the hours as directed by the Authorized Officer. Amounts of water to be provided will be the minimum needed to properly execute the compaction requirements in conformance with these specifications, and for laying dust during work periods.
- 603 - Water trucks used in this work shall be equipped with a distributing device of ample capacity and of such design as to ensure uniform application of water on the road bed.
- 605 - The Purchaser shall secure the necessary water permits and pay all required water fees for use of water sources selected by the Purchaser and approved by the Authorized Officer.

### **AGGREGATE SURFACE COURSE – 1200 CRUSHED ROCK MATERIAL**

- 1201 - This work shall consist of loading, hauling and placing one or more layers of crushed rock material on roadbeds and base courses approved for placing crushed rock material in accordance with these specifications and conforming to the dimensions and typical cross sections shown on the plans. Material not conforming to these specifications will be rejected, and shall be removed from the road at the purchaser's expense.
- 1202 - Crushed rock materials used in this work shall consist of quarry rock, stone, gravel, or other approved materials obtained from sources shown on the plans.
- 1202a - Crushed rock materials used in this work may be obtained from commercial sources selected by the Purchaser, providing the rock materials furnished comply with these specifications.
- 1203 - When crushed rock material is produced from gravel, not less than 65 percent by weight of the particles retained on the No. 4 sieve will have 2 manufactured fractured faces.

**TIMBER SALE ROAD SPECIFICATIONS**

---

- 1204 - Crushed rock material shall consist of hard durable rock fragments conforming to the following gradation requirements:

TABLE 1204

AGGREGATE SURFACE  
COURSE CRUSHED ROCK  
MATERIAL

Percentage by weight passing square mesh sieves  
AASHTO T 11 & T 27

GRADATION

Sieve Designation	C	C-1	D	D-1	E	E-1
1-1/2-inch	100	<b>100</b>	-	-	-	-
1-inch	-	-	100	100	-	-
3/4-inch	50-90	<b>60-90</b>	-	70-98	100	100
1/2-inch	-	-	-	-	-	70-98
No. 4	25-50	<b>30-55</b>	30-60	36-60	40-75	44-70
No. 8	-	<b>22-43</b>	-	25-47	-	30-54
No. 30	-	<b>11-27</b>	-	12-31	-	15-34
No. 40	5-25	-	5-30	-	5-35	-
No. 200	2-15	<b>3-15</b>	3-15	3-15	2-15	3-15

- 1205 - Crushed rock material retained on the No. 4 sieve shall have a percentage of loss of not more than 35 at 500 revolutions, as determined by AASHTO T 96.
- 1206 - Crushed rock material shall show a durability value of not less than 35 as determined by AASHTO T210.

**TIMBER SALE ROAD SPECIFICATIONS**

---

- 1207a - That portion of crushed rock material passing No. 4 sieve, including blending filler, shall have a sand equivalent of not less than 35, as determined by AASHTO T 176, except where that portion exhibits a sand equivalence of less than 35, the aggregate will be accepted if it complies with the additional requirement as follows:

TABLE 1207a

Sand Equivalent	Percent Passing #200 Sieve AASHTO T 27
34	9
33	8
32	7
31	6
30	5
29 or less	4

- 1208 - If additional binder or filler material is necessary to meet the grading or plasticity requirements or for satisfactory bonding of the material, it shall be uniformly blended with the crushed rock material at the crushing and screening plant prior to placing on the road, unless otherwise agreed. The material for such purposes shall be obtained from sources approved by the Authorized Officer and shall be free from stones, vegetative matter, and other deleterious materials.
- 1208a - Each layer of crushed rock material shall be thoroughly mixed on the roadbed by alternately blading, to full depth, until a uniform mixture has been obtained. The mixture shall then be spread to full width. When completed, the spreading shall produce a surface which is smooth, presents uniform shoulder lines, and conforms to the specified cross section.
- 1209 - Shaping and compacting of roadbed and/or base course shall be completed and approved in writing, prior to placing crushed rock material, in accordance to the requirements of Subsection 500 for placing on the roadbed and Subsections 900 for placing on the base course.
- 1210 - Crushed rock material conforming to the requirements of these specifications shall be placed on the approved roadbed and base course in accordance with these specifications and conforming to the lines, grades, dimensions, and typical cross sections shown on the plans and staked on the ground. Compacted layers shall not exceed 4 inches in depth. When more than one layer is required, each shall be shaped, processed, compacted, and approved in writing by the Authorized Officer

## **TIMBER SALE ROAD SPECIFICATIONS**

---

- before the succeeding layer is placed. Irregularities or depressions that develop during compaction of the top layer shall be corrected by loosening the material at these places and then adding or removing crushed rock material until the surface is smooth and uniform.
- 1210a - Crushed rock material used to repair or reinforce soft, muddy, frozen, yielding, or rutted roadbed shall not be construed as surfacing required by this specification.
- 1212 - Each layer of crushed rock material placed, processed, and shaped as specified shall be moistened or dried to a uniform moisture content suitable for maximum compaction and compacted to full width by compacting equipment conforming to the requirements of Subsections 103f, 103g, 103h, or 103i. Minimum compaction shall be 6 passes over each full-width layer, or fraction thereof.

### **SLOPE PROTECTION - 1400**

- 1401 - This work shall consist of furnishing, hauling, and placing stone materials for slope protection structures and splash pads (energy dissipaters) in accordance with these specifications and conforming to the lines, grades, dimensions, and typical cross-sections shown on the plans.
- 1402 - Stone material shall consist of hard angular quarry rock of such quality that it will not disintegrate on exposure to water or weathering, and shall be graded in accordance with these specifications.

**TIMBER SALE ROAD SPECIFICATIONS**

---

*NOTE: Guide for relation between volume, size and weight. (175 lbs./cu./ft.):*

<i>Volume/ Cubic Foot</i>	<i>Average Dimension in inches</i>	<i>Approximate Weight in Pounds</i>
<i>12</i>	<i>27.5 x 27.5 x 27.5</i>	<i>2100</i>
<i>6</i>	<i>21.8 x 21.8 x 21.8</i>	<i>1050</i>
<i>4</i>	<i>19.1 x 19.1 x 19.1</i>	<i>700</i>
<i>3</i>	<i>17.3 x 17.3 x 17.3</i>	<i>525</i>
<i>1</i>	<i>12.0 x 12.0 x 12.0</i>	<i>175</i>
<i>2/3</i>	<i>10.5 x 12.0 x 12.0</i>	<i>120</i>
<i>1/2</i>	<i>9.5 x 9.5 x 9.5</i>	<i>88</i>
<i>1/3</i>	<i>8.3 x 8.3 x 8.3</i>	<i>60</i>
<i>1/4</i>	<i>7.6 x 7.6 x 7.6</i>	<i>44</i>
<i>1/6</i>	<i>6.6 x 6.6 x 6.6</i>	<i>30</i>
<i>1/8</i>	<i>6.0 x 6.0 x 6.0</i>	<i>22</i>
<i>1/100</i>	<i>2.6 x 2.6 x 2.6</i>	<i>2</i>

- 1404 - The material shall be well graded from the smallest to the maximum size specified. Stones smaller than the specified 10 percent size shall consist of spalls and fine rock fragments so distributed as to provide a stable compact mass.
  
- 1405 - Rip rap shall conform to the following gradations:

**TIMBER SALE ROAD SPECIFICATIONS**

---

TABLE 1405<sup>1</sup>

Class	Range of Intermediate Dimensions <sup>2</sup> (inches)	Range of Rock Mass <sup>3</sup> (pounds)	% of Rock Equal or Smaller by Count
0	6-8	18-42	100
	5-6	10-18	85
	2-5	1-10	50
	0-2	0-1	15
1	9-15	59-270	100
	7-11	28-110	85
	5-8	10-42	50
	3-6	2-18	15
2	15-21	270-750	100
	11-15	110-270	85
	8-11	42-110	50
	6-8	10-42	15
3	21-27	750-1600	100
	15-19	270-560	85
	11-14	110-220	50
	8-10	42-81	15
4	27-33	1600-2900	100
	19-23	560-990	85
	14-17	220-400	50
	9-12	59-140	15

<sup>1</sup>Gradation includes spalls and rock fragments to provide a stable, dense mass.

<sup>2</sup>The intermediate dimension is the longest straight-line distance across the rock that is perpendicular to the rock's longest axis on the rock face with the largest projection plane.

<sup>3</sup>Rock mass is based on a specific gravity of 2.65 (165#/cu.ft.) and 85 percent of the cubic volume as calculated using the intermediate dimension.

---

**TIMBER SALE ROAD SPECIFICATIONS**

---

- 1405a - Stone materials shall show a durability value of not less than 50 as determined by AASHTO T 210.
- 1405b - Stone materials shall conform to a minimum apparent specific gravity of 2.50 and a maximum absorption of 4.2 percent as determined by AASHTO T 85.
- 1406 - The placement of slope protection stones by the end dumping method shall be conducted to prevent the stones from escaping beyond the embankment toe.
- 1407 - Determination of the acceptability of the slope protection material gradation will be through visual inspection and physical measurements by the Authorized Officer.

**EROSION CONTROL - 1700**

- 1701 - This work shall consist of measures to control soil erosion or water pollution during the construction operation through the use of berms, dikes, dams, sediment basins, fiber mats, netting, gravel, mulches, grasses, slope drains, and other erosion control devices or methods in accordance with these specifications and conforming to the lines, grades, dimensions and typical cross sections shown on the plans.
- 1704 - The erosion control provisions specified under this Subsection shall be coordinated with the Soil Stabilization requirements of Section 1800.
- 1705 - The surface area of erodible earth material exposed at any one time by clearing and grubbing shall not exceed 21,780 square feet (0.50 acres) after October 15 without prior approval by the Authorized Officer.
- 1706 - The surface area of erodible earth material exposed at one time by excavation, borrow, or fill within the right-of-way shall not exceed 21,780 square feet (0.50 acres) after October 15 without prior approval by the Authorized Officer.

**TIMBER SALE ROAD SPECIFICATIONS**

---

1707 - Completed and partially completed segments of the road at the following location:

Road No.	From M.P.	To M.P.
32-5-10.01 B	0.00	0.21
TR 03-14	0.00	0.13
TR 05-08	0.00	0.23
TR 09-05	0.00	0.25
TR 17-02	0.00	0.33
TR 17-15	0.00	0.22
TR 31-02	0.00	0.27

to be carried over the winter and early spring periods shall be stabilized by seeding and mulching in accordance with Section 1800.

1708 - Newly constructed roads to be carried over the winter period, shall be blocked to vehicular traffic.

1708a - Road segments not completed during dry weather periods shall be winterized, by providing a well-drained roadway using water bars, maintaining drainage, and performing additional measures necessary to minimize erosion and other damage to the roadway, as directed by the Authorized Officer. Portions of roads not having surface rock in place will be blocked or barricaded to prevent vehicular traffic.

1711 - The Purchaser shall construct energy dissipators (splash pads) for pipe culverts conforming to the requirements and details shown on the respective exhibits and on the plans.

**SOIL STABILIZATION – 1800**

1801 - This work shall consist of seeding and mulching on designated cut, fill, borrow, disposal, and special areas in accordance with these specifications. This work is required for road acceptance under Section 18 of this contract.

1802 - Soil stabilization work consisting of seeding and mulching shall be performed on existing roads and designated locations (culvert replacements and installations) in accordance with these specifications at the locations specified in the worklist.

## **TIMBER SALE ROAD SPECIFICATIONS**

---

1802a - Soil stabilization work consisting of seeding and mulching shall be performed on new road construction, landings, disturbed areas, and disposal sites in accordance with these specifications and as shown on the plans.

1803 - Soil stabilization work as specified under Subsections 1802 and 1802a shall be performed during the following seasonal periods:

From: August 1	To: October 15 (of the same year )
----------------	------------------------------------

If soil stabilization of disturbed areas is not completed by the specified fall date, the Purchaser shall treat disturbed areas in accordance with Subsection 1707 and then complete the requirements of Section 1800 the next construction season. The Authorized Officer may modify the above seasonal dates to conform to existing weather conditions and changes in the construction schedule.

1803a - The Purchaser shall begin soil stabilization work within 10 days of the starting work date when notified by the Authorized Officer.

1806a - Additional soil stabilization work consisting of seeding and mulching, may be required at the option of the Authorized Officer. Providing the additional stabilization is not due to Purchaser negligence as specified in Sec. 12 of the contract, a reduction in the total purchased price shall be made to offset the cost of furnishing and applying such additional stabilization material. Cost shall be based upon the unit price set forth in the current BLM Timber Appraisal Production Cost Schedule.

1808 - Mulch materials conforming to the requirements of Subsection 1808a shall be furnished by the Purchaser in the amounts specified under Subsection 1811 and applied in accordance with Subsection 1812.

1808a - Straw mulch shall be certified weed free from commercial grain fields and native grass fields. Straw mulch shall be from oats, wheat, rye, or other approved grain crops and shall be free from, mold, or other objectionable material. Straw mulch shall be in an air-dry condition and suitable for placement.

1809 - Mulch material shall be delivered to the work area in a dry state. Material found to be wet will not be accepted. Material to be used in the mulching operation may be stockpiled along the road designated for treatment provided that it is maintained in a dry state and has the approval of the Authorized Officer.

## **TIMBER SALE ROAD SPECIFICATIONS**

---

- 1810 - Bulk mulching material required under these specifications shall be delivered to the work area bound either by twine, string or hemp rope. Wire binding will not be permitted.
  
- 1812 - The Purchaser shall furnish and apply to the area designated for treatment as shown on the plans and as specified under Subsections 1802 and 1806a, a mixture of grass seed and mulch, material at the application rate to be determined by the Authorized Officer based on visual observation of trial applications.  
  
Mulches shall be spread/placed in treatment areas to a depth of 2 inches to allow seed germination or as directed by the Authorized Officer. Treatment area will be covered evenly and completely. Mulch can be broadcast onto the soil surface by hand or with hand/mechanical operated spreaders.
  
- 1814 - The Purchaser may reduce the application rate on partially covered slopes and refrain from application on areas already well stocked with grass or on rock surfaces as determined by the Authorized Officer.
  
- 1815 - The seed and mulch materials shall be placed by the dry method in accordance with the requirements set forth in Subsection 1815b.
  
- 1815b - Dry Method - Blowers, mechanical seeders, seed drills, landscape seeders, cultipaker seeders, fertilizer spreaders, or other approved mechanical seeding equipment may be used when seed and fertilizer are to be applied in dry form.
  
- 1819 - The Purchaser shall notify the Authorized Officer at least 3 days in advance of date he intends to commence the specified soil stabilization work.
  
- 1821 - Mulch that collects at the end of culverts or accumulates to excessive depths on the slopes shall be evenly spread by hand methods, as directed by the Authorized Officer.
  
- 1822 - No materials shall be applied when wind velocities would prevent a uniform application of the mix or slurry or when winds would drift the mix or slurry spray outside of the designated treatment area.
  
- 1824 - Twine, rope, sacks, and other debris resulting from the soil-stabilization operation shall be picked up and disposed of to the satisfaction of the Authorized Officer.

---

## TIMBER SALE ROAD SPECIFICATIONS

---

### ROADSIDE BRUSHING - 2100

- 2101 - This work shall consist of the removal of vegetation from the road prism - variable distance, and inside curves in accordance with these specifications and conforming to the lines, grades, dimensions, and typical cross sections shown on the Roadside Brushing Detail of this exhibit, at designated locations as shown in the plans.
- 2102 - Roadside brushing may be performed mechanically with self-powered, self-propelled equipment and/or manually with hand tools, including chain saws.
- 2103 - Vegetation cut manually and/or mechanically less than 6 inches in diameter when measured at D.B.H. shall be cut to a maximum height of 3 inches above the ground surface or above obstructions such as rocks or stumps on cut and fill slopes and all limbs below the 2 inch area will be severed from the trunk.
- 2103a - Vegetation shall be cut and removed from the road bed between the outside shoulders and the ditch centerline and such vegetation shall be cut to a maximum height of 1 inch above the ground and running surface. Limbs below the 1 inch area will be severed from the trunk. Sharp pointed ends will not be permitted. Cuts shall be parallel to the ground line or running surface.
- 2104 - Trees in excess of 6 inches in diameter at D.B.H. shall be delimbed, so that no limbs extend into the treated area or over the roadbed to a height of 14 feet above the running surface of the roadway on cut and fill slopes, within the road prism-variable distance. Limbs shall be cut to within 1 inch of the trunk to produce a smooth vertical face. Removal of trees larger than 6 inches in diameter for sight distance or safety may be directed by the Authorized Officer.
- 2105 - Vegetation that is outside of the road prism-variable distance that protrudes into the road prism and within 14 feet in elevation above the running surface shall be cut, to within 1 inches of the trunk to produce a smooth vertical face.
- 2106 - Vegetative growth capable of growing 1 foot in height or higher shall be cut, within the road prism-variable distance or as directed by the Authorized Officer.
- 2107 - Inside curves shall be brushed out for a sight distance of 200 feet chord distance or a middle ordinate distance of 25 feet, whichever is achieved first. Overhanging limbs and vegetation in excess of 1 foot in height, shall be cut within these areas.

## **TIMBER SALE ROAD SPECIFICATIONS**

---

- 2108 - Self-propelled equipment shall not be permitted on cut and fill slopes or in ditches.
- 2109 - Debris resulting from this operation shall be scattered (unless otherwise noted in the work list) downslope from the roadway. Debris shall not be allowed to accumulate in concentrations. Debris in excess of 1 foot in length and 2 inches in diameter shall not be allowed to remain on cut slopes, ditches, roadways or water courses, or as directed by the Authorized Officer.
- 2110 - Vegetation 6 inches and smaller in diameter shall be chipped where indicated in the work list. Chips shall be scattered downslope from the roadway. Vegetation over 6 inches in diameter shall be disposed of by direction of the Authorized Officer.
- 2114 - Sections of roadway to have vegetation removed will be marked at start and stop points with red-topped painted stakes.
- 2115 - Mechanical brush cutters shall not be operated when there are people and occupied vehicles within 400 feet of the immediate operating area.
- 2116 - Traffic warning signs shall be required at each end of the work area. Signs shall meet the requirements of the Manual on Uniform Traffic Devices.



## **ROAD MAINTENANCE SPECIFICATIONS**

---

### **ROAD MAINTENANCE SPECIFICATIONS TABLE OF CONTENTS**

<b>SECTION</b>	<b>DESCRIPTION</b>
3000	General
3100	Operational Maintenance
3200	Seasonal Maintenance
3300	Final Maintenance
3400	Other Maintenance
3500	Decommissioning

**ROAD MAINTENANCE SPECIFICATIONS**

**GENERAL - 3000**

3001 The Purchaser shall be required to maintain all roads listed and/or as shown on the Exhibit D2 map of this contract in accordance with Sections 3000, 3100, 3200, 3300, and 3400 of this exhibit.

Road No. and Segment	Length Miles Used	Ownership	Road Surface Type	Maintenance Responsibility
32-5-3.01	0.49	BLM	Aggregate	Purchaser
32-5-3.02	0.53	BLM	Aggregate	Purchaser
32-5-3.06	0.10	BLM	Natural	Purchaser
32-5-5.01	0.33	BLM	Aggregate	Purchaser
32-5-7.00 A	0.59	Private	Aggregate	Purchaser
32-5-7.01	0.21	BLM	Aggregate	Purchaser
32-5-8.00	2.09	BLM	Aggregate	Purchaser
32-5-8.01	1.05	BLM	Aggregate	Purchaser
32-5-8.02	0.18	BLM	Aggregate	Purchaser
32-5-8.04	0.17	BLM	Natural	Purchaser
32-5-9.00	2.49	BLM	Aggregate	Purchaser
32-5-9.01	0.62	BLM	Aggregate	Purchaser
32-5-10.00 A	0.73	BLM	Aggregate	Purchaser
32-5-10.01 A	0.70	Private	Natural	Purchaser
32-5-10.01 B	0.21	BLM	Natural	Purchaser
32-5-10.02 A	0.38	Private	Natural	Purchaser
32-5-10.02 B	0.47	Private	Natural	Purchaser
32-5-17.00 A	1.74	BLM	Aggregate	Purchaser
32-5-17.00 B	0.56	BLM	Aggregate	Purchaser
32-5-17.01	0.32	BLM	Aggregate	Purchaser
32-5-17.02	0.22	BLM	Aggregate	Purchaser
32-5-20.00 A	0.62	BLM	Bituminous	BLM

**ROAD MAINTENANCE SPECIFICATIONS**

Road No. and Segment	Length Miles Used	Ownership	Road Surface Type	Maintenance Responsibility
32-5-20.00 B	1.94	BLM	Aggregate	Purchaser
32-5-20.00 C	1.40	BLM	Aggregate	Purchaser
32-5-30.00 A	0.66	BLM	Aggregate	Purchaser
32-5-30.00 B	0.33	BLM	Aggregate	Purchaser
32-5-30.01	0.84	BLM	Aggregate	Purchaser
32-5-30.02	0.64	BLM	Aggregate	Purchaser
32-5-31.04	0.35	BLM	Aggregate	Purchaser
Windy Creek Rd	1.84	Private	Aggregate	Purchaser

- 3001a     The Purchaser shall be required to provide maintenance on roads in accordance with Subsections 3403 and 3404.
  
- 3002     The Purchaser shall maintain the cross section of existing dirt or graveled roads to the existing geometric standards.
  
- 3003     The minimum required maintenance on any roads shall include the provisions specified in Subsections 3101, 3104, and 3105.
  
- 3004     The Purchaser shall be responsible for providing timely maintenance and cleanup on any roads with logging units substantially completed prior to moving operations to other roads. The maximum length of non-maintained or non-cleanup of the road prism shall not exceed the sum of one 1 mile at any time. Release of maintenance requirements may be granted, upon written request, when the conditions specified in Sections 3300 and 3400 are met satisfactorily.

**OPERATIONAL MAINTENANCE - 3100**

- 3101     The Purchaser shall blade and shape the road surface and shoulders with a motor grader. Banks shall not be undercut. Back blading with tractors or similar equipment will be allowed only around landings and other areas when approved by the Authorized Officer.
  
- 3104     The purchaser shall perform other road cleanup including removal of debris, fallen timber, bank slough, and slides which can practicably be accomplished by a motor grader, rubber tired front end bucket loader, rubber tired backhoe or comparable equipment, and by the use of hand tools.
  
- 3104a     Removal of bank slough and slide material includes placement of material at the nearest designated, suitable disposal site where material cannot erode into streams, lakes, or reservoirs or

---

**ROAD MAINTENANCE SPECIFICATIONS**

---

cause undue damage to road fill slopes which have been planted or mulched to control soil erosion as directed by the Authorized Officer.

- 3104b The Purchaser shall be responsible for removal of all slides or slough, up to fifteen station yards in quantity, at any one site. This work includes unlimited multiple sites on all roads required to be maintained by the purchaser.

Prior to removal of any slough or slide material exceeding fifteen station yards at any one site, the Purchaser and the Authorized Officer or their Authorized Representatives shall agree in writing, in the field, to the quantity of material, method of disposal, and the disposal site. Work may commence immediately after agreement.

Upon completion of agreed upon work, a reduction in timber sale purchase price will be made to offset the cost of the work, based on current BLM Road Cost Guide. Adjustments in purchase price for completed work shall be made as necessary and no less than once per year when actual work is ongoing.

- 3105 The Purchaser shall be responsible for maintaining normal flow in drainage structures. This includes cleaning out drainage ditches, catch basins, clearing pipe inverts of sediment and other debris lodged in the barrel of the pipe, and maintaining water dips and water-bars using equipment specified in Subsection 3104 and other culvert cleaning and flushing equipment.

- 3106 The Purchaser shall be responsible for repair and replacement of all materials eroded from road shoulders and fill slopes, up to fifteen station yards in quantity, at any one site. This work includes unlimited multiple sites on all roads required to be maintained by the Purchaser. Prior to repair and replacement of eroded material exceeding fifteen station yards at any one site, the Purchaser and the Authorized Officer or their Authorized Representatives shall agree in writing, in the field, to the quantity of material, borrow source and method of repair. Work may commence immediately after agreement.

Upon completion of agreed upon work, a reduction in timber sale purchase price will be made to offset the cost of the work based upon current BLM Road Cost Guide. Adjustments in purchase price for completed work shall be made as necessary and no less than once per year when actual work is ongoing.

- 3107 The Purchaser shall cut or trim trees and brush which obstructs vision or prevents the safe passage of traffic along the traveled way when directed by the Authorized Officer.

The Purchaser shall also cut trees or brush encroaching on the road prism that are a result of his activities or winter damage during the contract period. Disposal of such vegetative material shall be by scattering below the road in accordance with Section 2100 of Exhibit C15.

---

**ROAD MAINTENANCE SPECIFICATIONS**

---

- 3108 The Purchaser shall avoid fouling gravel or bituminous surfaces through covering with earth and debris from side ditches, slides or other sources. The Purchaser shall also avoid blading surfacing material off the running surface of the roadway. Skidding of logs on the roadway in or outside designated logging units is not authorized without prior written approval by the Authorized Officer. Repair required caused by such skidding activity is not considered maintenance and shall be repaired at the Purchaser's expense.
- 3108a The Purchaser shall perform logging operations on gravel and/or bituminous roadways only where the locations have been marked on the ground and/or approved by the Authorized Officer. (Repair of the roads is not considered maintenance and shall be repaired at the Purchaser's expense.)

**SEASONAL MAINTENANCE - 3200**

- 3201 The Purchaser shall perform preventative maintenance at the end of Purchaser's hauling each season and during non-hauling periods which occur between other operations on the contract area. This includes requirements specified in Section 3100.
- 3202 The purchaser shall perform and complete maintenance specified in Sections 3000, 3100, and 3200 on all roads maintained by him, prior to October 1 each year, except as specified in Subsection 3203, after initial commencement of construction or logging operations. Thereafter, all roads shall have continuous preventive maintenance and road cleanup until suspension of seasonal operations. This includes all roads used and not used during the proceeding operating seasons.
- 3203 The Purchaser shall complete road cleanup and maintenance, as specified in Section 3100, at the completion of logging operations on any roads located in an area separate from the area where logging activities will resume.
- 3204 The Purchaser shall be responsible for performing post storm inspections and maintenance during the winter season to minimize erosion and potential road or watershed damage.

**FINAL MAINTENANCE - 3300**

- 3301 The Purchaser shall complete final maintenance and/or damage repairs on all roads used under terms of their contract within thirty 30 calendar days following the completion of hauling and in accordance with Sec. 16(b) of this contract. This work shall include any maintenance and/or damage repairs specified in Sections 3000, 3100, and 3200 necessary to meet the conditions specified in Subsection 3002 and shall be executed in accordance with Subsection 3302 of this section.

The Authorized Officer may grant acceptance of Purchaser's maintenance responsibility in part

---

## ROAD MAINTENANCE SPECIFICATIONS

---

where certain individual roads or road segments are no longer of any use to the Purchaser's remaining removal operations, providing that all contract requirements as specified under Sec. 16(b), Special Provisions Sections 3000, 3100, 3200 and 3300 of the maintenance specifications have been completed and a relinquishment of cutting and removal rights on cutting units tributary to these roads is signed by the Purchaser. Request for partial acceptance must be submitted in writing by the Purchaser.

- 3302 The Purchaser shall perform final road maintenance only when weather or soil moisture conditions are suitable for normal maintenance equipment operations as determined by the Authorized Officer.

If final maintenance is delayed after the date required in Subsection 3301 of this contract by adverse soil moisture or unsuitable equipment operating conditions, the Purchaser will be notified by the Authorized Officer when soil moisture and equipment operating conditions are suitable. The Purchaser shall then be required to complete final maintenance within 30 days.

### OTHER MAINTENANCE – 3400

- 3401 The Purchaser shall repair any damage to road surfaces that was specified under Subsection 3108 and 3108a. This repair includes restoring the roadway to the designed standard and replacement of surfacing with approved surface material. This repair is not limited to use of equipment specified in Subsection 3104.

- 3402 The Purchaser shall be permitted to remove ice and snow from roads authorized for use under this contract only when prior written approval has been secured from the Authorized Officer. The Purchaser shall submit a written request for permission to remove ice and snow in advance of the date operations are to begin.

Upon receiving written authorization for ice or snow removal, the Purchaser will perform the work according to the conditions and equipment requirements set forth in the authorization.

- 3403 The Purchaser shall be required to furnish and apply non-saline water during dry hauling periods, when directed by the Authorized Officer, for the purpose of laying dust and to prevent loss of surface material. The first application of water shall be made at the rate of one-half gallon per yd<sup>2</sup> of road surface traveled. Subsequent applications shall be made for each 40 MBF of timber or 120 yds<sup>3</sup> of rock hauled. Subsequent watering may be done at a rate less than one-half gallon per yd<sup>2</sup> when a specified lesser rate is approved by the Authorized Officer.

The following roads shall be watered:

**ROAD MAINTENANCE SPECIFICATIONS**

---

Road Number	From Sta./M.P.	to Sta./M.P.
32-5-17.0 A	0.00	0.10
32-5-17.0 A	0.64	0.79
32-5-20.0 B	0.62	0.87

The Purchaser shall secure any necessary water permits and pay all required water fees for use of the water sources selected by the Purchaser and approved by the Authorized Officer.

During drought periods when the transportation of water from the source to the roads noted above exceeds 15 miles, a reduction shall be made in the total purchase price to reflect the additional haul or the substitution of other acceptable dust palliatives in lieu of watering based on equipment rental rates from the current BLM Road Cost Guide.

3403a

During dry hauling conditions when watering is not required, the Purchaser shall reduce hauling speeds or restrict the number of loads hauled to reduce dust as directed by the Authorized Officer on the following roads:

Road Number	From Sta./M.P.	to Sta./M.P.
32-5-17.0 A	0.00	0.10
32-5-17.0 A	0.64	0.79
32-5-20.0 B	0.62	0.87

Adjustments to the above schedules may be made by the Authorized Officer at his option as hauling conditions improve. The Purchaser, at his option and expense, may elect to substitute watering or other dust palliatives in lieu of the above hauling requirements provided that written approval is received from the Authorized Officer. Such authorization shall include the approval of product specifications for the application and the product to be used.

**DECOMMISSIONING – 3500**

3501

Decommissioning (Long Term Closure – Subsection 3520 or Full Decommission – Subsection 3525) is required for road acceptance under Section 18 of this contract.

3504

Decommissioning work shall be completed after timber extraction and road use for unit maintenance activities associated with this timber sale. All work shall be performed during the dry season before October 15<sup>th</sup>.

## ROAD MAINTENANCE SPECIFICATIONS

---

- 3506 Stockpiled slash shall be used to protect exposed areas created by the Purchaser's operations described in these sections. Slash shall be uniformly spread and placed without bunching. The operation shall produce a dense, uniform mat. All slash stockpiles created by the purchaser shall be utilized for decommissioning operations.
- 3507 Culverts not designated as salvage by the Authorized Officer for the Government shall become the property of the Purchaser. The Purchaser shall be responsible for disposal of materials in a legal manner and for payment of any fees required. Sale of material on site is not allowed unless authorized in writing by the Authorized Officer.
- 3508 Protect areas with camouflaging and soil stabilization from damage by Purchaser traffic or construction equipment. Damaged areas shall be repaired by the Purchaser.
- 3509 Barricades shall be installed across full width of roadway at locations designated in the specifications and Exhibit D4. Barricades shall be constructed conforming to the lines, grades, dimensions and typical details as shown on Exhibit D7.
- Existing barricades removed during timber operations shall be replaced immediately after use. For activities that are not finished in one dry season, barricades shall be re-installed before the wet season, October 15<sup>th</sup>.
- 3513 Water bars shall be installed across full width of roadway at spacing shown in the specifications and Exhibit D4. Water bars shall be constructed conforming to the lines, grades, dimensions and typical details as shown on Exhibit D7. No water bar will be installed closer than 50 feet to a draw crossing.
- 3514 Protection of exposed surfaces shall be accomplished by placement of soil stabilization material in accordance with Section 1800 and placement of slash described in Subsection 3506 on designated roadways, disturbed areas, landings, and other areas disturbed by the purchaser's operations in accordance with these specifications and as shown in the plans.
- 3520 Long Term Closure of roads shall consist of all or part of the following treatments:
- a. Construct water bars along entire length of road at spacing shown in the specifications, or as staked or directed by the Authorized Officer's Representative.
  - b. The Purchaser shall Camouflage the road entrance for a minimum of 100 feet or to the first curve or hillcrest. Camouflaged roads shall consist of using boulders, brush, dead material, stumps, and other debris to disguise the entire length of the road prism to the extent possible.

No live trees should be used without approval by the Authorized Officer.

**ROAD MAINTENANCE SPECIFICATIONS**

- c. An earth berm or equivalent barricade shall be constructed near the beginning of road. The final locations will be staked by the Authorized Officer’s Representative.

3521 Long Term Closure shall be performed on existing roads in accordance with these specifications, and as shown on the plans at the following locations:

Road No or Site	Treatment
32-5-3.06	Waterbar, Barricade, Camouflage
32-5-17.02	Waterbar, Barricade, Camouflage

3525 Full Decommissioning of roads shall consist of all or part of the following treatments:

- a. Subsoiling shall be done using mechanical treatment to de-compact road surface to a depth 12 to 18 inches or to a point where 10 inch diameter stones are the dominant substrate (whichever is shallower). Where it is determined by the Authorized Officer that decompaction may cause unacceptable damage to the root systems of residual trees along a majority of the road, decompaction may be intermittent, or scarification may be used instead. Woody debris, brush, stumps, boulders, and other debris shall be placed along the roads entire length as determined by availability of materials to provide ground cover and discourage use. No live trees shall be cut or used without approval of the Authorized Officer.

Where multiple entrances exist, the work shall include obscuring all road entrances. Ditchlines at intersecting roads shall be restored. The Purchaser shall use soil, boulders, brush, dead material, stumps, and other debris to disguise the road prism to the extent possible.

- b. All culverts shall be removed from road for its entire length. Excavated culverts shall be left open to drain and have slopes of 1 1/2:1. Where draw culverts are removed the grade of the channel shall be restored to match existing stream. Culverts not designated as salvage for the Government shall become the property of the Contractor. The Contractor shall be responsible for legally disposing of material.
- c. Construct water bars along entire length of road at spacing shown in the specifications, or as staked or directed by the Authorized Officer’s Representative.
- d. The Purchaser shall Camouflaged the road entrance for a minimum of 100 feet or to the first curve or hillcrest. Camouflaged roads shall consist of using boulders, brush, dead material, stumps, and other debris to disguise the entire length of the road prism to the extent possible.

No live trees should be used without approval by the Authorized Officer.

**ROAD MAINTENANCE SPECIFICATIONS**

---

- e. An earth berm or equivalent barricade shall be constructed near the beginning of road. The final locations will be staked by the Authorized Officer’s Representative.

3526 Full Decommission shall be performed on existing roads in accordance with these specifications, and as shown on the plans at the following locations:

Road No or Site	Treatment
TR 03-14	Subsoil, Waterbars, Barricade, Camouflage, Seed and Mulch
TR 05-08	Subsoil, Waterbars, Barricade, Camouflage, Seed and Mulch
TR 09-05	Subsoil, Waterbars, Barricade, Camouflage, Seed and Mulch
TR 17-02	Subsoil, Waterbars, Barricade, Camouflage, Seed and Mulch
TR 17-15	Subsoil, Waterbars, Barricade, Camouflage, Seed and Mulch
TR 31-02	Subsoil, Waterbars, Barricade, Camouflage, Seed and Mulch



# EXHIBIT D2-2

## LEGEND

### Land Ownership

-  BLM
-  Non-BLM
-  Timber Units
-  Roadside Management

### Roads - Surface Type


-  Bituminous
-  Aggregate
-  Natural
-  Unknown

### Maintenance Responsibility

-  BLM
-  Purchaser

### Road Closures

-  Gate
-  Barricade (trees/dirt)



**ALWAYS  
THINK  
SAFETY**

Rev No.	Description	Date	Approval
UNITED STATES DEPARTMENT OF THE INTERIOR BUREAU OF LAND MANAGEMENT MEDFORD DISTRICT - MEDFORD, OREGON			
<b>BLOWN FORTUNE TIMBER SALE                  ROAD MAINTENANCE MAP</b>			
DRAFTED BY: BLM			
DATE: FEB 2020		SHEET: 2 OF 4	

# EXHIBIT D2-3

## LEGEND

### Land Ownership

-  BLM
-  Non-BLM
-  Timber Units
-  Roadside Management

### Roads - Surface Type


-  Bituminous
-  Aggregate
-  Natural
-  Unknown

### Maintenance Responsibility

-  BLM Maintenance
-  Purchaser Maintenance

### Road Closures

-  Gate
-  Barricade (trees/dirt)



**ALWAYS  
THINK  
SAFETY**

Rev No.	Description	Date	Approval
UNITED STATES DEPARTMENT OF THE INTERIOR BUREAU OF LAND MANAGEMENT MEDFORD DISTRICT - MEDFORD, OREGON			
<b>BLOWN FORTUNE TIMBER SALE                  ROAD MAINTENANCE MAP</b>			
DRAFTED BY: BLM			
DATE: FEB 2020		SHEET: 3 OF 4	

# EXHIBIT D2-4

## LEGEND

### Land Ownership

-  BLM
-  Non-BLM
-  Timber Units
-  Roadside Management

### Roads - Surface Type


-  Bituminous
-  Aggregate
-  Natural
-  Unknown

### Maintenance Responsibility

-  Purchaser Maintenance
-  BLM Maintenance

### Road Closures

-  Gate
-  Barricade (trees/dirt)



**ALWAYS  
THINK  
SAFETY**



Rev No.	Description	Date	Approval
UNITED STATES DEPARTMENT OF THE INTERIOR BUREAU OF LAND MANAGEMENT MEDFORD DISTRICT - MEDFORD, OREGON			
<b>BLOWN FORTUNE TIMBER SALE</b> <b>ROAD MAINTENANCE MAP</b>			
DRAFTED BY: BLM			
DATE: FEB 2020		SHEET: 4 OF 4	

# EXHIBIT D3-1

## LEGEND

### Land Ownership

-  BLM
-  Non-BLM
-  Timber Units

### Roads - Surface Type


-  Bituminous
-  Aggregate
-  Natural
-  Unknown

### Haul Roads


-  BLM Maintenance
-  Purchaser Maintenance

### Road Decommissioning

-  Full Decommission
-  Long Term Closure



ALWAYS  
**THINK**  
SAFETY



Rev No.	Description	Date	Approval
UNITED STATES DEPARTMENT OF THE INTERIOR BUREAU OF LAND MANAGEMENT MEDFORD DISTRICT - MEDFORD, OREGON			
<b>BLOWN FORTUNE TIMBER SALE</b> <b>DECOMMISSIONING MAP</b>			
DRAFTED BY: BLM			
DATE: FEB 2020		SHEET: 1 OF 6	

# EXHIBIT D3-2

## LEGEND

### Land Ownership

-  BLM
-  Non-BLM
-  Timber Units

### Roads - Surface Type


-  Bituminous
-  Aggregate
-  Natural
-  Unknown

### Haul Roads

-  BLM Maintenance
-  Purchaser Maintenance

### Road Decommissioning

-  Full Decommission



**ALWAYS  
THINK  
SAFETY**

Rev No.	Description	Date	Approval
UNITED STATES DEPARTMENT OF THE INTERIOR BUREAU OF LAND MANAGEMENT MEDFORD DISTRICT - MEDFORD, OREGON			
<b>BLOWN FORTUNE TIMBER SALE            DECOMMISSIONING MAP</b>			
DRAFTED BY: BLM			
DATE: FEB 2020		SHEET: 2 OF 6	

# EXHIBIT D3-3

## LEGEND

### Land Ownership

-  BLM
-  Non-BLM
-  Timber Units

### Roads - Surface Type


-  Bituminous
-  Aggregate
-  Natural
-  Unknown

### Haul Roads

-  BLM Maintenance
-  Purchaser Maintenance

### Road Decommissioning

-  Full Decommission



Rev No.	Description	Date	Approval
UNITED STATES DEPARTMENT OF THE INTERIOR BUREAU OF LAND MANAGEMENT MEDFORD DISTRICT - MEDFORD, OREGON			
<b>BLOWN FORTUNE TIMBER SALE            DECOMMISSIONING MAP</b>			
DRAFTED BY: BLM			
DATE: FEB 2020		SHEET: 3 OF 6	

# EXHIBIT D3-4

## LEGEND

### Land Ownership

-  BLM
-  Non-BLM
-  Timber Units

### Roads - Surface Type


-  Bituminous
-  Aggregate
-  Natural
-  Unknown

### Haul Roads


-  BLM Maintenance
-  Purchaser Maintenance

### Road Decommissioning

-  Full Decommission



ALWAYS  
**THINK**  
SAFETY



Rev No.	Description	Date	Approval
UNITED STATES DEPARTMENT OF THE INTERIOR BUREAU OF LAND MANAGEMENT MEDFORD DISTRICT - MEDFORD, OREGON			
<b>BLOWN FORTUNE TIMBER SALE</b> <b>DECOMMISSIONING MAP</b>			
DRAFTED BY: BLM			
DATE: FEB 2020		SHEET: 4 OF 6	

# EXHIBIT D3-5

## LEGEND

- Land Ownership**
- BLM
  - Non-BLM
  - Timber Units

## Roads - Surface Type


- Bituminous
- Aggregate
- Natural
- Unknown

## Haul Roads

- ▲ BLM Maintenance
- Purchaser Maintenance

## Road Decommissioning

- Full Decommission
- ★ Long Term Closure



**ALWAYS  
THINK  
SAFETY**

Rev No.	Description	Date	Approval
UNITED STATES DEPARTMENT OF THE INTERIOR BUREAU OF LAND MANAGEMENT MEDFORD DISTRICT - MEDFORD, OREGON			
<b>BLOWN FORTUNE TIMBER SALE                  DECOMMISSIONING MAP</b>			
DRAFTED BY: BLM			
DATE: FEB 2020		SHEET: 5 OF 6	

# EXHIBIT D3-6

## LEGEND

### Land Ownership

-  BLM
-  Non-BLM
-  Timber Units

### Roads - Surface Type


-  Bituminous
-  Aggregate
-  Natural
-  Unknown

### Haul Roads

-  BLM Maintenance
-  Purchaser Maintenance

### Road Decommissioning

-  Full Decommission



**ALWAYS  
THINK  
SAFETY**

Rev No.	Description	Date	Approval
UNITED STATES DEPARTMENT OF THE INTERIOR BUREAU OF LAND MANAGEMENT MEDFORD DISTRICT - MEDFORD, OREGON			
<b>BLOWN FORTUNE TIMBER SALE            DECOMMISSIONING MAP</b>			
DRAFTED BY: BLM			
DATE: FEB 2020		SHEET: 6 OF 6	

## Exhibit D4

Sale Name: Blown Fortune

Page 1 of 3

### Roads Decommissioning Work List

#### Definitions:

AGG = Aggregate

BST = Bituminous

NAT = Natural or Native Surface

CMP = Corrugated Metal Pipe

Pvt = Private (Industry or Citizen)

Jct = Junction/Intersection

MP = Mile Post

STA = Station

CY = Cubic Yard

Seg = Segment

#### GENERAL DEFINITIONS:

**Full Decommission** = Full Decommissioning shall include removing temporary culverts, decompacting the surface to a depth of 12 to 18 inches (ripping, sub-soiling, or pitting), installing waterbars per the Water Bar Spacing by Erosion Class Table shown in Exhibit D7 unless otherwise noted in the work list, and camouflaging and barricading road entrances. All disturbed soils shall be seeded with approved native seed species and mulched with weed-free straw or approved native slash materials. Camouflaged entrances shall consist of logs, slash, boulders and other debris placed along road entrances for a minimum of 100 feet or to the first curve or hillcrest to discourage vehicle use per Exhibit D8.

**Long Term Closure** = Long Term Closure shall include installing waterbars per the Water Bar Spacing by Erosion Class Table shown in Exhibit D7 unless otherwise noted in the work list, stabilizing or removing fills on unstable areas, barricading the road entrance, camouflaging the road entrance, removing culverts (armor if needed), and seeding with approved native seed species and mulching with weed-free straw or approved native materials.

**Camouflaging** = Camouflaged entrances shall consist of logs, slash, boulders and others debris placed along road entrances for a minimum of 100 feet or to the first curve or hillcrest to discourage vehicle use. Detail in Exhibit D8.

**Barricade** = Barricade only.

#### 32-5-3.6 Road – Non System – NAT – Sub: 14Ft – Ditch: 0Ft – X-Sect: Outsloped

<u>MP</u>	<u>Description</u>
0.00	Jct w/ 32-5-3.1. Upon completion of log haul begin long term closure and entrance camouflage. See Exhibit D2 for map. See Exhibit D7 for barricade and water bar construction specifications.
0.01	Construct barricade.
0.04	Construct water bar.
0.06	Construct water bar.
0.08	Construct water bar.
0.10	Jct. w/ temporary road TR 03-07. End road long term closure.

#### 32-5-17.2 Road – Fortune 17 Spur – NAT – Sub: 14Ft – Ditch: 0Ft – X-Sect: Outsloped

<u>MP</u>	<u>Description</u>
0.00	Jct w/ 32-5-17.0. Upon completion of log haul begin long term closure and entrance camouflage. See Exhibit D2 for map. See Exhibit D7 for barricade and water bar construction specifications.
0.01	Construct barricade.

## Exhibit D4

Sale Name: Blown Fortune

Page 2 of 3

0.05	Construct water bar.
0.07	Construct water bar.
0.09	Construct water bar.
0.11	Construct water bar.
0.13	Construct water bar.
0.15	Construct water bar.
0.17	Construct water bar.
0.19	Construct water bar.
0.22	End road long term closure.

### TR 03-14 Temp Road – NAT – Sub: 14Ft – Ditch: 0Ft – X-Sect: Outsloped

<u>STA</u>	<u>Description</u>
0+00	Jct w/ 32-5-3.2. Begin temp route full decommissioning and entrance camouflage. See Exhibit D3 for map. See Exhibit D7 for barricade and water bar construction specifications.
0+40	Construct barricade.
1+80	Construct water bar.
2+80	Construct water bar.
3+80	Construct water bar.
5+80	Construct water bar.
6+92	End temp road full decommissioning.

### TR 05-08 Temp Road – NAT – Sub: 14Ft – Ditch: 0Ft – X-Sect: Outsloped

<u>STA</u>	<u>Description</u>
0+00	Jct w/ 32-5-20.0. Begin temp route full decommissioning and entrance camouflage. See Exhibit D3 for map. See Exhibit D7 for barricade and water bar construction specifications.
0+40	Construct barricade.
2+40	Construct water bar.
4+40	Construct water bar.
6+40	Construct water bar.
8+40	Construct water bar.
10+40	Construct water bar.
12+15	End temp road full decommissioning.

### TR 09-05 Temp Road – NAT – Sub: 14Ft – Ditch: 0Ft – X-Sect: Outsloped

<u>STA</u>	<u>Description</u>
0+00	Jct w/ 32-5-10.0. Begin temp route full decommissioning and entrance camouflage. See Exhibit D3 for map. See Exhibit D7 for barricade and water bar construction specifications.
0+40	Construct barricade.
1+40	Construct water bar.
2+40	Construct water bar.
3+40	Construct water bar.
4+40	Construct water bar.
6+40	Construct water bar.
8+40	Construct water bar.
10+40	Construct water bar.
13+20	End temp road full decommissioning.

## Exhibit D4

Sale Name: Blown Fortune

Page 3 of 3

### TR 17-02 Temp Road – NAT – Sub: 14Ft – Ditch: 0Ft – X-Sect: Outsloped

<u>STA</u>	<u>Description</u>
0+00	Jct w/ 32-5-8.1. Begin temp route full decommissioning and entrance camouflage. See Exhibit D3 for map. See Exhibit D7 for barricade and water bar construction specifications.
0+40	Construct barricade.
2+40	Construct water bar.
4+40	Construct water bar.
6+40	Construct water bar.
8+40	Construct water bar.
10+40	Construct water bar.
12+40	Construct water bar.
14+40	Construct water bar.
15+40	Construct water bar.
16+40	Construct water bar.
17+42	End temp road full decommissioning.

### TR 17-15 Temp Road – NAT – Sub: 14Ft – Ditch: 0Ft – X-Sect: Outsloped

<u>STA</u>	<u>Description</u>
0+00	Jct w/ 32-5-20.0. Begin temp route full decommissioning and entrance camouflage. See Exhibit D3 for map. See Exhibit D7 for barricade and water bar construction specifications.
0+40	Construct barricade.
2+40	Construct water bar.
4+40	Construct water bar.
6+40	Construct water bar.
7+40	Construct water bar.
8+40	Construct water bar.
8+45	Remove temporary HDPE culvert.
9+40	Construct water bar.
11+62	End temp road full decommissioning.

### TR 31-02 Temp Road – NAT – Sub: 14Ft – Ditch: 0Ft – X-Sect: Outsloped

<u>STA</u>	<u>Description</u>
0+00	Jct w/ 32-5-30.2. Begin temp route full decommissioning and entrance camouflage. See Exhibit D3 for map. See Exhibit D7 for barricade and water bar construction specifications.
0+40	Construct barricade.
2+40	Construct water bar.
3+40	Construct water bar.
4+40	Construct water bar.
6+40	Construct water bar.
7+40	Construct water bar.
8+40	Construct water bar.
10+40	Construct water bar.
11+40	Construct water bar.
12+40	Construct water bar.
14+26	End temp road full decommissioning.

# EXHIBIT D5-1

ROAD NUMBER	FROM		TO		LENGTH		MAINTENANCE RESPONSIBILITY			DUST ABATEMENT/ TRACKING	INSTALL EARTH/LOG BARRICADE	INSTALL MEGA-GATE	INSTALL WATER BARS	CAMOUFLAGE ROAD ENTRANCE (100 FT)	SUB-SOIL/ RIPPING/ DECOMPACT SUBGRADE	SOIL STABILIZATION (SEED & MULCH)
	MILE/STA	MILE/STA	MILE/STA	MILE/STA	MILE	MILE	BLM MAINTENANCE	PURCHASER MAINTENANCE	THIRD PARTY MAINTENANCE							
	MILE	STA	MILE	STA	MILE	MILE	MILE	MILE	MILE							
32-5-3.1	0.00	0.49	0.49	0.49	0.49											
32-5-3.2	0.00	0.53	0.53	0.53	0.53		0.49									
32-5-3.6	0.00	0.10	0.10	0.10	0.10		0.53									
32-5-5.1	0.00	0.33	0.33	0.33	0.33		0.10			1		3	1			
32-5-7.0 A	0.00	0.59	0.59	0.59	0.59		0.33									
32-5-7.1	0.00	0.21	0.21	0.21	0.21		0.59									
32-5-8.0	0.00	2.09	2.09	2.09	2.09		0.21									
32-5-8.1	0.00	1.05	1.05	1.05	1.05		2.09									
32-5-8.2	0.00	0.18	0.18	0.18	0.18		1.05									
32-5-8.4	0.00	0.17	0.17	0.17	0.17		0.18									
32-5-9.0	0.00	2.49	2.49	2.49	2.49		0.17									
32-5-9.1	0.00	0.62	0.62	0.62	0.62		2.49									
32-5-10.0 A	0.00	0.73	0.73	0.73	0.73		0.62									
32-5-10.1 A	0.00	0.70	0.70	0.70	0.70		0.73									
32-5-10.1 B	0.70	0.91	0.91	0.21	0.21		0.70									
32-5-10.2 A	0.00	0.38	0.38	0.38	0.38		0.21									
32-5-10.2 B	0.38	0.85	0.85	0.85	0.85		0.38									
32-5-17.0 A	0.00	1.74	1.74	1.74	1.74		0.47									
							1.74		0.25							

## DECOMMISSIONING NOTES

- ALL TEMP ROUTE ARE TO BE DECOMMISSIONED PER EXHIBIT D SPECIFICATIONS AND DETAILS.
- DECOMMISSIONING SHALL INCLUDE WATER BARRING, SEEDING & MULCHING, AND BARRICADING.
- FULL DECOMMISSIONING SHALL INCLUDE RIPPING, WATER BARRING, SEEDING & MULCHING, AND BARRICADING.

\*FOR INFORMATIONAL USE ONLY.  
 QUANTITIES SHOWN ARE NOT PAY ITEMS.

ALWAYS  
**THINK**  
 SAFETY

**BLOWN FORTUNE  
 TIMBER SALE  
 ESTIMATE OF QUANTITIES\***

UNITED STATES DEPARTMENT OF THE INTERIOR  
 BUREAU OF LAND MANAGEMENT  
 MEDFORD DISTRICT - MEDFORD, OREGON

DRAFTED BY: BLM  
 DATE: FEB 2020  
 SCALE: NONE  
 SHEET: 1 OF 3  
 DRAWING NO.: OR-11-9113.4-1

REV. NO.	DESCRIPTION	DATE	APPROVAL

# EXHIBIT D5-2

ROAD NUMBER	FROM		TO		LENGTH		MAINTENANCE RESPONSIBILITY			DUST ABATEMENT/ WATERING	% ROCKING	ROAD CLOSURE AND DECOMMISSIONING					
	MILE/STA	MILE/STA	MILE/STA	MILE/STA	MILE/STA	MILE/STA	BLM MAINTENANCE	PURCHASER MAINTENANCE	THIRD PARTY MAINTENANCE			INSTALL EARTH/LOG BARRICADE	INSTALL MEGA-GATE	INSTALL WATER BARS	CAMOUFLAGE ROAD ENTRANCE (100 FT)	SUB-SOIL/ RIPPING/ DECOMPACT SUBGRADE	SOIL STABILIZATION (SEED & MULCH)
	MILE	MILE	MILE			EA	EA	EA	EA	MILE/STA	ACRE						
32-5-17.0 B	1.74	2.30	0.56														
32-5-17.1	0.00	0.32	0.32				0.56	0.32									
32-5-17.2	0.00	0.22	0.22				0.32	0.22									
32-5-20.0 A	0.00	0.62	0.62				0.62				1	8	1				
32-5-20.0 B	0.62	2.56	1.94				1.94			0.25							
32-5-20.0 C	2.56	3.96	1.4				1.4										
32-5-30.0 A	0.00	0.66	0.66				0.66										
32-5-30.0 B	0.66	0.99	0.33				0.33										
32-5-30.1	0.00	0.84	0.84				0.84										
32-5-30.2	0.00	0.64	0.64				0.64										
32-5-31.4	0.00	0.35	0.35				0.35										
Windy Creek Rd	0.00	1.84	1.84				1.84										

**DECOMMISSIONING NOTES**

- ALL TEMP ROUTE ARE TO BE DECOMMISSIONED PER EXHIBIT D SPECIFICATIONS AND DETAILS.
- DECOMMISSIONING SHALL INCLUDE WATER BARRING, SEEDING & MULCHING, AND BARRICADING.
- FULL DECOMMISSIONING SHALL INCLUDE RIPPING, WATER BARRING, SEEDING & MULCHING, AND BARRICADING.

\*FOR INFORMATIONAL USE ONLY. QUANTITIES SHOWN ARE NOT PAY ITEMS.

*ALWAYS*  
**THINK**  
*SAFETY*

**BLOWN FORTUNE  
TIMBER SALE  
ESTIMATE OF QUANTITIES\***


UNITED STATES DEPARTMENT OF THE INTERIOR  
BUREAU OF LAND MANAGEMENT  
MEDFORD DISTRICT - MEDFORD, OREGON

REV. NO.	DESCRIPTION	DATE	APPROVAL

DRAFTED BY: BLM      SCALE: NONE  
DATE: FEB 2020      SHEET: 2 OF 3  
DRAWING NO.: OR-11-9113.4-1




# EXHIBIT D6




## Typical Full Decommission

### Notes:

1. The Purchaser shall barricade and decompact the temp route subgrade. Barricades shall be constructed as shown in Exhibit D Barricade and Water Bar Details.
2. Ditch lines at intersecting roads will be restored to their original shape.
3. Road surface shall be decompacted for its entire length using mechanical equipment. Decompact road surface to a depth of 8 to 12 inches. Where it is determined by the Authorized Officer that decompaction may cause unacceptable damage to the root systems of residual trees along a majority of the temp route, decompaction may be intermittent, or scarification may be used instead. Decompacked areas shall be seed and mulched upon completion.
4. All temporary culverts (if any) shall be removed from temp routes entirely. Excavated culvert trenches shall be left open to drain and have side slopes laid back to 1½:1. Where draw culverts are removed, the grade of the channel shall be restored to match existing stream grade. Culverts not designated as salvage for the Government shall become the property of the Contractor. The Contractor shall be responsible for legally disposing of material.
5. See Section 1800 for Seeding and Mulching Specifications.



Typical Culvert Removal - Before



Typical Culvert Removal - After

ALWAYS  
**THINK**  
SAFETY

REV. NO.	DESCRIPTION	DATE	APPROV.

UNITED STATES DEPARTMENT OF THE INTERIOR  
BUREAU OF LAND MANAGEMENT  
MEDFORD DISTRICT - MEDFORD, OREGON

**BLOWN FORTUNE  
TIMBER SALE  
DECOMPACTION AND  
CULVERT REMOVAL DETAILS**

DRAFTED BY: BLM


SCALE: NONE

DATE: FEB 2020


SHEET: 1 OF 1

DRAWING NO.: OR-11-9113.4-4


# EXHIBIT D7




## LOG BARRICADE




1. Log barricade shall be constructed as shown above.
2. Exact location is listed in Decommissioning Work List.
3. All barricades shall be skewed 30 degrees.
4. The log length shall extend from the cut bank to the fill slope.
5. The minimum small end diameter of the log barricade shall be 24".




## TRENCH BARRICADE



1. Trench barricade shall be constructed as shown above.
2. Exact location is listed in the Work List.
3. All barricades shall be skewed as needed to drain or as directed by the Authorized Officer.
4. Trench barricade length shall extend from the cut bank to the fill slope or to a point sufficient to prohibit the crossing of motor vehicle traffic.




## WATER BAR



1. Water bars shall be constructed as shown above.
2. Exact location will be flagged by the Authorized Officer prior to construction.
3. All water bars shall be skewed 30 degrees.
4. Upon completion of skidding logs, for the logging season, each skid road will have cross drainage constructed as shown above.

## SKEW DIAGRAM



## WATER BAR SPACING\* BY EROSION CLASS^

ROAD GRADE	HIGH	MODERATE	LOW
%	FEET	FEET	FEET
2-5	200	300	400
6-10	150	200	300
11-15	100	150	200
16-20	75	100	150
21-35	50	75	100
35+	50	50	50

\* Spacing is determined by slope distance and is the maximum allowed for the grade.

^ The erosion classes include the following rock types:  
**High:** Granite, sandstone, andesite porphyry, glacial or alluvial deposits, soft matrix conglomerate, volcanic ash, and pyroclastics.  
**Moderate:** Basalt, andesite, quartzite, hard matrix conglomerate, and rhyolite.  
**Low:** Metasediments, metavolcanics, and hard shale.

ALWAYS  
**THINK**  
 SAFETY

REV. NO.	DESCRIPTION	DATE	APPROV.


UNITED STATES DEPARTMENT OF THE INTERIOR  
 BUREAU OF LAND MANAGEMENT  
 MEDFORD DISTRICT - MEDFORD, OREGON

**BLOWN FORTUNE  
 TIMBER SALE  
 BARRICADE AND  
 WATER BAR DETAILS**


DRAFTED BY: BLM  
 DATE: FEB 2020  
 DRAWING NO.: OR-11-9113.4-4

SCALE: NONE  
 SHEET: 1 OF 1

# EXHIBIT D8



Typical Entrance - Before




Typical Entrance - After

NOTES:

1. The Purchaser shall barricade and Camouflage the road prism and disguise the roadbed so that the road entrance and roadway are indiscernible from the intersecting road. Camouflaged entrances shall consist of logs, slash, boulders and others debris placed along road entrances for a minimum of 100 feet or to the first curve or hillcrest to discourage vehicle use. An Earth Berm or equivalent barricade shall be constructed at road entrance as approved by the Authorized Officer..
2. Where multiple entrances exist, the work shall include obscuring all road entrances. Ditchlines at intersecting roads will be restored as indicated on plan view. The Purchaser shall use soil, boulders, brush, dead material, stumps, and other debris to disguise the road prism to the extent possible. No live trees should be used without approval of the Authorized Officer.

REV. NO.	DESCRIPTION	DATE	APPROV.
UNITED STATES DEPARTMENT OF THE INTERIOR BUREAU OF LAND MANAGEMENT MEDFORD DISTRICT - MEDFORD, OREGON			
<b>BLOWN FORTUNE TIMBER SALE TYPICAL ROAD CAMOUFLAGE DETAIL</b>			
DRAFTED BY: BLM	SCALE: NONE		
DATE: FEB 2020	SHEET: 1 OF 1		
DRAWING NO.: -			





- ⊙ Skips
- Gate
- Intermittent Stream
- Perennial Stream
- Intermediate 40-ft contour
- Index 200-ft contour
- ==== Natural Surface Road
- Paved Road
- Rocked Road
- Blown Fortune Road Construction**
- Road Construction
- Temp Route Construction
- Temp Route Reconstruction
- Tractor Swing
- Blown Fortune Roadside Management Unit


- Blown Fortune Timber Sale Unit Snag Creation Areas**
- Land Use Allocation**
- Late Seral Reserve (LSR)
  - Riparian Reserve (RR)
  - Contract Area Boundary
  - Reserve Area
- Ownership**
- Bureau of Land Management
  - Other

0 500 1,000 2,000 Feet

40 FOOT CONTOUR INTERVAL


United States Department of the Interior  
 Bureau of Land Management  
 Medford District Office  
 3040 Biddle Road  
 Medford, OR 97504  
 (541) 618-2200

No warranty is made by the Bureau of Land Management as to the accuracy, reliability, or completeness of these data for individual or aggregate use with other data. Original data were compiled from various sources and may be updated without notification.



<ul style="list-style-type: none"> <li>⊙ Skips</li> <li>● Gate</li> <li>--- Intermittent Stream</li> <li>--- Perennial Stream</li> <li>— Intermediate 40-ft contour</li> <li>— Index 200-ft contour</li> <li>=== Natural Surface Road</li> <li>— Paved Road</li> <li>--- Rocked Road</li> </ul>	<p><b>Blown Fortune Road Construction</b></p> <ul style="list-style-type: none"> <li>== Road Construction</li> <li>== Temp Route Construction</li> <li>--- Temp Route Reconstruction</li> <li>● Tractor Swing</li> <li>Blown Fortune Roadside Management Unit</li> </ul>	<p><b>Blown Fortune Timber Sale Unit Snag Creation Areas</b></p> <p><b>Land Use Allocation</b></p> <ul style="list-style-type: none"> <li>□ Late Seral Reserve (LSR)</li> <li>□ Riparian Reserve (RR)</li> <li>□ Contract Area Boundary</li> <li>□ Reserve Area</li> </ul> <p><b>Ownership</b></p> <ul style="list-style-type: none"> <li>□ Bureau of Land Management</li> <li>□ Other</li> </ul>	<p>0 500 1,000 2,000 Feet</p> <p><b>40 FOOT CONTOUR INTERVAL</b></p> <p>United States Department of the Interior          Bureau of Land Management          Medford District Office          3040 Biddle Road          Medford, OR 97504          (541) 618-2200</p>
---	--	---	---

No warranty is made by the Bureau of Land Management as to the accuracy, reliability, or completeness of these data for individual or aggregate use with other data. Original data were compiled from various sources and may be updated without notification.



- ⊙ Skips
- Gate
- Intermittent Stream
- Perennial Stream
- Intermediate 40-ft contour
- Index 200-ft contour
- ==== Natural Surface Road
- Paved Road
- Rocked Road
- Blown Fortune Road Construction**
- Road Construction
- Temp Route Construction
- Temp Route Reconstruction
- Tractor Swing
- Blown Fortune Roadside Management Unit


- Blown Fortune Timber Sale Unit Snag Creation Areas**
- Land Use Allocation**
- Late Seral Reserve (LSR)
  - Riparian Reserve (RR)
  - Contract Area Boundary
  - Reserve Area
- Ownership**
- Bureau of Land Management
  - Other

0 500 1,000 2,000 Feet

**40 FOOT CONTOUR INTERVAL**


United States Department of the Interior  
 Bureau of Land Management  
 Medford District Office  
 3040 Biddle Road  
 Medford, OR 97504  
 (541) 618-2200

No warranty is made by the Bureau of Land Management as to the accuracy, reliability, or completeness of these data for individual or aggregate use with other data. Original data were compiled from various sources and may be updated without notification.



<ul style="list-style-type: none"> <li>⊙ Skips</li> <li>● Gate</li> <li>--- Intermittent Stream</li> <li>--- Perennial Stream</li> <li>— Intermediate 40-ft contour</li> <li>— Index 200-ft contour</li> <li>==== Natural Surface Road</li> <li>— Paved Road</li> <li>— Rocked Road</li> </ul>	<p><b>Blown Fortune Road Construction</b></p> <ul style="list-style-type: none"> <li>— Road Construction</li> <li>— Temp Route Construction</li> <li>— Temp Route Reconstruction</li> <li>● Tractor Swing</li> <li>Blown Fortune Roadside Management Unit</li> </ul>	<p><b>Blown Fortune Timber Sale Unit Snag Creation Areas</b></p> <p><b>Land Use Allocation</b></p> <ul style="list-style-type: none"> <li>□ Late Seral Reserve (LSR)</li> <li>□ Riparian Reserve (RR)</li> <li>□ Contract Area Boundary</li> <li>□ Reserve Area</li> </ul> <p><b>Ownership</b></p> <ul style="list-style-type: none"> <li>□ Bureau of Land Management</li> <li>□ Other</li> </ul>	<p>0 500 1,000 2,000 Feet</p> <p><b>40 FOOT CONTOUR INTERVAL</b></p> <p>United States Department of the Interior          Bureau of Land Management          Medford District Office          3040 Biddle Road          Medford, OR 97504          (541) 618-2200</p>
--	--	---	---

No warranty is made by the Bureau of Land Management as to the accuracy, reliability, or completeness of these data for individual or aggregate use with other data. Original data were compiled from various sources and may be updated without notification.



- ⊙ Skips
- Gate
- - - Intermittent Stream
- - - - Perennial Stream
- Intermediate 40-ft contour
- Index 200-ft contour
- ==== Natural Surface Road
- Paved Road
- Rocked Road
- Blown Fortune Road Construction**
- Road Construction
- Temp Route Construction
- Temp Route Reconstruction
- Tractor Swing
- Blown Fortune Roadside Management Unit

- Blown Fortune Timber Sale Unit Snag Creation Areas**
- Land Use Allocation**
- ▭ Late Seral Reserve (LSR)
  - ▭ Riparian Reserve (RR)
  - ▭ Contract Area Boundary
  - ▭ Reserve Area
- Ownership**
- ▭ Bureau of Land Management
  - ▭ Other


0 500 1,000 2,000 Feet

**40 FOOT CONTOUR INTERVAL**

United States Department of the Interior  
 Bureau of Land Management  
 Medford District Office  
 3040 Biddle Road  
 Medford, OR 97504  
 (541) 618-2200

No warranty is made by the Bureau of Land Management as to the accuracy, reliability, or completeness of these data for individual or aggregate use with other data. Original data were compiled from various sources and may be updated without notification.





1 inch = 1,000 feet


40 FOOT CONTOUR INTERVAL

No warranty is made by the Bureau of Land Management as to the accuracy, reliability, or completeness of these data for individual or aggregate use with other data. Original data were compiled from various sources and may be updated without notification.

Map created by SDT  
 3/10/2020



United States Department of the Interior  
 Bureau of Land Management  
 Medford District Office  
 3040 Biddle Road  
 Medford, OR 97504  
 (541) 618-2200



United States Department of the Interior  
 Bureau of Land Management  
 Medford District Office  
 3040 Biddle Road  
 Medford, OR 97504  
 (541) 618-2200




1 inch = 1,000 feet

40 FOOT CONTOUR INTERVAL

No warranty is made by the Bureau of Land Management as to the accuracy, reliability, or completeness of these data for individual or aggregate use with other data. Original data were compiled from various sources and may be updated without notification.

Map created by SDT  
 3/10/2020





1 inch = 1,000 feet


40 FOOT CONTOUR INTERVAL

No warranty is made by the Bureau of Land Management as to the accuracy, reliability, or completeness of these data for individual or aggregate use with other data. Original data were compiled from various sources and may be updated without notification.

United States Department of the Interior  
 Bureau of Land Management  
 Medford District Office  
 3040 Biddle Road  
 Medford, OR 97504  
 (541) 618-2200

Map created by SDT  
 3/10/2020





1 inch = 1,000 feet


40 FOOT CONTOUR INTERVAL

No warranty is made by the Bureau of Land Management as to the accuracy, reliability, or completeness of these data for individual or aggregate use with other data. Original data were compiled from various sources and may be updated without notification.

United States Department of the Interior  
 Bureau of Land Management  
 Medford District Office  
 3040 Biddle Road  
 Medford, OR 97504  
 (541) 618-2200

Map created by SDT  
 3/10/2020





1 inch = 1,000 feet


40 FOOT CONTOUR INTERVAL

No warranty is made by the Bureau of Land Management as to the accuracy, reliability, or completeness of these data for individual or aggregate use with other data. Original data were compiled from various sources and may be updated without notification.

United States Department of the Interior  
 Bureau of Land Management  
 Medford District Office  
 3040 Biddle Road  
 Medford, OR 97504  
 (541) 618-2200

Map created by SDT  
 3/10/2020





1 inch = 1,000 feet


40 FOOT CONTOUR INTERVAL

No warranty is made by the Bureau of Land Management as to the accuracy, reliability, or completeness of these data for individual or aggregate use with other data. Original data were compiled from various sources and may be updated without notification.

United States Department of the Interior  
 Bureau of Land Management  
 Medford District Office  
 3040 Biddle Road  
 Medford, OR 97504  
 (541) 618-2200

Map created by SDT  
 3/10/2020





1 inch = 1,000 feet


40 FOOT CONTOUR INTERVAL

No warranty is made by the Bureau of Land Management as to the accuracy, reliability, or completeness of these data for individual or aggregate use with other data. Original data were compiled from various sources and may be updated without notification.

Map created by SDT  
 3/10/2020



United States Department of the Interior  
 Bureau of Land Management  
 Medford District Office  
 3040 Biddle Road  
 Medford, OR 97504  
 (541) 618-2200



1 inch = 1,000 feet

40 FOOT CONTOUR INTERVAL

No warranty is made by the Bureau of Land Management as to the accuracy, reliability, or completeness of these data for individual or aggregate use with other data. Original data were compiled from various sources and may be updated without notification.

United States Department of the Interior  
 Bureau of Land Management  
 Medford District Office  
 3040 Biddle Road  
 Medford, OR 97504  
 (541) 618-2200

Map created by SDT  
 3/10/2020



### LEGEND

UNIT	UNIT ACRES	SLASH DISPOSAL TREATMENT PRESCRIPTION	HAND PILE TREATMENT AREA DESCRIPTION
3-7	10	SS-HPC-HPB	WHOLE UNIT
3-11	41	LS/SS-HPC-HPB/MPC-MPB	WITHIN 100 FT. OF ROAD # 32-5-9.0
3-14	11	SS-HPC-HPB/MPC-MPB	WHOLE CABLE PORTION OF UNIT
5-6	20	SS-HPC-HPB/UB	WHOLE UNIT
5-8	10	SS-HPC-HPB	WHOLE UNIT
8-9G	3	SS-HPC-HPB	WHOLE UNIT
9-5	8	SS-HPC-HPB	WHOLE UNIT
9-14	2	MPC-MPB	N/A
9-18	26	SS-HPC-HPB/UB	WHOLE UNIT
10-1	25	SS-HPC-HPB	WHOLE UNIT
17-1	75	SS-HPC-HPB/MPC-MPB/UB	WHOLE CABLE PORTION OF UNIT
17-2	75	SS-HPC-HPB/MPC-MPB	WHOLE CABLE PORTION OF UNIT
17-15	35	MPC-MPB	N/A
17-15G	4	MPC-MPB	N/A
17-16	6	MPC-MPB	N/A
17-17	23	LS/MPC-MPB	N/A
31-1	18	LS/SS-HPC-HPB	WITHIN 100 FT. OF ROAD # 32-5-30.1
31-2	28	SS-HPC-HPB/MPC-MPB	WHOLE CABLE PORTION OF UNIT
31-3	9	LS/SS-HPC-HPB	WITHIN 100 FT. OF ROAD # 32-5-30.1
32-5-8.0	5	MPC-MPB	N/A
32-5-8.2	1	MPC-MPB	N/A
32-5-9.0	2	MPC-MPB	N/A
<b>TOTAL</b>	<b>437</b>		

\* BOUNDARIES OF HARVEST UNITS ARE POSTED AND PAINTED IN ORANGE

LS = LOP & SCATTER

SS = SELECTIVE SLASHING

HPC-HPB = HAND PILE & COVER, HAND PILE BURN

MPC-MPB = MACHINE PILE & COVER, MACHINE PILE BURN

UB = UNDERBURN



1 inch = 1,000 feet

40 FOOT CONTOUR INTERVAL

No warranty is made by the Bureau of Land Management as to the accuracy, reliability, or completeness of these data for individual or aggregate use with other data. Original data were compiled from various sources and may be updated without notification.

United States Department of the Interior  
 Bureau of Land Management  
 Medford District Office  
 3040 Biddle Road  
 Medford, OR 97504  
 (541) 618-2200

Map created by SDT  
 3/10/2020



## SLASH DISPOSAL SUMMARY BY UNIT AND PRESCRIPTION

UNIT	UNIT ACRES	LOP & SCATTER ACRES	SELECTIVE SLASHING ACRES	HAND PILE, COVER & BURN ACRES	MACHINE PILE, COVER & BURN ACRES	UNDERBURN ACRES
3-7	10		10	10		
3-11	41	23	17	17	1	
3-14	11		9	9	2	
5-6	20		20	20		20
5-8	10		10	10		
8-9G	3		3	3		
9-5	8		8	8		
9-14	2				2	
9-18	26		26	26		26
10-1	25		25	25		
17-1	75		9	9	66	75
17-2	75		68	68	7	
17-15	35				35	
17-15G	4				4	
17-16	6				6	
17-17	23	3			20	
31-1	18	15	3	3		
31-2	28		6	6	22	
31-3	9	8	1	1		
32-5-8.0	5				5	
32-5-8.2	1				1	
32-5-9.0	2				2	
<b>TOTAL</b>	<b>437</b>	<b>49</b>	<b>215</b>	<b>215</b>	<b>173</b>	<b>121</b>



1 inch = 1,000 feet

40 FOOT CONTOUR INTERVAL

No warranty is made by the Bureau of Land Management as to the accuracy, reliability, or completeness of these data for individual or aggregate use with other data. Original data were compiled from various sources and may be updated without notification.

United States Department of the Interior  
 Bureau of Land Management  
 Medford District Office  
 3040 Biddle Road  
 Medford, OR 97504  
 (541) 618-2200

Map created by SDT  
 3/10/2020



### Legend

- ▲ Mountain Peaks
- Gates
- Ⓢ Skips
- Blown Fortune Road Construction**
  - ▬ Permanent Road Construction
  - ▬▬ Temporary Route Construction
  - ▬▬▬ Temporary Route Reconstruction
  - Cable Tractor Swing Route
  - ▬▬▬ Blown Fortune Roadside Management Units
- Roads**
- Surface Type**
  - ▬ Paved
  - ▬▬ Rocked
  - ▬▬▬ Natural
- Intermediate 40-ft contour
- Index 200-ft contour
- - - - Intermittent Stream
- - - - Perennial Stream
- Blown Fortune Timber Sale Units**
- Slash Disposal Treatment**
  - ▭ Lop & Scatter
  - ▨ Machine Pile Cover - Machine Pile Burn
  - ▭ - - - Selective Slash - Hand Pile Cover - Hand Pile Burn
  - ▭ Underburn
- ▭ Blown Fortune Contract Area Boundary
- ▭ BlownFortune Reserve Area
- ▭ Township and Range
- ▭ Section
- ▭ Lot
- Ownership**
  - ▭ O & C BLM O&C Lands
  - ▭ PD BLM PD Lands
  - ▭ ODF State Lands
  - ▭ PVT Private Lands



1 inch = 1,000 feet

40 FOOT CONTOUR INTERVAL

No warranty is made by the Bureau of Land Management as to the accuracy, reliability, or completeness of these data for individual or aggregate use with other data. Original data were compiled from various sources and may be updated without notification.


United States Department of the Interior  
 Bureau of Land Management  
 Medford District Office  
 3040 Biddle Road  
 Medford, OR 97504  
 (541) 618-2200

Map created by SDT  
 3/10/2020






EXHIBIT R  
SHEET 1 OF 1




SIDE VIEW



TOP VIEW

TYPICAL RIPPER POSITION



- NOTES: TYPICAL RIPPER TOOTH CONSTRUCTION
1. USE HARD SURFACING ROD FOR ALL EDGE AND SURFACE REINFORCEMENT.
  2. WELD THAT ATTACHES WINGS TO RIPPER TEETH MUST BE COMPATIBLE WITH METAL IN TEETH AND WINGS.
  3. RIPPER SHANKS AND RIPPER TEETH MAY BE NEW OR USED.
  4. WINGS SHALL PROVIDE TWO (2) INCHES OF LIFT FROM THE HORIZONTAL WHEN TEETH ARE EXTENDED FOURTEEN (14) INCHES BELOW THE GROUND SURFACE.

UNITED STATES DEPARTMENT OF THE INTERIOR BUREAU OF LAND MANAGEMENT ASHLAND RESOURCE AREA MEDFORD DISTRICT	
<b>WING RIPPER DETAIL</b>	
DESIGNED	
REVIEWED	
APPROVED	
DRAWN: JWR	SCALE: NONE
DATE: October 2009	SHEET 1 OF 1
DRAWING NO.	



UNITED STATES  
DEPARTMENT OF THE INTERIOR  
BUREAU OF LAND MANAGEMENT

Name of Bidder
Tract Number
Sale Name
Sale Notice <i>(dated)</i>
BLM District

**DEPOSIT AND BID FOR: (Check One):**

- Timber and/or Other Wood Products or**  
(Examples of Other Wood Products: biomass, firewood, posts, poles, etc...)
- Vegetative Resources**  
(Examples of Vegetative Resources: boughs, pinyon nuts, cones, plants, etc...)

<input type="checkbox"/> Sealed Bid for Sealed Bid Sale	<input type="checkbox"/> Written Bid for Oral Auction Sale
Time for opening sealed bids <input type="checkbox"/> a.m. <input type="checkbox"/> p.m.	Sale commences <input type="checkbox"/> a.m. <input type="checkbox"/> p.m.
On <i>(date)</i> Place	On <i>(date)</i> Place

In response to the above dated Sale Notice, the required deposit and bid are hereby submitted for the purchase of designated Timber and/or Other Wood Products or Vegetative Resources on the tract specified above.

Required bid deposit is \$ \_\_\_\_\_ and is enclosed in the form of:

- cash     money order     cashier's check     certified check     bank draft
- bid bond of corporate surety on approved list of the United States Treasury     guaranteed remittance approved by the authorized officer.

IT IS AGREED That the bid deposit shall be retained by the United States as liquidated damages if the bid is accepted and the undersigned fails to execute and return the contract, together with any required performance bond and any required payment within 30 days after the contract is received by the successful bidder. It is understood that no bid for less than the appraised price on a unit basis per product and species will be considered. If the bid is rejected the deposit will be returned.

**BID SCHEDULE – TIMBER AND/OR OTHER WOOD PRODUCTS OR VEGETATIVE RESOURCES**

*NOTE: Bidders should carefully check computations in completing the Bid Schedule*

BID SUBMITTED					ORAL BID MADE	
PRODUCT & SPECIES	UNIT	ESTIMATED VOLUME OR QUANTITY	UNIT PRICE	TOTAL VALUE	UNIT PRICE	TOTAL VALUE
			X	=	X	=
			X	=	X	=
			X	=	X	=
			X	=	X	=
			X	=	X	=
			X	=	X	=
			X	=	X	=
			X	=	X	=
			X	=	X	=
			X	=	X	=
			X	=	X	=
TOTAL PURCHASE PRICE						

If sale contract is executed, undersigned is liable for total purchase price including all modifications executed under the terms of the contract. Timber and/or Other Wood Products or Vegetative Resources designated for taking may be less or more than total estimated volume or quantity shown above. Undersigned certifies bid was arrived at by bidder or offeror independently, and was tendered without collusion with any other bidder or offeror. In submitting or confirming this bid, undersigned agrees to the foregoing provisions, applicable regulations, and certifies that he is authorized to act as, or on behalf of, the bidder.

Bid submitted on *(date)*

*(Check appropriate box, sign in ink, and complete the following)*

<input type="checkbox"/> Signature, if firm is individually owned	Name of firm <i>(type or print)</i>
<input type="checkbox"/> Signatures, if firm is a partnership or L.L.C.	Business address, include zip code <i>(type or print)</i>
<input type="checkbox"/> Corporation organized under the state laws of	<i>(To be completed following oral bidding)</i>
Signature of Authorized Corporate Signing Officer	I HEREBY confirm the above oral bid By <i>(signature)</i>
Title	Date
Submit bid, in <i>duplicate</i> , to qualify for either an oral auction or sealed bid sale together with the required bid deposit made payable to the Department of the Interior – BLM.  Oral Auction – Submit to Sales Supervisor prior to closing of qualifying period for tract.	Sealed Bid – Send to District Manager, who issued the sale notice, in a sealed envelope marked on the outside: (1) “Bid for Timber and/or Other Wood Products or (1a) “Vegetative Resources” (2) Time bids are to be opened (3) Legal description

### NOTICES

The Privacy Act and the regulations in 43 CFR 2.223(d) require that you be furnished with the following information:

**AUTHORITY:** 38 FR 6280 and 43 CFR 5442.1

**PRINCIPAL PURPOSE:** To qualify an oral auction bidder, and then if successful, to bind bidder to certain contract conditions.

**ROUTINE USES:** To determine that an individual is qualified to participate in oral auction bidding, and, as surety that bidder will fulfill contract requirements.

**EFFECT OF NOT PROVIDING INFORMATION:** Filing this deposit and bid information is necessary only when an individual wishes to participate in a sealed or auction bid sale for Timber and/or Other Wood Products or Vegetative Resources.

## **INSTRUCTIONS TO BIDDERS**

1. **AUTHORITY** – Timber and/or Other Wood Products or Vegetative Resources, located on the revested Oregon and California Railroad Grant Lands and on the reconveyed Coos Bay Wagon Road Grant Lands is administered and sold pursuant to authority of the Act of August 28, 1937 (50 Stat. 874; 43 U.S.C. 1181a); Timber and/or Other Wood Products or Vegetative Resources located on other public lands of the United States under jurisdiction of the Bureau of Land Management are administered and sold pursuant to authority of the Act of July 31, 1947 (61 Stat. 681), as amended, by the Act of July 23, 1955 (69 Stat. 367; 30 U.S.C. 601 et. seq.). Regulations of the Secretary of the Interior governing sale of Timber and/or Other Wood Products or Vegetative Resources, are codified in 43 CFR Group 5400.

2. **QUALIFICATIONS OF BIDDERS** – A bidder for sale of Timber and/or Other Wood Products or Vegetative Resources must be either (a) a citizen of the United States, (b) a partnership composed wholly of such citizens, (c) an unincorporated association composed wholly of such citizens, or (d) a corporation authorized to transact business in the State in which the Timber and/or Other Wood Products or Vegetative Resources are located.

3. **INSPECTION OF TIMBER AND/OR OTHER WOOD PRODUCTS OR VEGETATIVE RESOURCES** – Bidder is invited, urged, and cautioned to inspect the Timber and/or Other Wood Products or Vegetative Resources prior to submitting a bid. By executing the Timber and/or Other Wood Products or Vegetative Resources sale contract, bidder warrants that the contract is accepted on the basis of his examination and inspection of the Timber and/or Other Wood Products or Vegetative Resources and his opinion of its value.

4. **DISCLAIMER OF WARRANTY** – Government expressly disclaims any warranty of the fitness of the designated Timber and/or Other Wood Products or Vegetative Resources for any purpose of the bidder; all Timber and/or Other Wood Products or Vegetative Resources are to be sold “As Is” without any warranty of merchantability by Government. Any warranty as to the quantity or quality of Timber and/or Other Wood Products or Vegetative Resources to be sold is expressly disclaimed by Government.

5. **BIDS** – Sealed or written bids for not less than the advertised appraised price, per Timber and/or Other Wood Products or Vegetative Resources must be submitted in duplicate to the District Manager who issued *Timber and/or Other Wood Products or Vegetative Resources Sale Notice*.

(a) **Sealed Bid Sales** – Bids will be received until time for opening which is set out in the Notice. Enclose both copies of bid with required bid deposit in a sealed envelope marked on the outside *Bid for Timber and/or Other Wood Products or Vegetative Resources*, time bid is to be opened, tract number, and legal description of land on which Timber and/or Other Wood Products or Vegetative Resources are located. In event of a tie, the high bidder shall be determined by lot from among those who submitted the tie bids.

(b) **Auction Sales** – Submission of the required bid deposit and a written bid is required to qualify for oral bidding. Oral bidding shall begin from the highest written bid. No oral bid will be considered which is not higher than the preceding bid. In the event there is a tie in high written bids, and no oral bidding occurs, the bidder who was the first to submit his bid deposit and written bid shall be declared the high bidder. If the officer conducting the sale cannot determine who made the first submission of high tie written bids, the high bidder shall be determined by lot. High bidder must confirm his bid, in writing, immediately upon being declared high bidder.

(c) Except as otherwise provided in 43 CFR 5442.2, bids will not be considered in resale of Timber and/or Other Wood Products or Vegetative Resources remaining from an uncompleted contract from any person or affiliate of such person who failed to complete the original contract because of (1) cancellation for the purchaser’s breach or (2) through failure to complete payment by expiration date.

(d) When it is in the interest of the Government to do so, it may reject any and all bids and may waive minor deficiencies in bids or in sale advertisement.

6. **BID FORMS** – All sealed, written bids, and confirmation of oral bids shall be submitted on forms provided by Government.

(a) **Timber and/or Other Wood Products or Vegetative Resources Sales** – For each product and species, bids shall specify (1) Bureau of Land Management estimated unit volume or quantity, (2) bidder’s price per unit and total value, and (3) bidder’s total purchase price. Estimated volume and price per unit are to be used for administrative and appraisal purposes only. Upon award of contract, the high bidder agrees to pay the Government for the Timber and/or Other Wood Products or Vegetative Resources designated for removal in accordance with the terms of the contract. Timber and/or Other Wood Products or Vegetative Resources designated for taking may be less or more than total estimated volume or quantity shown above.

7. **BID DEPOSIT** – All bidders must make a deposit of not less than the amount specified in the *Timber and/or Other Wood Products or Vegetative Resources*

*Notice*. Deposit may be in the form of cash, money orders, bank drafts, cashiers or certified checks made payable to the Department of the Interior – BLM, bid bonds of a corporate surety shown on the approved list of the United States Treasury Department (*Applies To Timber Only*), or any approved guaranteed remittance approved by the Contracting Officer. Upon conclusion of bidding, the bid deposit of all bidders, except high bidder, will be returned. The cash deposit of the successful bidder may be applied toward the required sale deposit and/or the purchase price. Cash not applied to the sale deposit or the purchase price, or a corporate surety bid bond, will be returned at the time the contract is signed by the Government.

8. **AWARD OF CONTRACT** – Government may require high bidder to furnish such information as is necessary to determine the ability of bidder to perform the obligation of contract. Contract will be awarded to high bidder, unless he is not qualified or responsible or unless all bids are rejected. If high bidder is not qualified or responsible or fails to sign and return the contract together with required performance bond and any required payment, contract may be offered and awarded to the highest bidders qualified, responsible, and willing to accept the contract.

9. **TIMBER AND/OR OTHER WOOD PRODUCTS OR VEGETATIVE RESOURCES SALE CONTRACTS** – To be executed by purchaser, has been prepared by Government, and may be examined in the District or Field Manager’s office.

10. **PERFORMANCE BOND** – (*Primarily Used For Timber Sales*)

(a) A performance bond in an amount of not less than 20 percent of total purchase price is required, but the amount of the bond shall not be in excess of \$500,000, except when the purchaser opts to increase the minimum bond to permit cutting prior to payment as provided in 43 CFR 5451.2, or in the event the purchaser is a holder of an unresolved default the bond may be increased as provided in 43 CFR 5450.1(b). Performance bond may be (1) bond of a corporate surety shown on approval list issued by the United States Treasury Department and executed on an approved standard form, (2) personal surety bond executed on an approved standard form if Government determines principals and bondsman are capable of carrying out the terms of the contract, (3) cash bonds, (4) negotiable securities of the United States, or (5) any guaranteed remittance approved by the Contracting Officer.

(b) If purchaser elects to cut Timber and/or Other Wood Products or Vegetative Resources without skidding or yarding it to a loading point or removing it prior to the payment of the second or subsequent installments, Government shall require an increase in amount of performance bond initially required by an amount equal to the value of Timber and/or Other Wood Products or Vegetative Resources to be cut. Such increase must be on a bond rider form supplied by Government and be approved, in writing, by Government prior to cutting Timber and/or Other Wood Products or Vegetative Resources covered by the bond increase. This increased amount of bond shall be used to assure payment for Timber and/or Other Wood Products or Vegetative Resources cut in advance of payment.

11. **PAYMENT BOND**— (*Primarily Used For Timber Sales*)

If purchaser elects to (a) cut and remove Timber and/or Other Wood Products or Vegetative Resources, or (b) remove Timber and/or Other Wood Products or Vegetative Resources already cut which has been secured by an increased performance bond as provided in paragraph 10(b) above, before payment of the second or subsequent installments, Government shall require a payment bond on a form supplied by Government. Purchaser shall obtain written approval from Government of payment bond prior to cutting and/or removal of Timber and/or Other Wood Products or Vegetative Resources covered by the bond. Payment bond shall be used to assure payment for Timber and/or Other Wood Products or Vegetative Resources cut and/or removed in advance of payment.

12. **PAYMENT OF PURCHASE PRICE** – For sales of \$500 or more, Government may allow payment by installments. Except as discussed in paragraphs 10 and 11 above, no part of any Timber and/or Other Wood Products or Vegetative Resources sold may be severed, cut, or removed unless advance payment has been made as provided in contract.

13. **LIQUIDATED DAMAGES** – Within thirty (30) days from receipt of *Timber and/or Other Wood Products or Vegetative Resources Sale Contract*, the successful bidder shall sign contract and return it to Government, together with required bond and any required payment. If successful bidder fails to comply within the stipulated time, his bid deposit shall be retained by Government as liquidated damages.

14. **NINETY-DAY SALES** – If no bid is received within time specified in the advertisement of sale and if Government determines that there has been no significant rise in the market value of Timber and/or Other Wood Products or Vegetative Resources, it may, in its discretion, keep the sale open, not to exceed ninety (90) days.

15. *UNAUTHORIZED USE OF GOVERNMENT PROPERTY* – A sale may be refused to high bidder who has been notified that he has failed to make satisfactory arrangements for payment of damages resulting from unauthorized use of, or injury to, property of the United States.

16. *EQUAL OPPORTUNITY CLAUSE* – This contract is subject to the provisions of Executive Order No. 11246 of September 24, 1965, as amended, which sets forth the nondiscrimination clauses. Copies of this order may be obtained from the District Manager. 43 CFR 60-1.7(b) requires that the Equal Opportunity *Compliance Report Certification* will be completed by prospective contractors. Certification may be obtained from District Manager.

17. *LOG EXPORT* – All timber offered for sale except as noted in the *Timber Sale Notice* is restricted from export from the United States in the form of unprocessed timber and cannot be used as a substitute for exported private timber. For the purpose of this contract, unprocessed timber is defined as: (1) any logs except those of utility grade or below, such as saw logs, peeler logs, and pulp logs; (2) cants or squares to be subsequently remanufactured exceeding eight and three quarters (8-3/4) inches in thickness; (3) split or round bolts or other roundwood not processed to standards and specifications suitable for end product use; or (4)

western red cedar lumber which does not meet lumber of American Lumber Standards Grades of Number 3 dimensions or better, or Pacific Lumber Inspection Bureau R-List Grades of Number 3 common or better. Timber manufactured into the following will be considered processed: (1) lumber and construction timbers, regardless of size, manufactured to standards and specifications suitable for end product uses; (2) chips, pulp and pulp products; (3) green or dry veneer and plywood; (4) poles and piling cut or treated for use as such; (5) cants, squares, and lumber cut for remanufacture of eight and three quarters (8-3/4) inches in thickness or less; or (6) shakes and shingles. In event purchaser wishes to sell any or all of timber restricted from export in the form of unprocessed timber, the buyer, exchanges, or recipient shall be required to comply with contractual provisions relating to “*unprocessed timber*”. Special reporting, branding and painting of logs may be included in contract provisions.\*

18. *DETAILED INFORMATION* – Detailed information concerning contract provisions, bid, performance bond forms, tract location maps, and access conditions may be obtained from the District Manager. All persons interested in bidding on the products listed are encouraged to familiarize themselves with all such detailed information.