



United States Department of the Interior

BUREAU OF LAND MANAGEMENT
Northwest Oregon District Office
1717 Fabry Road SE, Salem, Oregon 97306
<http://www.blm.gov>



Date: August 8, 2018
Sale Name: Number 4
Contract No.: ORN04-TS-2018.0404
Sale Date: August 22, 2018

CORRECTION NOTICE

The logging residue reduction acreage was incorrect on Special Contract Provision Section 42 gg. The acreage has been updated as shown below to remain consistent with the appraisal.

The Totals and Bid Deposit required were listed correctly and remain unchanged.

The Logging Residue Reduction acreage on the Special Contract Provision section 42 gg. has been updated as follows:

Purchaser shall perform logging residue reduction and site preparation work on approximately forty-five (45) acres of harvest area located in the sale area. Approximately twenty-six (26) acres will be machine pile construction, cover, and burn in the ground-based regeneration cut areas, approximately twelve (12) acres will be slashed and lopped, and approximately seven (7) acres will be landing pile covering and burning.

This correction does not affect the appraisal price or minimum

If you would like a new Prospectus containing all the updated documents please contact the Northwest District office at 503-375-5646 or the Tillamook Field Office at 503-815-1100.

If you have any questions please contact Brian Christensen either by email at bchristensen@blm.gov or by phone at 503-815-1119.

LOGGING RESIDUE REDUCTION

gg. In addition to the requirements of Sec. 15 of this contract, and notwithstanding the Purchasers satisfactory compliance with State laws and regulations regarding offsetting or abating the additional fire hazard created by this operation and the States willingness to release the Purchaser from liability for such hazard, the Purchaser shall remain responsible to the Government for performance of the following hazard reduction measure(s) required by this contract: Perform logging residue reduction and site preparation work on approximately forty-five (45) acres of harvest area located in the sale area. The required work shall consist of any treatment or combination of treatments, as determined by the Authorized Officer and specified in writing by the Contracting Officer. The number of acres and specific location of each treatment shall be determined by the Authorized Officer. Approximately twenty-six (26) acres will be machine pile construction, cover, and burn in the ground-based regeneration cut areas. Approximately twelve (12) acres will be slashed and lopped. There will be approximately seven (7) acres of landing pile covering and burning. Prior to commencement of any operation under this Section of the contract, a slash disposal and pre-work conference between the purchaser's representative and the Authorized Officer must be held at a location designated by the Authorized Officer. The number of acres of each treatment shall be determined by the Authorized Officer. All slash disposal shall be done in accordance with the plans developed at this pre-work conference. Slash, as defined for this section, shall mean all material (brush, limbs, tops, unmerchantable stems, and chunks) severed or knocked over as a result of purchasers operations under the terms of this contract.

1. Slashing and lopping shall be completed on approximately twelve (12) acres post harvest in areas designated by the Authorized Officer in the sale area shown on Exhibit A. All standing woody vegetation (brush), whips, and designated trees over one (1) foot in height and less than six (6) inches diameter shall be felled (slashed) and lopped into six (6) foot or smaller lengths. Designated trees to be slashed include red alder and bigleaf maple.

a. All logging slash and slashed woody vegetation that is greater than six (6) feet in length and between one (1) inch and six (6) inches in diameter shall be lopped. Larger material which has a portion meeting this specification must be bucked at the six (6) inch diameter.

b. All woody vegetation, whips, and designated trees shall be completely severed from the stump(s). Stump height shall not exceed six (6) inches measured on the uphill side.

c. All conifer tree species shall be reserved and undamaged.

2. Excavator pile and burn slash within ground based portion of regeneration harvest units from skid trails and within twenty-five (25) feet of Dixie Mountain Road, Otto Miller Road 3N-2-29.2, 3N-2-29.3, 3N-3-13.5, and 3N-2-18 roads in the sale area. Slash shall be piled by an excavator equipped with a hydraulic thumb. Finished piles shall be tight and free of dirt.

a. Unmerchantable logs greater than six (6) inches on the small end shall be left in place, or positioned so that they will not be burned.