

# PROSPECTUS

**LUMP SUM SALE**  
**LOCKED GATE(S) – TS KEY**  
**Sale Date: March 24, 2026**

(1) Roseburg Sale No.: 2026.0004  
 Douglas County, Oregon: CBWR: Oral Auction

**Sale Name:** Reston Pieces  
**Bid Deposit Required:** \$100,200.00

All timber designated for cutting on:

W <sup>1</sup> / <sub>2</sub> SW <sup>1</sup> / <sub>4</sub>	Sec. 15,	T. 28 S.,	R. 8 W.,	Willamette Meridian
NE <sup>1</sup> / <sub>4</sub>	Sec. 21,	T. 28 S.,	R. 8 W.,	Willamette Meridian
SW <sup>1</sup> / <sub>4</sub>	Sec. 23,	T. 28 S.,	R. 8 W.,	Willamette Meridian
NW <sup>1</sup> / <sub>4</sub> NE <sup>1</sup> / <sub>4</sub> , N <sup>1</sup> / <sub>2</sub> NW <sup>1</sup> / <sub>4</sub>	Sec. 29,	T. 28 S.,	R. 8 W.,	Willamette Meridian

Approx. Number Merch. Trees	Est. Vol. MBF 32' Log	Species	Est. Vol. MBF 16' Log	Appraised Price Per MBF	Est. Volume Times Appraised Price
16,208	3825	Douglas-fir	4,641	<b>\$190.50</b>	\$884,110.50
2,849	917	Grand Fir	1,131	<b>\$88.40</b>	\$99,980.40
911	151	Incense-cedar	196	<b>\$38.60</b> *	\$7,565.60
521	73	Western Hemlock	92	<b>\$75.40</b>	\$6,936.80
106	8	Western Redcedar	11	<b>\$256.10</b>	\$2,817.10
<b>20,595</b>	<b>4,974</b>		<b>6,071</b>		<b>\$1,001,410.40</b>

\* Minimum Stumpage Values were used to compute the Appraised Price/MBF (10% of Pond Value)

Product	Unit of Measure	Estimated Number of Units	Appraised Price Per Green Ton	Estimated Units Times Appraised Price
Biomass	Green Tons	184	\$3.00	\$552.00

<b>Total Appraised Value:</b>	<b>\$1,001,962.40</b>
-------------------------------	-----------------------

**KEY CHECK OUT PROCESS:** Please contact our BLM Office at 541-440-4930, to make an appointment to check out gate keys. Form ORR000-9113-09, Check-Out For Gate Key, will need to be completed before keys can be issued. No deposit is required for these keys.

**THE VOLUMES LISTED** herein are estimates only, based on 16-foot taper breaks, which must be taken into consideration if comparisons are made with volume predictions based on other standards. The volumes based on 32-foot taper breaks are shown for comparison purposes. No sale shall be made for less than the total actual purchase price.

**APPRAISED PRICES** are determined by analytical appraisal methods unless otherwise noted on individual timber sale notices.

**LOG EXPORT AND SUBSTITUTION RESTRICTIONS:** All timber sales, including timber from Federal rights-of-ways, shall be subject to the restrictions relating to the export and substitution of unprocessed timber from the United States in accordance with P.L. 94-165 and 43 CFR 5400 and 5424 as amended.

Excepting Port-Orford-cedar, all timber offered for sale hereunder is restricted from export from the United States in the form of unprocessed timber and is prohibited from being used as a substitute for exported private timber.

**CRUISE INFORMATION:** For All Harvest Areas and Right-Of-Way Timber: Douglas-fir, Grand Fir, and Incense-cedar under 40" DBH were 3P sampled, containing a total of 128 randomly selected sample trees. The sample trees have been cruised and their volume computed on form class tables for estimating volume in 16-foot lengths. The volume of the randomly selected sample trees has been expanded to a total sale volume. A map showing the location of the sample trees is available at the Roseburg District Office. All other merchantable species including Western Hemlock and Western Redcedar were 100% cruised.

With respect to merchantable trees of all species: the average tree is 15.2 inches D.B.H.O.B., the average log contains 64 bd. ft., the total gross volume is approximately 6,584 MBF and 92% recovery is expected.

**CUTTING AREA:** An area of approximately 4 acres distributed throughout 1 unit will be thinned, an area approximately 146 acres distributed throughout 6 units will be variable-retention regeneration harvested, and rights-of-ways totaling approximately 9 acres will be cleared.

**TIMBER ACREAGE:**

Area 1: 4 acres	Area 3: 4 acres	Area 5: 33 acres	Area 7: 46 acres
Area 2: 34 acres	Area 4: 14 acres	Area 6: 15 acres	R/W: 9 acres

**ACCESS:** Access to the sale area is provided by Government and privately controlled roads.

**DIRECTIONS TO SALE AREA:** From Roseburg, proceed south on Interstate 5 approximately 5.5 miles and take Exit 119 towards Winston. Then, travel west on Old Highway 99 for approximately 3 miles. At the intersection of Old Highway 99 and Highway 42 (NW Douglas BLVD), turn right, heading West onto Highway 42. Proceed approximately 9.1 miles, then turn right, heading North onto Reston Road. Proceed approximately 3.1 miles, turn left, heading West onto the 28-8-23.1 road. From there, follow the Exhibit D map to access Units 1 and 2.

From the 28-8-23.1 road, turn left, heading North on Reston Road. Proceed approximately 2.4 miles North on Reston Road to the intersection of Reston Road and Coos Bay Wagon Road. Turn left, heading West, onto Coos Bay Wagon Road:

- To access Unit 3, proceed on Coos Bay Wagon Road approximately 0.9 miles. Turn left, heading Southwest, onto the 28-8-15.1 road and follow the Exhibit D map to Unit 3.
- To access Units 4, 5, and 6, proceed on Coos Bay Wagon Road approximately 2.7 miles. Turn left, heading South onto the 28-8-16.2 road and follow the Exhibit D map to Units 4, 5, and 6.

- To access Unit 7, proceed on Coos Bay Wagon Road approximately 4.1 miles. Turn left, heading South onto the 28-8-20.1 road and follow the Exhibit D map to Unit 7.

**ROAD MAINTENANCE:** Rockwear and maintenance fees of \$4,866.05 will be required to be paid to the BLM; rockwear and maintenance fees of \$929.58 will be required to be paid to Roseburg Resource Co.; rockwear and maintenance fees of \$370.50 will be required to be paid to Lone Rock Timberland Co.; and rockwear and maintenance fees of \$68.40 will be required to be paid to Manulife Investment Management.

**ROAD CONSTRUCTION:** Estimates include the following: renovate 280+67 stations of road, construct 83+25 stations of road, and decommission 8+40 stations of road. Additional information is available in Exhibit C and Exhibit D of the Timber Sale Contract.

**DURATION OF CONTRACT** will be **36 months** for cutting and removal of timber. The contract will contain SPECIAL PROVISIONS regarding: logging; road construction, renovation, maintenance, and use; environmental protection; administrative check scaling; fire prevention and control; slash disposal and site preparation; snag creation; buyout securities; and log branding and painting.

**ADDITIONAL INFORMATION:** This prospectus includes maps and tables that cannot be made Section 508 compliant. For help with its data or information, please contact the Roseburg District Office at 541-440-4930.

**NOTES:**

1. Seasonal restrictions apply to this sale regarding logging operations, use of native surfaced roads and road work. Refer to Sections 44(A)(5)(b), 44(A)(6)(b), 44(A)(7)(b), 44(A)(11), 44(A)(12), 44(A)(13), 44(B)(2), 44(C)(3)(c), 44(C)(4)(d), 44(F)(1)(e)(8), and 44(F)(1)(e)(9) for details. A “seasonal restriction matrix” is included with this prospectus to serve as a guide in planning and scheduling operations.
2. Due to expiring Marbled Murrelets surveys, cutting and yarding operations in the yarding wedge of Harvest Unit 6 and Harvest Unit 6 shall be completed no later than March 1, 2029. See Exhibit F for detailed map of restricted areas.
3. License agreements with Roseburg Resources Co., Lone Rock Timberland LLC, Seneca Jones Timber Co., and Manulife Investment Management are required. The terms and conditions of the license agreement are available for inspection at the Roseburg District Office.
4. Slash disposal requirements consist of the following: machine piling, covering and burning slash and debris within a fifty (50) foot radius of landings; in unit machine piling, covering and burning slash within the portion of Harvest Area 7 designated for ground-based harvest; in unit hand piling, covering and burning slash within Harvest Areas 4 and 6; and in portions of Harvest Areas 2, 5, and 7, designated for cable harvest. The Purchaser will have the option to assist in burning or to make a buyout security deposit to the Bureau of Land Management in lieu thereof. Refer to Sections 44(F) and 44(H) for details.
5. Girdling (or felling) of approximately 543 trees in the Harvest Land Base to create snags (or down woody material) after completion of logging operations will be required. The purchaser will have to complete the snag creation requirements described in Section 44(G) and there will be no buyout security offered as shown in Section 44(H).
6. Upon completion of logging operations, the Purchaser shall, perform subsoiling operations on approximately seven tenths (0.7) of a mile of landings, main skid trails, and associated compacted areas such as turnouts, truck turnarounds and log decking areas as designated by the Authorized Officer. Refer to Section 44(C)(4) for details.

7. As appraised, approximately 79% of the sale area is available for wet season operations, including Harvest Areas 4 and 6, and portions of Harvest Areas 2, 5, and 7 (118 acres). Wet season operations may be maximized at the Purchaser's expense by:
- Cable yarding Harvest Area 1 to the existing rocked road (28-8-23.2) approved for wet season operations, instead of ground-based yarding (approximately 4 acres).
  - Cable yarding Harvest Area 3 to the existing rocked road (28-8-15.1) approved for wet season operations, instead of ground-based yarding (approximately 4 acres).
  - Adding rock to 28-8-20.2 and Spur 4 in Harvest Unit 7 as necessary for wet season cable yarding, instead of ground-based yarding (approximately 14 acres).

In order to maximize wet season operations, a logging plan must be submitted and approved by the Authorized Officer.

8. This contract contains provisions for the sale and removal of additional timber necessary to facilitate safe and efficient Purchaser operations. It is estimated that approximately 7 MBF of such additional timber would be removed under the contract but is not included in the advertised sale volume. Refer to Sections 44(A)(9) and 44(A)(10) for details.

The approximate additional timber volume associated with the yarding wedge to facilitate the operations of Harvest Unit 6 is not included in the above estimation.

9. In addition, this contract contains provisions for the protection and retention of trees in Harvest Areas that are greater than or equal to 40 inches DBH **and** that were established prior to 1850; trees meeting these criteria may be cut, if necessary for safety or operational reasons, but they will be retained as the property of the government and will not be sold or otherwise removed from the contract area. Refer to Sections 43(e), 44(A)(9)(b), 44(A)(10)(b), and 44(A)(10)(f)(3) for details.

THIS IS A SALE PROSPECTUS ONLY. ATTACHMENTS MAY NOT INCLUDE ALL EXHIBITS REFERRED TO IN THE CONTRACT PROVISIONS. THE COMPLETE CONTRACT, INCLUDING ALL EXHIBITS, IS AVAILABLE FOR INSPECTION AT THE ROSEBURG DISTRICT OFFICE.

Section 43. TIMBER RESERVED FROM CUTTING -The following timber in the Contract Area is hereby reserved from cutting and removal under the terms of this contract and is retained as the property of the Government.

- (a) All timber on the Reserve Areas, as shown on Exhibit A.
- (b) All retention trees marked with orange paint above and below stump height within the cutting areas and all orange painted and posted trees which are on or mark the boundaries of the Reserve Areas, as shown on Exhibit A.
- (c) All existing downed trees at the time of the timber cruise classified as decay Classes 3, 4, and 5 within the Harvest Areas, as shown on Exhibit A. Reserved existing downed trees may be bucked to facilitate yarding. Decay classes are illustrated on Exhibit E, which is attached hereto and made a part of hereof.
- (d) All snags in the Harvest Areas, as shown on Exhibit A. Snags which pose a hazard to operations may be felled with the approval of the Authorized Officer.
- (e) All trees in the Harvest Areas shown on Exhibit A that are both greater than or equal to ( $\geq$ ) forty (40) inches diameter at breast height (DBH) **and** were established prior to 1850, as determined by the Authorized Officer.

Section 44. The Purchaser shall comply with the special provisions which are attached hereto and made apart hereof, unless otherwise authorized in writing by the Authorized Officer.

Section 44(A) Logging:

- (1) Before beginning operations on the Contract Area for the first time or after a shutdown of ten (10) or more days, the Purchaser shall notify the Authorized Officer in writing of the day they plan to begin operations. The Purchaser shall also notify the Authorized Officer in writing if they intend to cease operations for any period of ten (10) or more days.
- (2) Prior to the commencement of operations, the Purchaser shall obtain from the Authorized Officer written approval of a written operations and logging plan commensurate with the terms and conditions of the contract which shall include measures needed to assure protection of the environment and watershed. A pre-work conference between the Purchaser's authorized representative and the Authorized Officer must be held at a location designated by the Authorized Officer before the logging plan will be approved. All logging shall be done in accordance with the plan developed by this provision.
- (3) In the Harvest Areas shown on Exhibit A, all trees designated for cutting which are within one hundred (100) feet of the Reserve Areas shall be felled and yarded away from these areas.
- (4) No yarding, skidding or log loading is permitted in or through the Reserve Areas or retention aggregates as shown on Exhibit A, unless otherwise approved by the Authorized Officer.
- (5) In Thinning Harvest Area 1 shown on Exhibit A, all trees designated for cutting shall be manually felled, limbed and cut into log lengths not to exceed forty-two (42) feet before being yarded, unless otherwise approved by the Authorized Officer. Thinning Harvest Area 1 may be felled mechanically using a feller-processor or feller-buncher with the approval of the Authorized Officer and in accordance with the following specifications:
  - (a) Mechanized felling operations shall generally be limited to slopes of thirty-five (35) percent or less.
  - (b) Mechanized felling operations are subject to seasonal operating restrictions as described in Section 44(A)(7)(b) of this contract.
  - (c) The feller-processor or feller-buncher shall be approved by the Authorized Officer prior to the start of mechanized felling operations. Only purpose-built carriers with boom-mounted felling heads may be approved. The purpose-built carrier may be of the articulated, rubber-tired design or the zero tail swing, leveling, track-mounted design.
  - (d) In Harvest Areas where mechanical felling is permitted with the approval of the Authorized Officer, all trees designated for cutting may be felled and whole tree yarded except when excessive stand damage occurs as determined by the Authorized Officer. If excessive stand damage occurs, all trees shall be completely

limbed and bucked into log lengths not to exceed forty-two (42) feet prior to being yarded.

- (6) In Variable-Retention Regeneration Harvest Areas 2, 3, 4, 5, 6, and 7 shown on Exhibit A, all trees designated for cutting shall be manually felled, unless otherwise approved by the Authorized Officer. In Variable-Retention Regeneration Harvest Area 3, and portions of Variable-Retention Regeneration Harvest Areas 2, 5, and 7 may be felled mechanically using a feller-processor or feller-buncher with the approval of the Authorized Officer and in accordance with the following specifications:
- (a) Mechanized felling operations shall generally be limited to slopes of thirty-five (35) percent or less.
  - (b) Mechanized felling operations are subject to seasonal operating restrictions as described in Section 44(A)(7)(b) of this contract.
  - (c) The feller-processor or feller-buncher shall be approved by the Authorized Officer prior to the start of mechanized felling operations. Only purpose-built carriers with boom-mounted felling heads may be approved. The purpose-built carrier may be of the articulated, rubber-tired design or the zero tail swing, leveling, track-mounted design.
- (7) In Harvest Areas 1 and 3, and portions of Harvest Areas 2, 5, and 7 designated for ground-based yarding as shown on Exhibit A (approximately 32 acres):
- (a) Ground-based yarding operations shall generally be limited to slopes of thirty-five (35) percent or less, and existing skid trails shall be utilized to the greatest extent possible.
  - (b) No ground-based yarding shall be permitted between October 15 of one calendar year and May 15 of the following calendar year, both days inclusive, or other periods of unseasonably wet weather and soil moisture conditions, unless otherwise approved by the Authorized Officer.
  - (c) A rubber-tired or track-mounted skidder may be used in accordance with the following specifications:
    - (1) The skidder shall be approved by the Authorized Officer prior to ground-based yarding operations.
    - (2) Yarding shall be done with one end of the log suspended.
    - (3) The skidder shall be restricted to designated skid trails. Skid trails shall be clearly identified on the ground, twelve (12) feet or less in width and spaced at least one hundred fifty (150) feet apart. Designated skid trails, whether existing or newly proposed, shall be approved by the Authorized Officer prior to the felling of timber.

- (d) A track-mounted log loader, or shovel yarding system, may be used in accordance with the following specifications:
  - (1) The track-mounted log loader shall be approved by the Authorized Officer prior to ground-based yarding operations.
  - (2) The track-mounted log loader shall be restricted to designated skid trails and shall utilize the swing yarding method to the greatest extent practicable. The designated skid trail network shall minimize both the amount of ground covered by the tractor treads and the number of passes over any single spot on the ground. Designated skid trails, whether existing or newly proposed, shall be approved by the Authorized Officer prior to the felling of timber.
  - (3) The track-mounted log loader shall be required to place logging slash in front of the machine's tracks prior to traveling designated skid trails in order to reduce soil compaction.
  
- (e) A cut-to-length system may be used in accordance with the following specifications:
  - (1) The harvester shall be required to cut off limbs and tops in front of the machine's tracks in order to reduce the potential for soil compaction. The harvester must have a lateral reach of twenty (20) feet or more, and the machine's lateral reach must be utilized as much as possible.
  - (2) The forwarder shall operate only on designated skid trails approved by the Authorized Officer. Forwarder trails shall be located on existing skid trails and/or the slash-covered areas traversed by the harvester. Forwarder trails shall be perpendicular to hill-slope contour lines as much as possible. Forwarder trails shall be located such that there are two harvester trails between forwarder trails, resulting in a spacing of at least one hundred (100) feet between forwarder trails.
  - (3) Logs that are too large for the harvester/forwarder operation may be yarded with a rubber-tired or track-mounted skidder, or a track-mounted log loader approved by the Authorized Officer, and as directed by the Authorized Officer. The skidder shall operate on designated skid trails approved by the Authorized Officer.
  
- (8) In the Variable-Retention Regeneration Harvest Areas 4 and 6, and portions of Harvest Areas 2, 5, and 7 designated for cable yarding as shown on Exhibit A (approximately 118 acres):
  - (a) Yarding shall be done with a cable skyline system utilizing a mechanical slack-pulling carriage capable of maintaining a fixed position on the skyline while lateral yarding and having a lateral capability of seventy-five (75) feet. The carriage must not move during in-haul. The system shall have the capability to yard in multi-span configuration.

- (b) The leading end of all logs shall be suspended free of the ground during yarding. Lift trees and/or intermediate support trees shall be employed where necessary to meet this requirement.
  - (c) All logs shall be yarded away from or parallel to streams as shown on Exhibit A.
  - (d) Prior to attaching any logging equipment to a reserve tree, the Purchaser shall obtain approval from the Authorized Officer and shall take precautions to protect the tree from damage as directed by the Authorized Officer.
  - (e) Trees designated for cutting shall be yarded with limbs attached to the bole and the top attached to the top log, unless approved by the Authorized Officer.
- (9) Before cutting and removing any trees necessary to facilitate logging in the Harvest Areas shown on Exhibit A, the Purchaser shall identify the location of the skid trails, cable yarding corridors, and tailhold, tieback, guyline, lift, intermediate support, and danger trees on the ground in a manner approved by the Authorized Officer at the pre-work conference and documented in the logging plan. Said Purchaser identification of trees to be cut and removed does not constitute authority to proceed with cutting and removal. In addition, before proceeding with cutting the following conditions must be met:
- (a) All skid trails and/or cable yarding corridors upon which timber is identified by the Purchaser to be cut and removed in accordance with this special provision must be necessary for the safe and expeditious removal of timber sold under this contract and shall be limited to the minimum width necessary for yarding of logs with a minimum of damage to reserve trees, however, unless otherwise approved in writing by the Authorized Officer, the width of skid trails shall be limited to twelve (12) feet and cable yarding corridors shall be limited to fifteen (15) feet.
  - (b) The Purchaser shall take all reasonable measures to limit the need for cutting any Harvest Area tree that is greater than or equal to ( $\geq$ ) forty (40) inches DBH and that was established prior to 1850, as determined by the Authorized Officer. Where cutting such trees is necessary for safety or operational reasons, as determined by the Authorized Officer, the Purchaser may immediately cut, but shall not remove, the trees when the trees have been marked with yellow paint above and below stump height by the Authorized Officer and thereby approved for cutting but not removal by the Authorized Officer.
  - (c) The Purchaser may immediately cut and remove additional timber to clear skid trails and cable yarding corridors; and provide tailhold, tieback, guyline, lift and intermediate support trees; and to clear danger trees when the trees have been marked with blue paint above and below stump height by the Authorized Officer and thereby approved for cutting and removal by the Authorized Officer. The volume of the timber to be sold will be determined by the Authorized Officer in accordance with Bureau of Land Management prescribed procedures. No timber may be cut or removed under terms of this provision unless sufficient installment payments have been made in accordance with Section 3(b) of the contract or sufficient bonding has been provided in accordance with Section 3(f) of the contract.

- (d) The Purchaser agrees that sale of this additional timber shall be accomplished by a unilateral modification of the contract executed by the Contracting Officer and that such timber shall be sold at the unit prices shown in Exhibit B of this contract unless: the value of the timber must be reappraised subject to the terms for contract extension set forth in Section 9 of the contract; or the Authorized Officer determines that trees otherwise reserved in Section 43 of the contract or any tree that exceeds thirty-two (32) inches diameter at breast height shall be appraised and sold by bilateral modification of the contract at current fair market value in accordance with Section 8 of the contract.
  - (e) This authorization for the Purchaser to cut and remove additional timber prior to the execution of a modification may be withdrawn by the Contracting Officer if the Authorized Officer determines that the Purchaser has cut and removed any tree not previously marked and approved for cutting by the Authorized Officer, which under Section 10 of the contract constitutes a violation of the contract and under Section 13 of the contract may constitute a trespass rendering the Purchaser liable for damages under applicable law.
  - (f) If authorization is withdrawn, the Contracting Officer shall issue a written notice to the Purchaser that the sale of additional timber under this special provision is no longer approved. In this case, the Purchaser shall inform the Authorized Officer at least one (1) working day prior to the need for cutting and removing any additional timber, and execute a bilateral modification prior to cutting for such additional approved timber at the unit prices shown in Exhibit B of the contract or in accordance with Section 8 or Section 9 of the contract as determined by the Authorized Officer in accordance with this provision. The Contracting Officer may issue a written order to the Purchaser to suspend, delay, or interrupt any or all contract work for the period of time deemed necessary and appropriate for the Government to safely measure and mark additional timber.
  - (g) The Government may reserve trees previously designated for cutting and removal by applying orange paint as replacements for additional trees cut and removed for skid trails and/or cable yarding corridors when the Authorized Officer determines such reservation is necessary to maintain stand densities consistent with objectives set forth in the management prescription(s). This may include the replacement of trees damaged by storm events, or insects or disease. The volume of this timber to be reserved will be determined by the Authorized Officer in accordance with Bureau of Land Management prescribed procedures and the value shall be based on the unit prices shown in Exhibit B of the contract. The Purchaser agrees that the Total Purchase Price shall be reduced accordingly through a unilateral modification to the contract executed by the Contracting Officer.
- (10) In accordance with the requirements of Section 8 it has been determined that the sale of additional timber located in the Contract Area, as shown on Exhibit A, which is obstructing needed cable yarding corridors, hazardous to workers, needed for guyline, tail hold or tieback trees, and/or severely damaged from the normal conduct of felling or yarding operations is needed to meet all applicable State safety laws, codes or regulations. This timber must be cut

or removed so that the Purchaser can continue active falling and yarding operations. The Purchaser is, therefore, authorized to cut and remove such additional timber in accordance with the provisions of Section 8 of the contract; provided that:

- (a) Trees reserved for the tree improvement program and trees reserved for the wildlife habitat objectives under Section 43 of the contract are not included in the authorization.
- (b) Trees in the Harvest Areas that are greater than or equal to ( $\geq$ ) forty (40) inches DBH **and** that were established prior to 1850, as determined by the Authorized Officer, are not included in the authorization.
- (c) The Purchaser shall identify each tree sold and cut in accordance with the provision by marking the cut surface of the stump and the bottom log immediately after falling with high visibility red paint. The stump shall be marked by flagging the location of the stump with plastic fluorescent pink ribbon hung within five (5) feet of the stump at eye level so that the stump can be visually located from a distance of not less than one hundred (100) feet.
- (d) The volume and value for such timber shall be determined by the Authorized Officer in accordance with Bureau of Land Management prescribed procedures and paid for by the Purchaser in accordance with Section 3(b) or 3(f) of the contract through a unilateral modification executed by the Contracting Officer.
- (e) No timber may be cut or removed under the terms of this provision until all contract payments required by Section 3(b) or 3(f) of the contract have been made.
- (f) The permission to cut and remove additional timber contained in this provision may be withdrawn by the Contracting Officer if the Authorized Officer determines that the Purchaser:
  - (1) Failed to properly mark any stump as designated in this provision.
  - (2) Failed to identify the location of any stump.
  - (3) Cut any Harvest Area tree that was greater than or equal to ( $\geq$ ) forty (40) inches DBH **and** that was established prior to 1850.
  - (4) Cut any tree that was reserved for tree improvement and/or wildlife habitat.
  - (5) Cut any tree in or adjacent to cable yarding corridors that was not necessary to facilitate cable yarding.
  - (6) Cut any reserve tree in or adjacent to skid trails that was not necessary to facilitate ground based yarding.
  - (7) Failed to properly segregate any pulled-over tree that was yarded to the landing.
  - (8) Cut any reserve tree that was not severely damaged (as defined during the pre-work conference) from felling and yarding operations.
  - (9) Cut more than the minimum number of trees necessary to properly serve as guyline anchor stumps.
  - (10) Cut or topped more than the minimum number of trees necessary to properly serve as tail hold trees.

- (11) Cut more than the minimum number of trees necessary to properly serve as tie-backs for topped tail hold trees.
- (12) Failed to maintain accurate and current (no more than twenty-four [24] hours old) documentation of additional timber cut and removed.

If the permission to cut and remove additional timber provision is withdrawn, the Authorized Officer shall deliver to the Purchaser a written notice that additional sale of timber under this special provision is no longer approved.

If the permission to cut and remove additional timber provision is withdrawn, the Purchaser shall inform the Authorized Officer at least two (2) working days prior to the need for cutting and yarding any guyline tree, tailhold tree, tie-back tree, danger tree, corridor tree, pulled over tree, and severely damaged tree. All sales of additional timber shall comply with Section 8 of the contract. The Contracting Officer may order the Purchaser, in writing, to suspend, delay, or interrupt all or any part of the work of this contract for the period of time that the Contracting Officer determines appropriate for the Government to safely measure and mark additional timber.

All cable yarding corridors and/or ground based equipment skid trails upon which timber may be cut and removed in accordance with this special provision must be needed for the removal of timber sold under this contract and shall be limited to the narrowest width necessary for the yarding of logs with minimum damage to reserved trees.

The Purchaser shall be liable for damages in accordance with Section 13 of the contract for any reserved timber cut or removed in violation of the terms of this special provision.

- (11) Except for right-of-way logging, no falling or yarding shall be conducted in Thinning Harvest Area 1, as shown on Exhibit A, between April 15 and July 15 (bark slip period), both days inclusive, unless otherwise approved by the Authorized Officer.
- (12) Due to expiring Marbled Murrelets surveys, cutting and yarding operations in the yarding wedge and Harvest Unit 6 shall be completed no later than March 1, 2029. See Exhibit F for detailed map of restricted areas.
- (13) No logging activity or log hauling shall be conducted on unsurfaced roads between October 15 of one calendar year and May 15 of the following calendar year (wet season), both days inclusive, unless otherwise approved by the Authorized Officer.
- (14) For a distance of fifty (50) feet from the perimeter of each landing designated by the Authorized Officer, all logs more than eight (8) inches in diameter at the large end and longer than eight (8) feet in length shall be decked or windrowed at the location designated by the Authorized Officer, except logs sold and removed from the Contract Area. If a log or piece of log meeting or exceeding the above specifications is bucked and left in place, all portions of that log shall be yarded and decked at the above described location.

Section 44(B) Road Construction, Maintenance & Use:

- (1) Purchaser shall construct and renovate roads, as shown on Exhibit A and Exhibit C. Any required construction, renovation or pre-haul maintenance shall be completed in strict accordance with the plans and specifications shown on Exhibit C, which is attached hereto and made a part hereof. Any required construction, renovation, or pre-haul maintenance of structures and roads shall be completed and accepted, in accordance with Section 18, prior to the removal of any timber, except right-of-way timber, over that road.
- (2) No road construction or renovation shall be conducted between October 15 of one calendar year and May 15 of the following calendar year, both days inclusive, or other periods of unseasonably wet weather and soil moisture conditions, unless otherwise approved by the Authorized Officer.
- (3) Upon completion of logging operations, the following roads and spurs shall be decommissioned in strict accordance with the plans and specifications shown on Exhibit D, which is attached hereto and made a part hereof: Road 28-8-20.2 Segment C and Spur 4.
- (4) The Purchaser is authorized to use the roads listed and shown on Exhibit D which are under the jurisdiction of the Bureau of Land Management for the removal of Government timber sold under the terms of this contract provided that the Purchaser pay the required maintenance and rockwear obligations described in Section 44(B)(5). Any road listed on Exhibit D and requiring improvement or renovation in Exhibit C of this contract shall be maintained by the Purchaser until receiving written acceptance of the construction or renovation from the Authorized Officer. The Purchaser shall pay current Bureau of Land Management maintenance and rockwear fees for the sale of additional timber under modification to the contract.
- (5) The Purchaser shall pay the Government a rockwear and maintenance obligation in the amount of Four Thousand Eight Hundred Sixty-Six and 05/100 dollars (\$4,866.05) for the transportation of timber included in the contract price over roads listed on the Exhibit D. The above rockwear and maintenance amount is for use of four and four tenths (4.4) miles of road or less. Unless the total rockwear and maintenance amount is paid prior to commencement of operations on the Contract Area, payments shall be made in installments of not less than Five Hundred and No/100 dollars (\$500.00) payable in the same manner as and together with payments required in Section 3 of this contract.
- (6) The Purchaser shall perform any required road repair and maintenance work on roads used by them, under the terms of Exhibit D of this contract.
- (7) The Purchaser also agrees that if they elect to use any other private road which is the subject of a right-of-way agreement with the Government for the removal of Government timber sold under the terms of this contract, the Purchaser shall request and agree to the modification of this contract to provide for such use and for allowances for amortization of the Government's share of the capital investment of any such road.

**IF OTHER THAN ROSEBURG RESOURCES CO PURCHASES:**

- (8) In the use, construction or renovation of Road 28-8-16.2 Segment A, the Purchaser shall comply with the conditions, including but not limited to those set out below, of the Right-of-Way and Road Use Agreement R-976B, dated April 17, 1981, between the United States of America and Roseburg Resources Co, available for inspection at the Bureau of Land Management, Roseburg District Office, 777 N.W. Garden Valley Blvd., Roseburg, Oregon 97471. These conditions include:
- (a) Prior to the use of said roads, the Purchaser shall furnish the Authorized Officer a copy of the executed license agreement.
  - (b) Payment of a rockwear obligation in the amount of Nine Hundred Twenty-Nine and 58/100 dollars (\$929.58).
  - (c) Payment of a road use obligation in the amount of Three Hundred Fifty-Two and 26/100 dollars (352.26).
  - (d) Default by the Purchaser of said Right-of-Way and Road Use Agreement, or any License Agreement executed pursuant thereto, for failure to pay appropriate stumpage fees, road use fees or road maintenance fees shall be considered a violation of this contract. The amount of unpaid fees shall be considered as the amount of damage suffered by the Government as a result of the violation of this provision.
- (9) In the use, construction or renovation of Road 28-8-23.6 Segment B, the Purchaser shall comply with the conditions, including but not limited to those set out below, of the Right-of-Way and Road Use Agreement R-851, dated August 15, 1967, between the United States of America and Roseburg Resources Co, available for inspection at the Bureau of Land Management, Roseburg District Office, 777 N.W. Garden Valley Blvd., Roseburg, Oregon 97471. These conditions include:
- (a) Prior to the use of said roads, the Purchaser shall furnish the Authorized Officer a copy of the executed license agreement.
  - (b) Payment for right-of-way timber from the construction of Road 28-8-23.6 Segment B located in the NE $\frac{1}{4}$ NW $\frac{1}{4}$  Section 26, T. 28 S., R. 8 W., WM., to Roseburg Resources Co., prior to cutting – timber volume and value to be determined.
  - (c) Default by the Purchaser of said Right-of-Way and Road Use Agreement, or any License Agreement executed pursuant thereto, for failure to pay appropriate stumpage fees, road use fees or road maintenance fees shall be considered a violation of this contract. The amount of unpaid fees shall be considered as the amount of damage suffered by the Government as a result of the violation of this provision.

**IF ROSEBURG RESOURCES CO PURCHASES:**

- (10) The Government is hereby granted the allowance listed here as payment towards the Government's share of the replacement cost of the following road(s) included in Right-of-Way and Road Use Agreement R-976B:

<b>Agreement</b>	<b>Road</b>	<b>Volume (MBF)</b>	<b>Road Use Fee</b>	<b>Subtotal</b>
R-976B	28-8-16.2A	1,957	\$0.18	\$352.26
<b>Total Road Use Fees:</b>				<b>\$352.26</b>

It is understood that the purchase price stated in Section 2 of this contract is the net price and no deductions will be made from the purchase price because of such allowances.

**IF OTHER THAN LONE ROCK TIMBERLAND LLC PURCHASES:**

- (11) In the use, construction or renovation of Road 28-8-23.1 Segment A, the Purchaser shall comply with the conditions, including but not limited to those set out below, of the Right-of-Way and Road Use Agreement R-768, dated September 17, 1964, between the United States of America and Lone Rock Timberland LLC, available for inspection at the Bureau of Land Management, Roseburg District Office, 777 N.W. Garden Valley Blvd., Roseburg, Oregon 97471. These conditions include:

- (a) Prior to the use of said roads, the Purchaser shall furnish the Authorized Officer a copy of the executed license agreement.
- (b) Payment of a rockwear obligation in the amount of Three Hundred Seventy and 50/100 dollars (\$370.50).
- (c) In the construction of Road 28-8-23.6 Segments A, the purchaser shall provide payment for right-of-way timber located in SW¼SE¼, Section 23, T. 28 S., R 8 W., W.M., to Lone Rock Timberland LLC, prior to cutting as follows:

<b>Number of Trees</b>	<b>Species</b>	<b>Estimated Volume (MBF)</b>	<b>Appraised Price per MBF</b>	<b>Value</b>
24	Douglas-fir	5.7	\$293.72	\$1,674.20
24	<b>Totals</b>	5.7		\$1,674.20

- (d) Default by the Purchaser of said Right-of-Way and Road Use Agreement, or any License Agreement executed pursuant thereto, for failure to pay appropriate stumpage fees, road use fees or road maintenance fees shall be considered a violation of this contract. The amount of unpaid fees shall be considered as the amount of damage suffered by the Government as a result of the violation of this provision.

**IF OTHER THAN SENECA JONES TIMBER CO PURCHASES:**

- (12) In the use, construction or renovation of Road 28-8-20.1 Segment A, 28-8-20.2 Segment A, and 28-8-20.3 Segment A, the Purchaser shall comply with the conditions, including but not

limited to those set out below, of the Right-of-Way and Road Use Agreement R-656, dated April 3, 1962, between the United States of America and Seneca Jones Timber Co., available for inspection at the Bureau of Land Management, Roseburg District Office, 777 N.W. Garden Valley Blvd., Roseburg, Oregon 97471. These conditions include:

- (a) Prior to the use of said roads, the Purchaser shall furnish the Authorized Officer a copy of the executed license agreement.
- (b) Payment of a road use obligation in the amount of Sixty-Seven Thousand Two Hundred Three and 95/100 dollars (\$67,203.95).
- (c) In the construction of Road 28-8-20.2 Segment B and Road 28-8-20.3 Segment B, the purchaser shall provide payment for right-of-way timber located in SE¼SW¼ and SW¼SW¼, Section 20, T. 28 S., R 8 W., W.M., to Seneca Jones Timber Co., prior to cutting as follows:

Number of Trees	Species	Estimated Volume (MBF)	Appraised Price per MBF	Value
41	Douglas-fir	2.9	\$314.27	\$911.38
2	Western Hemlock	0.1	\$82.54	\$8.25
43	<b>Totals</b>	3.0		\$919.63

- (d) Default by the Purchaser of said Right-of-Way and Road Use Agreement, or any License Agreement executed pursuant thereto, for failure to pay appropriate stumpage fees, road use fees or road maintenance fees shall be considered a violation of this contract. The amount of unpaid fees shall be considered as the amount of damage suffered by the Government as a result of the violation of this provision.

**IF SENECA JONES TIMBER CO PURCHASES:**

- (13) The Government is hereby granted the allowance listed here as payment towards the Government's share of the replacement cost of the following road(s) included in Right-of-Way and Road Use Agreement R-656:

Agreement	Road	Volume (MBF)	Road Use Fee	Subtotal
R-656	28-8-20.1A	2,395	\$12.83	\$30,727.85
R-656	28-8-20.2A	790	\$8.79	\$6,944.10
R-656	28-8-20.3A	1,605	\$18.40	\$29,532.00
<b>Total Road Use Fees:</b>				<b>\$67,203.95</b>

It is understood that the purchase price stated in Section 2 of this contract is the net price and no deductions will be made from the purchase price because of such allowances.

**IF OTHER THAN MANULIFE INVESTMENT MANAGEMENT PURCHASES:**

- (14) In the use, construction or renovation of Road 28-8-21.0 Segment B and Segment C Portion, the Purchaser shall comply with the conditions, including but not limited to those set out below, of the Right-of-Way and Road Use Agreement R-976A, dated April 17, 1981, between

the United States of America and Manulife Investment Management, available for inspection at the Bureau of Land Management, Roseburg District Office, 777 N.W. Garden Valley Blvd., Roseburg, Oregon 97471. These conditions include:

- (a) Prior to the use of said roads, the Purchaser shall furnish the Authorized Officer a copy of the executed license agreement.
- (b) Payment of a rockwear obligation in the amount of Sixty-Eight and 40/100 dollars (\$68.40).
- (c) Payment of a road use obligation in the amount of Four Thousand Nine Hundred and 00/100 dollars (\$4,900.00).
- (d) In the renovation of Road 28-8-22.1 Segment A, the purchaser shall provide payment for right-of-way timber located in NW¼NW¼, Section 22, T. 28 S., R 8 W., W.M., to Manulife Investment Management, prior to cutting as follows:

Number of Trees	Species	Estimated Volume (MBF)	Appraised Price per MBF	Value
11	Douglas-fir	0.6	\$296.01	\$177.61
11	<b>Totals</b>	0.6		\$177.61

- (e) Default by the Purchaser of said Right-of-Way and Road Use Agreement, or any License Agreement executed pursuant thereto, for failure to pay appropriate stumpage fees, road use fees or road maintenance fees shall be considered a violation of this contract. The amount of unpaid fees shall be considered as the amount of damage suffered by the Government as a result of the violation of this provision.

**IF MANULIFE INVESTMENT MANAGEMENT PURCHASES:**

- (15) The Government is hereby granted the allowance listed here as payment towards the Government's share of the replacement cost of the following road(s) included in Right-of-Way and Road Use Agreement R-976A:

Agreement	Road	Volume (MBF)	Road Use Fee	Subtotal
R-976A	28-8-21.0B	400	\$3.26	\$1,304.00
R-976A	28-8-21.0C (Por)	400	\$8.99	\$3,596.00
<b>Total Road Use Fees:</b>				<b>\$4,900.00</b>

It is understood that the purchase price stated in Section 2 of this contract is the net price and no deductions will be made from the purchase price because of such allowances.

**Section 44(C) Environmental Protection:**

- (1) In addition to the requirements set forth in Section 26 of this contract, the Purchaser shall clean road surfaces, cut banks, landings, ditch lines and culverts of all debris created by logging operations.

- (2) In addition to the requirements set forth in Section 26 of this contract, the Purchaser shall steam clean or pressure wash all logging and road building equipment, except logging trucks, prior to initial move-in, to minimize the likelihood of spreading noxious weeds and non-native plant species to the Contract Area. Equipment washing shall occur at a location approved by the Authorized Officer. Equipment will be visually inspected by the Authorized Officer prior to use. Any logging or road building equipment removed from the Contract Area during the duration of the contract must be steam cleaned or pressure washed before it is returned to the Contract Area. Cleaning shall be defined as removal of all dirt, grease, plant parts and material that may carry noxious weed seeds.
  
- (3) In addition to the requirements set forth in Section 26 of this contract, the Purchaser shall winterize all native surfaced roads used under Section 44(B)(1) or any portion thereof, in accordance with the plans and specifications shown on Exhibit D, and in accordance with the following stipulations:
  - (a) The Purchaser intends to use the native surfaced roads or portions thereof for more than a single operating season; or, circumstances require that the roads or portions thereof overwinter before decommissioning.
  - (b) Winterizing shall consist of water-barring, blocking and mulching to the satisfaction of the Authorized Officer.
  - (c) Winterizing shall take place prior to the end of the operating season as described in Section 44(A)(13) of this contract, or as directed by the Authorized Officer.
  
- (4) In addition to the requirements set forth in Section 26 of this contract, the Purchaser shall, upon completion of logging operations, perform subsoiling operations on approximately seven-tenths (0.7) mile of landings, main skid trails, and associated compacted areas such as turnouts, truck turnarounds and log decking areas as designated by the Authorized Officer and in accordance with the following stipulations:
  - (a) All subsoiling equipment shall be inspected and approved by the Authorized Officer before subsoiling begins.
  - (b) The compacted surfaces shall be subsoiled (broken up, loosened, and de-compacted) using excavator attachments, log loader tongs or other approved equipment.
  - (c) Slash and other organic debris and some topsoil will be spread over the subsoiled surface to cover at least (50) percent of the subsoiled area, where levels of this material are available. Waterbars shall be constructed concurrently with subsoiling operations on grades steeper than ten (10) percent, as directed by the Authorized Officer.
  - (d) Subsoiling shall occur during the same dry season as ground-based harvesting as described in Section 44(A)(7)(b), unless otherwise approved by the Authorized Officer.

- (e) Subsoiling shall be completed to a minimum depth of eighteen (18) inches below the ground surface, unless otherwise approved by the Authorized Officer.
- (f) Treated areas shall span the total width of compaction, as identified by the Authorized Officer. At least eighty (80) percent of the compacted soil profile shall be shattered. No more than fifty (50) percent of the treated soil shall have clods greater than two (2) inches in diameter, unless otherwise approved by the Authorized Officer.
- (g) Subsoiling shall not occur within a five foot radius of the boles of residual trees where major roots can be cut, mangled or pulled, unless otherwise directed by the Authorized Officer.
- (h) Equipment shall not be allowed to operate on slopes in excess of thirty-five (35) percent or to cross streams or drainages unless approved by the Authorized Officer.

Section 44(D) Miscellaneous:

- (1) The Government, at its option, may administratively check scale any portion of the timber removed from the Contract Area, and if necessary, conduct check scaling of independent scalers contracted to BLM for administrative check scaling purposes. The Purchaser hereby agrees to make such contract timber available for such scaling at a location or locations to be approved in writing by the Authorized Officer. At the approved location or locations, the Purchaser shall provide an area for logs to be safely rolled out for scaling, to unload logs from trucks, place logs in a manner so that both ends and three faces of each log are visible for scaling, and to reload or remove logs after scaling has been completed. In the event that BLM elects to administratively check scale, and if such check scaling causes a delay in log transportation time, an adjustment will be made to the purchase price as follows: if the entire sale is check scaled, the purchase price of this contract shall be reduced by Four Thousand Five Hundred Fifty-Three and 25/100 dollars (\$4,553.25); in the event only a portion of the contract timber is scaled, the purchase price shall be reduced by that portion of Four Thousand Five Hundred Fifty-Three and 25/100 dollars (\$4,553.25); which is equal to the percentage of timber sold which was actually scaled by the Government. For purposes of computing this price reduction, the percentage of timber sold which has been scaled shall be determined by the Government. Any reduction in purchase price under the terms of this provision shall be full compensation to the Purchaser for any expense or loss incurred as a result of such scaling. Scaling shall be conducted in accordance with the Eastside (Scribner Decimal C) Rules by BLM scalers, and/or independent scalers contracted to BLM. A copy of the scale report will be made available to Purchaser upon request.

Section 44(E) Fire Prevention and Control:

- (1) Primarily for purposes of fire prevention and control, the Purchaser shall, prior to the operation of power driven equipment in construction or logging operations under this contract during the closed fire season or periods of fire danger, prepare a fire prevention and control plan to the satisfaction of the Authorized Officer.

Section 44(F) Slash Disposal and Site Preparation:

- (1) Fire Hazard Reduction. In addition to the requirements of Section 15 of this contract, and notwithstanding the Purchaser's satisfactory compliance with state laws and regulations regarding offsetting or abating the additional fire hazard created by this operation and the State's willingness to release the Purchaser from liability for such hazard, the Purchaser shall remain responsible to the Government for performance of the following hazard reduction measures required by this contract:
  - (a) Slash shall be disposed of in accordance with the written instructions of the Authorized Officer.
  - (b) Slash, as defined for this section, shall mean all material (brush, limbs, tops, unmerchantable stems and chunks) severed or knocked over as a result of the Purchaser's operations under the terms of this contract.
  - (c) Covering of slash piles shall be done concurrently with piling operations. The covers shall be firmly fixed to each pile.
  - (d) Finished piles shall be tight and free of earth.
  - (e) Machine pile and cover all slash within fifty (50) feet of all landings (approximately 41 landings) and the portion of Harvest Area 7 designated for ground-based harvest, as shown on Exhibit A (approximately 14 acres), and other locations as directed by Authorized Officer in accordance with the following specifications:
    - (1) Landings shall be piled and covered within thirty (30) days of the completion of yarding from each landing.
    - (2) Machine piles shall be capped with a ten (10) foot by ten (10) foot cover of four (4) mil black plastic to maintain a dry ignition point
    - (3) Machine piles shall be located away from unit boundaries, retention trees, snags, downed logs and stumps.
    - (4) Maximum off-road machine pile size shall be twenty (20) feet in diameter by (10) feet in height.
    - (5) Off-road machine piling operations shall generally be limited to slopes of fifty (50) percent or less; when operating on slopes between thirty-five (35) and fifty (50) percent, equipment shall be required to travel straight up and down the slope, thereby minimizing soil displacement associated with side-hill travel.
    - (6) In order to limit soil disturbance, the piling method shall minimize both the total amount of ground covered by the tractor treads and the number of passes over any single spot on the ground.

- (7) Equipment used for off-road machine piling shall be approved by the Authorized Officer prior to the start of operations; only small or medium-sized excavators (track-hoes) may be approved.
  - (8) Off-road machine piling operations are subject to seasonal operating restrictions as described in Section 44(A)(7)(b) of this contract.
  - (9) Off-road machine piling and covering shall be completed the first dry season (July 15 – October 15) following the completion of logging operations in each harvest area.
- (f) Hand pile and cover all slash in Harvest Areas 4 and 6, and in portions of Harvest Areas 2, 5, and 7, designated for cable harvest, as shown on Exhibit A, which is attached hereto and make a part hereof, or as directed by the Authorized Officer, in accordance with the following specifications:
- (1) All logging slash and slashed brush more than two (2) feet long and between one (1) and six (6) inches in diameter at the large end shall be hand piled and covered. Larger material which has a portion meeting this specification must be bucked at the six (6) inch diameter, and that portion piled.
  - (2) Piles shall be located as directed by the Authorized Officer. No pile shall be located on down logs or within ten (10) feet of any other pile, orange painted reserve trees, or the unit boundary, unless approved by the Authorized Officer.
  - (3) Maximum pile size shall be eight (8) feet in diameter by six (6) feet in height. Minimum pile size shall be four (4) feet in diameter by four (4) feet in height.
  - (4) Covering shall be done concurrently with piling. A minimum of fifty (50) percent of the pile is to be covered using four (4) mil. black plastic or equivalent, and anchored or weighted down to the satisfaction of the Authorized Officer.
  - (5) Operations required by this provision shall begin within thirty (30) days after completion of logging of each Harvest Area and shall be concluded within sixty (60) days after completion of logging of each Harvest Area.
- (g) The Purchaser shall perform logging residue reduction and site preparation work by machine piling on approximately 14 acres of harvest area located in portion of Harvest Area 7; and hand piling on approximately 12 acres of harvest area located in Harvest Areas 4 and 6, and in portions of Harvest Areas 2, 5, and 7, as shown on Exhibit A.
- (1) The required work shall consist of any treatment or combination of treatments listed in the table below, as determined by the Authorized Officer and specified in writing by the Contracting Officer. The number of acres of each treatment shall be determined by the Authorized Officer.

<b>Treatment</b>	<b>Cost/Acre</b>
Machine Pile + Cover	\$550.00
Machine Pile Burn	\$95.00
Hand Pile + Cover	\$650.00
Hand Pile Burn	\$95.00

- (2) The required work shall consist of any treatment or combination of treatments listed in the table below, as determined by the Authorized Officer and specified in writing by the Contracting Officer. The number of acres of each treatment shall be determined by the Authorized Officer.

The following treatments were assumed for appraisal purposes on this contract:

<b>Appraised Treatment</b>	<b>Acres</b>	<b>Cost/Acre</b>	<b>Total Cost/Treatment</b>
Machine Pile + Cover	14	\$550.00	\$7,700.00
Machine Pile Burn	14	\$95.00	\$1,330.00
Hand Pile + Cover	12	\$650.00	\$7,800.00
Hand Pile Burn	12	\$95.00	\$1,140.00
<b>Total Appraised Cost:</b>			<b>\$17,970.00</b>

- (3) The total Purchase Price set forth in Section 2 shall be adjusted in a unilateral modification executed by the Contracting Officer by the amount that the total cost of the site preparation treatments designated pursuant to Section 44(f)(1) differs from \$17,970.00, as calculated by using the estimated acres determined by the Authorized Officer and the per acre costs listed in Section 44(f)(1).

- (2) Notwithstanding the provisions of Section 15 of this contract, the Government shall assume all obligations for disposal or reduction of fire hazards created by the Purchaser's operations on Government lands, except for burning and mop-up assistance as required herein. In accordance with written instructions to be issued by the Authorized Officer at least ten (10) days in advance of the earliest date of required performance, the Purchaser shall, under supervision of the Authorized Officer or designated representative, assist in preparing units for burning, mop-up and patrol by furnishing, at the Purchaser's own expense, the services of personnel and equipment on each unit as shown below:

For igniting and burning landing piles in all Harvest Areas, the Purchaser shall provide one (1) eight (8) person hand crew including a designated crew foreman. The crew shall be equipped with fuel, ten (10) drip torches or propane burners, four (4) fire shovels, four (4) pulaskis, one (1) power saw and enough radios to facilitate inter-crew communications. All crew members must have a current qualification card for FFT2 or higher. All qualifications are defined according to National Wildfire Coordinating Group (NWCG) Wildland Fire Qualifications System guide, PMS 310-1. Qualifications and equipment levels are the minimum and may exceed those stated above.

Aircraft and pilots used for logging residue reduction or the suppression of escaped fires from logging residue reduction operations, shall be acquired from a list of aircraft and pilots

approved (i.e. carded for these specific activities) by the Office of Aircraft Services or the U.S. Forest Service. This list is available from BLM District Offices upon request.

All listed personnel shall be physically fit, experienced and fully capable of functioning as required. All personnel shall arrive at the project area with the following personal safety equipment: lug-soled leather boots with minimum eight (8) inch uppers that provide ankle support; an approved hardhat; leather gloves; long pants and a long sleeve shirt made of approved aramid fabric (Nomex or equivalent); and an approved fire shelter.

All listed tools and equipment shall be in good usable condition. All power-driven equipment shall be fully fueled and available for immediate use. During periods of use under this subsection, the Purchaser shall provide fuel and maintenance for all such power-driven equipment. In addition, all listed personnel directly involved in burning operations shall be certified Fire Fighters qualified according to National Wildfire Coordinating Group (NWCG) Wildland Fire Qualification System guide, PMS 310-1 and provide documentation. The work leaders must be fluent in English and be able to effectively speak to all crew members under their direction. Personnel who do not meet these requirements or who do not have proper clothing and personal protective equipment (PPE) will not be allowed to participate.

Except as provided hereafter for fire escapement, the Purchaser shall continue the required assistance in mop-up on each Harvest Area as shown on Exhibit A for seventy-two (72) hours as directed by the Authorized Officer within a thirty (30) day period beginning 8:00 a.m. the day following completion of ignition in that unit or until released from such services by the Authorized Officer, whichever occurs first.

In the event of a fire escapement, the Purchaser's personnel and equipment shall, under supervision of the Authorized Officer, take action to suppress, including control and mop-up, the escaped fire until released from such service by the Government. If it becomes necessary to suppress a fire which escapes from the prescribed fire area for a period beyond midnight of ignition day, then the Government shall, at its option:

- (a) Reimburse Purchaser for such additional use of personnel and equipment at wage rates shown in the current Administratively Determined Pay Rates for Western Area and at equipment rates shown in current Oregon-Washington Interagency Fire Fighting Equipment Rental Rates schedule, until the Purchaser is released from such service by the Government, or
- (b) Release the Purchaser from additional suppression work and assume responsibility for suppressing the escaped fire.

In situations where an escaped fire is controlled and contained by an adequate fire break (e.g., trail, road, stream, rock formation), the Government may permit the Purchaser to remove personnel for that day; provided that, all mop-up work on the escaped fire area is included with mop-up work on the prescribed fire area. In such an event, the Purchaser must sign a statement of agreement to complete mop-up work on all escaped fire areas concurrently with mop-up work on the prescribed fire area.

In case of injury to personnel or damage to equipment furnished by the Purchaser as required by this subsection, liability shall be borne by the Purchaser, unless such injury or damage is caused by Government negligence.

Time is of the essence in complying with this provision. In the event the Purchaser fails to provide the personnel and equipment required herein, the Purchaser shall be responsible for all additional costs incurred by the Government in disposing of slash including but not limited to the wages and other costs of providing federal employees and others as substitute labor force, the cost of providing substitute equipment and appropriate additional overhead expenses. If the Purchaser's failure results in a deferral of burning and new conditions necessitate additional site preparation work and/or use of additional personnel and equipment to accomplish planned burning, the Purchaser shall also be responsible for such additional costs.

Section 44(G) Harvest Land Base Snag Creation:

- (1) Notwithstanding the provisions of Section 13 of this contract, the Purchaser shall, within 1 year following the completion of yarding operations, create approximately Five Hundred Forty-Three (543) snags, as shown on Exhibit G, or as directed by the Authorized Officer and in accordance with the following stipulations:
  - (a) Trees used to create snags under this subsection are not included in the volume or the appraised unit prices shown on Exhibit B and shall not be yarded or otherwise removed from the Harvest Land Base (HLB).
  - (b) The Purchaser shall create snags in a variety of spatial patterns, including aggregated groups and individual trees.
  - (c) The Purchaser may meet snag creation requirements with trees from any species.
  - (d) Snags shall generally be located a minimum distance of one and one-half (1½) tree lengths away from power lines, structures, roads that will remain open after logging operations are complete, and/or property lines where BLM managed lands abut non-federal ownership; where it is not possible to meet this requirement, the Purchaser shall fall trees equivalent to the required number of snags and retain the felled trees on site as down woody material.
  - (e) Snags shall generally be created by girdling live, green trees three (3) to five (5) feet above the root collar; girdling will generally consist of two (2) one-half (½) to three-quarter (¾) circumference girdles spaced vertically one (1) to two (2) feet apart on opposing sides of the tree; the girdling cuts shall completely sever the cambial tissue, without cutting into the sapwood more than one and one-half (1½) inches. In addition to girdling, trees severely damaged through normal logging operations and/or natural disturbance events subsequent to this logging entry may be counted towards the snag creation requirements with the approval of the Authorized Officer—examples would include, but need not be limited to, intermediate support trees, tail trees, trees pulled over during yarding, recent broken tops or windfalls.

- (f) The Purchaser shall number each snag created; the number shall be painted on the bole of the snag using high visibility paint such that the number is visible from at least one hundred (100) feet away. The Purchaser shall depict the number and location of snags on a legible map along with a tally by diameter which shall be submitted to the Authorized Officer to facilitate inspection.
- (g) In addition to the requirements described herein, for the Harvest Land Base (HLB) Variable-Retention Regeneration Harvest Areas 2, 3, 4, 5, 6, and 7, snags shall be created primarily in the Retention Aggregates, as shown on Exhibit G. As necessary to meet the requirements described above, the Purchaser may also create snags within the Harvest Area boundaries using dispersed retention trees.
- (h) In addition to the requirements described herein, for the Harvest Land Base (HLB) Thinning Harvest Area 1, snags shall be created primarily within the Harvest Area boundaries using dispersed retention trees. As necessary to meet the requirements described above, the Purchaser may also create snags in the Retention Aggregates adjacent to Harvest Area 1, as shown on Exhibit G.

Section 44(H) Buyout Securities:

- (1) The Purchaser shall assist in burning as described in Section 44(F)(2). The Purchaser shall have the option of completing this work, or in lieu thereof, may make a contribution to the Bureau of Land Management in the amount of Five Thousand Six Hundred Twenty-Seven and 00/100 dollars (\$5,627.00) and upon making such contribution, the Purchaser shall be relieved of the obligations set out in this subsection. The amount of the contribution shown above shall be paid prior to cutting. The Purchaser shall notify the Authorized Officer of his intention to make this contribution upon execution of this contract.

Section 44(l) Log Branding and Painting:

- (1) Unless otherwise authorized in writing by the Contracting Officer, the Purchaser shall brand clearly and legibly one end of all logs with a scaling diameter (small end inside bark) of over ten (10) inches, prior to the removal of timber from the contract area. All loads of eleven (11) logs or more will have a minimum of ten (10) logs clearly and legibly branded on one end regardless of the diameter of the logs. All logs will be branded on loads of ten (10) logs or less. One end of all branded logs to be processed domestically will be marked with a three (3) square inch spot of highway yellow paint. The Purchaser will stop trucks for accountability monitoring at mutually agreed upon locations when notified by the Authorized Officer.

If multiple trailers (mule trains) are used, each bunked load shall be considered an individual load, and these guidelines will apply to each bunked load. If a flatbed stake trailer is used, each bundle will be treated as a separate load.

At the discretion of the Contracting Officer, the Purchaser may be required to brand and paint all logs. Any increased costs for log branding and painting shall be the responsibility of the Purchaser.

Seasonal Restriction Matrix

Note: This matrix is provided to serve prospective purchasers as a guide only; refer to the timber sale contract Special Provisions for a complete statement of the seasonal operating restrictions.

Seasonal Restriction

Harvest Area	Activity	Jan		Feb		Mar		Apr		May		Jun		Jul		Aug		Sep		Oct		Nov		Dec		
		1	15	1	15	1	15	1	15	1	15	1	15	1	15	1	15	1	15	1	15	1	15	1	15	
<b>Unit 1</b> (thin)	Right-of-way logging and clearing, road construction, renovation <sup>1</sup>	■	■	■	■	■	■	■	■												■	■	■	■	■	■
	Hand falling <sup>3</sup>																									
	Mechanized falling and bucking <sup>2,3</sup>	■	■	■	■	■	■	■	■	■	■	■	■	■	■							■	■	■	■	■
	Ground-based yarding <sup>2,3</sup>	■	■	■	■	■	■	■	■	■	■	■	■	■	■							■	■	■	■	■
	Loading or hauling on rocked roads																									
<b>Unit 2 &amp; 5</b> (regen)	Right-of-way logging and clearing, road construction, renovation <sup>1</sup>	■	■	■	■	■	■	■	■													■	■	■	■	■
	Hand falling and bucking																									
	Mechanized falling and bucking <sup>2</sup>	■	■	■	■	■	■	■	■	■	■	■	■	■	■							■	■	■	■	■
	Ground-based yarding <sup>2</sup>	■	■	■	■	■	■	■	■	■	■	■	■	■	■							■	■	■	■	■
	Cable yarding on rocked roads																									
Loading or hauling on rocked roads																										
<b>Unit 3</b> (regen)	Right-of-way logging and clearing, road construction, renovation <sup>1</sup>	■	■	■	■	■	■	■	■													■	■	■	■	■
	Hand falling and bucking																									
	Mechanized falling and bucking <sup>2</sup>	■	■	■	■	■	■	■	■	■	■	■	■	■	■							■	■	■	■	■
	Ground-based yarding <sup>2</sup>	■	■	■	■	■	■	■	■	■	■	■	■	■	■							■	■	■	■	■
	Loading or hauling on rocked roads																									

<sup>1</sup>Wet season restriction applying to use of unsurfaced (or limited strength) roads and all road construction/renovation from October 15 – May 15 may be shortened or extended depending on weather conditions.

<sup>2</sup>Wet season restriction applying to ground-based yarding from October 15 – July 15 may be shortened or extended depending on soil moisture and weather conditions.

<sup>3</sup>Bark slip restriction from April 15 – July 15 may be conditionally waived.

<sup>4</sup>Due to expiring Marbled Murrelets surveys, cutting and yarding operations in the yarding wedge of Harvest Unit 6 and Harvest Unit 6 shall be completed no later than March 1, 2029. See Exhibit F for detailed map of restricted areas.

Seasonal Restriction Matrix

Seasonal Restriction

Harvest Area	Activity	Jan		Feb		Mar		Apr		May		Jun		Jul		Aug		Sep		Oct		Nov		Dec	
		1	15	1	15	1	15	1	15	1	15	1	15	1	15	1	15	1	15	1	15	1	15	1	15
<b>Unit 4</b> (regen)	Right-of-way logging and clearing, road construction, renovation <sup>1</sup>																								
	Hand falling and bucking																								
	Mechanized falling and bucking <sup>2</sup>																								
	Cable yarding on rocked roads																								
	Loading or hauling on rocked roads																								
<b>Unit 6</b> <sup>4</sup> (regen)	Right-of-way logging and clearing, road construction, renovation <sup>1</sup>																								
	Hand falling and bucking																								
	Mechanized falling and bucking <sup>2</sup>																								
	Cable yarding on rocked roads																								
	Loading or hauling on rocked roads																								
<b>Unit 7</b> (regen)	Right-of-way logging and clearing, road construction, renovation, subsoiling <sup>1</sup>																								
	Hand falling and bucking																								
	Mechanized falling and bucking <sup>2</sup>																								
	Ground-based yarding <sup>2</sup>																								
	Cable yarding on rocked roads																								
	Loading or hauling on dirt roads <sup>1</sup>																								
	Loading or hauling on rocked roads																								
	Off-road machine piling <sup>2</sup>																								

<sup>1</sup> Wet season restriction applying to use of unsurfaced (or limited strength) roads and all road construction/renovation from October 15 – May 15 may be shortened or extended depending on weather conditions.

<sup>2</sup> Wet season restriction applying to ground-based yarding from October 15 – July 15 may be shortened or extended depending on soil moisture and weather conditions.

<sup>3</sup> Bark slip restriction from April 15 – July 15 may be conditionally waived.

<sup>4</sup> Due to expiring Marbled Murrelets surveys, cutting and yarding operations in the yarding wedge and Harvest Unit 6 shall be completed no later than March 1, 2029. See Exhibit F for detailed map of restricted areas.

UNITED STATES  
DEPARTMENT OF THE INTERIOR  
BUREAU OF LAND MANAGEMENT

Name of Bidder
Tract Number <b>(1) 2026.0004</b>
Sale Name <b>Reston Pieces</b>
Sale Notice (dated) <b>02/27/2026</b>
BLM Office <b>Roseburg District</b>

**DEPOSIT AND BID FOR: (Check One):**

- Timber and/or Other Wood Products**  
(Examples of Other Wood Products: biomass, firewood, posts, poles, etc...)
- Vegetative Resources**  
(Examples of Vegetative Resources: boughs, pinyon nuts, cones, plants, etc...)

<input type="checkbox"/> Sealed Bid for Sealed Bid Sale	<input checked="" type="checkbox"/> Written Bid for Oral Auction Sale
Deadline for accepting sealed bids <input type="checkbox"/> a.m. <input type="checkbox"/> p.m.	Sale commences <b>10:00</b> <input checked="" type="checkbox"/> a.m. <input type="checkbox"/> p.m.
On (date) Place	On <b>03/24/2026</b> Place <b>777 NW Garden Valley Blvd.</b>

In response to the above dated Sale Notice, the required deposit and bid are hereby submitted for the purchase of designated Timber and/or Other Wood Products or Vegetative Resources on the tract specified above.

Required bid deposit is \$ 100,200.00 and is enclosed in the form of:

- cash  money order  cashier's check  certified check  bank draft
- bid bond of corporate surety on approved list of the United States Treasury  guaranteed remittance approved by the authorized officer.

IT IS AGREED That the bid deposit shall be retained by the United States as liquidated damages if the bid is accepted and the undersigned fails to execute and return the contract, together with any required performance bond and any required payment within 30 days after the contract is received by the successful bidder. If not otherwise specified in the advertisement, bids for less than the advertised price will not be considered. If the bid is rejected the deposit will be returned.

**BID SCHEDULE – TIMBER AND/OR OTHER WOOD PRODUCTS OR VEGETATIVE RESOURCES**

*NOTE: Bidders should carefully check computations in completing the Bid Schedule*

BID SUBMITTED					ORAL BID MADE	
PRODUCT & SPECIES	UNIT of MEASURE	ESTIMATED VOLUME OR QUANTITY	UNIT PRICE	PRODUCT VALUE (Quantity X Price)	UNIT PRICE	PRODUCT VALUE (Quantity X Price)
Douglas-Fir	MBF	4,641	\$	\$	\$	= \$
Grand Fir	MBF	1,131	\$ 88.40	\$ 99,980.40	\$	= \$
Incense-cedar	MBF	196	\$ 38.60	\$ 7,565.60	\$	= \$
Western Hemlock	MBF	92	\$ 75.40	\$ 6,936.80	\$	= \$
Western Redcedar	MBF	11	\$ 256.10	\$ 2,817.10	\$	= \$
Biomass	G Tons	184	\$ 3.00	\$ 552.00	\$	= \$
TOTAL PURCHASE PRICE				\$	\$	\$

If sale contract is executed, undersigned is liable for total purchase price including all modifications executed under the terms of the contract. Timber and/or Other Wood Products or Vegetative Resources designated for removal may be less or more than total estimated volume or quantity shown above.

Bid submitted on *(date)*

By signing this form, the signatory is certifying the following:

- (a) The signatory is a citizen of the United States, a partnership composed wholly of such citizens, an unincorporated association composed wholly of such citizens, or a corporation authorized to transact business in the state in which the timber is located.
- (b) The signatory is the age of majority in the state of the sale.
- (c) The signatory is an authorized representative if not signing as an individual and certifies that he or she is authorized to act as or on behalf of the bidder.
- (d) The signatory and any affiliates have not exported unprocessed private timber from west of the 100th meridian in the lower 48 states in the 24-months prior to the sale date shown on this form.
- (e) The signatory's bid was arrived at by bidder or offeror independently and was tendered without collusion with any other bidder or offeror.
- (f) The signatory and any affiliates are not currently suspended or debarred from contracting with the Federal government unless issued an exception by the Department's Director of the Office of Acquisition and Property Management (exception must be attached to bid form).

Mark each box above to acknowledge each of the certifying statements and complete sections 1-3 as appropriate and sections 4 and 5:

1. Signature, if firm is individually owned	4. Name of firm <i>(type or print)</i>
2. Signatures, if firm is a partnership or L.L.C. i. _____ ii. _____	5. Business address, include zip code <i>(type or print)</i>
3. Corporation - organized under the state laws of: Signature of Authorized Corporate Officer: _____ Title: _____	<i>(To be completed following oral bidding)</i> I HEREBY confirm the above oral bid By <i>(signature)</i> : _____ Date _____

Submit bid to qualify for either an oral auction or sealed bid sale, together with the required bid deposit.  
Make remittance payable to: "Department of the Interior – BLM"

Oral Auction – Submit to Sale Supervisor prior to closing of qualifying period for tract.

Sealed Bid – Send to Contracting Officer, who issued the sale notice, in a sealed envelope marked on the outside with:

- (1) "Bid for Timber and/or Other Wood Products" or "Bid for Vegetative Resources" depending on the products being sold.
- (2) Time bids are to be opened.
- (3) Legal description.
- (4) Sale name and number.

### NOTICES

The Privacy Act and the regulations in 43 CFR 2.223(d) require that you be furnished with the following information:

**AUTHORITY:** 38 FR 6280 and 43 CFR 5442.1

**PRINCIPAL PURPOSE:** To qualify an oral auction bidder, and then if successful, to bind bidder to certain contract conditions.

**ROUTINE USES:** To determine that an individual is qualified to participate in oral auction bidding, and, as surety that bidder will fulfill contract requirements.

**EFFECT OF NOT PROVIDING INFORMATION:** Filing this deposit and bid information is necessary only when an individual wishes to participate in a sealed or auction bid sale for Timber and/or Other Wood Products or Vegetative Resources.

## INSTRUCTIONS TO BIDDERS

1. *AUTHORITY* – Timber and/or Other Wood Products or Vegetative Resources, located on the revested Oregon and California Railroad Grant Lands and on the reconveyed Coos Bay Wagon Road Grant Lands is administered and sold pursuant to authority of the Act of August 28, 1937 (50 Stat. 874; 43 U.S.C. 2601); Timber and/or Other Wood Products or Vegetative Resources located on other public lands of the United States under jurisdiction of the Bureau of Land Management are administered and sold pursuant to authority of the Act of July 31, 1947 (61 Stat. 681), as amended, by the Act of July 23, 1955 (69 Stat. 367; 30 U.S.C. 601 et. seq.). Regulations of the Secretary of the Interior governing sale of Timber and/or Other Wood Products or Vegetative Resources, are codified in 43 CFR Group 5400.

2. *QUALIFICATIONS OF BIDDERS* – A bidder for sale of Timber and/or Other Wood Products or Vegetative Resources must be either (a) a citizen of the United States, (b) a partnership composed wholly of such citizens, (c) an unincorporated association composed wholly of such citizens, or (d) a corporation authorized to transact business in the state in which the Timber and/or Other Wood Products or Vegetative Resources are located.

3. *INSPECTION OF TIMBER AND/OR OTHER WOOD PRODUCTS OR VEGETATIVE RESOURCES* – Bidder is invited, urged, and cautioned to inspect the Timber and/or Other Wood Products or Vegetative Resources prior to submitting a bid. By executing the Timber and/or Other Wood Products or Vegetative Resources sale contract, bidder warrants that the contract is accepted on the basis of his/her examination and inspection of the Timber and/or Other Wood Products or Vegetative Resources and his/her opinion of its value.

4. *DISCLAIMER OF WARRANTY* – Government expressly disclaims any warranty of the fitness of the designated Timber and/or Other Wood Products or Vegetative Resources for any purpose of the bidder; all Timber and/or Other Wood Products or Vegetative Resources are to be sold “As Is” without any warranty of merchantability by Government. Any warranty as to the quantity or quality of Timber and/or Other Wood Products or Vegetative Resources to be sold is expressly disclaimed by Government.

5. *BIDS* – Each Sealed or written bid for Timber and/or Other Wood Products or Vegetative Resources must be submitted to the Contracting Officer who issued *Timber and/or Other Wood Products or Vegetative Resources Sale Notice*.

(a) *Sealed Bid Sales* – Bids will be received until time specified in the Advertisement. Enclose the bid with required bid deposit in a sealed envelope marked on the outside *Bid for Timber and/or Other Wood Products or Vegetative Resources*, time bid is to be opened, timber sale name and number, and legal description of land on which Timber and/or Other Wood Products or Vegetative Resources are located. In event of a tie, the high bidder shall be determined by lot from among those who submitted the tie bids.

(b) *Oral Auction Sales* – Submission of the required bid deposit and a written bid is required to qualify for oral bidding. Oral bidding shall begin from the highest written bid. No oral bid will be considered which is not higher than the preceding bid. In the event there is a tie in high written bids, and no oral bidding occurs, the bidder who was the first to submit his/her bid deposit and written bid shall be declared the high bidder. If the officer conducting the sale cannot determine who made the first submission of high tie written bids, the high bidder shall be determined by lot. High bidder must confirm his/her bid, in writing, immediately upon being declared high bidder.

(c) Except as otherwise provided in 43 CFR 5442.2, bids will not be considered in resale of Timber and/or Other Wood Products or Vegetative Resources remaining from an uncompleted contract from any person or affiliate of such person who failed to complete the original contract because of (1) cancellation for the purchaser’s breach or (2) through failure to complete payment by expiration date.

(d) When it is in the interest of the Government to do so, it may reject any and all bids and may waive minor deficiencies in bids or in sale advertisement.

6. *BID FORMS* – All sealed, written bids, and confirmation of oral bids shall be submitted on forms provided by Government.

(a) *Timber and/or Other Wood Products or Vegetative Resources Sales* – For each product and species, bids shall specify (1) Bureau of Land Management estimated unit volume or quantity, (2) bidder’s price per unit and total value, and (3) bidder’s total purchase price. Estimated volume and price per unit are to be used for administrative and appraisal purposes only. Upon award of contract, the high bidder agrees to pay the Government for the Timber and/or Other Wood Products or Vegetative Resources designated for removal in accordance with the terms of the contract. Timber and/or Other Wood Products or Vegetative Resources designated for removal may be less or more than the total estimated volume or quantity shown above.

7. *BID DEPOSIT* – All bidders must make a deposit of not less than the amount specified in the *Timber and/or Other Wood Products or Vegetative Resources Notice*. Deposit may be in the form of cash, money orders, bank drafts, cashiers or certified checks made payable to the Department of the Interior – BLM, bid bonds of a corporate surety shown on the approved list of the United States Treasury Department (*Applies To Timber Only*), or any approved guaranteed remittance approved by the Contracting Officer. Upon conclusion of bidding, the bid deposit of all bidders, except high bidder, will be returned. The cash deposit of the successful bidder shall be applied toward the required sale deposit and/or the purchase price. If the BLM fails to award the timber sale within 90 days of the determination of the high bidder, a portion of the bid deposit may be refunded to the high bidder upon written request to the authorized officer, such that the BLM retains a deposit of at least 5% of the appraised value. The remainder of the full bid deposit must be resubmitted to the BLM once the high bidder is notified in writing that the delay of award has been remedied and the authorized officer is prepared to issue the contract. If the high bidder is unable to provide the full amount of the bid deposit within 30 days of the written notification, the sale may be re-auctioned and the high bidder will be barred from participating in any subsequent auctions for the same tracts.

8. *AWARD OF CONTRACT* – Government may require high bidder to furnish such information as is necessary to determine the ability of bidder to perform the obligation of contract. Contract will be awarded to high bidder, unless he/she is not qualified or responsible or unless all bids are rejected. If high bidder is not qualified or responsible or fails to sign and return the contract together with required performance bond and any required payment, contract may be offered and awarded to the highest bidders qualified, responsible, and willing to accept the contract. If contract award is delayed more than 90 days, half of the bid deposit may be refunded to the high bidder until the sale award process resumes.

9. *TIMBER AND/OR OTHER WOOD PRODUCTS OR VEGETATIVE RESOURCES SALE CONTRACTS* – To be executed by purchaser, has been prepared by Government, and may be examined in the District or Field Manager’s office.

10. *PERFORMANCE BOND – (Primarily Used For Timber Sales)*

(a) A performance bond in an amount of not less than 20 percent of total purchase price is required, but the amount of the bond shall not be in excess of \$500,000, except when the purchaser opts to increase the minimum bond to permit cutting prior to payment as provided in 43 CFR 5451.2, or in the event the purchaser is a holder of an unresolved default the bond may be increased as provided in 43 CFR 5450.1(b). Performance bond may be (1) bond of a corporate surety shown on approval list issued by the United States Treasury Department and executed on an approved standard form, (2) personal surety bond executed on an approved standard form if Government determines principals and bondsman are capable of carrying out the terms of the contract, (3) cash bonds, (4) negotiable securities of the United States, or (5) any guaranteed remittance approved by the Contracting Officer.

(b) If purchaser elects to cut Timber and/or Other Wood Products or Vegetative Resources without skidding or yarding it to a loading point or removing it prior to the payment of the second or subsequent installments, Government shall require an increase in amount of performance bond initially required by an amount equal to the value of Timber and/or Other Wood Products or Vegetative Resources to be cut. Such increase must be on a bond rider form supplied by Government and be approved, in writing, by Government prior to cutting Timber and/or Other Wood Products or Vegetative Resources covered by the bond increase. This increased amount of bond shall be used to assure payment for Timber and/or Other Wood Products or Vegetative Resources cut in advance of payment.

11. *PAYMENT BOND – (Primarily Used For Timber Sales)*

If purchaser elects to (a) cut and remove Timber and/or Other Wood Products or Vegetative Resources, or (b) remove Timber and/or Other Wood Products or Vegetative Resources already cut which has been secured by an increased performance bond as provided in paragraph 10(b) above, before payment of the second or subsequent installments, Government shall require a payment bond on a form supplied by Government. Purchaser shall obtain written approval from Government of payment bond prior to cutting and/or removal of Timber and/or Other Wood Products or Vegetative Resources covered by the bond. Payment bond shall be used to assure payment for Timber and/or Other Wood Products or Vegetative Resources cut and/or removed in advance of payment.

12. *PAYMENT OF PURCHASE PRICE* – For sales of \$500 or more, Government may allow payment by installments. Except as discussed in paragraphs 10 and 11 above, no part of any Timber and/or Other Wood Products or Vegetative Resources sold may be severed, cut, or removed unless advance payment has been made as provided in contract.

13. *LIQUIDATED DAMAGES* – Within thirty (30) days from receipt of *Timber and/or Other Wood Products or Vegetative Resources* Sale Contract, the successful bidder shall sign contract and return it to Government, together with required bond and any required payment. If successful bidder fails to comply within the stipulated time, his/her bid deposit shall be retained by Government as liquidated damages.

14. *NINETY-DAY SALES* – If no bid is received within time specified in the advertisement of sale and if Government determines that there has been no significant rise in the market value of Timber and/or Other Wood Products or Vegetative Resources, it may, in its discretion, keep the sale open, not to exceed ninety (90) days.

15. *UNAUTHORIZED USE OF GOVERNMENT PROPERTY* – A sale may be refused to high bidder who has been notified that he/she has failed to make satisfactory arrangements for payment of damages resulting from unauthorized use of, or injury to, property of the United States.

16. [RESERVED]

17. *LOG EXPORT* – All timber offered for sale except as noted in the *Timber Sale Notice* is restricted from export from the United States in the form of unprocessed timber and any exporters of unprocessed private timber west of the 100th meridian in the contiguous 48 states within 24-months of the sale date are not eligible to purchaser Federal Timber west of the 100th meridian in the contiguous 48 states. For the purpose of this contract, unprocessed timber is defined as:

(1) any logs except those of utility grade or below, such as saw logs, peeler logs, and pulp logs; (2) cants or squares to be subsequently remanufactured exceeding eight and three quarters (8-3/4) inches in thickness; (3) split or round bolts or other roundwood not processed to standards and specifications suitable for end product use; or (4) western red cedar lumber which does not meet lumber of American Lumber Standards Grades of Number 3 dimensions or better, or Pacific Lumber Inspection Bureau R-List Grades of Number 3 common or better.

Timber manufactured into the following will be considered processed: (1) Lumber or construction timbers, except western red cedar, meeting current American Lumber Standards Grades or Pacific Lumber Inspection Bureau Export R or N list grades, sawn on four sides, not intended for remanufacture; (2) Lumber, construction timbers, or cants for remanufacture, except western red cedar, meeting current American Lumber Standards Grades or Pacific Lumber Inspection Bureau Export R or N list clear grades, sawn on four sides, not to exceed twelve inches in thickness; (3) Lumber, construction timbers, or cants for remanufacture, except western red cedar, that do not meet the grades referred to in subclause 2 and are sawn on four sides, with wane less than ¼ of any face, not exceeding 8¾ inches in thickness; (4) Chips, pulp, or pulp products; (5) Veneer or plywood; (6) Poles, posts, or piling cut or treated with preservatives for use as such; (7) Shakes or shingles; (8) Aspen or other pulpwood bolts, not exceeding 100 inches in length, exported for processing into pulp; (9) Pulp logs, cull logs, and incidental volumes of grade 3 and 4 saw logs processed at domestic pulp mills, domestic chip plants, or other domestic operations for the primary purpose of conversion of the logs into chips, or to the extent that a small quantity of such logs are processed, into other products at domestic processing facilities.

18. *DETAILED INFORMATION* – Detailed information concerning contract provisions, bid, performance bond forms, tract location maps, and access conditions may be obtained from the Contracting Officer. All persons interested in bidding on the products listed are encouraged to familiarize themselves with all such detailed information.

Township 28 South, Range 8 West, Sections 15, 21, 23, and 29, Willamette Meridian

Harvest Area	Thinning Acres	Regeneration Acres	Total Harvest Acres	Harvest Method
1	4	0	4	Ground
2	0	34	34	Cable/Ground
3	0	4	4	Ground
4	0	14	14	Cable
5	0	33	33	Cable/Ground
6	0	15	15	Cable
7	0	46	46	Cable/Ground
<b>Totals</b>	<b>4</b>	<b>146</b>	<b>150</b>	


THINNING HARVEST AREA .....	4 Acres
REGENERATION HARVEST AREA .....	146 Acres
RIGHT-OF-WAY (CLEARING) .....	9 Acres
TOTAL HARVEST AREA .....	159 Acres
RESERVE AREA .....	361 Acres
TOTAL CONTRACT AREA .....	520 Acres

1. Harvest Area boundaries are posted with tags that read "Boundary of Timber Reserve" and boundary trees are blazed and painted orange. Trees marked with orange blazes to delineate the boundaries of the Harvest Areas and trees marked with orange paint within the Harvest Areas are reserved by the government.
2. Property lines are posted with orange and white tags that read "Timber Cutting Boundary".
3. Clearing limits on road rights-of-ways within the Harvest Areas are posted with fluorescent orange paper flasher tags. Clearing limits on road rights-of-ways outside the Harvest Areas on BLM managed lands are posted with tags that read "Right-of-Way", and trees are blazed and painted orange; trees marked with orange blazes to delineate clearing limits outside the harvest areas are reserved by the government. Clearing limits on road rights-of-ways over private property are posted with tags that read "Right-of-Way."
4. Ground-based yarding is limited to dry season operations and slopes 35% or less within the ground-based area shown on Exhibit A, approximately 32 acres.



R 8 W


T 28 S



- Gate
- Stream
- Road Construction
- Road Renovation
- Existing Road
- County Road
- Contract Area
- Retention Aggregates
- Harvest Area - Cable Yarding
- Harvest Area - Ground Based
- Reserve Area

Scale: 1:12,000

1 inch = 1,000 feet



Date: 2/2/2026

Roseburg District  
 Bureau of Land Management  
 777 NW Garden Valley Blvd.  
 Roseburg, Oregon 97471




No warranty is made by the Bureau of Land Management as to the accuracy, reliability, or completeness of these data for individual or aggregate use with other data. Original data were compiled from various sources and may be updated without notification.



R 8 W


T 28 S



- Gate
- Survey Corner
- Stream
- Road Construction
- Road Renovation
- Existing Road
- County Road
- Contract Area
- Yarding Wedge
- Retention Aggregates
- Harvest Area - Cable Yarding
- Harvest Area - Ground Based
- Reserve Area

Scale: 1:12,000

1 inch = 1,000 feet



Date: 2/2/2026

Roseburg District  
 Bureau of Land Management  
 777 NW Garden Valley Blvd.  
 Roseburg, Oregon 97471




No warranty is made by the Bureau of Land Management as to the accuracy, reliability, or completeness of these data for individual or aggregate use with other data. Original data were compiled from various sources and may be updated without notification.



R 8 W


T 28 S



- Gate
- Survey Corner
- Stream
- Road Construction
- Road Renovation
- Existing Road
- County Road
- Contract Area
- Retention Aggregates
- Harvest Area - Cable Yarding
- Harvest Area - Ground Based
- Reserve Area

Scale: 1:12,000

1 inch = 1,000 feet



Date: 2/2/2026

Roseburg District  
Bureau of Land Management  
777 NW Garden Valley Blvd.  
Roseburg, Oregon 97471



No warranty is made by the Bureau of Land Management as to the accuracy, reliability, or completeness of these data for individual or aggregate use with other data. Original data were compiled from various sources and may be updated without notification.

UNITED STATES  
DEPARTMENT OF THE INTERIOR  
BUREAU OF LAND MANAGEMENT

Contract No.  
ORR05-TS-2026.0004  
Reston Pieces

**EXHIBIT B / PRE-SALE**

5450-003

The following estimates and calculations of value of timber sold are made solely as an administrative aid for determining: (1) adjustments made or credits given in accordance with Secs. 6, 9, or 11; (2) when payments are due; and (3) value of timber subject to any special bonding provisions. The value of timber will be determined by multiplying the value per acre as shown below, times the amount of acreage as determined by the Authorized Officer, which has been cut or removed or designated for taking. Except as provided in Sec. 2, Purchaser shall be liable for total purchase price even though quantity of timber actually cut or removed or designated for taking is less than the estimated volume or quantity shown. Cutting areas are shown on **Exhibit A**.

SPECIES	ESTIMATED VOLUME OR QUANTITY (Units Specified)		PRICE PER UNIT	ESTIMATED VOLUME OR QUANTITY X UNIT PRICE
Douglas Fir	4,641.0	MBF	\$190.50	\$884,110.50
Grandfir	1,131.0	MBF	\$88.40	\$99,980.40
Incense-cedar	196.0	MBF	\$38.60	\$7,565.60
Western Hemlock	92.0	MBF	\$75.40	\$6,936.80
Western Redcedar	11.0	MBF	\$256.10	\$2,817.10
Mixed Species	184.0	GTON	\$3.00	\$552.00
<b>TOTALS</b>	<b>6,071.0 MBF, 184.0 GTON</b>			<b>\$1,001,962.40</b>

The apportionment of the total purchase price is as follows:

Unit 1

Douglas Fir	57.0 MBF	X	\$190.50 =	\$10,858.50
Grandfir	73.0 MBF	X	\$88.40 =	\$6,453.20
Incense-cedar	1.0 MBF	X	\$38.60 =	\$38.60
Mixed Species	4.0 GTON	X	\$3.00 =	\$12.00
<b>Total</b>	<b>131.0 Mbf, 4.0 Gton</b>			<b>\$17,362.30 ÷ 4.0 acres = \$4,340.58/Acre</b>

Unit 2

Douglas Fir	877.0 MBF	X	\$190.50 =	\$167,068.50
Grandfir	276.0 MBF	X	\$88.40 =	\$24,398.40
Incense-cedar	15.0 MBF	X	\$38.60 =	\$579.00
Western Hemlock	1.0 MBF	X	\$75.40 =	\$75.40
Mixed Species	35.0 GTON	X	\$3.00 =	\$105.00
<b>Total</b>	<b>1169.0 Mbf, 35.0 Gton</b>			<b>\$192,226.30 ÷ 34.0 acres = \$5,653.71/Acre</b>

Unit 3

Douglas Fir	100.0 MBF	X	\$190.50 =	\$19,050.00
Grandfir	58.0 MBF	X	\$88.40 =	\$5,127.20
Incense-cedar	2.0 MBF	X	\$38.60 =	\$77.20
Mixed Species	5.0 GTON	X	\$3.00 =	\$15.00
<b>Total</b>	<b>160.0 Mbf, 5.0 Gton</b>			<b>\$24,269.40 ÷ 4.0 acres = \$6,067.35/Acre</b>

Unit 4 - 20.2 & 20.3 Roads

Douglas Fir	300.0 MBF	X	\$190.50 =	\$57,150.00
Grandfir	78.0 MBF	X	\$88.40 =	\$6,895.20
Incense-cedar	3.0 MBF	X	\$38.60 =	\$115.80

UNITED STATES  
DEPARTMENT OF THE INTERIOR  
BUREAU OF LAND MANAGEMENT

Contract No.

ORR05-TS-2026.0004

**EXHIBIT B / PRE-SALE**

Reston Pieces

5450-003

The following estimates and calculations of value of timber sold are made solely as an administrative aid for determining: (1) adjustments made or credits given in accordance with Secs. 6, 9, or 11; (2) when payments are due; and (3) value of timber subject to any special bonding provisions. The value of timber will be determined by multiplying the value per acre as shown below, times the amount of acreage as determined by the Authorized Officer, which has been cut or removed or designated for taking. Except as provided in Sec. 2, Purchaser shall be liable for total purchase price even though quantity of timber actually cut or removed or designated for taking is less than the estimated volume or quantity shown. Cutting areas are shown on **Exhibit A**.

Unit 4 - 20.2 & 20.3 Roads

Western Hemlock	1.0 MBF	X	\$75.40	=	\$75.40
Mixed Species	12.0 GTON	X	\$3.00	=	\$36.00
Total	382.0 Mbf, 12.0 Gton				\$64,272.40 ÷ 14.0 acres = \$4,590.89/Acre

Unit 5

Douglas Fir	674.0 MBF	X	\$190.50	=	\$128,397.00
Grandfir	62.0 MBF	X	\$88.40	=	\$5,480.80
Incense-cedar	137.0 MBF	X	\$38.60	=	\$5,288.20
Mixed Species	26.0 GTON	X	\$3.00	=	\$78.00
Total	873.0 Mbf, 26.0 Gton				\$139,244.00 ÷ 33.0 acres = \$4,219.52/Acre

Unit 6

Douglas Fir	401.0 MBF	X	\$190.50	=	\$76,390.50
Grandfir	168.0 MBF	X	\$88.40	=	\$14,851.20
Western Redcedar	4.0 MBF	X	\$256.10	=	\$1,024.40
Incense-cedar	9.0 MBF	X	\$38.60	=	\$347.40
Western Hemlock	1.0 MBF	X	\$75.40	=	\$75.40
Mixed Species	18.0 GTON	X	\$3.00	=	\$54.00
Total	583.0 Mbf, 18.0 Gton				\$92,742.90 ÷ 15.0 acres = \$6,182.86/Acre

Unit 7

Douglas Fir	1,863.0 MBF	X	\$190.50	=	\$354,901.50
Grandfir	309.0 MBF	X	\$88.40	=	\$27,315.60
Western Redcedar	7.0 MBF	X	\$256.10	=	\$1,792.70
Incense-cedar	22.0 MBF	X	\$38.60	=	\$849.20
Western Hemlock	80.0 MBF	X	\$75.40	=	\$6,032.00
Mixed Species	69.0 GTON	X	\$3.00	=	\$207.00
Total	2281.0 Mbf, 69.0 Gton				\$391,098.00 ÷ 46.0 acres = \$8,502.13/Acre

Unit 22.1RD - 28-8-22.1 Road

Douglas Fir	17.0 MBF	X	\$190.50	=	\$3,238.50
Grandfir	1.0 MBF	X	\$88.40	=	\$88.40
Incense-cedar	1.0 MBF	X	\$38.60	=	\$38.60
Mixed Species	1.0 GTON	X	\$3.00	=	\$3.00

UNITED STATES  
DEPARTMENT OF THE INTERIOR  
BUREAU OF LAND MANAGEMENT

Contract No.  
ORR05-TS-2026.0004  
Reston Pieces

**EXHIBIT B / PRE-SALE**

5450-003

The following estimates and calculations of value of timber sold are made solely as an administrative aid for determining: (1) adjustments made or credits given in accordance with Secs. 6, 9, or 11; (2) when payments are due; and (3) value of timber subject to any special bonding provisions. The value of timber will be determined by multiplying the value per acre as shown below, times the amount of acreage as determined by the Authorized Officer, which has been cut or removed or designated for taking. Except as provided in Sec. 2, Purchaser shall be liable for total purchase price even though quantity of timber actually cut or removed or designated for taking is less than the estimated volume or quantity shown. Cutting areas are shown on **Exhibit A**.

Total	19.0 Mbf, 1.0 Gton		\$3,368.50	÷ 1.0 acres = \$3,368.50/Acre
-------	--------------------	--	------------	-------------------------------

Unit 23.6RD - 28-8-23.6 Road

Douglas Fir	187.0 MBF	X	\$190.50	=	\$35,623.50
Grandfir	70.0 MBF	X	\$88.40	=	\$6,188.00
Incense-cedar	2.0 MBF	X	\$38.60	=	\$77.20
Mixed Species	8.0 GTON	X	\$3.00	=	\$24.00
Total	259.0 Mbf, 8.0 Gton		\$41,912.70	÷ 4.0 acres = \$10,478.18/Acre	

Unit SPR1-2 - Spur 1 & Spur 2


Douglas Fir	47.0 MBF	X	\$190.50	=	\$8,953.50
Grandfir	24.0 MBF	X	\$88.40	=	\$2,121.60
Incense-cedar	1.0 MBF	X	\$38.60	=	\$38.60
Mixed Species	2.0 GTON	X	\$3.00	=	\$6.00
Total	72.0 Mbf, 2.0 Gton		\$11,119.70	÷ 1.0 acres = \$11,119.70/Acre	

Unit SPR3

Douglas Fir	27.0 MBF	X	\$190.50	=	\$5,143.50
Mixed Species	1.0 GTON	X	\$3.00	=	\$3.00
Total	27.0 Mbf, 1.0 Gton		\$5,146.50	÷ 1.0 acres = \$5,146.50/Acre	

Unit SPR4

Douglas Fir	91.0 MBF	X	\$190.50	=	\$17,335.50
Grandfir	12.0 MBF	X	\$88.40	=	\$1,060.80
Incense-cedar	3.0 MBF	X	\$38.60	=	\$115.80
Western Hemlock	9.0 MBF	X	\$75.40	=	\$678.60
Mixed Species	3.0 GTON	X	\$3.00	=	\$9.00
Total	115.0 Mbf, 3.0 Gton		\$19,199.70	÷ 2.0 acres = \$9,599.85/Acre	



**Legend**

- Purchaser
- Private
- Harvest Area
- Gate
- BLM
- Private



Date: 2/2/2026  
 Roseburg District  
 Bureau of Land Management  
 777 NW Garden Valley Blvd.  
 Roseburg, Oregon 97471



No warranty is made by the Bureau of Land Management as to the accuracy, reliability, or completeness of these data for individual or aggregate use with other data. Original data were compiled from various sources and may be updated without notification.

**United States Department of the Interior  
Bureau of Land Management Roseburg District  
EXHIBIT D**

Sale Name: Reston Pieces							
Contract No. ORR05-TS-2026.0004							
Road Number	Road Seg.	Segment Length	Segment Owner	Road Use Fees	Surface Type	Timber Haul Fees	Maintained By
28-8-15.1	A	0.36	BLM		Rock	\$0.95	Purchaser
28-8-15.1	B(POR)	0.24	BLM		Rock	\$0.95	Purchaser
28-8-16.2	A	0.50	RRC	\$0.18	Rock	\$0.95	Purchaser
28-8-16.2	B1	0.45	BLM		Rock	\$0.95	Purchaser
28-8-20.1	A(POR)**	1.15	SENECA	\$12.83	Rock		Purchaser
28-8-20.2	A**	0.18	SENECA	\$8.79	Rock		Purchaser
28-8-20.2	B	0.02	BLM		Native		Purchaser
28-8-20.2	C	0.07	BLM		Native		Purchaser
28-8-20.3	A**	0.22	SENECA	\$18.40	Rock		Purchaser
28-8-20.3	B	0.05	BLM		Rock	\$0.95	Purchaser
28-8-20.3	C	0.11	BLM		Rock	\$0.95	Purchaser
28-8-21.0	A	0.68	BLM		Rock	\$0.95	Purchaser
28-8-21.0	B	0.05	MANULIFE	\$3.26	Rock	\$0.95	Purchaser
28-8-21.0	C(POR)	0.13	MANULIFE	\$8.99	Rock	\$0.95	Purchaser
28-8-22.1	A	0.02	BLM		Rock	\$0.95	Purchaser
28-8-22.1	B	0.10	BLM		Rock	\$0.95	Purchaser
28-8-23.1	A	0.25	LRT	PAID OFF	Rock	\$0.95	Purchaser
28-8-23.2	A(POR)	0.53	BLM		Rock	\$0.95	Purchaser
28-8-23.3	A(POR)	0.55	BLM		Rock	\$0.95	Purchaser
28-8-23.6	A	0.04	BLM		Rock	\$0.95	Purchaser
28-8-23.6	B	0.74	BLM		Rock	\$0.95	Purchaser
SPUR 1	A	0.04	BLM		Rock	\$0.95	Purchaser
SPUR 2	A	0.23	BLM		Rock	\$0.95	Purchaser
SPUR 3	A	0.13	BLM		Rock	\$0.95	Purchaser
SPUR 4	A	0.07	BLM		Native		Purchaser

\*\* Rockwear fees waived by road segment owner in lieu of spot rock. See Exhibit C Plans for details.

---

## ROAD MAINTENANCE SPECIFICATIONS

---

General road maintenance specifications are designated by numeric symbols according to the type of work performed as follows:

SECTION	DESCRIPTION
3000	General
3100	Operational Maintenance
3200	Seasonal Maintenance
3300	Final Maintenance
3400	Other Maintenance
3500	Decommissioning

---

## ROAD MAINTENANCE SPECIFICATIONS

---

### GENERAL - 3000

- 3001 The Purchaser shall be required to maintain all roads listed and/or referenced in section 42(D) Special Provisions of this contract in accordance with Sections 3000, 3100, 3200, 3300, 3400, and 3500 of this exhibit.
- 3002 The Purchaser shall maintain the cross section of existing dirt or graveled roads to the existing geometric standards. Any roads required to be constructed, improved, or renovated under terms of this contract shall be maintained to the geometric standards required in Exhibit C of this contract.
- 3003 The minimum required maintenance on any roads shall include the provisions specified in Subsections 3101, 3104, and 3105.
- 3004 The Purchaser shall be responsible for providing timely maintenance and cleanup on any roads with logging units substantially completed prior to moving operations to other roads. The maximum length of non-maintained or non-cleanup of the road prism shall not exceed the sum of one (1) mile at any time. Release of maintenance requirements may be granted, upon written request, when the conditions specified in Sections 3300 and 3400 are met satisfactorily.

### OPERATIONAL MAINTENANCE - 3100

- 3101 The Purchaser shall blade and shape the road surface and shoulders with a motor grader. Banks shall not be undercut. Back blading with tractors or similar equipment will be allowed only around landings and other areas when approved by the Authorized Officer.
- 3104 The purchaser shall perform other road cleanup including removal of debris, fallen timber, bank slough, and slides which can practicably be accomplished by a motor grader, rubber tired front end bucket loader, rubber-tired backhoe, street sweeper, or comparable equipment, and by the use of hand tools.
- 3104a Removal of bank slough and slide material includes placement of material at the nearest designated, suitable disposal site where material cannot erode into streams, lakes, or reservoirs or cause undue damage to road fill slopes which have been planted or mulched to control soil erosion as directed by the Authorized Officer.
- 3104b The Purchaser shall be responsible for removal of all slides or slough, up to fifteen station yards in quantity, at any one site. This work includes unlimited multiple sites on all roads required to be maintained by the purchaser.

---

## ROAD MAINTENANCE SPECIFICATIONS

---

Prior to removal of any slough or slide material exceeding fifteen station yards at any one site, the Purchaser and the Authorized Officer or their Authorized Representatives shall agree in writing, in the field, to the quantity of material, method of disposal, and the disposal site. Work may commence immediately after agreement.

Upon completion of agreed upon work, a reduction in timber sale purchase price will be made to offset the cost of the work, based on current BLM Road Cost Guide. Adjustments in purchase price for completed work shall be made as necessary and no less than once per year when actual work is ongoing.

3105 The Purchaser shall be responsible for maintaining normal flow in drainage structures. This includes cleaning out drainage ditches, catch basins, clearing pipe inverts of sediment and other debris lodged in the barrel of the pipe, and maintaining water dips and water-bars using equipment specified in Subsection 3104 and other culvert cleaning and flushing equipment.

3106 The Purchaser shall be responsible for repair and replacement of all materials eroded from road shoulders and fill slopes, up to fifteen station yards in quantity, at any one site. This work includes unlimited multiple sites on all roads required to be maintained by the Purchaser. Prior to repair and replacement of eroded material exceeding fifteen station yards at any one site, the Purchaser and the Authorized Officer or their Authorized Representatives shall agree in writing, in the field, to the quantity of material, borrow source and method of repair. Work may commence immediately after agreement.

Upon completion of agreed upon work, a reduction in timber sale purchase price will be made to offset the cost of the work based upon current BLM Road Cost Guide. Adjustments in purchase price for completed work shall be made as necessary and no less than once per year when actual work is ongoing.

3107 The Purchaser shall cut or trim trees and brush which obstructs vision or prevents the safe passage of traffic along the traveled way when directed by the Authorized Officer.

The Purchaser shall also cut trees or brush encroaching on the road prism that are a result of his activities or winter damage during the contract period. Disposal of such vegetative material shall be by scattering below the road.

3108 The Purchaser shall avoid fouling gravel or bituminous surfaces through covering with earth and debris from side ditches, slides, or other sources. The Purchaser shall also avoid blading surfacing material off the running surface of the roadway.

3108a The Purchaser shall perform logging operations on gravel or bituminous roadways only where the locations have been marked on the ground and/or approved by the Authorized Officer. Upon completion of log haul, the road surface shall be swept clean of debris. Repair of the roads is not considered maintenance and shall be conducted at the Purchaser's expense.

---

**ROAD MAINTENANCE SPECIFICATIONS**

---

- 3108b Any damage to bituminous roadways, as a result of logging operations, is not considered maintenance and shall be repaired at the Purchaser's expense.
- 3109 The maximum allowable rut depth on aggregate surfaced roads is 2". Roads with ruts exceeding this requirement shall be bladed and brought back into conformance with the typical sections shown in the drawings. Rut depth shall be measured by centering a minimum 3-foot-long straightedge across the wheel rut maintaining contact with the aggregate at both ends of the straight edge. The rut depth shall be the distance measured between the bottom of the straight edge and the lowest point of the wheel rut.

**SEASONAL MAINTENANCE - 3200**

- 3201 The Purchaser shall perform preventative maintenance at the end of Purchaser's hauling each season and during non-hauling periods which occur between other operations on the contract area. This includes requirements specified in Section 3100.
- 3202 The Purchaser shall perform, and complete maintenance specified in Sections 3000, 3100, and 3200 on all roads maintained by the Purchaser, prior to October 1 each year, except as specified in Subsection 3203, after initial commencement of construction or logging operations. Thereafter, all roads shall have continuous preventive maintenance and road cleanup until suspension of seasonal operations. This includes all roads used and not used during the proceeding operating seasons.
- 3203 The Purchaser shall complete road cleanup and maintenance, as specified in Section 3100, at the completion of logging operations on any roads located in an area separate from the area where logging activities will resume.
- 3204 The Purchaser shall be responsible for performing post storm inspections and maintenance during the winter season to minimize erosion and potential road or watershed damage.

**FINAL MAINTENANCE - 3300**

- 3301 The Purchaser shall complete final maintenance and/or damage repairs on all roads used under the terms of their contract within thirty 30 calendar days following the completion of hauling or the expiration of the Purchaser's right to cut and remove timber and in accordance with Sec. 16(b) of this contract. This work shall include any maintenance and/or damage repairs specified in Sections 3000, 3100, and 3200 necessary to meet the conditions specified in Subsection 3002 and shall be executed in accordance with Subsection 3302 of this section.

The Authorized Officer may grant acceptance of Purchaser's maintenance responsibility in part where certain individual roads or road segments are no longer of any use to the Purchaser's

---

## ROAD MAINTENANCE SPECIFICATIONS

---

remaining removal operations, providing that all contract requirements as specified under Sec. 16(b), Special Provisions, Sections 3000, 3100, 3200 and 3300 of the maintenance specifications have been completed and a relinquishment of cutting and removal rights on cutting units tributary to these roads is signed by the Purchaser. Request for partial acceptance must be submitted in writing by the Purchaser.

3302 The Purchaser shall perform final road maintenance only when weather or soil moisture conditions are suitable for normal maintenance equipment operations as determined by the Authorized Officer.

If final maintenance is delayed after the date required in Subsection 3301 of this contract by adverse soil moisture or unsuitable equipment operating conditions, the Purchaser will be notified by the Authorized Officer when soil moisture and equipment operating conditions are suitable. The Purchaser shall then be required to complete final maintenance within 30 days.

### **OTHER MAINTENANCE - 3400**

3401 The Purchaser shall repair any damage to road surfaces that was specified under Subsection 3108. This repair includes restoring the roadway to the designed standard and replacement of surfacing with approved surface material. This repair is not limited to use of equipment specified in Subsection 3104.

3402 The Purchaser shall be permitted to remove ice and snow from roads authorized for use under this contract only when prior written approval has been secured from the Authorized Officer. The Purchaser shall submit a written request for permission to remove ice and snow in advance of the date operations are to begin.

Upon receiving written authorization for ice or snow removal, the Purchaser will perform the work according to the conditions and equipment requirements set forth in the authorization.

### **DECOMMISSIONING – 3500**

3501 Decommissioning shall consist of removing culverts, installing water bars, placement of slash, and blocking road from access by vehicles. This work is required for road acceptance under Section 18 of this contract.

3503 Decommissioning shall be performed on existing roads in accordance with these specifications, and as shown on the Exhibit D Trench Barrier and Waterbar Details at the following locations:

**ROAD MAINTENANCE SPECIFICATIONS**


---

Road No	From Sta. / M.P.	To Sta. / M.P.	Method of Decommissioning
28-8-20.2 Const.	0+00	4+60	Block and Waterbar
Spur 4	0+00	3+80	Block and Waterbar

- 3506 Stockpiled slash shall be used to protect exposed areas created by the Purchaser's decommissioning operations described in these sections. Slash shall be uniformly spread and placed without bunching. The operation shall produce a dense, uniform mat. Where slash is not available exposed soil areas shall be stabilized in accordance with Section 1800.
- 3508 Protect areas treated with slash placement from damage by Purchaser traffic or construction equipment. Damaged areas shall be repaired by the Purchaser.
- 3509 Access shall be blocked with barricades as shown on the typical detail sheet at locations listed in Section 3503.
- 3511 Water barring shall be done on designated roadways, turnouts, disturbed areas, and landings.
- 3513 Water bars shall be installed across full width of roadway at the spacing shown on the Exhibit D Waterbar Detail sheet.
- 3514 Protection of exposed surfaces shall be accomplished by placement of slash described in Subsection 3506 or placement of soil stabilization material in accordance with Section 1800 on designated roadways landings, cut banks, fill slopes, and other areas disturbed by the purchaser's decommissioning operations in accordance with these specifications and as shown in the plans.

ROAD MAINTENANCE SPECIFICATIONS


EXHIBIT D  
TRENCH BARRIER DETAIL




TRENCH BARRIER  
SCALE: NONE

**ROAD MAINTENANCE SPECIFICATIONS**

EXHIBIT D  
 WATERBAR DETAIL




ROAD PLAN  
 SCALE: NONE






WATERBAR SPACING IN FEET	
ROAD GRADIENT IN %	SPACING
3 TO 5	300
6 TO 10	200
11 TO 15	150
16 TO 20	75
21 TO 35	50

ROAD PROFILE  
 SCALE: NONE

**Dead Tree (Snag) Decay Classification**

					
<b>Class</b>	<b>1</b>	<b>2</b>	<b>3</b>	<b>4</b>	<b>5</b>
Bark	Tight intact	50% loose or missing	75% Missing	75% Missing	75% Missing
Heartwood decay	Minor	None to advanced	Incipient to advanced	Incipient to advanced	Advanced to crumbly
Sapwood decay	None to incipient	Non to incipient	None to 25%	25% +	50% + advanced
Limbs	Mostly present	Small limbs missing	Few remain	Few remain	Absent
Top breakage	May be present	May be present	Approx. 1/3	Approx. 1/3-1/2	Approx. 1/2 +
Bole form	Intact	Intact	Mostly intact	Losing form, soft	Form mostly lost

**Coarse Woody Debris (Downed Log) Decay Classification**

					
<b>Class</b>	<b>1</b>	<b>2</b>	<b>3</b>	<b>4</b>	<b>5</b>
Bark	Intact	Intact	Trace	Absent	Absent
Twigs	Present	Absent	Absent	Absent	Absent
Texture	Intact	Intact to soft	Hard, large pieces	Soft, blocky pieces	Soft, powdery
Shape	Round	Round	Round	Round to oval	Oval
Color of wood	Original	Original	Original to faded	Light brown to faded brown	Faded to light yellow or gray
Bole portion on ground	None, elevated on supports	Parts touch, still elevated	Bole on ground	Partially below ground	Mostly below ground




Bureau of Land Management

# EXHIBIT F Marbled Murrelet Restriction Map Sheet 1 of 1

R 8 W

Reston Pieces  
Contract #ORR05-TS-2026.0004


T 28 S



- Gate
- Survey Corner
- - - Stream
- == Existing Road
- Road Construction
- Road Renovation
- County Road
- ⌋ Contract Area
- Harvest Area - Cable Yarding
- ▤ Harvest Area - Ground Based
- ▨ Retention Aggregates
- ▩ Yarding Wedge
- ▧ Reserve Area
- ▧ Marbled Murrelet Restriction March 1, 2029

Scale: 1:12,000

1 inch = 1,000 feet



Date: 2/4/2026

Roseburg District  
Bureau of Land Management  
777 NW Garden Valley Blvd.  
Roseburg, Oregon 97471



No warranty is made by the Bureau of Land Management as to the accuracy, reliability, or completeness of these data for individual or aggregate use with other data. Original data were compiled from various sources and may be updated without notification.



Bureau of Land Management


# EXHIBIT G Snag Creation Area Map Sheet 1 of 3

R 8 W

Reston Pieces

Contract #ORR05-TS-2026.0004


T 28 S



- Gate
- Stream
- Existing Road
- Road Construction
- Road Renovation
- County Road
- Contract Area
- Harvest Area
- Retention Aggregates
- Yarding Wedge
- Reserve Area
- Snag Creation Area

Scale: 1:12,000

1 inch = 1,000 feet



Date: 2/4/2026

Roseburg District  
Bureau of Land Management  
777 NW Garden Valley Blvd.  
Roseburg, Oregon 97471




No warranty is made by the Bureau of Land Management as to the accuracy, reliability, or completeness of these data for individual or aggregate use with other data. Original data were compiled from various sources and may be updated without notification.



# EXHIBIT G Snag Creation Area Map Sheet 2 of 3

R 8 W




T 28 S

- Gate
- Survey Corner
- Stream
- Existing Road
- Road Construction
- Road Renovation
- County Road

- Contract Area
- Harvest Area
- Retention Aggregates
- Yarding Wedge
- Reserve Area
- Snag Creation Area

Scale: 1:12,000

1 inch = 1,000 feet



Date: 2/4/2026

Roseburg District  
Bureau of Land Management  
777 NW Garden Valley Blvd.  
Roseburg, Oregon 97471




No warranty is made by the Bureau of Land Management as to the accuracy, reliability, or completeness of these data for individual or aggregate use with other data. Original data were compiled from various sources and may be updated without notification.



# EXHIBIT G Snag Creation Area Map Sheet 3 of 3

R 8 W




T 28 S

- Gate
- Survey Corner
- Stream
- Existing Road
- Road Construction
- Road Renovation
- County Road

- Contract Area
- Harvest Area
- Retention Aggregates
- Yarding Wedge
- Reserve Area
- Snag Creation Area

Scale: 1:12,000

1 inch = 1,000 feet



Date: 2/6/2026

Roseburg District  
Bureau of Land Management  
777 NW Garden Valley Blvd.  
Roseburg, Oregon 97471



No warranty is made by the Bureau of Land Management as to the accuracy, reliability, or completeness of these data for individual or aggregate use with other data. Original data were compiled from various sources and may be updated without notification.



**United States  
Department of the Interior  
Bureau of Land Management**

**Timber Appraisal**

---

<b>Sale Name:</b> Reston Pieces T.S.	<b>Sale Date:</b> Tuesday, March 24, 2026
<b>BLM District:</b> Roseburg DO	<b>Unit of Measure:</b> 16' MBF
<b>Contract #:</b> ORR05-TS-2026.0004	<b>Contract Term:</b> 36 months
<b>Sale Type:</b> Advertised	<b>Contract Mechanism:</b> 5450-003

Lump Sum Sale of Timber and other Wood Products

---

**Content**

- Timber Appraisal Summary**
- Stumpage Summary**
- Unit Summary**
- Stump to Truck**
- Transportation**
- Engineering Allowances**
- Other Allowances**

**Prepared By:** Radford, Sean M - 2/10/2026

**Approved By:** Kehoe, Mark C - 2/19/2026

## Legal Description of Contract Area

Land Status	County	Township	Range	Section	Subdivision	Meridian
CBWR	Douglas	28 S	8 W	15	W1/2SW1/4	Willamette
CBWR	Douglas	28 S	8 W	21	NE1/4	Willamette
CBWR	Douglas	28 S	8 W	23	SW1/4	Willamette
CBWR	Douglas	28 S	8 W	29	NW1/4NE1/4, N1/2NW1/4	Willamette

## Species Totals

Species	Net	Gross Merch	Gross	# of Merch Logs	# of Cull Logs	# of Trees
Douglas Fir	4,641.0	4,939.0	4,977.0	82,058	753	16,208
Grandfir	1,131.0	1,222.0	1,230.0	15,573	110	2,849
Incense-cedar	196.0	253.0	259.0	2,685	61	911
Western Hemlock	92.0	96.0	105.0	1,691	143	521
Western Redcedar	11.0	12.0	13.0	269	32	106
<b>Totals</b>	<b>6,071.0</b>	<b>6,522.0</b>	<b>6,584.0</b>	<b>102,276</b>	<b>1,099</b>	<b>20,595</b>

## Cutting Area Acres

Regeneration Harvest Acres	Partial Cut Acres	Right of Way Acres	Total Acres	Net Volume per Acre
146.0	4.0	9.0	159.0	38.2

**Logging Costs**

Stump to Truck	\$1,085,094.77
Transportation	\$329,625.00
Road Construction	\$361,748.38
Maintenance/Rockwear	\$15,722.51
Road Use	\$72,456.21
Other Allowances	\$37,802.00
<b>Total:</b>	<b>\$1,902,448.87</b>
<b>Total Logging Cost per MBF:</b>	<b>\$313.37</b>

**Utilization Centers**

<u>Location</u>	<u>Distance</u>	<u>% of Net Volume</u>
Dillard, OR	18.3 miles	96%
Roseburg, OR	29.8 miles	4%

**Profit & Risk**

Profit	11%
Risk	2%
<b>Total Profit &amp; Risk</b>	<b>13%</b>

**Tract Features**

<b>Quadratic Mean DBH</b>	15.2 in
<b>Average GM Log</b>	64 bf
<b>Average Volume per Acre</b>	38.2 mbf
<b>Recovery</b>	92%
<b><u>Net MBF volume:</u></b>	
<b>Green</b>	6,071.0 mbf
<b>Salvage</b>	0 mbf
<b>Export</b>	0 mbf
<b><u>Ground Base Logging:</u></b>	
<b>Percent of Sale Volume</b>	33%
<b>Average Yarding Slope</b>	15%
<b>Average Yarding Distance</b>	200 ft
<b><u>Cable Logging:</u></b>	
<b>Percent of Sale Volume</b>	67%
<b>Average Yarding Slope</b>	60%
<b>Average Yarding Distance</b>	700 ft
<b><u>Aerial Logging:</u></b>	
<b>Percent of Sale Volume</b>	0%
<b>Average Yarding Slope</b>	0%
<b>Average Yarding Distance</b>	0 ft

**Cruise**

<b>Cruise Completed</b>	December 2026
<b>Cruised By</b>	SR, JC, CK
<b>Cruise Method</b>	
3P cruised all DF, GF, IC up to 40" DBH. 100% cruised all WH and WRC.	

## Stumpage Computation

Species	# of Trees	Net Volume	Pond Value	(-) Profit & Risk	(-) Logging Costs	(+) Marginal Log Value	Appraised Price/MBF	Appraised Value (\$)
Douglas Fir	16,208	4,641.0	\$579.14	\$75.29	\$313.37	\$0.00	\$190.50	\$884,110.50
Grandfir	2,849	1,131.0	\$461.75	\$60.03	\$313.37	\$0.00	\$88.40	\$99,980.40
Incense-cedar	911	196.0	\$385.20	\$50.08	\$313.37	\$0.00	\$38.60 *	\$7,565.60
Western Hemlock	521	92.0	\$446.82	\$58.09	\$313.37	\$0.00	\$75.40	\$6,936.80
Western Redcedar	106	11.0	\$654.57	\$85.09	\$313.37	\$0.00	\$256.10	\$2,817.10
<b>Totals</b>	<b>20,595</b>	<b>6,071.0</b>						<b>\$1,001,410.40</b>

\* Minimum Stumpage values were used to compute the Appraised Price/MBF (10.00% of Pond Value)

## Other Wood Products

Product	Unit of Measure	# of Units	\$/Unit	Appraised Value
Biomass	Green Tons	184	\$3.00	\$552.00
<b>Totals</b>				<b>\$552.00</b>

**Total Appraised Value: \$1,001,962.40**

**Percent of Volume By Log Grade**

Species	No. 1 & 2 Peeler	No. 3 Peeler	Special Mill	No. 2 Sawmill	No. 3 Sawmill	No. 4 Sawmill	Camp Run
Douglas Fir				54.0%	42.0%	4.0%	

Species	Peeler	No. 1 Sawmill	Special Mill	No. 2 Sawmill	No. 3 Sawmill	No. 4 Sawmill	Camp Run
Grandfir				70.0%	28.0%	2.0%	

Species	No. 1 Sawmill	No. 2 Sawmill	No. 3 Sawmill	No. 4 Sawmill	No. 5 Sawmill	No. 6 Sawmill	Camp Run
Incense-cedar							100.0%

Species	Peeler	No. 1 Sawmill	Special Mill	No. 2 Sawmill	No. 3 Sawmill	No. 4 Sawmill	Camp Run
Western Hemlock				44.0%	49.0%	7.0%	

Species	No. 1 Sawmill	No. 2 Sawmill	No. 3 Sawmill	No. 4 Sawmill			Camp Run
Western Redcedar							100.0%

## Unit: 1

Species	Net	Gross Merch	Gross	# of Trees
Grandfir	73.0	79.0	80.0	181
Douglas Fir	57.0	61.0	62.0	173
Incense-cedar	1.0	1.0	1.0	7
<b>Totals:</b>	<b>131.0</b>	<b>141.0</b>	<b>143.0</b>	<b>361</b>

## Net Volume/Acre: 32.8 MBF

Regeneration Harvest	0.0
Partial Cut	4.0
Right of Way	0.0
<b>Total Acres:</b>	<b>4.0</b>

## Unit: 2

Species	Net	Gross Merch	Gross	# of Trees
Douglas Fir	877.0	933.0	939.0	2,525
Grandfir	276.0	298.0	300.0	547
Incense-cedar	15.0	19.0	20.0	64
Western Hemlock	1.0	1.0	2.0	1
<b>Totals:</b>	<b>1,169.0</b>	<b>1,251.0</b>	<b>1,261.0</b>	<b>3,137</b>

## Net Volume/Acre: 34.4 MBF

Regeneration Harvest	34.0
Partial Cut	0.0
Right of Way	0.0
<b>Total Acres:</b>	<b>34.0</b>

## Unit: 3

Species	Net	Gross Merch	Gross	# of Trees
Douglas Fir	100.0	106.0	107.0	452
Grandfir	58.0	62.0	63.0	151
Incense-cedar	2.0	3.0	3.0	20
<b>Totals:</b>	<b>160.0</b>	<b>171.0</b>	<b>173.0</b>	<b>623</b>

## Net Volume/Acre: 40.0 MBF

Regeneration Harvest	4.0
Partial Cut	0.0
Right of Way	0.0
<b>Total Acres:</b>	<b>4.0</b>

**Unit: 4**

Species	Net	Gross Merch	Gross	# of Trees
Douglas Fir	300.0	319.0	322.0	1,303
Grandfir	78.0	85.0	85.0	256
Incense-cedar	3.0	3.0	3.0	16
Western Hemlock	1.0	1.0	1.0	6
<b>Totals:</b>	<b>382.0</b>	<b>408.0</b>	<b>411.0</b>	<b>1,581</b>

**Net Volume/Acre: 27.3 MBF**

Regeneration Harvest	14.0
Partial Cut	0.0
Right of Way	0.0
<b>Total Acres:</b>	<b>14.0</b>

**Unit: 5**

Species	Net	Gross Merch	Gross	# of Trees
Douglas Fir	674.0	716.0	719.0	2,547
Incense-cedar	137.0	178.0	181.0	622
Grandfir	62.0	67.0	68.0	178
<b>Totals:</b>	<b>873.0</b>	<b>961.0</b>	<b>968.0</b>	<b>3,347</b>

**Net Volume/Acre: 26.5 MBF**

Regeneration Harvest	33.0
Partial Cut	0.0
Right of Way	0.0
<b>Total Acres:</b>	<b>33.0</b>

**Unit: 6**

Species	Net	Gross Merch	Gross	# of Trees
Douglas Fir	401.0	427.0	430.0	1,532
Grandfir	168.0	182.0	183.0	461
Incense-cedar	9.0	12.0	13.0	42
Western Redcedar	4.0	4.0	5.0	28
Western Hemlock	1.0	1.0	1.0	4
<b>Totals:</b>	<b>583.0</b>	<b>626.0</b>	<b>632.0</b>	<b>2,067</b>

**Net Volume/Acre: 38.9 MBF**

Regeneration Harvest	15.0
Partial Cut	0.0
Right of Way	0.0
<b>Total Acres:</b>	<b>15.0</b>

**Unit: 7**

Species	Net	Gross Merch	Gross	# of Trees
Douglas Fir	1,863.0	1,983.0	1,995.0	6,517
Grandfir	309.0	333.0	335.0	800
Western Hemlock	80.0	84.0	91.0	456
Incense-cedar	22.0	28.0	29.0	119
Western Redcedar	7.0	8.0	8.0	78
<b>Totals:</b>	<b>2,281.0</b>	<b>2,436.0</b>	<b>2,458.0</b>	<b>7,970</b>

**Net Volume/Acre: 49.6 MBF**

Regeneration Harvest	46.0
Partial Cut	0.0
Right of Way	0.0
<b>Total Acres:</b>	<b>46.0</b>

**Unit: 28-8-22.1 RD**

Species	Net	Gross Merch	Gross	# of Trees
Douglas Fir	17.0	18.0	18.0	73
Grandfir	1.0	1.0	1.0	3
Incense-cedar	1.0	1.0	1.0	2
<b>Totals:</b>	<b>19.0</b>	<b>20.0</b>	<b>20.0</b>	<b>78</b>

**Net Volume/Acre: 19.0 MBF**

Regeneration Harvest	0.0
Partial Cut	0.0
Right of Way	1.0
<b>Total Acres:</b>	<b>1.0</b>

**Unit: 28-8-23.6 RD**

Species	Net	Gross Merch	Gross	# of Trees
Douglas Fir	187.0	199.0	201.0	515
Grandfir	70.0	76.0	76.0	128
Incense-cedar	2.0	3.0	3.0	11
<b>Totals:</b>	<b>259.0</b>	<b>278.0</b>	<b>280.0</b>	<b>654</b>

**Net Volume/Acre: 64.8 MBF**

Regeneration Harvest	0.0
Partial Cut	0.0
Right of Way	4.0
<b>Total Acres:</b>	<b>4.0</b>

**Unit: SPUR 1 & 2**

Species	Net	Gross Merch	Gross	# of Trees
Douglas Fir	47.0	50.0	51.0	149
Grandfir	24.0	26.0	26.0	102
Incense-cedar	1.0	1.0	1.0	4
<b>Totals:</b>	<b>72.0</b>	<b>77.0</b>	<b>78.0</b>	<b>255</b>

**Net Volume/Acre: 72.0 MBF**

Regeneration Harvest	0.0
Partial Cut	0.0
Right of Way	1.0
<b>Total Acres:</b>	<b>1.0</b>

**Unit: SPUR 3**

Species	Net	Gross Merch	Gross	# of Trees
Douglas Fir	27.0	30.0	32.0	102
<b>Totals:</b>	<b>27.0</b>	<b>30.0</b>	<b>32.0</b>	<b>102</b>

**Net Volume/Acre: 27.0 MBF**

Regeneration Harvest	0.0
Partial Cut	0.0
Right of Way	1.0
<b>Total Acres:</b>	<b>1.0</b>

**Unit: SPUR 4, 20.2/20.3 RD**

Species	Net	Gross Merch	Gross	# of Trees
Douglas Fir	91.0	97.0	101.0	320
Grandfir	12.0	13.0	13.0	42
Western Hemlock	9.0	9.0	10.0	54
Incense-cedar	3.0	4.0	4.0	4
<b>Totals:</b>	<b>115.0</b>	<b>123.0</b>	<b>128.0</b>	<b>420</b>

**Net Volume/Acre: 57.5 MBF**

Regeneration Harvest	0.0
Partial Cut	0.0
Right of Way	2.0
<b>Total Acres:</b>	<b>2.0</b>

**Comments:**

Volume for Spur 3 came from 1 ac. of Unit 5

Total Stump To Truck	Net Volume	\$/MBF
\$1,085,094.77	6,071.0	\$178.73

### Stump to Truck: Falling, Bucking, Yarding, & Loading

Yarding System	Unit of Measure	# of Units of Measure	\$/Unit of Measure	Total Cost	Remarks
Track Skidder	GM MBF	498.0	\$235.91	\$117,483.18	ALL NEW CONSTRUCT RDS, 5 loads/day 5 MBF/load
Cable: Medium Yarder	GM MBF	736.0	\$207.28	\$152,558.08	Unit 2, 7 loads/day 5 MBF/load
Cable: Medium Yarder	GM MBF	626.0	\$181.37	\$113,537.62	Unit 6, 8 loads/day 5 MBF/load
Cable: Medium Yarder	GM MBF	931.0	\$161.22	\$150,095.82	Unit 5, 9 loads/day 5 MBF/load
Cable: Medium Yarder	GM MBF	408.0	\$161.22	\$65,777.76	Unit 4, 9 loads/day 5 MBF/load
Shovel	GM MBF	887.0	\$145.18	\$128,774.66	Units 1, 3 and Portions of Units 2, 5, 7 loads/day 5 MBF/load
Cable: Medium Yarder	GM MBF	1,695.0	\$145.10	\$245,944.50	Unit 7, 10 loads/day 5 MBF/load
Wheel Skidder	GM MBF	741.0	\$132.15	\$97,923.15	Unit 7, Ground Base, 10 loads/day 5 MBF/load
<b>Subtotal</b>				<b>\$1,072,094.77</b>	

### Additional Costs

Item	Unit of Measure	# of Units of Measure	\$/Unit of Measure	Total Cost	Remarks
Intermediate Support	Each	18.0	\$200.00	\$3,600.00	
Lift Tree	Each	52.0	\$100.00	\$5,200.00	
<b>Subtotal</b>				<b>\$8,800.00</b>	

### Additional Moves

Equipment	Unit of Measure	# of Units of Measure	\$/Unit of Measure	Total Cost	Remarks
Cable: Medium Yarder	Hour	4.0	\$150.00	\$600.00	Cable
Loader	Hour	4.0	\$150.00	\$600.00	Cable
Processor	Hour	4.0	\$150.00	\$600.00	Cable
Track Skidder	Hour	4.0	\$150.00	\$600.00	Ground Base
Shovel/Loader	Hour	6.0	\$150.00	\$900.00	Ground Base
Processor	Hour	6.0	\$150.00	\$900.00	Ground Base
<b>Subtotal</b>				<b>\$4,200.00</b>	

**Comments:**

Total Sale GM = 6,522 MBF, Fuel \$4.00/gal

Track Skidder – SPURS 1, 2, 3, 4, 20.2 RD, 20.3 RD, 23.6 RD, 22.1 RD - 9 ac. = 498 MBF (16' GM)

Wheeled Skidder – 14 ac. of Unit 7

Unit 7 = 14 ac. x 53 MBF/ac. = 741 MBF (16' GM)

Shovel – Units 1, 3 and portions of Units 2 and 5 - 24 ac.

Unit 1 = 4 ac. x 35.3 MBF/ac. = 141 MBF (16' GM)

Unit 3 = 4 ac. x 42.8 MBF/ac. = 171 MBF (16' GM)

Unit 2 = 14 ac. x 36.8 MBF/ac. = 515 MBF (16' GM)

Unit 5 = 2 ac. x 30.0 MBF/ac. = 60 MBF (16' GM)

Total = 141 + 171 + 515 + 60 = 887 MBF (16' GM)

Cable, Med Tower, Mech. Delimiting – 112 ac.

Total sale GM = 6,522 MBF – 498 MBF – 741 MBF - 887 MBF = 4,396 MBF (16' GM) total Cable

Uphill Cable – 112 ac. = 4,396 MBF (16' GM)

Cable Ground – Units 2,4,5,6, 7

Unit 2: Cable: Medium Tower, Mech. Delimiting

7 loads/day = \$207.28/MBF x 736 MBF (16' GM) = \$152,558.08

Unit 4: Medium Tower, Mech. Delimiting

9 loads/day = \$161.22/MBF x 408 MBF (16' GM) = \$65,777.76

Unit 5: Medium Tower, Mech. Delimiting

9 loads/day = \$161.22/MBF x 931 MBF (16' GM) = \$150,095.82

Unit 6: Medium Tower, Mech. Delimiting

8 loads/day = \$181.37/MBF x 626 MBF (16' GM) = \$113,537.62

Unit 7: Medium Tower, Mech. Delimiting

10 loads/day = \$145.10/MBF x 1,695 MBF (16' GM) = \$245,944.50

Total Cable = \$727,913.78 = \$165.59/MBF

Ground Base

Unit 7: Wheeled Skidder, Manual Felling w/ Processor

10 loads/day = \$132.15/MBF x 741 MBF (16' GM) = \$97,923.15

Units 1, 3 and portions of Units 2 and 5: Shovel, Manual Felling w/ Processor

7 loads/day = \$145.18/MBF x 887 MBF (16' GM) = \$128,774.66

ALL SPURS and NEW road Construction: Tracked Skidder w/ Processor

5 loads/day = \$235.91/MBF x 498 MBF (16' GM) = \$117,483.18

Additional Moves

Cable inter-unit move-ins: \$1,800.00

Yarder: 2 moves, 2hrs/move = 4 hours x \$150/hour = \$600.00

Loader: 2 moves, 2hrs/move = 4 hours x \$150/hour = \$600.00

Processor: 2 moves, 2hrs/move = 4 hours x \$150/hour = \$600.00

Ground-based inter-unit move-ins: \$2,400.00

Track Skidder: 2 moves, 2hrs/move = 4 hours x \$150/hour = \$600.00

Loader/Shovel: 3 moves, 2hrs/move = 6 hours x \$150/hour = \$900.00

Processor: 3 moves, 2hrs/move = 6 hours x \$150/hour = \$900.00

NO additional moves for Wheeled Skidders

Logging Cost Summary

Cable: Medium Tower, Mech. Delimiting = \$727,913.78

Wheeled Skidder, Manual Felling w/ Processor = \$97,923.15

Tracked Skidder, Manual Felling w/ Processor = \$117,483.18

Shovel, Manual Felling w/ Processor = \$128,774.66

Additional Moves = \$4,200.00

Lift Trees: 52 Trees x \$100.00/tree = \$5,200.00

Intermediate Supports: 18 supports x \$200.00/support = \$3,600.00

Total: \$1,085,094.77

Total	Net Volume	\$/MBF
\$329,625.00	6,071.0	\$54.30

Utilization Center	One Way Mileage	Description	Unit of Measure	# of Units	\$/Unit of Measure	Total Cost	% of Sale Volume
Dillard, OR	18.3	from weighted midpoint	Hour	2,504.0	\$125.00	\$313,000.00	96%
Roseburg, OR	29.8	from weighted midpoint	Hour	133.0	\$125.00	\$16,625.00	4%

**Comments:**

All Cedar volume

Load(s) = 265 GM MBF / 5 MBF/Ld = 53 Ld(s) (Rounded)

RTM = (91 Min/Ld + 60 Min Delay) / 60 Min/Hr = 2.5 Hrs/Ld

2.5 Hrs/Ld X 53 Loads = 133 Total Hrs.

133 Hrs X \$125/Hr = \$16,625.00 Transportation Cost

All sale volume except for IC, WRC

Load(s) = 6,257 GM MBF / 5 MBF/Ld = 1,252 Ld(s) (Rounded)

RTM = (56 Min/Ld + 60 Min Delay) / 60 Min/Hr = 2 Hrs/Ld

2 Hrs/Ld X 1,252 Loads = 2,504 Total Hrs.

2,504 Hrs X \$125/Hr = \$313,000.00 Transportation Cost

Dillard = \$313,000.00

Roseburg = \$16,625.00

\$329,625.00

**Engineering Allowances**

Total	Net Volume	\$/MBF
\$449,927.10	6,071.0	\$74.11

Cost Item	Total Cost
Road Construction:	\$361,748.38
Road Maintenance/Rockwear:	\$15,722.51
Road Use Fees:	\$72,456.21

Total	Net Volume	\$/MBF
\$37,802.00	6,071.0	\$6.23

### Environmental Protection

Cost item	Total Cost
Equipment Cleaning	\$1,485.00
Sub-soiling: Transport	\$220.00
Sub-soiling: Excavator Work	\$1,035.00
<b>Subtotal</b>	<b>\$2,740.00</b>

### Miscellaneous

Cost item	Total Cost
Snag Creation	\$9,712.00
<b>Subtotal</b>	<b>\$9,712.00</b>

### Slash Disposal & Site Prep

Cost item	Total Cost
Burn Landing Piles	\$2,255.00
Burn Hand Piles	\$1,140.00
Burn Machine Piles	\$1,330.00
Landing Piling/Covering	\$5,125.00
Machine Piling/Covering	\$7,700.00
Hand Piling/Covering	\$7,800.00
<b>Subtotal</b>	<b>\$25,350.00</b>

## Comments:

### 1. Fire Protection Included in Logging Costs

### 2. Slash Disposal

- Landing piling/covering: 41 Landings x \$125/landing = \$5,125.00
- To burn landing piles (Buy Out \$ not included): 41 x \$55 = \$2,255.00
- Machine piling/covering: 14 acres x \$550.00/ac = \$7,700.00
- To burn machine piles (Buy Out \$ not included): 14 acres x \$95.00/ac = \$1,330.00
- Hand piling/covering: 12 acres x \$650.00/ac = \$7,800.00
- To burn hand piles (Buy Out \$ not included): 12 acres x \$95.00/ac = \$1,140.00

### Miscellaneous:

### 3. Equipment Cleaning

- Two Rubber Tire Skidder x 3 hours = 6 hours
- One Yarder x 3 hours = 3 hours
- Two Shovels x 3 hours = 6 hours
  - o 1 shovel for ground base, and 1 shovel for Cable Yarding
- One Track Skidder x 3 hours = 3 hours
- Two Processers x 3 hours = 6 hours
  - o 1 processer for ground base, and 1 processer for Cable Yarding
- One Excavator for sub-soiling x 3 hours = 3 hours
- 27 Total Hours x \$55/ hour = \$ 1,485.00

### 4. Skid Trail Sub-soiling

- .67 miles of skid trails / .75 miles sub-soiled/day = 1 day x 9 hours/day = 9 hrs. x \$115.00/hour = \$1,035.00
- 1 move to sale x 2 hours/move x \$ 110/hour = \$220.00
- Total sub-soil cost = \$1,035.00 + \$220.00= \$1,255.00

### 5. Snag Creation

- 543 snags ÷ 35 snags/day = 16 days of work
- \$607/day for cutter x 16 days = \$9,712.00

Total for Other Allowances: \$37,802.00

### Slash Disposal Buyout Option

- \$4,725.00 x 19.09% = \$902.00
- 19.09% represents admin fee
- \$4,725.00 + \$902.00 = \$5,627.00

Total Buyout Cost = \$5,627.00

UNITED STATES  
DEPARTMENT OF THE INTERIOR  
BUREAU OF LAND MANAGEMENT

Version: 8.0.0.32  
Updated: 11/4/2022

**Summary of All Roads and Projects**

T.S. Contract Name: Reston Pieces    Tract No: 2026.0004    Sale Date:  
Prepared by: JHarder Ph:    Print Date: 1/23/2026 7:27:38 AM  
Construction: 83.25 sta  
Renov: 280.67 sta

200 Clearing and Grubbing: 1.92 acres .....	\$8,524.71
300 Excavation: 17565 cy .....	\$84,750.59
Haul < 500 ft: 69959 sta-yds	
Haul > 500 ft: 0 yd-mi	
400 Drainage: .....	\$29,919.60
Culvert: 0.00 lf                      DownSpout: 0.00 lf	
PolyPipe: 520.00 lf	
500 Renovation: .....	\$9,973.88
Blading 5.31 mi	
700-1200 Surfacing: .....	\$208,502.50
Commercial Quarry Name: B&D 5,310.00 LCY	
1300 Geotextiles: .....	\$0.00
1400 Slope Protection: .....	\$0.00
1800 Soil Stabilization: 0.00 acres .....	\$0.00
1900 Cattleguards: .....	\$0.00
2100 RoadSide Brushing: .....	\$2,018.19
Manual Brushing: 1.23 acres	
2300 Engineering: 0.00 sta. ....	\$0.00
2400 Minor Concrete: .....	\$0.00
2500 Gabions: .....	\$0.00
8000 Miscellaneous: .....	\$0.00
Mobilization: Const. \$11,802.12    Surf. \$6,256.79.....	\$18,058.91
Quarry Development: .....	\$0.00
Total: 6,071 mbf @ \$59.586/mbf = \$361,748.38	

Notes:

Quantities shown are estimates only and not pay items.  
Surfacing Quantities are loose cubic yards.

UNITED STATES  
DEPARTMENT OF THE INTERIOR  
BUREAU OF LAND MANAGEMENT

Contract Name: Reston Pieces  
Sale Date:  
Tract No: 2026.0004

**ROAD CONSTRUCTION SUMMARY**

1/ Const/Impr/Renov/Decom/Temp    2/ yd-miles haul    3/ Lin ft CMP    4/ Lin ft Polypipe    5/ Lin ft Downspout    6/ slide removal cy

Road Number	Type 1/	Miles	Clear Grubb	Excav -ation	Drain -age	Reno- vation	Surf- acing	Geo- textile	Slope Protect	Soil Stabil	Cattle Guard	Rdside Brush	Engin- eering	Minor Concrete	Gab- ions	Miscel- laneous	Mobil- ization	Quarry Develop	Sub- Total
28-8-15.1	R	0.61				\$1,146 0.61 mi						\$357 0.37ac					\$52		\$1,555
28-8-16.2	R	0.95				\$1,784 0.95 mi											\$61		\$1,846
28-8-20.1	R	1.15				\$2,160 1.15 mi	\$2,365 65 LCY										\$232		\$4,757
28-8-20.2	R	0.18				\$338 0.18 mi	\$182 5 LCY										\$24		\$544
28-8-20.2 Const	C	0.09	\$425 0.11 ac	\$579 88cy 2/ 0.66													\$34		\$1,038
28-8-20.3	R	0.23				\$432 0.23 mi	\$364 10 LCY										\$39		\$835
28-8-20.3 Const	C	0.16	\$734 0.19 ac	\$9,098 1598cy 2/ 222.08	\$4,095 4/ 80'		\$22,014 560 LCY										\$1,894		\$37,835
28-8-21.0	R	0.86				\$1,615 0.86 mi	\$7,862 200 LCY					\$1,661 0.86ac					\$618		\$11,756
28-8-22.1 Const	C	0.13	\$618 0.16 ac	\$2,754 378cy 2/ 82.39	\$2,048 4/ 40'		\$19,262 490 LCY										\$1,425		\$26,107
28-8-23.1	R	0.25				\$470 0.25 mi											\$16		\$486
28-8-23.2	R	0.53				\$996 0.53 mi											\$34		\$1,030
28-8-23.3	R	0.55				\$1,033 0.55 mi											\$35		\$1,069
28-8-23.6 Const	C	0.76	\$4,700 0.93 ac	\$51,972 12346cy 2/ 394.96	\$19,682 4/ 320'		\$95,523 2430 LCY										\$8,765		\$180,642
SPUR 1	C	0.06	\$270 0.07 ac	\$2,984 360cy 2/ 128.60			\$12,579 320 LCY										\$921		\$16,754

Road Number	Type 1/	Miles	Clear Grubb	Excav -ation	Drain -age	Renovation	Surf-acing	Geo-textile	Slope Protect	Soil Stabil	Cattle Guard	Rdside Brush	Engin-eering	Minor Concrete	Gab-ions	Miscel-laneous	Mobil-ization	Quarry Develop	Sub-Total
SPUR 2	C	0.16	\$734 0.19 ac	\$10,412 1681cy 2/ 312.37	\$2,048 4/ 40'		\$22,407 570 LCY										\$1,894		\$37,494
SPUR 3	C	0.14	\$695 0.18 ac	\$5,830 877cy 2/ 182.63	\$2,048 4/ 40'		\$25,945 660 LCY										\$1,963		\$36,481
SPUR 4	C	0.07	\$348 0.09 ac	\$1,123 237cy 2/ 1.29													\$50		\$1,521

---

**TIMBER SALE ROAD SPECIFICATIONS**

---

**TABLE OF CONTENTS**

<b>SECTION</b>	<b>DESCRIPTION</b>
100	General
200	Clearing and Grubbing
300	Excavation and Embankment
400	Pipe Culverts
500	Renovation and Improvement of Existing Roads
600	Watering
1000	Aggregate Base Course - Crushed Rock
1200	Aggregate Surface Course - Crushed Rock
1700	Erosion Control
1800	Soil Stabilization
2100	Roadside Brushing

---

**TIMBER SALE ROAD SPECIFICATIONS**

---

**GENERAL – 100**

101 - Prewrite Conference(s):

A prework conference will be held prior to the start of new construction, improvement, renovation, quarry development, surfacing, and mulching operations. The Purchaser shall request the conference at least 48 hours prior to the time it is to be held. The conference will be attended by the Purchaser and/or his representatives, subcontractors and/or his or their representatives and the Authorized Officer and/or his representatives.

The purpose of the prework conference will be to review the required work, exhibits and specifications, and to establish a work schedule and a list of the Purchaser's representatives, and subcontractors.

102 - Definitions:

AASHTO - American Association of State Highway and Transportation Officials. Current editions of tests and specifications.

Abrasion Resistance - The ability of a fabric surface to resist wear by friction.

ACI - American Concrete Institute

Apparent Opening Size (AOS) - Number of the U.S. Bureau of Standard sieve (or its opening size in millimeters or inches) having openings closest in size to the diameter of uniform particles which will allow 5 percent by weight to pass through the geotextile material when shaken in a prescribed manner. This is also referred to as Equivalent Opening Size (EOS).

ASTM - American Society for Testing and Materials.

Base Course - Surfacing structure consisting of crushed gravel or stone, crushed sandstone, pitrun rock, bank, or river-run gravels, etc., to provide support and, in the event no surface course is placed, the running surface for traffic load.

BLM - Bureau of Land Management

Borrow - Excavated material required for embankments and other portions of the work.

---

## TIMBER SALE ROAD SPECIFICATIONS

---

Burst Strength - The resistance of a geotextile material to rupture from pressure applied at right angles to the plane of the geotextile material under specified conditions, usually expressed as the amount of pressure causing failure. Rupture or burst results from tensile failure of the geotextile material.

Culvert - A pipe, pipe-arch, arch, or box structure constructed of metal, concrete, plastic, or wood which provides an opening under the roadway primarily for the conveyance of liquids, pedestrians or livestock.

Curve Widening - Widening required on inside of curves to accommodate long log and equipment hauling trucks.

Embankment - A structure of soil, aggregate, or rock material placed on a prepared ground surface and constructed to subgrade.

End Haul - Excavated material moved, other than by dozer, to an embankment or waste area to prevent sidecasting material outside of the road prism.

Excess Excavation - Material from the roadway in excess of that needed for construction of the designed roadway (waste).

Grab Tensile Strength - A modified tensile strength of a geotextile material. The strength of a specific width of geotextile material together with the additional strength contributed by adjacent areas. Typically, grab strength is determined on a 12-inch-wide strip of geotextile material, with the tensile load applied at the midpoint of the geotextile material width through 1-inch-wide jaw faces.

Grading - Leveling to grade, shaping, and smoothing of a road subgrade; the shaping of roadside ditches as to grade and contour. In some instances, includes smoothing of the cut bank.

Nonwoven Geotextile Material - A textile structure produced by bonding or interlocking of fibers, or both, accomplished by mechanical or chemical means.

Overhaul - Distance excavated material is transported in excess of the distance included in the cost for excavation.

Penetration Resistance - The geotextile material property determined by the force required to penetrate a geotextile material with a sharp pointed object. Initial penetration is by separating the fibers. Further penetration is essentially a tearing process.

---

## TIMBER SALE ROAD SPECIFICATIONS

---

Percent Open Area - The net area of a geotextile material that is not occupied by geotextile material filaments, normally determinable only for woven and nonwoven geotextile material having distinct, visible, and measurable openings that continue directly through the geotextile material.

Permeability - The geotextile material property which permits water to be transmitted in the longitudinal or transverse planes of the geotextile material.

Pioneer Road - Temporary construction access built along the route of the project.

Piping - The process by which soil particles are washed in or through pore spaces in drains and filters or poorly compacted fill/backfill material.

Plans - The approved drawings, or exact reproductions thereof which show the locations, character, dimensions, and details of the work to be done.

Pore Size - The size of an opening between geotextile material filaments; apparent opening size (AOS) is used to quantify this geotextile material property.

Puncture Resistance - The geotextile material property determined by the force required to penetrate a geotextile material with a blunt object. Failure results in a tearing of the geotextile material.

Purchaser - The individual, partnership, joint venture, or corporation contracting with the Government under the terms of a Timber Sale Contract and acting independently or through their, or its agents, employees, or contractors.

Reasonably Close Conformity - Compliance with reasonable and customary manufacturing and construction tolerances where working tolerances are not specified.

Reinforcement - Strengthening of concrete with iron bars or mesh: geotextile with geotextile material inclusion: subgrade with aggregate: etc.

Roadbed - The graded portion of the road within top and side slopes, prepared as a foundation for the pavement structure and shoulders.

Road Centerline - The longitudinal center of a roadbed.

Road Improvement - Work done to an existing road which improves it over its original design standard.

Road Renovation - Work done to an existing road which restores it to its original design.

---

## TIMBER SALE ROAD SPECIFICATIONS

---

Roadway - The portion of a road within limits of construction. Usually from the toe of the fill slope to a point where the cut slope intersects natural ground line. Synonym - road prism.

Scale - In quarrying, consists of the removal of loose or overhanging rock adhering to the solid face after a shot or a round of shots has been fired.

Scarification - The process of loosening or breaking up of the surface layer of soil or road, usually to a specified depth.

Separation - Function of geotextile material as a partition between adjacent materials to prevent mixing of those materials.

Shoulder - The portion of the roadbed contiguous with the traveled way designed for accommodation of stopped vehicles, safety, and lateral support of base and surface courses.

Slash - All material (brush, limbs, tops, unmerchantable stems, and chunks) severed or knocked over as a result of clearing or brushing operations.

Slash Mulch - A mulch consisting of clearing, grubbing, or logging debris, commonly used for road decommissioning. If slash mulch is not available, other mulches may be substituted as described in sections 1800 and 3500 of this contract.

Spalls - Flakes or chips of stone.

Specifications - A general term applied to all directions, provisions, and requirements pertaining to performance of the work.

Specific Gravity - The ratio of the density of a material to the density of water obtained by weighing known volumes of both items in air. A specific gravity less than one implies that the material will float.

Structures - Bridges, culverts, catch basins, retaining walls, underdrains, flumes, splash pads, downspouts, and other project features which may be involved in the work and not otherwise classified in these specifications.

Subbase - Reinforcement of the subgrade with large particles of pitrun rock or crushed stone. Usually confined to roads having wet subgrades or subgrades with weak support characteristics.

Surface Course - Top layer of a road structure consisting of finely crushed gravels or asphalt designed to provide a smooth-running surface for traffic load.

---

## TIMBER SALE ROAD SPECIFICATIONS

---

Subgrade - The top surface of a roadbed upon which the traveled way and shoulders are constructed.

Tensile Strength - The strength shown by a geotextile material subjected to tension as distinct from torsion, compression, or shear.

Tensile Stress - Strain Modulus - A measure of the resistance to elongation under stress. The ratio of the change in tensile stress to the corresponding change in strain.

Tensile Test - A test which subjects geotextile material to tensile forces and measures resultant stresses and strains.

Timber - Standing trees, downed trees, or logs which can be measured in board feet.

Traveled Way - The portion of the roadbed used for the movement of vehicles, exclusive of shoulders.

Typical Cross Sections - Cross-sectional plane of a typical roadway; showing natural ground line and designed roadway in relation to cut and fill, through cut, and through fill.

Turnout - Extra widening of the roadbed at appropriate intervals on single-lane roads for passing purposes.

Ultraviolet (UV) Radiation Stability - The ability of geotextile material to resist deterioration from exposure to sunlight.

Unaged Cloth - Cloth in condition received from the manufacturer or distributor.

Woven Geotextile Material - A textile structure comprising two or more sets of filaments of yarns interlaced in such a way that the elements pass each other at essentially right angles with one set of elements parallel to the geotextile material axis.

102a - Tests Used in These Specifications:

AASHTO T 11

Quantity of rock finer than No. 200 sieve.

AASHTO T 27

Sieve analysis of fine and coarse aggregate using sieves with square openings; gradation.

AASHTO T 89

Liquid limit of material passing the No. 40 sieve. Water content at which the soil passes from a plastic to a liquid state.

---

**TIMBER SALE ROAD SPECIFICATIONS**

---

AASHTO T 90

Plastic limits and plasticity index of soil.

- a. Plastic limit - lowest water content at which the soil remains plastic.
- b. Plasticity index - range of water content, within which the material is in a plastic state.  
Numerical difference between the liquid and plastic limits of the soil.

AASHTO T 96

Resistance to abrasion of small size coarse aggregate by use of the Los Angeles machine.

AASHTO T 99

Relationship between soil moisture and density of soil.

Method A - 4" mold, soil passing a No. 4 sieve

25 blows/layer & 3 layers.

Method C - 4" mold, soil passing a 3/4 inch sieve

25 blows/layer & 3 layers.

Method D - 6" mold, soil passing a 3/4 inch sieve. 56 blows/layer & 3 layers.

AASHTO T 119

Slump of hydraulic cement concrete.

AASHTO T 152

Air content of freshly mixed concrete.

AASHTO T 166

Specific Gravity of compacted Bituminous Mixtures.

AASHTO T 176

Shows relative portions of fine dust or claylike materials in soil or graded aggregate.

AASHTO T 180

(OSHD 106-71) moisture density relationship of soil same as AASHTO T 99 proctor but uses a 10-lb rammer & 18-in drop height.

AASHTO T 191

Sand Cone. Density of soil in place: For subgrade use 6-inch or 12-inch cone. For rock surfacing for 1-1/2-inch minus to 3-inch minus use 12-inch cone.

AASHTO T 205

Rubber balloon. Density of soil in place. Use for compacted or firmly bonded soil.

AASHTO T 209

Maximum Specific Gravity of Bituminous Paving Mixtures.

---

**TIMBER SALE ROAD SPECIFICATIONS**

---

AASHTO T 210

Durability of aggregates based on resistance to produce fines.

AASHTO T 224

Correction for coarse particles in the soil.

AASHTO T 238

Density of Soil and Soil-Aggregate in place by nuclear methods.

AASHTO T 248

Reducing field samples of aggregate to testing size by mechanical splitter, quartering, or miniature stockpile sampling.

ASTM D 4564

Determination of relative density of cohesionless soils.

DMSO (dimethyl sulfide)

Determines volume of expanding clays in aggregates. Usually associated with marine basalts.

- 103 - Compaction equipment shall meet the following requirements:
- 103a - Padded Drum (Tamping) Rollers. The unit shall consist of a drum with pads, be either self-propelled or towed by a tractor, and capable of operating at a speed of 6 mph. The drum shall be no less than 48 inches in diameter over the pads and not less than 60 inches in width. The pads shall have a minimum height of 3 inches, and a face area of not less than 14 square inches. The weight at drum shall be no less than 8000 lb.
- 103b - Sheepfoot (Tamping) rollers. A tamping roller unit shall consist of two watertight metal drums mounted in frames in such manner as to be fully oscillating, together with a tractor having sufficient weight and power under actual working conditions to pull the roller drums at a minimum speed of 2.5 miles per hour. The drums shall be no less than 60 inches in diameter and no less than 54 inches in length, measured at the drum's surface, and shall be studded with tamping feet projecting not less than 7 inches from the face of the drums.

The distance between circumferential rows of tamper feet shall be such that the diagonal distance from any foot to the nearest foot in each adjacent row shall be not more than 12 inches. The cross-sectional area of the face of each tamper foot, measured perpendicular to the axis of the stud, shall be not less than 5-1/2 square inches nor more than 8 square inches.

---

**TIMBER SALE ROAD SPECIFICATIONS**

---

The weight of the tamping-roller unit shall be such as to exert a minimum pressure of 250 pounds per square inch on the ground area in contact with the tamping feet, and the roller shall be so designed that the weight may be increased to exert a pressure up to 500 pounds per square inch on the ground area in contact with the tamping feet. The ground pressure shall be determined by dividing the total weight of the roller unit, not including the weight of the tractor, by the total cross-sectional area of the tamping feet in one row of tamping feet parallel to the axis of the roller.

103c - Smooth-wheel power rollers. Smooth-wheel power rollers shall either be of the 3-wheel type, weighing not less than 10 tons, or of the tandem type, 2-wheel, or 3-wheel, weighing not less than 8 tons. Smooth-wheel roller shall provide compression of 325 pounds per linear inch of width of rear wheels or drum.

103d - Pneumatic-tired rollers. Pneumatic-tired rollers shall be of the double-axle type equipped with pneumatic tires each of equal size and type. The spacing between the sidewalls of adjacent tires shall not exceed 5 inches and the rear tires shall be staggered in relation to the front tires. The rolling width of the unit shall be not less than 60 inches, exclusive of the power unit. The roller shall be so constructed that the contact pressure is uniformly distributed on all the tires, and the tires shall be inflated to maintain the air pressure in the several tires within a total tolerance of 5 pounds per square inch. The roller shall be so constructed that the total weight shall be between 1,000 and 2,000 pounds per tire. The actual operating weight of the rollers shall be as ordered by the Authorized Officer.

Each pneumatic-tired roller shall be drawn by equipment having sufficient power and weight under normal working condition to pull the roller at a minimum speed of 5 miles per hour, or it may be self-propelled to obtain a minimum speed of 5 miles per hour.

103e - Grid roller. A grid roller shall consist of two or more cylindrical drums independently mounted on a common shaft in a rigid frame. Each drum shall have a minimum outside diameter of 5 feet and a minimum width of 2 feet 6 inches. The overall width of the roller exclusive of frame shall be not less than 5 feet 6 inches of which not more than 6 inches shall be used for center spacing between two roller drums. The face of the drums shall have the appearance of woven open mesh made by interlacing bars of not less than 1-1/4 inches nor more than 1-3/4 inches diameter spaced on 4-1/2 inches to 5-1/2 inches center. Net opening between the bars shall be not less than 3 inches nor more than 4 inches. The roller shall be so constructed that counterweights can be used to adjust the gross weight of the roller to not less than 27,000 pounds. The grid roller shall be drawn by a power unit capable of propelling the fully loaded

---

**TIMBER SALE ROAD SPECIFICATIONS**

---

roller through 6 inches of loose embankment material at a speed of at least 4 miles per hour.

- 103f - Vibratory roller. The drum diameter shall be not less than 48 inches, the drum width not less than 58 inches, and have a turning radius of 15 feet or less. Vibration frequency shall be regulated in steps to 1400, 1500, and 1600 vibrations per minute (VPM), corresponding to engine speeds of 1575, 1690, and 1800 RPM. The centrifugal force developed shall be 7 tons at 1600 RPM. It shall be activated by a power unit of not less than 25 horsepower. The vibratory roller shall be self-propelled or drawn by a vehicle of sufficient horsepower to enable the unit to travel through a loose layer of material at a speed ranging from 0.9 mile to 1.8 miles per hour, as directed by the Authorized Officer.

The towing vehicle and roller or self-propelled unit meeting the above requirements shall be considered a vibratory roller unit.

- 103g - Vibratory compactor. Vibratory compactors shall consist of multiple or gang-type compacting units or pads with a minimum variable width of 2 feet. It shall be self-contained and capable of compacting material as required.

- 103h - Drum drive self-propelled vibratory grid roller. The unit shall consist of one cylindrical drum with a drum diameter of not less than 56 inches, nor more than 66 inches and the drum width shall be 84 inches. Vibration frequency shall be regulated in steps from 1200 to 1800 vibrations per minute (VPM), and the centrifugal force developed shall be at least 40,000 pounds at 1800 RPM. The vibratory grid roller shall be self-propelled and have a power unit of not less than 112 horsepower. The "grid" design shall be a herringbone or z-bar pattern around the circumference of the drum. The grid bars shall be 1 inch in height and spaced not more than 8-1/2 inches apart.

- 103i - Other. Compaction equipment approved by the Authorized Officer.

**CLEARING AND GRUBBING - 200**

- 201 - This work shall consist of clearing, grubbing, removing, and disposing of vegetation, debris, surface objects, and protruding obstructions within the clearing limits in accordance with these specifications and conforming to the lines, grades, dimensions, and typical cross sections shown on the plans.

- 201a - This work shall consist of clearing, grubbing, removing, and disposing of vegetation, debris, surface objects, and protruding obstructions from borrow pits, quarries, channel changes, stockpile sites, etc., in accordance with these specifications.

---

**TIMBER SALE ROAD SPECIFICATIONS**

---

- 202 - Where clearing limits have not been staked, established by these specifications, or shown on the plans, the limits shall extend 10 feet back of the top of the cut slope and 5 feet out from the toe of the fill slope.
- 202a - Where clearing limits for structures have not been staked or shown on the plans, the limits shall extend 10 feet out from the outside edge of the structure.
- 202b - Where clearing limits for borrow pits, or quarries, stockpile sites, channel changes, and ditches have not been staked or shown on the plans, the limits shall extend 10 feet back of the top of the cut slope and 5 feet outside of the outside slope lines.
- 203 - Clearing shall consist of the removal and disposal of trees, logs, rotten material, brush, and other vegetative materials and surface objects in accordance with these specifications and within the limits established for clearing as specified under Subsections 202, 202a, 202b, and as shown on the plans.
- 203a - Brush under 2 feet in height need not be cut within the limits established for clearing.
- 203c - Disposal of logs from private timber cleared within the limits established as staked on the ground shall consist of decking at a location designated by the Authorized Officer.
- 204 - Grubbing shall consist of the removal and disposal of stumps, roots, and other wood material embedded in the ground and protruding obstacles remaining as a result of the clearing operation in accordance with Subsections 204a, 204b, 204c, and 204d.
- 204a - Stumps, including those overhanging cut banks, shall be removed within the required excavation limits.
- 204b - Stumps and other protruding objects shall be completely removed within the limits of required embankments having heights of less than 4 feet. When authorized, stumps and other nonperishable objects may be left provided they do not extend more than 6 inches above the existing ground line.
- 204c - On excavated areas, roots and embedded wood shall be removed to a depth not less than 6 inches below the subgrade.
- 204d - On areas to be occupied by embankments having heights greater than 4 feet, no stump or portion thereof shall remain within 3 feet of embankment subgrades or slope surfaces after grubbing is completed.

---

**TIMBER SALE ROAD SPECIFICATIONS**

---

- 205 - Clearing and grubbing debris shall not be placed or permitted to remain in or under road embankment sections.
- 210 - Disposal of clearing and grubbing debris shall be by piling or scattering over government owned lands outside of established clearing limits in a manner acceptable to the Authorized Officer. The areas for such scattering or piling shall have the prior approval of the Authorized Officer. Piled slash may be re-used as mulch during road decommissioning.
- 210a - Disposal of clearing and grubbing on non-government property by scattering this material outside of clearing limits will be permitted provided the Purchaser obtains a written permit from the property owner on whose property the disposal is to be made. The Purchaser shall furnish the Authorized Officer a certified copy of the permit and a written release from the property owner absolving the Government from responsibilities in connection with the disposal of debris on said property.
- 212 - No grading will be permitted prior to completion and approval by the Authorized Officer of the required clearing and grubbing work, except that stump grubbing may proceed with the excavation of the road prism.
- 213 - No clearing or grubbing debris shall be left lodged against standing trees.

**EXCAVATION AND EMBANKMENT - 300**

- 301 - This work shall consist of excavating, overhaul, placement of embankments, backfilling, borrowing, leveling, ditching, grading, insloping, outsloping, crowning and scarification of the subgrade, compaction, disposal of excess and unsuitable materials, and other earth-moving work in accordance with these specifications and conforming to the lines, grades, dimensions, and typical cross sections shown on the plans.
- 302 - Excavation shall also consist of the excavation of road and landing cut sections, borrow sites, backfilling, leveling, ditching, grading, compaction, and other earth moving work necessary for the construction of the roadway in accordance with these specifications and conforming to the lines, grades, dimensions, and typical cross sections shown on the plans and as marked on the ground with stakes or metal tags.

---

**TIMBER SALE ROAD SPECIFICATIONS**

---

- 303 - Suitable material removed from the excavation shall be used in the formation of embankment subgrade, shoulders, slopes, bedding, backfill for structures, and for other purposes as shown on the plans.
- 305 - Embankment construction shall consist of the placement of excavated and borrowed materials, backfilling, leveling, grading, compaction, and other earth-moving work necessary for the construction of the roadway and landings in accordance with these specifications and conforming to the lines, grades, dimensions, and typical cross sections shown on the plans.
- 305a - Material used in the construction of embankment sections shall be free of stumps, cull logs, brush, muck, sod, roots, frozen material, and other deleterious materials and shall be placed and compacted as specified.
- 305b - Embankment materials shall be placed in successive parallel layers on areas cleared of stumps, cull logs, brush, sod, and other vegetative and deleterious materials, except as provided under Subsection 204. Roadway embankments of earth material shall be placed in horizontal layers not exceeding 12 inches in depth.
- 305c - Embankments formed of material containing less than 25 percent rock not larger than 8 inches in the greatest dimension shall be placed in 12-inch layers. Material containing more than 25 percent rock not larger than 12 inches in the greatest dimension shall be placed in successive layers not exceeding 2 feet in thickness. Individual rocks and boulders greater than 12 inches in diameter may be used to construct 2 foot embankment layers, provided they are carefully distributed, with interstices filled with fine material to form a dense and compact mass.
- 305d - Where embankments are constructed predominantly of blasted rock material, depth of layers shall not exceed 4 feet. Rock fragments having dimensions greater than 4 feet will be permitted provided that they have no dimensions greater than 6 feet and that clearance between adjacent fragments is adequate for the placing and compacting of material in horizontal layers as specified, and that no part of the larger fragments comes within 4 feet of subgrade.
- 306 - Layers of embankment, selected borrow, final subgrade, and selected roadway excavation material as specified under Subsections 305a, and 305b shall be moistened or dried to a uniform optimum moisture content suitable for maximum

---

**TIMBER SALE ROAD SPECIFICATIONS**

---

density and compacted to full width with compacting equipment conforming to requirements of Subsections 103f and 103i.

- 306a - Optimum moisture content shall be determined by hand clump test i.e., where a soil sample forms a firm ball by hand that does not crumble, free moisture is not visible on the surface, and material does not squeeze between fingers.
- 306b - Minimum compaction for each layer of embankment, selected borrow, and selected roadway excavation material placed at optimum moisture shall be a minimum of 8 complete passes or until visual displacement ceases.
- 308 - In the case of rock fills, placement of material in layers is not required and such material may be placed by end-dumping or other methods approved by the Authorized Officer provided that the rock be reasonably prevented from escaping beyond the embankment toe.
- 312 - When material, except solid rock, encountered in cuts at subgrade, is suitable for use in forming the finished roadbed, the top 6-inch layer of the subgrade shall be thoroughly scarified for the full width of the roadbed. Roots, sod, and other deleterious material or stones that will not pass a 6-inch square opening shall be removed. The scarified material shall be processed to the optimum moisture content suitable for maximum density and compacted in accordance with Subsection 306.
- 313 - In cut areas where solid rock is encountered at, or near subgrade, the rock shall be excavated to a minimum depth of 6 inches below subgrade elevation and the excavated area backfilled with suitable material. The backfill material shall be processed to the optimum moisture content suitable for maximum density and compacted to full width in accordance with the requirements of Subsection 306.
- 320 - Ditches shall conform to the slope, grade, dimensions, and shape of the required cross section shown on the plans. Roots, stumps, rocks, and other projections shall be removed to form smooth, even slopes.
- 321 - Excess excavated, unsuitable, or slide materials shall not be disposed of on areas where the material will encroach on a stream course or other body of water. Such materials shall be disposed of in accordance with Subsection and 321c. Materials not disposed of in this manner shall be retrieved and disposed of at the Purchaser's expense and at the direction of the Authorized Officer.

---

**TIMBER SALE ROAD SPECIFICATIONS**

---

- 321b - Excess construction material as specified under Subsection 321 shall be loaded, hauled, and disposed of at a designated disposal site or used as embankment for designated roadbeds as shown on the plans.
- 321c - End-dumping will be permitted for the placement of excess materials under Subsection 321 in designated disposal areas or within areas approved by the Authorized Officer. Watering, rolling, and placement in layers are not required. Materials placed shall be sloped, shaped, and otherwise brought to a visible condition acceptable to the Authorized Officer.
- 324 - Excavated material shall not be allowed to cover boles of standing trees to a depth in excess of 2 feet on the uphill side.
- 327 - The finished grading shall be approved by the Authorized Officer in segments. The Purchaser shall give the Authorized Officer 3 days' notice prior to start of surfacing operations.

**PIPE CULVERTS - 400**

- 401 - This work shall consist of furnishing and installing pipe culverts and other erosion control devices in accordance with these specifications and conforming to the lines, grades, dimensions, and typical cross sections shown on the plans. Individual lengths and locations are approximate; final lengths and locations will be determined by the Authorized Officer upon completion of the roadbed and upon installation of the appurtenance structures. Additional pipe and erosion control devices may be required at the option of the Authorized Officer, in which case a reduction in the total purchase price shall be made to offset the cost of furnishing and installing such items. Costs will be based upon the unit prices set forth in the current BLM Timber Appraisal Production Cost Schedule.
- 403 - Grade culverts shall have a gradient of 2 percent to 4 percent greater than the adjacent road grade. Grade culverts shall be skewed down grade 30 degrees as measured from the perpendicular to the centerline unless otherwise specified on the plans.
- 405b - Corrugated-aluminum-alloy pipe culverts and pipe-arch culverts shall conform to the requirements of AASHTO M 196.

---

**TIMBER SALE ROAD SPECIFICATIONS**

---

- 405e - Corrugated-polyethylene pipe for culverts 12-inch through 36-inch diameter shall meet the requirements of AASHTO M 294.
- 406 - Coupling bands shall conform to the requirements of AASHTO M 36 and AASHTO M 218 or AASHTO M 274 with the exception of band widths and the "Hugger"-type band which shall conform to the details, dimensions, and typical diagram shown on the plans.
- 406a - "Hugger"-type coupling bands shall only be used with annular corrugated pipe and pipe-arch culverts, or helically corrugated pipe and pipe-arch culverts having annular reformed ends. Annular reformed ends shall consist of two annular corrugations.
- 407 - Special sections, such as elbows, branch connections, and flared-end sections, shall be of the same gauge as the pipe to which they are joined, and shall conform to the requirements of AASHTO M 36 and AASHTO M 218 or AASHTO M 274.
- 408 - Pipe culverts and pipe-arch culverts shall be placed on the bed starting at the downstream end with the inside circumferential laps pointing downstream and with the longitudinal laps at the side or quarter points. Coupling bands of the type required under these specifications shall be installed so as to provide the circumferential and longitudinal strength necessary to preserve the pipe alignment, prevent separation of the pipe sections, and minimize infiltration of fill material.
- 410 - Pipe shall be unloaded and handled with reasonable care. If the Authorized Officer determines any structure is damaged to the extent that it is unsuitable for use in the road construction, it shall be replaced at the Purchaser's expense.
- 411 - Trenches necessary for the installation of pipe culverts shall conform to the lines, grades, dimensions, and typical diagram shown on the Culvert Installation Detail Sheet.
- 412 - Where ledge rock or boulders are encountered, they shall be excavated a minimum of 10 inches below the invert grade for a width of at least 2 feet on each side of the pipe and shall be backfilled with compacted select fill material.

**TIMBER SALE ROAD SPECIFICATIONS**

---

- 412a - Where soft or spongy soils are encountered, they shall be excavated a minimum of 2 feet below the invert grade for a width of at least one pipe diameter on each side of the pipe and shall be backfilled with compacted select fill material.
  
- 413 - Pipe culverts shall be bedded on select fill material, having a depth of not less than 6 inches as shown on plans. Foundation material shall be of uniform density throughout the length of the structure and shall be shaped to fit the pipe.
  
- 416 - Select fill material for pipe culverts shall be fine readily compactable soil, or crushed rock material in accordance with Section 1204 gradation C, as shown on the plans.
  
- 417 - For pipe culverts:  
Side-fill material conforming to the requirements of Subsection 416 shall be placed and compacted under the haunches of the pipe, and shall be brought up evenly and simultaneously on both sides of the pipe to 1 foot above the pipe, in layers not exceeding 6 inches in depth and 1 pipe diameter/span, or a minimum of 2 feet in width each side of, and adjacent to, the full length of the pipe barrel. Each layer shall be moistened or dried to a uniform moisture content suitable for maximum compaction and immediately compacted by approved hand or pneumatic tampers as specified in Subsection 306.
  
- 418 - Side fills beyond the compaction limits specified under Subsection 417 shall be compacted as specified under Section 300.
  
- 419 - The pipe culvert after being bedded and backfilled as required by these specifications shall be protected by a 1-foot cover of fill before heavy equipment is permitted to cross the drainage structures. Removal of the protection fill shall be as directed by the Authorized Officer.
  
- 423 - Construction of catch basins conforming to lines, grades, dimensions, and typical diagrams shown on the plans, shall be required for culverts.
  
- 424 - Construction of splash pads conforming to lines, grades, dimensions, and typical diagram shown on the plans, shall be required for grade culverts.
  
- 427 - Record culvert sizes, lengths and location actually installed on a copy of the culvert list. This culvert list shall be furnished to the Authorized Officer.

---

**TIMBER SALE ROAD SPECIFICATIONS**

---

- 428 - Remove and dispose of old culverts in a legal manner, and for any fees required. The Purchaser shall remove the old culverts from the work site prior to road acceptance.
- 429 - Keep the excavation site dewatered so that the installation of culverts is completed under dry conditions. Dispose of excess water in a manner that will avoid damage to adjacent property. Diversion streams shall not be returned to the natural channel until all in-stream work has been completed.

**RENOVATION AND IMPROVEMENT OF EXISTING ROADS - 500**

**AGGREGATE BASE COURSE - 1000**

**CRUSHED ROCK MATERIAL**

- 1001 - This work shall consist of furnishing, hauling, and placing one or more lifts of crushed rock material on roadbeds and landings approved for placing crushed rock material, in accordance with these specifications and conforming to the dimensions and typical cross sections shown on the plans. Material not conforming to these specifications will be rejected and shall be removed from the road at the purchaser's expense.
- 1002a - Crushed rock materials may be obtained from commercial sources selected by the Purchaser at his option and expense providing that the rock materials selected comply with the specifications in this section.
- 1002b - In accordance with Subsections 1005, 1006, and 1006a, the following test reports for crushed rock material shall be submitted to, and approved by, the Authorized Officer, prior to delivery and placement of aggregate: AASHTO T96, AASHTO T210, and DMSO. Tests must have been conducted within the last 365 days and be for the same quarry shot that the crushed rock is coming from. New tests must be performed if there is a new shot, or other change in the material being supplied to the crusher.
- 1002c - In accordance with Subsection 1004, the following test reports for crushed rock material shall be submitted to and approved by the Authorized Officer, prior to delivery and placement of aggregate: AASHTO T11 and AASHTO T27.
- 1003 - Crushed rock material produced from gravel shall have 2 manufactured fractured faces on 65 percent, by weight, of the material retained on the No. 4 sieve.

**TIMBER SALE ROAD SPECIFICATIONS**

---

1004 - Crushed rock materials shall consist of hard durable rock fragments conforming to the following gradation requirements (as determined by AASHTO T11 & T27):

TABLE 1004

AGGREGATE BASE COURSE  
CRUSHED ROCK MATERIAL

Percentage by Weight Passing Square Mesh Sieves  
 (AASHTO T 11 & T 27)

GRADATION

Sieve Designation	A	B	C	D	F	G	H	I
6 -inch	-	-	-	-	-	-	-	100
3-inch	100	-	100	-	100	-	-	45-65
2-inch	90-95	100	-	-	65-95	100	100	-
1 1/2-inch	-	90-95	-	-	-	-	-	-
1-inch	45-75	50-90	-	100	-	50-85	60-90	-
3/4-inch	-	-	-	-	28-70	-	-	-
1/2-inch	-	-	-	0-20	-	27-60	44-70	-
3/8-inch	-	-	-	-	-	-	-	-
No. 4	15-45	15-50	-	0-5	10-35	15-40	28-50	0-10
No. 8	-	-	-	-	-	-	20-41	-
No. 10	-	-	-	-	-	-	-	-
No. 30	-	-	-	-	5-22	8-26	9-26	-
No. 40	5-25	5-25	-	-	-	-	-	-
No. 200	2-15	2-15	-	-	3-10	3-12	3-12	-

1004j - Gabion rock shall be sound, durable and from a source approved by the Authorized Officer. Rock shall not be less than 4 inches minimum dimension, nor greater than 8 inches maximum dimension. The rock shall be reasonably well graded between the limiting sizes.

1005 - Crushed rock material retained on the No. 4 sieve shall have a percentage of loss of not more than 35 at 500 revolutions, as determined by AASHTO T 96.

---

**TIMBER SALE ROAD SPECIFICATIONS**

---

- 1006 - Crushed rock material shall show durability value of not less than 35, as determined by AASHTO T 210.
  
- 1006a - The crushed rock material shall show a loss of not more than 20 percent by weight, when submerged in DMSO, dimethyl sulfoxide, for five days, according to Federal Highway Administration Region 10 Accelerated Weathering Test Procedure.
  
- 1008a - Each layer of crushed rock material shall be thoroughly mixed on the roadbed by alternately blading, to full depth, until a uniform mixture has been obtained. The mixture shall then be spread to full width. When completed, the spreading shall produce a surface which is smooth, presents uniform shoulder lines, and conforms to the specified cross section.
  
- 1009 - The roadbed, as shaped and compacted under Sections 300 and 500 of these specifications, shall be approved by the Authorized Officer prior to placement of crushed rock materials. Notification for final inspection prior to rocking shall be 72 hours prior to that inspection.
  
- 1010 - Crushed rock materials shall be placed and processed on the approved roadbed in accordance with these specifications and conforming to the lines, grades, dimensions, and typical cross sections shown on the plans and compacted in layers not to exceed 3 inches in depth. When more than one layer is required, each shall be shaped, processed, compacted, and approved in writing by the Authorized officer before the succeeding layer is placed. Irregularities or depressions that develop during compaction of the top layer shall be corrected by loosening the material at these places and adding or removing crushed rock material until the surface is smooth and uniform.
  
- 1010a - Crushed rock material used to repair or reinforce a soft, muddy, frozen, yielding, or rutted roadbed shall not be construed as surfacing under this specification unless approved as such by the Authorized Officer prior to placement.
  
- 1012 - Each layer of crushed rock material shall be placed, processed, shaped, moistened or dried to a uniform moisture content suitable for maximum compaction, and compacted to full width by compaction equipment conforming to the requirements of Subsection 103f and 103i. Minimum compaction shall be a minimum of 8 passes over each full-width layer, or until visual displacement ceases.

---

**TIMBER SALE ROAD SPECIFICATIONS**

---

**AGGREGATE SURFACE COURSE - 1200**  
**CRUSHED ROCK MATERIAL**

- 1201 - This work shall consist of furnishing, hauling, and placing one or more layers of crushed rock material on roadbeds and base courses approved for placing crushed rock material in accordance with these specifications and conforming to the dimensions and typical cross sections shown on the plans. Material not conforming to these specifications will be rejected and shall be removed from the road at the purchaser's expense.
- 1202a - Crushed rock materials used in this work may be obtained from commercial sources selected by the Purchaser at his option and expense, providing the rock materials furnished comply with these specifications.
- 1202b - In accordance with Subsections 1205, 1206, and 1206a, the following test reports for crushed rock material shall be submitted to and approved by the Authorized Officer, prior to delivery and placement of aggregate: AASHTO T96, AASHTO T210, and DMSO. Tests must have been conducted within the last 365 days and be for the same quarry shot that the crushed rock is coming from. New tests must be performed if there is a new shot, or other change in the material being supplied to the crusher.
- 1202c - In accordance with Subsection 1204, the following test reports for crushed rock material shall be submitted to and approved by the Authorized Officer, prior to delivery and placement of aggregate: AASHTO T11 and AASHTO T27.
- 1203 - When crushed rock material is produced from gravel, not less than 65 percent by weight of the particles retained on the No. 4 sieve will have 2 manufactured fractured faces.
- 1204 - Crushed rock material shall consist of hard durable rock fragments conforming to the following gradation requirements (as determined by AASHTO T11 & T27):

**TIMBER SALE ROAD SPECIFICATIONS**

---

TABLE 1204

AGGREGATE SURFACE COURSE  
CRUSHED ROCK MATERIAL

Percentage by weight passing square mesh sieves  
 AASHTO T 11 & T 27

GRADATION

Sieve Designation	C	C-1	D	D-1	E	E-1
1-1/2-inch	100	100	-	-	-	-
1-inch	-	-	100	100	-	-
3/4-inch	50-90	60-90	-	70-98	100	100
1/2-inch	-	-	-	-	-	70-98
No. 4	25-50	30-55	30-60	36-60	40-75	44-70
No. 8	-	22-43	-	25-47	-	30-54
No. 30	-	11-27	-	12-31	-	15-34
No. 40	5-25	-	5-30	-	5-35	-
No. 200	2-15	3-15	3-15	3-15	2-15	3-15

- 1205 - Crushed rock material retained on the No. 4 sieve shall have a percentage of loss of not more than 35 at 500 revolutions, as determined by AASHTO T 96.
- 1206 - Crushed rock material shall show a durability value of not less than 35 as determined by AASHTO T210.
- 1206a - The crushed rock material shall show a loss of not more than 20 percent by weight, when submerged in DMSO, dimethyl sulfoxide, for five days, according to Federal Highway Administration Region 10 Accelerated Weathering Test Procedure.
- 1208a - Each layer of crushed rock material shall be thoroughly mixed on the roadbed by alternately blading, to full depth, until a uniform mixture has been obtained. The mixture shall then be spread to full width. When completed, the spreading shall produce a surface which is smooth, presents uniform shoulder lines, and conforms to the specified cross section.

---

**TIMBER SALE ROAD SPECIFICATIONS**

---

- 1209 - Shaping and compacting of roadbed base course shall be completed and approved by the Authorized Officer, prior to placing crushed rock material, in accordance with the requirements of Subsections 300 and 500. Notification for final inspection prior to rocking shall be 72 hours prior to the inspection.
  
- 1210 - Crushed rock material conforming to the requirements of these specifications shall be placed on the approved roadbed and base course in accordance with these specifications and conforming to the lines, grades, dimensions, and typical cross sections shown on the plans. Compacted layers shall not exceed 3 inches in depth. When more than one layer is required, each shall be shaped, processed, compacted, and approved by the Authorized Officer before the succeeding layer is placed. Irregularities or depressions that develop during compaction of the top layer shall be corrected by loosening the material at these places and then adding or removing crushed rock material until the surface is smooth and uniform.
  
- 1210a - Crushed rock material used to repair or reinforce soft, muddy, frozen, yielding, or rutted roadbed shall not be construed as surfacing required by this specification unless approved by the Authorized Officer.
  
- 1212 - Each layer of crushed rock material placed, processed, and shaped as specified shall be moistened or dried to a uniform moisture content suitable for maximum compaction and compacted to full width by compacting equipment conforming to the requirements of Subsections 103f 103i. Minimum compaction shall be 8 passes over each full-width layer, or until visual displacement ceases.

**EROSION CONTROL - 1700**

- 1701 - This work shall consist of measures to control soil erosion or water pollution during the construction operation through the use of berms, dikes, dams, sediment basins, fiber mats, netting, gravel, mulches, grasses, slope drains, geofabric rolls, and other erosion control devices or methods in accordance with these specifications and conforming to the lines, grades, dimensions and typical cross sections shown on the plans.
  
- 1703 - This work shall consist of furnishing and installing silt fences, straw bales, geofabric rolls, or similar erosion control devices in accordance with these

---

**TIMBER SALE ROAD SPECIFICATIONS**

---

specifications and in reasonably close conformity with the lines and grades as directed by the Authorized Officer.

- 1703a - Additional erosion control work consisting of furnishing and installing silt fences, straw bales, geofabric rolls, or similar erosion control devices, may be required at the option of the Authorized Officer. Providing that the additional erosion control is not due to Purchaser negligence as specified in Sec. 12 of the contract, a reduction in the total purchased price shall be made to offset the cost of furnishing and installing such additional erosion control devices. Costs shall be based upon the unit price set forth in the current BLM Timber Appraisal Production Cost Schedule.
- 1704 - The erosion control provisions specified under this Subsection shall be coordinated with the Soil Stabilization requirements of Section 1800.
- 1708a - Road segments not completed during dry weather periods shall be winterized, by providing a well-drained roadway using water bars, maintaining drainage, and performing additional measures necessary to minimize erosion and other damage to the roadway, as directed by the Authorized Officer. Portions of roads not having surface rock in place will be blocked or barricaded to prevent vehicular traffic.

**SOIL STABILIZATION – 1800**

- 1801 - This work shall consist of seeding and mulching on designated cut, fill, borrow, disposal, and special areas in accordance with these specifications and as shown on the plans. This work is required for road acceptance under Section 18 of this contract.
- 1802a - Soil stabilization work consisting of seeding and mulching shall be performed on new road construction, road renovation, improvements, landings, and disturbed areas in accordance with these specifications and as shown on the plans.
- 1803 - Soil stabilization work as specified under Subsection 1802a shall be performed during the following seasonal periods:

From: September 1 <sup>st</sup>	To: October 15 <sup>th</sup>
---------------------------------	------------------------------

---

**TIMBER SALE ROAD SPECIFICATIONS**

---

If soil stabilization of disturbed areas is not completed by the specified fall date, the Purchaser shall treat disturbed areas in accordance with Section 1700. The Authorized Officer may modify the above seasonal dates to conform to existing weather conditions and changes in the construction schedule.

- 1803a - The Purchaser shall begin soil stabilization work within 10 days of the starting work date when notified by the Authorized Officer.
- 1804 - The BLM shall provide native grass/forb seed for this project.
- 1806a - Additional soil stabilization work consisting of seeding, and mulching, may be required at the option of the Authorized Officer. Providing the additional stabilization is not due to Purchaser negligence as specified in Sec. 12 of the contract, a reduction in the total purchased price shall be made to offset the cost of furnishing and applying such additional stabilization material. Cost shall be based upon the unit price set forth in the current BLM Timber Appraisal Production Cost Schedule.
- 1808 - Mulch materials conforming to the requirements of Subsection 1808a shall be furnished by the Purchaser in the amounts specified under Subsection 1811 and applied in accordance with Subsection 1812.
- 1808a - Straw mulch shall be certified weed free from commercial grain fields and native grass fields. Straw mulch shall be from oats, wheat, rye, or other approved grain crops and shall be free from, mold, or other objectionable material. Straw mulch shall be in an air-dry condition and suitable for placement.
- 1809 - Mulch material shall be delivered to the work area in a dry state. Material found to be wet will not be accepted. Material to be used in the mulching operation may be stockpiled along the road designated for treatment provided that it is maintained in a dry state and has the approval of the Authorized Officer.
- 1810 - Bulk mulching material required under these specifications shall be delivered to the work area bound either by twine, string, or hemp rope. Wire binding will not be permitted.
- 1811 - The Purchaser shall furnish and apply to approximately 0.5 acres designated for treatment as shown on the plans and as specified under Subsections 1802a and

---

**TIMBER SALE ROAD SPECIFICATIONS**

---

1806a, a mixture of grass seed and mulch material at the following rate of application:

Grass Seed	25 lbs./acre
Mulch	2000 lbs./acre

The above proportion and application rate are subject to adjustment by the Authorized Officer during the application operation.

- 1812 - The Purchaser shall furnish and apply to the area designated for treatment as shown on the plans and as specified under Subsections 1802a and 1806a, a mixture of grass seed and mulch material, at the application rate to be determined by the Authorized Officer based on visual observation of trial applications.

Mulches shall be spread/placed in treatment areas to a depth of 2 inches to allow seed germination or as directed by the Authorized Officer. Treatment area will be covered evenly and completely. Mulch can be broadcast onto the soil surface by hand or with hand/mechanical operated spreaders.

- 1814 - The Purchaser may reduce the application rate on partially covered slopes and refrain from application on areas already well stocked with grass or on rock surfaces as determined by the Authorized Officer.

- 1815 - The seed and mulch materials shall be placed by the dry method in accordance with the requirements set forth in Subsection 1815b.

- 1815b - Dry Method - Blowers, mechanical seeders, seed drills, landscape seeders, cultipaker seeders, fertilizer spreaders, or other approved mechanical seeding equipment may be used when seed and fertilizer are to be applied in dry form.

- 1819 - The Purchaser shall notify the Authorized Officer at least 3 days in advance of date he intends to commence the specified soil stabilization work.

- 1820 - When sprayed, the mix must overlap on the ground uniformly so that there will be no voids in the treated areas.

---

**TIMBER SALE ROAD SPECIFICATIONS**

---

- 1821 - Mulch that collects at the end of culverts or accumulates to excessive depths on the slopes shall be evenly spread by hand methods, as directed by the Authorized Officer.
- 1822 - No materials shall be applied when wind velocities would prevent a uniform application of the mix or when winds would drift the mix outside of the designated treatment area.
- 1824 - Twine, rope, sacks, and other debris resulting from the soil-stabilization operation shall be picked up and disposed of to the satisfaction of the Authorized Officer.

**ROADSIDE BRUSHING - 2100**

- 2101 - This work shall consist of the removal of vegetation from the road prism - variable distance, and inside curves in accordance with these specifications and conforming to the lines, grades, dimensions, and typical cross sections shown on the Roadside Brushing Detail Sheet of this exhibit, at designated locations as shown in the plans.
- 2102 - Roadside brushing maybe performed mechanically with self-powered, self-propelled equipment and/or manually with hand tools, including chain saws.
- 2103 - Vegetation cut manually and/or mechanically less than 6 inches in diameter when measured 6 inches above the ground shall be cut to a maximum height of 2 inches above the ground surface or above obstructions such as rocks or stumps on cut and fill slopes and all limbs below the 2 inch area will be severed from the trunk.
- 2103a - Vegetation shall be cut and removed from the roadbed between the outside shoulders and the ditch centerline and such vegetation shall be cut to a maximum height of 2 inches above the ground and running surface. Limbs below the 2 inch area will be severed from the trunk. Sharp pointed ends will not be permitted. Cuts shall be parallel to the ground line or running surface.
- 2104 - Trees in excess of 6 inches in diameter when measured 6 inches above the ground line shall be limbed, so that no limbs extend into the treated area or over the roadbed to a height of 14 feet above the running surface of the roadway on cut and fill slopes, within the road prism-variable distance. Limbs shall be cut to

---

**TIMBER SALE ROAD SPECIFICATIONS**

---

within 1 inch of the trunk to produce a smooth vertical face. Removal of trees larger than 6 inches in diameter for sight distance or safety may be directed by the Authorized Officer.

- 2105 - Vegetation that is outside of the road prism-variable distance that protrudes into the road prism and within 14 feet in elevation above the running surface shall be cut, to within 1 inch of the trunk to produce a smooth vertical face.
- 2106 - Vegetative growth capable of growing 1 foot in height or higher shall be cut, within the road prism-variable distance or as directed by the Authorized Officer.
- 2107 - Inside curves shall be brushed out for a sight distance of 200 feet chord distance or a distance of 15 feet from edge of subgrade, whichever is achieved first. Overhanging limbs and vegetation in excess of 1 foot in height, shall be cut within these areas.
- 2108 - Self-propelled equipment shall not be permitted on cut and fill slopes or in ditches.
- 2109 - Debris resulting from this operation shall be scattered downslope from the roadway. Debris shall not be allowed to accumulate in concentrations. Debris in excess of 1 foot in length and 2 inches in diameter shall not be allowed to remain on cut slopes, ditches, roadways or water courses, or as directed by the Authorized Officer.
- 2115 - Mechanical brush cutters shall not be operated when there are people and occupied vehicles within 400 feet of the immediate operating area.
- 2116 - Traffic warning signs shall be required at each end of the work area. Signs shall meet the requirements of the Manual on Uniform Traffic Devices.

UNITED STATES DEPARTMENT OF THE INTERIOR  
BUREAU OF LAND MANAGEMENT  
ROSEBURG DISTRICT  
TIMBER SALE EXHIBIT C

CONTRACT NAME: RESTON PIECES  
CONTRACT NO: ORR05-TS-2026.0004

ROAD NUMBER	STA/MP TO STA/MP	CONST.	RENOV.	DECOM.	EXISTING SURFACE TYPE	PROPOSED BASE COURSE		PROPOSED SURFACE COURSE		ROAD DIMENSIONS			TYP. ROAD SECTION	SHEET NO.
						DEPTH	TYPE	DEPTH	TYPE	A	B	C		
28-8-15.1	0+00 - 32+21		X		ROCK						16'	14'	4	5
28-8-16.2	0+00 - 50+16		X		ROCK						16'	14'	4	5
28-8-20.1	0+00 - 60+72		X		ROCK			NOTE 2	1204C		16'	14'	4	5
28-8-20.2	0+00 - 9+65		X		ROCK			NOTE 2	1204C		16'	14'	4	5
28-8-20.3	0+00 - 12+30		X		ROCK			NOTE 2	1204C		16'	14'	4	5
28-8-21.0	0+00 - 45+41		X		ROCK			NOTE 2	1204C		16'	14'	4	5
28-8-23.1	0+00 - 13+20		X		ROCK						16'	14'	4	5
28-8-23.2	0+00 - 27+98		X		ROCK						16'	14'	4	5
28-8-23.3	0+00 - 29+04		X		ROCK						16'	14'	4	5
28-8-20.2 CONST	0+00 - 4+60	X		X	NATIVE						14'		5	10
28-8-20.3 CONST	0+00 - 8+45	X			NATIVE	9"	1004A			16'	14'		4	11
28-8-22.1	0+00 - 7+05	X			NATIVE	9"	1004A			16'	14'		4	12
28-8-23.6	0+00 - 40+35	X			NATIVE	9"	1004A			16'	14'		4	13,14,15,16
SPUR 1	0+00 - 3+05	X			NATIVE	9"	1004A			16'	14'		4	6
SPUR 2	0+00 - 8+30	X			NATIVE	9"	1004A			16'	14'		4	7
SPUR 3	0+00 - 7+65	X			NATIVE	9"	1004A			16'	14'		4	8
SPUR 4	0+00 - 3+80	X		X	NATIVE						14'		5	9

INDEX OF SHEETS	
SHEET	DESCRIPTION
1	ROAD SUMMARY
2	SUMMARY OF QUANTITIES
3	TYPICAL SECTIONS
4	VICINITY MAP
5	RENOVATION NOTES
6	CONSTRUCTION NOTES
7	CONSTRUCTION NOTES
8	CONSTRUCTION NOTES
9	CONSTRUCTION NOTES
10	CONSTRUCTION NOTES
11	CONSTRUCTION NOTES
12	CONSTRUCTION NOTES
13	CONSTRUCTION NOTES
14	CONSTRUCTION NOTES
15	CONSTRUCTION NOTES
16	CONSTRUCTION NOTES
17	CULVERT SUMMARY
18	CULVERT INSTALLATION
19	BRUSHING DETAILS

NOTES:

- SEE EXHIBIT D
- PLACE ROCK COURSES ONLY AT LOCATIONS SPECIFIED IN RENOVATION NOTES. SEE RENOVATION NOTES FOR DIMENSIONS OR QUANTITIES.



UNITED STATES DEPARTMENT OF THE INTERIOR BUREAU OF LAND MANAGEMENT OREGON STATE OFFICE ROSEBURG DISTRICT	
RESTON PIECES ROAD SUMMARY	
DESIGNED: J. HARDER	DATE: 1/16/2026
CONTRACT NO. ORR05-TS-2026.0004	SHEET 1 OF 19

UNITED STATES DEPARTMENT OF THE INTERIOR  
 BUREAU OF LAND MANAGEMENT  
 ROSEBURG DISTRICT  
 TIMBER SALE EXHIBIT C

CONTRACT NAME: RESTON PIECES  
 CONTRACT NO: ORR05-TS-2026.0004


ROAD NUMBER	LENGTH	CLEARING AND GRUBBING	ROADSIDE BRUSHING	CLEANING CULVERTS	SURFACING				BLADING	PULLING DITCHES	COMPACTION	CULVERT INSTALLATION (18") <sup>2</sup>	CULVERT INSTALLATION (24") <sup>2</sup>	EXCAVATION	EMBANKMENT
						1004A	1004H	1204C							
					RIPRAP	3" MINUS	3" OPEN	1½" MINUS							
	STA/MI	ACRES	ACRES	STA/MI	L.C.Y.	L.C.Y.	L.C.Y.	L.C.Y.	STA/MI	STA/MI	STA/MI	LINEAR FEET	LINEAR FEET	C.Y. (IN-PLACE)	C.Y. (IN-PLACE)
28-8-15.1	32+21		0.37	32+21					32+21	32+21	32+21				
28-8-16.2	50+16			50+16					50+16	50+16	50+16				
28-8-20.1	60+72			60+72				65**	60+72	60+72	60+72				
28-8-20.2	9+65			9+65				5**	9+65	9+65	9+65				
28-8-20.3	12+30			12+30				10**	12+30	12+30	12+30				
28-8-21.0	45+41		0.86	45+41				200**	45+41	45+41	45+41				
28-8-23.1	13+20			13+20					13+20	13+20	13+20				
28-8-23.2	27+98			27+98					27+98	27+98	27+98				
28-8-23.3	29+04			29+04					29+04	29+04	29+04				
28-8-20.2	4+60	0.11							4+60		4+60			88	85
28-8-20.3	8+45	0.19				560			8+45	8+45	8+45	80		1598	1594
28-8-22.1	7+05	0.16				490			7+05	7+05	7+05	40		378	376
28-8-23.6	40+35	0.93				2430			40+35	40+35	40+35	160	160	12346	10344
SPUR 1	3+05	0.07				320			3+05	3+05	3+05			360	360
SPUR 2	8+30	0.19				570			8+30	8+30	8+30	40		1681	1677
SPUR 3	7+65	0.18				660			7+65	7+65	7+65	40		877	876
SPUR 4	3+80	0.09							3+80		3+80			237	235

NOTES


1. ALL QUANTITIES ARE ESTIMATES AND NOT PAY ITEMS
  2. SEE CULVERT SUMMARY FOR DETAILS
- \*\* THIS SPOT ROCK MAY BE USED FOR PRE-HAUL RENOVATION OR POST HAUL MAINTENANCE ON ANY PART OF THE HAUL ROUTE, AS APPROVED BY THE AUTHORIZED OFFICER. UPON COMPLETION OF OPERATIONS, THE UNUSED PORTION OF THIS AGGREGATE SHALL BE STOCKPILED AT LOCATIONS DESIGNATED IN RENOVATION NOTES.




UNITED STATES DEPARTMENT OF THE INTERIOR BUREAU OF LAND MANAGEMENT OREGON STATE OFFICE      ROSEBURG DISTRICT	
RESTON PIECES	
SUMMARY OF QUANTITIES	
DESIGNED: J. HARDER	DATE: 1/16/2026
CONTRACT NO. ORR05-TS-2026.0004      SHEET 2 OF 19	




SECTION OUT SLOPE ROAD ①




SECTION INSLOPE ROAD ②




SECTION INSLOPE ROAD ③



SECTION ROAD ④




SECTION ROAD ⑤




TYPICAL TURNOUT DIMENSIONS

NOTES:

1. Backslope to match existing backslope unless otherwise specified.
2. Backslope for Non-Design Roads:  
Slopes under 50%, 3/4:1  
Slopes over 50%, 1/2:1  
Solid Rock 1/4:1
3. Out slope road segments with grades less than 6%, crown or inslope road segments with grades exceeding 6%.
4. Inslope road sections permitted only for temporary roads. Native surface restricted to summer haul.



SECTION FILL WIDENING



DEGREE OF CURVE	8-21	22-35	36-51	52-64	65-79	80-90
EXTRA WIDTH IN FEET	1	2	3	4	5	6


CURVE WIDENING TABLE FOR NON-DESIGN ROADS OR AS SHOWN ON PLANS. MAX 75' CURVE OR AS SHOWN ON PLANS.



UNITED STATES DEPARTMENT OF THE INTERIOR  
BUREAU OF LAND MANAGEMENT  
OREGON STATE OFFICE ROSEBURG DISTRICT

**RESTON PIECES  
TYPICAL SECTIONS**

DESIGNED: J. HARDER | DATE: 1/16/2026  
CONTRACT NO. ORR05-TS-2026.0004 | SHEET 3 OF 19



### Legend

- BLM
- Harvest Area
- Road Renovation
- Road Construction
- +

 Gate

United States Department of the Interior  
 Bureau of Land Management  
 Roseburg District  
 777 NW Garden Valley Blvd  
 Roseburg, Oregon 97471


Transverse Mercator  
 Zone 10 North NAD 1983

UNITED STATES DEPARTMENT OF THE INTERIOR  
 BUREAU OF LAND MANAGEMENT  
 ROSEBURG DISTRICT OFFICE

RESTON PIECES  
 Contract # TS-ORR05-2026.0004

### VICINITY MAP

No warranty is made by the Bureau of Land Management as to the accuracy, reliability, or completeness of these data for individual or aggregate use with other data. Original data were compiled from various sources and may be updated without notification.



# ROAD RENOVATION

**Notes:**


1. All roads shall be renovated in accordance with attached specifications and the work items listed below. Renovation may include roadside brushing, installing culverts and splash pads, blading, shaping, cleaning ditches, removing slide material, and cleaning existing drainage structures. Features to construct are so noted. Existing features are noted at approximate station in the notes below. The Purchaser shall dispose of all culvert pipe removed as a part of the work described in this contract at a legal site off of BLM land.
2. All renovation and construction shall be done and approved prior to any hauling activity.
3. Existing turnouts, on roads to be renovated, shall be surfaced to the same standard as the adjacent roadway.
4. Back slopes shall be cut to match existing unless otherwise specified.
5. All work shall be performed according to OSHA safety requirements.

<u>MILE POST</u>	<u>DESCRIPTION</u>	<u>MILE POST</u>	<u>DESCRIPTION</u>
	<b>28-8-15.1</b>		<b>28-8-23.1</b>
000	BEGIN RENOVATION AT JUNCTION WITH COUNTY ROAD 112 BEGIN BLADING, COMPACTING, PULLING DITCHES, AND CLEANING CULVERTS	0+00	BEGIN RENOVATION AT JUNCTION WITH RESTON ROAD BEGIN BLADING, COMPACTING, PULLING DITCHES, AND CLEANING CULVERTS
32+21	END RENOVATION AT HARVEST UNIT BOUNDARY.	13+20	END RENOVATION AT JUNCTION WITH 28-8-23.2.
	<b>28-8-16.2</b>		<b>28-8-23.2</b>
0+00	BEGIN RENOVATION AT JUNCTION WITH COUNTY ROAD 112. BEGIN BLADING, COMPACTING, PULLING DITCHES, AND CLEANING CULVERTS	0+00	BEGIN RENOVATION AT JUNCTION WITH 28-8-23.1 BEGIN BLADING, COMPACTING, PULLING DITCHES, AND CLEANING CULVERTS
50+16	END RENOVATION AT JUNCTION WITH 28-8-21.0.	27+98	END RENOVATION AT HARVEST UNIT BOUNDARY.
	<b>28-8-20.1</b>		<b>28-8-23.3</b>
0+00	BEGIN RENOVATION AT JUNCTION WITH HWY 112 BEGIN BLADING, COMPACTING, PULLING DITCHES, AND CLEANING CULVERTS BEGIN SPOT ROCK (65CY**)	0+00	BEGIN RENOVATION AT JUNCTION WITH 28-8-23.2 BEGIN BLADING, COMPACTING, PULLING DITCHES, AND CLEANING CULVERTS
60+72	END RENOVATION AT JUNCTION WITH 28-8-20.3. END SPOT ROCK	29+04	END RENOVATION AT JUNCTION WITH 28-8-23.6 NEW CONSTRUCTION.
	<b>28-8-20.2</b>		
0+00	BEGIN RENOVATION AT JUNCTION WITH 28-8-20.1 BEGIN BLADING, COMPACTING, PULLING DITCHES, AND CLEANING CULVERTS BEGIN SPOT ROCK (5CY**)		
9+65	END RENOVATION AT JUNCTION WITH 28-8-20.2 NEW CONSTRUCTION. END SPOT ROCK		
	<b>28-8-20.3</b>		
0+00	BEGIN RENOVATION AT JUNCTION WITH 28-8-20.1 BEGIN BLADING, COMPACTING, PULLING DITCHES, AND CLEANING CULVERTS BEGIN SPOT ROCK (10CY**)		
12+30	END RENOVATION AT JUNCTION WITH 28-8-20.3 NEW CONSTRUCTION. END SPOT ROCK		
	<b>28-8-21.0</b>		
0+00	BEGIN RENOVATION AT JUNCTION WITH 28-8-16.2 BEGIN BLADING, COMPACTING, PULLING DITCHES, AND CLEANING CULVERTS **STOCKPILE REMAINING SPOT ROCK AT JUNCTION WITH 28-8-16.2		
45+41	END RENOVATION AT JUNCTION WITH 28-8-22.1.		



UNITED STATES DEPARTMENT OF THE INTERIOR BUREAU OF LAND MANAGEMENT OREGON STATE OFFICE      ROSEBURG DISTRICT	
<b>RESTON PIECES RENOVATION NOTES</b>	
DESIGNED: J. HARDER	DATE: 1/16/2026
CONTRACT NO. ORR05-TS-2026.0004	SHEET 5 OF 19


SPUR 1 CONSTRUCTION				
ST-	DIST-NCE FT	BE-RING	% GR-DE	NOTES
0+00	30	N20E	0	JUNCTION WITH SPUR 2 ST- 0+25
0+30	30	N6W	0	
0+60	35	N29W	4	CONSTRUCT TURNOUT RIGHT
0+95	35	N21W	7	
1+30	30	N46W	7	
1+60	35	N49W	6	SHIFT CENTERLINE RIGHT 5 FT
1+95	50	W	3	SHIFT CENTERLINE LEFT 2 FT
2+45	60	N79W	0	CONSTRUCT DITCH OUT RIGHT
3+05				CONSTRUCT 70' X 70' L-NDING




**LEGEND**

- CONSTRUCTION CENTER LINE
- EXISTING ROAD
- Y— CULVERT TO BE INSTALLED
- DITCHOUT TO BE CONSTRUCTED

- NOTES:
- RIGHT OF W-Y WIDTH WILL BE 30' EITHER SIDE OF CENTERLINE, -ND IS M-RKED WITH FL-SHER T-GS.
  - CONSTRUCTION WILL H- E - 16' SUBGR-DE, CROWNED, 2' DITCH, -ND SURF-CED WITH 9" OF CRUSHED -GGREG-TE.
  - COURSES -RE TRUE BE-RINGS.




UNITED STATES DEPARTMENT OF THE INTERIOR BUREAU OF LAND MANAGEMENT OREGON STATE OFFICE ROSEBURG DISTRICT	
<b>RESTON PIECES CONSTRUCTION PLANS</b>	
DESIGNED: J. H-RDER	D-TE: 1/16/2026
CONTR-CT NO. ORR05-TS-2026.0004	SHEET 6 OF 19



SPUR 2 CONSTRUCTION				
ST-	DIST-NCE FT	BEARING	% GR-DE	NOTES
0+00	25	N52E	4	JUNCTION WITH 28-8-21.0
0+25	80	N65E	6	INSTALL 18" X 40' CULVERT
1+05	95	N33E	9	SHIFT CENTERLINE LEFT 7FT
2+00	100	N32E	6	
3+00	65	N48E	4	SHIFT CENTERLINE RIGHT 2FT
3+65	100	N43E	6	SHIFT CENTERLINE LEFT 3FT
4+65	100	N37E	9	SHIFT CENTERLINE LEFT 7FT
5+65	20	N49E	10	SHIFT CENTERLINE RIGHT 3FT
5+85	50	N55E	11	SHIFT CENTERLINE RIGHT 3FT
6+35	50	N64E	8	CONSTRUCT TURNOUT LEFT SHIFT CENTERLINE RIGHT 2FT
6+85	80	N74E	7	SHIFT CENTERLINE RIGHT 4FT
7+65	30	N75E	3	CONSTRUCT DITCH OUT LEFT
7+95	35	N80E	0	
8+30				CONSTRUCT 70' X 70' LANDING

- NOTES:
- RIGHT OF W-Y WIDTH WILL BE 30' EITHER SIDE OF CENTERLINE, -ND IS M-RKED WITH FL-SHER T-GS.
  - CONSTRUCTION WILL H- E - 16' SUBGR-DE, CROWNED, 2' DITCH, -ND SURF-CED WITH 9" OF CRUSHED -GGREG-TE.
  - COURSES -RE TRUE BE-RINGS.




UNITED STATES DEPARTMENT OF THE INTERIOR  
 BUREAU OF LAND MANAGEMENT  
 OREGON STATE OFFICE ROSEBURG DISTRICT

**RESTON PIECES  
 CONSTRUCTION PLANS**

DESIGNED: J. H-RDER D-TE: 1/16/2026  
 CONTR-CT NO. ORR05-TS-2026.0004 SHEET 7 OF 19


28-8-21.0



**LEGEND**  
 ○— CONSTRUCTION CENTER LINE  
 — EXISTING ROAD  
 >— CULVERT TO BE INSTALLED  
 <— DITCHOUT TO BE CONSTRUCTED

SPUR 3 CONSTRUCTION				
ST-	DIST-NCE FT	BEARING	% GR-DE	NOTES
0+00	30	S18E	-1	JUNCTION WITH 28-8-21.0
0+30	50	S35E	-1	SHIFT CENTERLINE 2FT LEFT
0+80	50	S41E	-4	
1+30	50	S30E	-7	SHIFT CENTERLINE 3FT RIGHT
1+80	30	S43E	-6	
2+10	60	S61E	-4	SHIFT CENTERLINE 2FT LEFT
2+70	40	S32E	-3	INSTALL 18" X 40' CULVERT
3+10	50	S28E	1	
3+60	35	S62E	4	CONSTRUCT 50' X 50' LANDING
3+95	30	N68E	2	
4+25	45	N52E	-3	
4+70	60	N34E	-5	CONSTRUCT 50' X 50' LANDING
5+30	75	N25E	-5	
6+05	70	N38E	-1	CONSTRUCT DITCH OUT RIGHT
6+75	40	N53E	0	
7+15	50	N30E	0	SHIFT CENTERLINE 5FT LEFT
7+65				CONSTRUCT 70' X 70' LANDING

- NOTES:
1. RIGHT OF W-Y WIDTH WILL BE 30' EITHER SIDE OF CENTERLINE.
  2. CONSTRUCTION WILL H- E - 16' SUBGR-DE, CROWNED, 2' DITCH, -ND SURF-CED WITH 9" OF CRUSHED -GGREG-TE.
  3. COURSES -RE TRUE BE-RINGS.




UNITED STATES DEPARTMENT OF THE INTERIOR  
 BUREAU OF LAND MANAGEMENT  
 OREGON STATE OFFICE ROSEBURG DISTRICT


**RESTON PIECES  
 CONSTRUCTION PLANS**

DESIGNED: J. H-RDER | D-TE: 1/16/2026  
 CONTR-CT NO. ORR05-TS-2026.0004 | SHEET 8 OF 19

SPUR 4 CONSTRUCTION				
ST-	DIST-NCE FT	BEARING	% GR-DE	NOTES
0+00	50	S28E	-5	JUNCTION WITH ST- 1+10 28-8-20.2
0+50	45	S59E	-8	
0+95	50	S75E	-8	
1+45	30	S55E	-6	
1+75	15	S40E	-2	
1+90	40	S35E	1	
2+30	70	S23E	-2	
3+00	80	S38E	0	
3+80				CONSTRUCT 70' X 70' LANDING



- NOTES:
1. RIGHT OF W-Y WIDTH WILL BE 30' EITHER SIDE OF CENTERLINE, -ND IS M-RKED WITH FL-SHER T-GS.
  2. CONSTRUCTION WILL H- E - 14' SUBGR-DE, CROWNED WITH N-TIVE SURF-CING.
  3. RO-D TO BE W-TERB-RRED UPON COMPLETION OF H-UL PER EXHIBIT D.
  4. COURSES -RE TRUE BE-RINGS.




UNITED STATES DEPARTMENT OF THE INTERIOR  
BUREAU OF LAND MANAGEMENT  
OREGON STATE OFFICE ROSEBURG DISTRICT

**RESTON PIECES  
CONSTRUCTION PLANS**


DESIGNED: J. H-RDER D-TE: 1/16/2026  
CONTR-CT NO. ORR05-TS-2026.0004 SHEET 9 OF 19

28-8-20.2 CONSTRUCTION				
ST-	DIST-NCE FT	BE-RING	% GR-DE	NOTES
0+00	55	S16W	-6	JUNCTION WITH 28-8-20.2
0+55	55	S8W	-6	
1+10	65	S15W	-7	PROPERTY LINE
1+75	45	S13W	-8	
2+20	65	S28W	-7	
2+85	45	S18W	-5	
3+30	60	S45W	-4	
3+90	70	S35W	-3	
4+60				CONSTRUCT 70' X 70' L-NDING




**LEGEND**  
 -○- NEW CONSTRUCTION  
 — EXISTING ROAD  
 ◆ SURVEY MONUMENT

- NOTES:**
- RIGHT OF W-Y WIDTH WILL BE 30' EITHER SIDE OF CENTERLINE, -ND IS M-RKED WITH FL-SHER T-GS.
  - CONSTRUCTION WILL H- E - 14' SUBGR-DE, CROWNED WITH N-TIVE SURF-CING.
  - RO-D TO BE W-TERB-RRED UPON COMPLETION OF H-UL PER EXHIBIT D.
  - COURSES -RE TRUE BE-RINGS.



UNITED STATES DEPARTMENT OF THE INTERIOR BUREAU OF LAND MANAGEMENT OREGON STATE OFFICE ROSEBURG DISTRICT	
<b>RESTON PIECES CONSTRUCTION PLANS</b>	
DESIGNED: J. H-RDER	D-TE: 1/16/2026
CONTR-CT NO. ORR05-TS-2026.0004	SHEET 10 OF 19



28-8-20.3 CONSTRUCTION				
ST-	DIST-NCE FT	BE-RING	% GR-DE	NOTES
0+00	30	S3W	-3	JUNCTION WITH 28-8-20.3
0+30	50	S8W	-4	
0+80	50	S25E	-1	SHIFT CENTERLINE 8FT LEFT
1+30	50	S20E	1	INST-LL 18" X 40' CULVERT
1+80	40	S43E	4	SHIFT CENTERLINE 5FT LEFT
2+20	55	S32E	7	
2+75	60	S45E	5	PROPERTY LINE
3+35	65	S42E	2	
4+00	45	S48E	3	SHIFT CENTERLINE 2FT LEFT INST-LL 18" X 40' CULVERT
4+45	65	S41E	4	
5+10	75	S32E	7	
5+85	100	S25E	4	
6+85	40	S10E	-1	
7+25	40	S10E	-5	
7+65	80	S14E	-3	
8+45				CONSTRUCT 70' X 70' LANDING


- LEGEND**
- NEW CONSTRUCTION
  - EXISTING ROAD
  - ◆ SURVEY MONUMENT
  - > CULVERT TO BE INSTALLED
  - > DITCHOUT TO BE CONSTRUCTED

- NOTES:**
1. RIGHT OF W-Y WIDTH WILL BE 30' EITHER SIDE OF CENTERLINE, -ND IS M-RKED WITH "RIGHT OF W-Y" -ND FL-SHER T-GS.
  2. CONSTRUCTION WILL H- E - 16' SUBGR-DE, CROWNED, 2' DITCH, -ND SURF-CED WITH 9" OF CRUSHED -GGREG-TE.
  3. COURSES -RE TRUE BE-RINGS.

UNITED STATES DEPARTMENT OF THE INTERIOR  
BUREAU OF LAND MANAGEMENT  
OREGON STATE OFFICE ROSEBURG DISTRICT

## RESTON PIECES CONSTRUCTION PLANS

DESIGNED: J. H-RDER      D-TE: 1/16/2026  
CONTR-CT NO. ORR05-TS-2026.0004      SHEET 11 OF 19




CONSTRUCT 70' X 70' LANDING

28-8-22.1 CONSTRUCTION				
ST-	DIST-NCE FT	BE-RING	% GR-DE	NOTES
0+00	50	N50E	-8	JUNCTION WITH 28-8-22.1 INST-LL 18" X 40' CULVERT
0+50	40	N58E	-10	
0+90	50	N42E	-11	SHIFT CENTERLINE 2FT LEFT
1+40	85	N50E	-10	
2+25	35	N50E	-10	PROPERTY LINE SHIFT CENTERLINE 2FT LEFT
2+60	30	N39E	-9	SHIFT CENTERLINE 3FT LEFT
2+90	75	N38E	-10	
3+65	75	N47E	-10	SHIFT CENTERLINE 2FT RIGHT
4+40	85	N58E	-6	SHIFT CENTERLINE 2FT RIGHT
5+25	65	N53E	-1	CONSTRUCT DITCH OUT RIGHT
5+90	60	N53E	0	
6+50	55	N49E	3	
7+05				CONSTRUCT 70' X 70' L-NDING CONSTRUCT DITCH OUT RIGHT

**LEGEND**

- NEW CONSTRUCTION
- EXISTING ROAD
- ◆ SURVEY MONUMENT
- >—< CULVERT TO BE INSTALLED
- > DITCHOUT TO BE CONSTRUCTED



SOUTH WEST CORNER OF SECTION 15, T28S R8W.

BLM  
SW 1/4 SW 1/4  
T28W R8W  
SEC. 15

HTFF  
NW 1/4 NW 1/4  
T28W R8W  
SEC. 22

STA 2+25 LIES 0' SOUTH AND 855'  
EAST OF THE SOUTH WEST CORNER  
OF SECTION 15, T28S R8W

STA 0+00 LIES 685' EAST AND 144'  
SOUTH OF THE NORTH WEST  
CORNER OF SECTION 22, T28S R8W

INSTALL 18" X 40'  
CULVERT

CONSTRUCT 70' X 70' LANDING  
CONSTRUCT DITCH OUT RIGHT

CONSTRUCT DITCH OUT RIGHT

**NOTES:**

1. RIGHT OF W-Y WIDTH WILL BE 30' EITHER SIDE OF CENTERLINE, -ND IS M-RKED WITH "RIGHT OF W-Y" -ND FL-SHER T-GS.
2. CONSTRUCTION WILL H- E - 16' SUBGR-DE, CROWNED, 2' DITCH, -ND SURF-CED WITH 9" OF CRUSHED -GGREG-TE.
3. COURSES -RE TRUE BE-RINGS.

UNITED STATES DEPARTMENT OF THE INTERIOR  
BUREAU OF LAND MANAGEMENT  
OREGON STATE OFFICE ROSEBURG DISTRICT

**RESTON PIECES  
CONSTRUCTION PLANS**


DESIGNED: J. H-RDER D-TE: 1/16/2026

CONTR-CT NO. ORR05-TS-2026.0004 SHEET 12 OF 19



28-8-23.6 CONSTRUCTION				
ST-	DIST-NCE FT	BE-RING	% GR-DE	NOTES
0+00	50	S31W	-4	JUNCTION WITH 28-8-23.3. INST-LL 18" X 40' CULVERT
0+50	50	S18W	-2	SHIFT CENTERLINE 3FT LEFT
1+00	55	S25W	1	SHIFT CENTERLINE 5FT LEFT
1+55	40	S35W	3	
1+95	65	S47W	0	PROPERTY LINE
2+60	40	S44W	-2	SHIFT CENTERLINE 3FT LEFT
3+00	45	S70W	-4	
3+45	35	S71W	-7	
3+80	35	S75W	-7	SHIFT CENTERLINE 8FT LEFT
4+15	40	S83W	-7	SHIFT CENTERLINE 4FT LEFT
4+55	30	S85W	-7	SHIFT CENTERLINE 8FT LEFT
4+85	35	S84W	-3	SHIFT CENTERLINE 8FT LEFT
5+20	40	N85W	0	SHIFT CENTERLINE 6FT LEFT
5+60	20	N81W	-4	

28-8-23.6 CONSTRUCTION				
ST-	DIST-NCE FT	BE-RING	% GR-DE	NOTES
5+80	15	N80W	-6	
5+95	35	N79W	-2	INST-LL 24" X 40' CULVERT SHIFT CENTERLINE 3FT LEFT
6+30	50	N79W	1	
6+80	10	N82W	4	SHIFT CENTERLINE 2FT LEFT
6+90	10	N77W	6	INST-LL 24" X 40' CULVERT SHIFT CENTERLINE 4FT LEFT
7+00	20	N75W	11	SHIFT CENTERLINE 6FT LEFT
7+20	25	N71W	12	SHIFT CENTERLINE 2FT LEFT
7+45	10	N66W	11	
7+55	15	N68W	11	INST-LL 24" X 40' CULVERT
7+70	35	N79W	15	
8+05	35	S86W	15	SHIFT CENTERLINE 6FT LEFT
8+40	20	S66W	15	SHIFT CENTERLINE 7FT LEFT
8+60	35	S76W	15	SHIFT CENTERLINE 4FT LEFT
8+95	50	N73W	15	SHIFT CENTERLINE 3FT LEFT
9+45	70	N73W	15	SHIFT CENTERLINE 8FT LEFT
10+15	30	N70W	15	SHIFT CENTERLINE 10FT LEFT
10+45	110	S85W	15	SHIFT CENTERLINE 12FT LEFT
11+55	65	S69W	12	SHIFT CENTERLINE 15FT LEFT
12+20	30	N74W	5	SHIFT CENTERLINE 11FT LEFT



STA 0+00 LIES 88' EAST AND 390' NORTH OF THE S 1/4 CORNER OF SECTION 23, T28S R8W

STA 1+95 LIES 145' NORTH AND 0' EAST OF THE S 1/4 CORNER OF SECTION 23, T28S R8W

1/4 CORNER COMMON TO SECTIONS 23 & 26, T28S R8W.

NOTES:


- RIGHT OF W-Y WIDTH WILL BE 30' EITHER SIDE OF CENTERLINE, -ND IS M-RKED WITH "RIGHT OF W-Y" -ND FL-SHER T-GS.
- CONSTRUCTION WILL H- E - 16' SUBGR-DE, CROWNED, 2' DITCH, -ND SURF-CED WITH 9" OF CRUSHED -GGREG-TE.
- COURSES -RE TRUE BE-RINGS.

UNITED STATES DEPARTMENT OF THE INTERIOR  
BUREAU OF LAND MANAGEMENT  
OREGON STATE OFFICE ROSEBURG DISTRICT

RESTON PIECES  
CONSTRUCTION PLANS

DESIGNED: J. H-RDER D-TE: 1/16/2026  
CONTR-CT NO. ORR05-TS-2026.0004 SHEET 13 OF 19






**LEGEND**  
 ●— CONSTRUCTION CENTER LINE  
 — EXISTING ROAD  
 X— CULVERT TO BE INSTALLED  
 — DITCHOUT TO BE CONSTRUCTED

28-8-23.6 CONSTRUCTION				
STA	DISTANCE FT	BEARING	% GRADE	NOTES
12+50	35	N53W	5	CONSTRUCT 50' X 50' LANDING SHIFT CENTERLINE 15FT LEFT
12+85	30	N42W	7	SHIFT CENTERLINE 15FT LEFT
13+15	35	N32W	14	SHIFT CENTERLINE 12FT LEFT
13+50	70	N11W	15	INSTALL 18" X 40' CULVERT SHIFT CENTERLINE 8FT LEFT
14+20	40	N10W	15	SHIFT CENTERLINE 10FT LEFT
14+60	25	N21W	15	SHIFT CENTERLINE 12FT LEFT
14+85	50	N27W	15	SHIFT CENTERLINE 11FT LEFT
15+35	60	N51W	15	SHIFT CENTERLINE 12FT LEFT
15+95	50	N85W	15	SHIFT CENTERLINE 3FT LEFT
16+45	65	S69W	15	
17+10	60	S62W	15	SHIFT CENTERLINE 6FT LEFT
17+70	30	S77W	11	
18+00	50	S89W	10	
18+50	50	N89W	11	INSTALL 18" X 40' CULVERT SHIFT CENTERLINE 6FT LEFT
19+00	25	S80W	10	SHIFT CENTERLINE 12FT LEFT
19+25	85	S63W	5	SHIFT CENTERLINE 9FT LEFT
20+10	70	S71W	3	CONSTRUCT TURNOUT RIGHT SHIFT CENTERLINE 3FT RIGHT
20+80	70	S81W	6	
21+50	40	N89W	2	SHIFT CENTERLINE 6FT RIGHT
21+90	70	N68W	3	SHIFT CENTERLINE 3FT RIGHT
22+60	50	N38W	6	
23+10	80	N29W	10	INSTALL 24" X 40' CULVERT SHIFT CENTERLINE 2FT LEFT

28-8-23.6 CONSTRUCTION				
STA	DISTANCE FT	BEARING	% GRADE	NOTES
23+90	70	N44W	10	CONSTRUCT 50' X 50' LANDING SHIFT CENTERLINE 15FT LEFT
24+60	100	N40W	10	SHIFT CENTERLINE 10FT LEFT
25+60	100	N19W	12	
26+60	70	N12W	15	SHIFT CENTERLINE 7FT LEFT
27+30	80	N13W	12	


- NOTES:
- RIGHT OF WAY WIDTH WILL BE 30' EITHER SIDE OF CENTERLINE, AND IS MARKED WITH "RIGHT OF WAY" AND FLASHER TAGS.
  - CONSTRUCTION WILL HAVE A 16' SUBGRADE, CROWNED, 2' DITCH, AND SURFACED WITH 9" OF CRUSHED AGGREGATE.
  - COURSES ARE TRUE BEARINGS.



UNITED STATES DEPARTMENT OF THE INTERIOR  
 BUREAU OF LAND MANAGEMENT  
 OREGON STATE OFFICE ROSEBURG DISTRICT

**RESTON PIECES  
 CONSTRUCTION PLANS**


DESIGNED: J. HARDER      DATE: 1/16/2026  
 CONTRACT NO. ORR05-TS-2026.0004      SHEET 14 OF 19



**LEGEND**  
 ○— CONSTRUCTION CENTER LINE  
 — EXISTING ROAD  
 >— CULVERT TO BE INSTALLED  
 — DITCHOUT TO BE CONSTRUCTED

28-8-23.6 CONSTRUCTION				
ST-	DIST-NCE FT	BE-RING	% GR-DE	NOTES
28+10	80	N20W	8	
28+90	100	N20W	4	
29+90	60	N25W	0	CONSTRUCT 50' X 50' L-NDING
30+50	100	N40W	-3	SHIFT CENTERLINE 4FT RIGHT
31+50	80	N46W	-3	SHIFT CENTERLINE 2FT LEFT
32+30	100	N39W	-6	SHIFT CENTERLINE 8FT LEFT
33+30	60	N50W	-8	INST-LL 18" X 40' CULVERT SHIFT CENTERLINE 15FT LEFT
33+90	70	N38W	-6	SHIFT CENTERLINE 11FT LEFT
34+60	100	N32W	-3	CONSTRUCT TURNOUT RIGHT
35+60	100	N1W	-1	
36+60	70	N5W	-5	SHIFT CENTERLINE 5FT RIGHT
37+30	60	N2W	-10	SHIFT CENTERLINE 9FT RIGHT
37+90	75	N24W	-12	SHIFT CENTERLINE 2FT RIGHT

- NOTES:
- RIGHT OF W-Y WIDTH WILL BE 30' EITHER SIDE OF CENTERLINE, -ND IS M-RKED WITH "RIGHT OF W-Y" -ND FL-SHER T-GS.
  - CONSTRUCTION WILL H- E - 16' SUBGR-DE, CROWNED, 2' DITCH, -ND SURF-CED WITH 9" OF CRUSHED -GGREG-TE.
  - COURSES -RE TRUE BE-RINGS.




UNITED STATES DEPARTMENT OF THE INTERIOR  
 BUREAU OF LAND MANAGEMENT  
 OREGON STATE OFFICE ROSEBURG DISTRICT

**RESTON PIECES  
 CONSTRUCTION PLANS**


DESIGNED: J. H-RDER | D-TE: 1/16/2026  
 CONTR-CT NO. ORR05-TS-2026.0004 | SHEET 15 OF 19

28-8-23.6 CONSTRUCTION				
ST-	DIST-NCE FT	BE-RING	% GR-DE	NOTES
38+65	80	N28W	-11	SHIFT CENTERLINE 5FT RIGHT
39+45	35	N5W	-6	
39+80	55	N22E	-3	SHIFT CENTERLINE 7FT LEFT
40+35				CONSTRUCT 70' X 70' L-NDING. CONSTRUCT DITCHOUT LEFT



**LEGEND**  
 ○—○ CONSTRUCTION CENTER LINE  
 ——— EXISTING ROAD  
 >—< CULVERT TO BE INSTALLED  
 —< DITCHOUT TO BE CONSTRUCTED

- NOTES:
- RIGHT OF W-Y WIDTH WILL BE 30' EITHER SIDE OF CENTERLINE, -ND IS M-RKED WITH "RIGHT OF W-Y" -ND FL-SHER T-GS.
  - CONSTRUCTION WILL H- E - 16' SUBGR-DE, CROWNED, 2' DITCH, -ND SURF-CED WITH 9" OF CRUSHED -GGREG-TE.
  - COURSES -RE TRUE BE-RINGS.



UNITED STATES DEPARTMENT OF THE INTERIOR  
 BUREAU OF LAND MANAGEMENT  
 OREGON STATE OFFICE ROSEBURG DISTRICT

**RESTON PIECES  
 CONSTRUCTION PLANS**

DESIGNED: J. H-RDER D-TE: 1/16/2026  
 CONTR-CT NO. ORR05-TS-2026.0004 SHEET 16 OF 19

**CULVERT LIST**

CULVERT LOCATIONS						DOWNSPOUT (NOTE 4)					REMARKS (NOTE 6)
DESIGNED (NOTE 2)			AS BUILT			MATERIAL	TYPE	SIZE (IN)	LENGTH (FT)	ELBOW TYPE (NOTE 5)	
ROAD NO. STATION OR M.P.	MATERIAL (NOTE 7)	SIZE (IN)	LENGTH (FT)	SKEW ANGLE	INSTALL TYPE (NOTE 3)						
<b>SPUR 2</b>											
STA 0+25	*	18"	40	30°	TYPE 2						
<b>SPUR 3</b>											
STA 2+70	*	18	40	30°	TYPE 2						
<b>28-8-20.3</b>											
STA 1+30	*	18	40	30°	TYPE 2						
STA 4+00	*	18	40	30°	TYPE 2						
<b>28-8-22.1</b>											
STA 0+00	*	18	40	30°	TYPE 2						
<b>28-8-23.6</b>											
STA 0+00	*	18	40	30°	TYPE 2						
STA 5+95	*	24	40	30°	TYPE 2						
STA 6+90	*	24	40	30°	TYPE 2						
STA 7+55	*	24	40	30°	TYPE 2						
STA 13+50	*	18	40	30°	TYPE 2						
STA 18+50	*	18	40	30°	TYPE 2						
STA 23+10	*	24	40	30°	TYPE 2						
STA 33+30	*	18	40	30°	TYPE 2						


**NOTES:**

- DESIGNED CULVERT LENGTHS AND LOCATIONS ARE APPROXIMATE.
- ALL CULVERTS HAVE 2 2/3" X 1/2" CORRUGATIONS UNLESS OTHERWISE SPECIFIED.
- SEE CULVERT INSTALLATION SHEET.
- DOWNSPOUT TYPES:
  - FULL
  - HALF
  - FLUME
- ELBOW TYPES:
  - CONVENTIONAL OR FABRICATED
  - TURNER TYPE
  - SLIP JOINT
- INCLUDE SPECIAL SECTIONS, STRUCTURES, HEADWALLS, FOOTINGS, AND OTHER DATA.
- MATERIAL TYPES  
 HDPE = HIGH-DENSITY POLYETHYLENE  
 CMP = CORRUGATED METAL PIPE (STEEL OR ALUMINUM)


ROUND PIPE CULVERT		
MATERIAL	SIZE	LENGTH
*	18"	360'
*	24"	160'

\* MATERIAL TYPE: HI-DENSITY POLYETHYLENE OR ALUMINIZED








CROSS SECTION AT CATCH BASIN  
CULVERT INSTALATION TYPE 2, 3, AND 4




PLAN VIEW




CATCH BASIN ELEVATION



BEDDING OF CULVERTS ON STABLE NATURAL GROUND FOUNDATION



BEDDING OF CULVERTS ON SOFT SPONGY, UNSTABLE SOIL FOUNDATION OR COMPACTED EMBANKMENT







BEDDING OF CULVERTS IN SOLID ROCK OR BOULDER FOUNDATION



NOTES:

1. BEDDING MATERIAL SHALL BE PLACED LOOSE AND SHAPED TO FIT THE BOTTOM OF THE CULVERT
2. BACKFILL IN ACCORDANCE WITH SECTION 417 OF SPECIFICATIONS
3. MAINTAIN 8" MIN DEPTH BETWEEN HIGH POINT OF ROCK AND/OR BOULDERS AND THE BOTTOM OF THE CULVERT BEDDING


BEDDING OF CULVERTS



CULVERT INSTALLATION TYPES



THE GRADE OF CROSS DRAINS SHALL BE AT LEAST 2% GREATER THAN THE GRADE OF THE DITCH



CULVERT MARKER INSTALLATION


UNITED STATES DEPARTMENT OF THE INTERIOR  
BUREAU OF LAND MANAGEMENT  
OREGON STATE OFFICE ROSEBURG DISTRICT

RESTON PIECES  
CULVERT INSTALLATIONS


DESIGNED: J. HARDER DATE: 1/16/2026  
CONTRACT NO. ORR05-TS-2026.0004 SHEET 18 OF 19

NOTE:


1. ALL AREAS WITHIN THE VARIABLE DISTANCE SHALL BE CLEARED OF VEGETATION.
2. ALL AREAS WITHIN THE VARIABLE DISTANCE SHALL BE FREE OF ALL OVERHANGING LIMBS AND BRANCHES WITHIN 14 FEET ELEVATION ABOVE RUNNING SURFACE. 




EXAMPLE 1



EXAMPLE 2



EXAMPLE 3



CURVE



UNITED STATES DEPARTMENT OF THE INTERIOR	
BUREAU OF LAND MANAGEMENT	
OREGON STATE OFFICE	ROSEBURG DISTRICT
RESTON PIECES BRUSHING DETAIL	
DESIGNED: J. HARDER	DATE: 1/16/2026
CONTRACT NO. ORR05-TS-2026.0004	SHEET 19 OF 19