

Surface Use Plan of Operations
Plans for Surface Reclamation
Conditions of Approval
 Sample Template

[] Indicates site-specific values to be filled in by the field office.

I. Reclamation Objectives:

The objective of interim reclamation is to restore vegetative cover and a portion of the landform sufficient to maintain healthy, biologically active topsoil; control erosion; and minimize habitat, visual, and forage loss during the life of the well or facilities.

The long-term objective of final reclamation is to return the land to a condition approximating that which existed prior to disturbance. This includes restoration of the landform and natural vegetative community, hydrologic systems, visual resources, and wildlife habitats. To ensure that the long-term objective will be reached through human and natural processes, actions will be taken to ensure standards are met for site stability, visual quality, hydrological functioning, and vegetative productivity.

II. Reclamation Performance Standards

The following reclamation performance standards will be met:

Interim Reclamation – Includes disturbed areas that may be redisturbed during operations and will be redisturbed at final reclamation to achieve restoration of the original landform and a natural vegetative community.

Will be judged successful when the BLM authorized officer determines that...

- Disturbed areas not needed for active, long-term production operations or vehicle travel have been recontoured, protected from erosion, and revegetated with a self-sustaining, vigorous, diverse, native (or as otherwise approved) plant community sufficient to minimize visual impacts, provide forage, stabilize soils, and impede the invasion of noxious, invasive, and non-native weeds.

Final Reclamation – Includes disturbed areas where the original landform and a natural vegetative community have been restored.

Will be judged successful when the BLM authorized officer determines that...

- The original landform has been restored for all disturbed areas including well pads, production facilities, roads, pipelines, and utility corridors.
- General: A self-sustaining, vigorous, diverse, native (or otherwise approved) plant community is established on the site, with a density sufficient to control

erosion and invasion by non-native plants and to reestablish wildlife habitat or forage production. At a minimum, the established plant community will consist of species included in the seed mix and/or desirable species occurring in the surrounding natural vegetation.

- Specific: No single species will account for more than [30]% total vegetative composition unless it is evident at higher levels in the adjacent landscape. Permanent vegetative cover will be determined successful when the basal cover of desirable perennial species is at least [80]% of the basal cover on adjacent or nearby undisturbed areas where vegetation is in a healthy condition; or [80]% of the potential basal cover as defined in the National Resource Conservation Service Ecological Site(s) for the area. Plants must be resilient as evidenced by well-developed root systems and flowers. [Shrubs, will be well established and in a “young” age class at a minimum (therefore, not comprised mainly of seedlings that may not survive until the following year).]
- In agricultural areas, irrigation systems and soil conditions are reestablished in such a way as to ensure successful cultivation and harvesting of crops.
- Erosion features are equal to or less than surrounding area and erosion control is sufficient so that water naturally infiltrates into the soil and gullying, headcutting, slumping, and deep or excessive rills (greater than 3 inches) are not observed.
- The site is free of State- or county-listed noxious weeds, oil field debris and equipment, and contaminated soil. Invasive and non-native weeds are controlled.

III. Reclamation Actions

During initial well pad, production facility, road, pipeline, and utility corridor construction and prior to completion of the final well on the well pad, pre-interim reclamation stormwater management actions will be taken to ensure disturbed areas are quickly stabilized to control surface water flow and to protect both the disturbed and adjacent areas from erosion and siltation. This may involve construction and maintenance of temporary silt ponds, silt fences, berms, ditches, and mulching.

When the last well on the pad has been completed, some portions of the well location will undergo interim reclamation and some portions of the well pad will usually undergo final reclamation. Most well locations will have limited areas of bare ground, such as a small area around production facilities or the surface of a rock road. Other areas will have interim reclamation where workover rigs and fracturing tanks may need a level area to set up in the future. Some areas will undergo final reclamation where portions of the well pad will no longer be needed for production operations and can be recontoured to restore the original landform.

The following minimum reclamation actions will be taken to ensure that the reclamation objectives and standards are met. It may be necessary to take additional

reclamation actions beyond the minimum in order to achieve the Reclamation Standards.

Reclamation - General

Procedure:

- The BLM will be notified 24 hours prior to commencement of any reclamation operations.

Housekeeping:

- Immediately upon well completion, the well location and surrounding areas(s) will be cleared of, and maintained free of, all debris, materials, trash, and equipment not required for production.
- No hazardous substances, trash, or litter will be buried or placed in pits. Upon well completion, any hydrocarbons in the pit will be remediated or removed.

Vegetation Clearing:

- Vegetation removal and the degree of surface disturbance will be minimized wherever possible.
- *[Example of site-specific requirement: During vegetation clearing activities, trees and woody vegetation removed from the well pad and access road will be moved aside prior to any soil disturbing activities. Care will be taken to avoid mixing soil with the trees and woody vegetation. Trees left for wood gathering will be cut [twelve inches or less from the ground], delimbed, and the trunks, six (6) inches or more in diameter will be removed and placed either by the uphill side of the access road, or moved to the end of the road, or to a road junction for easy access for wood gatherers and to reduce vehicle traffic on the well pad. Trees with a trunk diameter less than six (6) inches and woody vegetation will be used to trap sediment, slow runoff, or scattered on reclaimed areas to stabilize slopes, control erosion, and improve visual resources.]*

Topsoil Management:

- Operations will disturb the minimum amount of surface area necessary to conduct safe and efficient operations. When possible, equipment will be stored and operated on top of vegetated ground to minimize surface disturbance.
- In areas to be heavily disturbed, the top [eight (8)] inches of soil material, will be stripped and stockpiled around the perimeter of the well location and along the perimeter of the access road to control run-on and run-off, and to make redistribution of topsoil more efficient during interim reclamation. Stockpiled topsoil may include vegetative material. Topsoil will be clearly segregated and stored separately from subsoils.
- Earthwork for interim and final reclamation will be completed within 6 months of well completion or plugging unless a delay is approved in writing by the BLM authorized officer.
- Salvaging and spreading topsoil will not be performed when the ground or topsoil is frozen or too wet to adequately support construction equipment. If such

equipment creates ruts in excess of four (4) inches deep, the soil will be deemed too wet.

- No major depressions will be left that would trap water and cause ponding unless the purpose is to trap runoff and sediment.

Seeding:

- Seedbed Preparation. Initial seedbed preparation will consist of recontouring to the appropriate interim or final reclamation standard. All compacted areas to be seeded will be ripped to a minimum depth of 18 inches with a minimum furrow spacing of 2 feet, followed by recontouring the surface and then evenly spreading the stockpiled topsoil. Prior to seeding, the seedbed will be scarified and left with a rough surface.
- If broadcast seeding is to be used and is delayed, final seedbed preparation will consist of contour cultivating to a depth of 4 to 6 inches within 24 hours prior to seeding, dozer tracking, or other imprinting in order to loosen up the soil and create seed germination micro-sites.
- Seed Application. Seeding will be conducted no more than 24 hours following completion of final seedbed preparation. A certified weed-free seed mix designed by BLM (shown below) to meet reclamation standards will be used. The following seed mix and rates will be used on all disturbed surfaces, including pipelines and road cut & fill slopes:

Species of Seed	Cultivar	App. Rate PLS (lbs/ac)
Total:		

- The application rate shown in the table is based on 45 pure live seeds (PLS) per square foot, drill-seeded to a depth of 0.25 to 0.5 inch, which is the method that will be used where feasible. [However, shrub species will be seeded during the winter on the ground surface or preferably on top of snow.] In areas that will not be drill-seeded, the seed mix will be broadcast-seeded at twice the application rate shown in the table and covered no more than 0.25 inch deep with a harrow, drag bar, or roller or will be broadcast-seeded into imprints, such as fresh dozer cleat marks.

- No seeding will occur from [May 15 to September 15]. Fall seeding is preferred and will be conducted after [September 15] and prior to ground freezing. [Shrub species will be seeded separately and will be seeded during the winter.] Spring seeding will be conducted after the frost leaves the ground and no later than [May 15].

Erosion Control and Mulching:

- Mulch, silt fencing, wattles, hay bales, and other erosion control devices will be used on areas at risk of soil movement from wind and water erosion.
- Mulch will be used if necessary to control erosion, create vegetation micro-sites, and retain soil moisture and may include hay, small-grain straw, wood fiber, live mulch, cotton, jute, or synthetic netting. Mulch will be free from mold, fungi, and certified free of noxious or invasive weed seeds.
- If straw mulch is used, it will contain fibers long enough to facilitate crimping and provide the greatest cover.

Pit Closure:

- Reserve pits will be closed and backfilled within six months of release of the rig. All reserve pits remaining open after six months will require written authorization of the authorized officer. Immediately upon well completion, any hydrocarbons or trash in the pit will be removed. Pits will be allowed to dry, be pumped dry, or solidified in-situ prior to backfilling.
- Following completion activities, pit liners will be completely removed or removed down to the solids level and disposed of at an approved landfill, or treated to prevent their reemergence to the surface and interference with long-term successful revegetation. If it was necessary to line the pit with a synthetic liner, the pit will not be trenched (cut) or filled (squeezed) while containing fluids. When dry, the pit will be backfilled with a minimum of 5 feet of soil material. In relatively flat areas the pit area will be slightly mounded above the surrounding grade to allow for settling and to promote surface drainage away from the backfilled pit.

Management of Invasive, Noxious, and Non-Native Species:

- All reclamation equipment will be cleaned prior to use to reduce the potential for introduction of noxious weeds or other undesirable non-native species.
- An intensive weed monitoring and control program will be implemented prior to site preparation for planting and will continue until interim or final reclamation is approved by the authorized officer.
- Monitoring will be conducted at least annually during the growing season to determine the presence of any invasive, noxious, and non-native species. Invasive, noxious, and non-native species that have been identified during monitoring will be promptly treated and controlled. A Pesticide Use Proposal (PUP) will be submitted to the BLM for approval prior to the use of herbicides.

Interim Reclamation Procedures - Additional

Recontouring:

- Interim reclamation actions will be completed no later than 6 months from when the final well on the location has been completed, weather permitting. The portions of the cleared well site not needed for active operational and safety purposes will be recontoured to the original contour if feasible, or if not feasible, to an interim contour that blends with the surrounding topography as much as possible. Sufficient semi-level area will remain for setup of a workover rig and to park equipment. In some cases, rig anchors may need to be pulled and reset after recontouring to allow for maximum interim reclamation.
- If the well is a producer, the interim cut and fill slopes prior to re-seeding will not be steeper than a 3:1 ratio, unless the adjacent native topography is steeper. Note: Constructed slopes may be much steeper during drilling, but will be recontoured to the above ratios during interim reclamation.
- Roads and well production equipment, such as tanks, treaters, separators, vents, electrical boxes, and equipment associated with pipeline operation, will be placed on location so as to permit maximum interim reclamation of disturbed areas. If equipment is found to interfere with the proper interim reclamation of disturbed areas, the equipment will be moved so proper recontouring and revegetation can occur.

Application of Topsoil & Revegetation:

- Topsoil will be evenly respread and aggressively revegetated over the entire disturbed area not needed for all-weather operations including road cuts & fills and to within a few feet of the production facilities, unless an all-weather, surfaced, access route or small “teardrop” turnaround is needed on the well pad.
- In order to inspect and operate the well or complete workover operations, it may be necessary to drive, park, and operate equipment on restored, interim vegetation within the previously disturbed area. Damage to soils and interim vegetation will be repaired and reclaimed following use. To prevent soil compaction, under some situations, such as the presence of moist, clay soils, the vegetation and topsoil will be removed prior to workover operations and restored and reclaimed following workover operations.

Visual Resources Mitigation:

- Trees, if present, and tall vegetation will be left along the edges of the pads whenever feasible to provide screening.
- To help mitigate the contrast of recontoured slopes, reclamation will include measures to feather cleared lines of vegetation and to save and redistribute cleared trees, debris, and rock over recontoured cut and fill slopes.
- To reduce the view of production facilities from visibility corridors and private residences, facilities will not be placed in visually exposed locations (such as ridgelines and hilltops).
- Production facilities will be clustered and placed away from cut slopes and fill slopes to allow the maximum recontouring of the cut and fill slopes.

- All long-term above ground structures will be painted [Covert Green] (from the BLM “Supplemental Environmental Colors” chart) to blend with the natural color of the late summer landscape background.

Final Reclamation Procedures - Additional

- Final reclamation actions will be completed within 6 months of well plugging, weather permitting.
- All disturbed areas, including roads, pipelines, pads, production facilities, and interim reclaimed areas will be recontoured to the contour existing prior to initial construction or a contour that blends indistinguishably with the surrounding landscape. Resalvaged topsoil will be respread evenly over the entire disturbed site to ensure successful revegetation. To help mitigate the contrast of recontoured slopes, reclamation will include measures to feather cleared lines of vegetation and to save and redistribute cleared trees, woody debris, and large rocks over recontoured cut and fill slopes.
- Water breaks and terracing will only be installed when absolutely necessary to prevent erosion of fill material. Water breaks and terracing are not permanent features and will be removed and reseeded when the rest of the site is successfully revegetated and stabilized.
- If necessary to ensure timely revegetation, the pad will be fenced to BLM standards to exclude livestock grazing for the first two growing seasons or until seeded species become firmly established, whichever comes later. Fencing will meet standards found on page 18 of the Gold Book, 4th Edition, or will be fenced with operational electric fencing.
- Final abandonment of pipelines and flowlines will involve flushing and properly disposing of any fluids in the lines. All surface lines and any lines that are buried close to the surface that may become exposed in the foreseeable future due to water or wind erosion, soil movement, or anticipated subsequent use, must be removed. Deeply buried lines may remain in place unless otherwise directed by the authorized officer.

Reclamation Monitoring and Final Abandonment Approval

- Reclaimed areas will be monitored annually. Actions will be taken to ensure that reclamation standards are met as quickly as reasonably practical and are maintained during the life of the permit.
- Reclamation monitoring will be documented in an annual reclamation report submitted to the authorized officer by [March 1]. The report will document compliance with all aspects of the reclamation objectives and standards, identify whether the reclamation objectives and standards are likely to be achieved in the near future without additional actions, and identify actions that have been or will be taken to meet the objectives and standards. The report will also include acreage figures for: Initial Disturbed Acres; Successful Interim Reclaimed Acres; Successful Final Reclaimed Acres. Annual reports will not be submitted for sites approved by the authorized officer in writing as having met interim or final

reclamation standards. Monitoring and reporting continues annually until interim or final reclamation is approved. Any time 30% or more of a reclaimed area is redisturbed, monitoring will be reinitiated.

- The authorized officer will be informed when reclamation has been completed, appears to be successful, and the site is ready for final inspection.

DRAFT