PIPELINE STATIONING

4597+44 END WETLANDS
4597+78 P.I. = 30°45'00" RT
4595+47 P.I. = 43°42'41" RT
4594+78 P.I. = 39°30'00" RT
4594+56 EAST FORK LITTLE BEAR RIVER
4593+67 P.I. = 19°47'50" LT
4592+86 P.I. = 23°43'01" LT
4592+06 ϕ4 < 43°24'' LT
CROSS EQUATION ADD
4592+94 Inc. END REALIGNMENT
4591+87 PROPERTY LINE
4591+80 P.I. = 18°30'00" LT
4591+30 ACCESS RD C-14A
4589+87 RANGE LINE
4588+49 P.I. = 5°26'46" RT
4588+24 ACCESS RD C-14A
4587+92 END WETLANDS
4587+24 BOR WETLANDS
4585+92 END WETLANDS
4584+56 BOR WETLANDS
4583+43 P.I. = 16°53'07" LT
4581+74 P.I. = 5°33'16" RT
4580+92 P.I. = 32°09'30" RT
4580+46 ACCESS RD C-14A
4579+73 P.I. = 40°23'17" LT
4574+97 P.I. = 11°03'14" LT
4574+75 ACCESS RD C-14A
4574+14 END WETLANDS
4573+60 ACCESS RD C-14A
4573+57 P.I. = 41°16'22" LT
4573+27 BOR WETLANDS
4572+61 P.I. = 1°03'56" RT
4572+55 ACCESS RD C-14A
4572+07 P.I. = 46°31'14" RT
4571+38 ACCESS RD C-14A
4570+62 P.I. = 22°21'01" LT
4568+76 P.I. = 12°32'54" LT
4568+13 MLV 7
4566+72 P.I. = 26°58'38" RT
4563+24 ACCESS RD C-14C
4561+74 P.I. = 50°42'00" RT & BOR REALIGNMENT
4561+17 PORCUPINE CANAL
4557+60 WILDFOOT 92
4554+78 P.I. = 13°23'54" RT
4548+16 PROPERTY LINE

PORCUPINE CANAL
TEMPORARY WORK SPACE LIMITS
2.349 ACRES WORK SPACE
45°
MLV No.
C-14A
Lime Kiln Canyon Staging Area 1.15 ac.
VEGETATIVE BUFFER SEE NOTE 3
0.410 ACRE WORK SPACE
FENCE OFF TREES SEE NOTE 2
SEE NOTE 1
1.242 ACRES WORK SPACE
FENCE OFF TREES SEE NOTES 2 & 3
EQUIPMENT BRIDGE
FOR RIVER CROSSING DETAILS, SEE DRAWING 300A-39G
60' x 125' ADDITIONAL TEMPORARY WORK SPACE
LITTLE BEAR RIVER
EAST FORK
La PLATA RD
SECTION 13
SECTION 18

GENERAL NOTES

1. ADDITIONAL TEMPORARY WORKSPACE REQUESTED WITHIN 50 FEET OF WETLAND TO ACCOMMODATE SPOIL STORAGE.
2. CONTRACTOR TO NOTIFY THE LANDOWNER 48 HOURS PRIOR TO CLEARING TO COORDINATE TREE REMOVAL.
3. PARTS OF THE SOUTHERLY CONSTRUCTION RIGHT OF WAY FOLLOW THE VEGETATIVE BUFFER ALONG THE EAST FORK OF THE LITTLE BEAR RIVER, CONTRACTOR WILL MAKE EVERY EFFORT TO PRESERVE SAID BUFFER.

REFERENCE DRAWINGS

300A-39	ALIGNMENT SHEET
300A-39A	DETAILED PLAN – MLV-7
300A-39Z	EAST FORK LITTLE BEAR RIVER CROSSING

DESIGN DATA
CODE: TITLE 49, PART 192 CFR, CLASS 1, df= .50 &
PRESSURE: 1440 PSIG MAOP .80

SCALE, PROJECTION & SURVEY DATA
100' 50' 0 100' 200'
SCALE: 1"= 100' HORIZONTAL
GPS SURVEY (G.P.S. TRIMBLE 5800 SERIES)
UTM ZONE 12 , NAD83 (US FT), NAVD88, GEOID03

NO.	DATE	BY	DESCRIPTION	PROJ. ID	APPR.
B	4/21/10	JDK	CHG DWG # WAS 300A-30H	128575	JJJ
A	3/18/10	JDK	IMPLEMENTATION FILING	128575	JJJ

REVISIONS

RUBY PIPELINE LLC

CONSTRUCTION RIGHT OF WAY PLAN
RUBY PIPELINE LN 300A-42 INCH IN THE EAST FORK LITTLE BEAR RIVER AREA

Division: ROCKY MOUNTAIN		Op. Area: ELKO	
State: UTAH		Co./Par.: CACHE	
Section: 13/18	Township: 9N	Range: 1E/2E	
Drafter: JDK	Date: 07/16/09	Project ID: 128575	Type: C3D
Chk'd:	Date:	Scale: AS SHOWN	
Appr:	Date:	Filename: 0300-A-0039Y	

300A-39Y
Sheet: 1 of 1 Rev: 0

IMPLEMENTATION PLAN 05/24/2010