



## APPENDIX D

### BEST MANAGEMENT PRACTICES AND MITIGATION MEASURES

*This Page Intentionally Left Blank*

# **APPENDIX D**

## **BEST MANAGEMENT PRACTICES AND MITIGATION MEASURES**

---

Best Management Practices (BMP) are state-of-the-art mitigation measures applied on a site-specific basis to avoid, minimize, reduce, rectify, or compensate for adverse environmental or social impacts. They are applied to management actions to aid in achieving desired outcomes for safe, environmentally responsible resource development, by preventing, minimizing, or mitigating adverse impacts and reducing conflicts.

This appendix provides a list of sample Best Management Practices that have been collected from various BLM and FS documents addressing geothermal and fluid mineral leasing and development, including resource management plans (RMPs), forest plans, and environmental reports for geothermal leasing and development. The purpose of this appendix is to provide a list of recommended BMPs that would be incorporated as appropriate into the permit application by the lessee or would be included in the approved use authorization by the BLM as conditions of approval. When implementing new BMPs, offices are encouraged to work with an affected lessee early in the process, to explain how BMPs may fit into their development proposals and how BMPs can be implemented with the least economic impact to the lessee. Offices should discuss potential resource impacts with the lessee and seek the operator's recommended solutions. The office should also encourage the lessee to incorporate necessary and effective BMPs into their project proposal. Best Management Practices not incorporated into the permit application by the lessee may be considered and evaluated through the environmental review process and incorporated into the use authorization as conditions of approval or rights-of-way stipulations.

All offices will incorporate appropriate environmental BMPs into proposed use authorizations after appropriate environmental review. Environmental BMPs to be considered in nearly all circumstances include the following:

- Interim reclamation of well locations and access roads soon after the well is put into production;
- Painting of all new facilities a color that best allows the facility to blend with the background, typically a vegetated background;
- Design and construction of all new roads to a safe and appropriate standard, “no higher than necessary” to accommodate their intended use; and
- Final reclamation recontouring of all disturbed areas, including access roads, to the original contour or a contour that blends with the surrounding topography.

Other environmental BMPs are more suitable for consideration by an administrative unit on a case-by-case basis, (1) depending on their effectiveness, (2) the balancing of increased operating costs vs. the benefit to the public and resource values, (3) the availability of less restrictive mitigation alternatives that accomplish the same objective, and (4) other site specific factors. Examples of typical, case-by-case BMPs are identified below.

Guidelines for applying and selecting project-specific requirements include determining whether the measure would (1) ensure compliance with relevant statutory or administrative requirements, (2) minimize local impacts associated with siting and design decisions, (3) promote post construction stabilization of impacts, (4) maximize restoration of previous habitat conditions, (5) minimize cumulative impacts, or (6) promote economically feasible development of geothermal energy on BLM-administered or FS-administered land.

The following typical BMPs provide the BLM, FS, industry, and stakeholders a menu of improved practices for developing geothermal energy and minimize impacts to the biophysical and cultural landscape. The list is extensive but is not meant to be all inclusive given the constant development of improved practices, diversity of the western states, and potential for unique site-specific conditions. Local land use plans may contain other BMPs that better address such unique situations. Where the BMPs presented here are inconsistent with or incompatible with those developed under a specific land use plan, the staff will conduct an environmental review to determine the appropriate practices.

Only those individual mitigation measures reasonably necessary to ensure environmentally responsible geothermal development should be selected from the list below. Not all of the individual mitigation measures below will apply in most situations and selection of appropriated BMPs and mitigation measures should be dependent on factors such as the project size, location, site specific

characteristics, and potential resource impacts. Prior to inclusion into a permit, the measures may be further modified to meet site-specific situations and agency requirements.

A menu of typical BMPs can also be found on the BLM Washington Office Fluid Minerals web site at: [www.blm.gov/bmp](http://www.blm.gov/bmp)

**Note:** Commenters to the Draft EIS noted that the list of BMPs and mitigation measures appeared to be redundant, contradictory, confusing, and placed extensive emphasis on certain resources while deemphasizing others. The following list has been consolidated and updated to address those concerns. The BMPs and mitigation measures are arranged from Information Collection and Monitoring to Final Reclamation and have been further subcategorized. While many of the BMPs and mitigation measures will apply to all phases of geophysical exploration and development; to avoid duplication, the measures are listed only once.

## INFORMATION COLLECTION & MONITORING

### General

- Prior to geothermal exploration and development, a complete subsurface geotechnical investigation will be conducted to analyze the soil and geologic conditions. The investigation will evaluate and identify potential geologic hazards and would provide remedial grading recommendations, foundation and slab design criteria, and soil parameters for the design of geothermal power infrastructure.
- The operator will collect available information describing the environmental and socio-cultural conditions in the vicinity of the proposed project and will provide the information to the agency.
- A monitoring program will be developed by the operator to ensure that environmental conditions are monitored during the exploration and well drilling, testing, construction, and utilization and reclamation phases. The monitoring program requirements, including adaptive management strategies, will be established at the project level to ensure that potential adverse impacts of geothermal development are mitigated. The monitoring program will identify the monitoring requirements for each major environmental resource present at the site, establish metrics against which monitoring observations can be measured, identify potential mitigation measures, and establish protocols for incorporating monitoring observations and additional mitigation measures into ongoing activities. The operator will provide results of the monitoring program to the agency in an annual report.
- [Refer to the Reclamation section for reclamation-specific monitoring.]

- The operator will comply with the Secretary of Agriculture’s rules and regulations for all use and occupancy of the NFS lands prior to approval of an exploration plan by the Secretary of Interior and for uses of all existing improvements, such as forest development roads, within and outside the area permitted by the Secretary of Interior; and use and occupancy of the NFS lands not authorized by an exploration plan approved by the Secretary of Interior.

### **Paleontological and Cultural Resources**

- Before any specific permits are issued under leases, treatment of cultural resources will follow the procedures established by the Advisory Council on Historic Preservation for compliance with Section 106 of the National Historic Preservation Act. A pedestrian inventory will be undertaken of all portions that have not been previously surveyed or are identified by BLM as requiring inventory to identify properties that are eligible for the NRHP. Those sites not already evaluated for NRHP eligibility will be evaluated based on surface remains, subsurface testing, archival, and/or ethnographic sources. Subsurface testing will be kept to a minimum whenever possible if sufficient information is available to evaluate the site or if avoidance is an expected mitigation outcome. Recommendations regarding the eligibility of sites will be submitted to the BLM, and a treatment plan will be prepared to detail methods for avoidance of impacts or mitigation of effects. The BLM will make determinations of eligibility and effect and consult with SHPO as necessary based on each proposed lease application and project plans. The BLM may require modification to exploration or development proposals to protect such properties, or disapprove any activity that is likely to result in adverse effects that cannot be successfully avoided, minimized or mitigated. Avoidance of impacts through project design will be given priority over data recovery as the preferred mitigation measure. Avoidance measures include moving project elements away from site locations or to areas of previous impacts, restricting travel to existing roads, and maintaining barriers and signs in areas of cultural sensitivity. Any data recovery will be preceded by approval of a detailed research design, Native American Consultation, and other requirements for BLM issuance of a permit under the Archaeological Resources Protection Act (BLM 2007a).
- If cultural resources are present at the site, or if areas with a high potential to contain cultural material have been identified, a cultural resources management plan (CRMP) will be developed. This plan will address mitigation activities to be taken for cultural resources found at the site. Avoidance of the area is always the preferred mitigation option. Other mitigation options include archaeological

survey and excavation (as warranted) and monitoring. If an area exhibits a high potential, but no artifacts were observed during an archaeological survey, monitoring by a qualified archaeologist could be required during all excavation and earthmoving in the high-potential area. A report will be prepared documenting these activities. The CRMP also will (1) establish a monitoring program, (2) identify measures to prevent potential looting/vandalism or erosion impacts, and (3) address the education of workers and the public to make them aware of the consequences of unauthorized collection of artifacts and destruction of property on public land (BLM 2005).

- Operators will determine whether paleontological resources exist in a project area on the basis of the sedimentary context of the area, a records search for past paleontological finds in the area, and/or, depending on the extent of existing information, a paleontological survey.
- If paleontological resources are present at the site, or if areas with a high potential to contain paleontological material have been identified, a paleontological resources management plan will be developed. This plan will include a mitigation plan for avoidance, removal of fossils, or monitoring. If an area exhibits a high potential but no fossils were observed during survey, monitoring by a qualified paleontologist may be required during excavation and earthmoving in the sensitive area. The operator will submit a report to the agency documenting these activities. The paleontological resources management plan also will (1) establish a monitoring program, (2) identify measures to prevent potential looting/vandalism or erosion impacts, and (3) address the education of workers and the public to make them aware of the consequences of unauthorized collection of fossils on public land.

### **Water Resources**

- Operators will develop a storm water management plan for the site to ensure compliance with applicable regulations and prevent off-site migration of contaminated storm water or increased soil erosion.
- Operators will gain a clear understanding of the local hydrogeology. Areas of groundwater discharge and recharge and their potential relationships with surface water bodies will be identified.
- Operators will avoid creating hydrologic conduits between two aquifers during foundation excavation and other activities.

### **Vegetation and Fish and Wildlife**

- The operator will conduct surveys for plant and animal species that are listed or proposed for listing as threatened or endangered and their habitats in areas proposed for development where these species could potentially occur, following accepted protocols and in consultation with the USFWS or NMFS, as appropriate. Particular care should be taken to avoid disturbing listed species during surveys in any designated critical habitat. The operator will monitor activities and their effects on ESA-listed species throughout the duration of the project.
- The operator will identify important, sensitive, or unique habitat and biota in the project vicinity and site and should design the project to avoid (if possible), minimize, or mitigate potential impacts on these resources. The design and siting of the facilities will follow appropriate guidance and requirements from the BLM, FS, and other resource agencies, as available and applicable.

### **National Scenic and Historic Trails**

- When any ROW application includes remnants of a National Historic Trail, is located within the viewshed of a National Historic Trail's designated centerline, or includes or is within the viewshed of a trail eligible for listing on the NRHP, the operator will evaluate the potential visual impacts to the trail associated with the proposed project and identify appropriate mitigation measures for inclusion in the operation plan.

### **Air Quality and Climate**

- The operator will coordinate with the [State Air Quality Division] to develop and implement an air quality monitoring plan.

## **PLANNING, LOCATION, AND DESIGN**

### **Traffic Planning**

- Operators will consult with local planning authorities regarding increased traffic prior to the construction phase, including an assessment of the number of vehicles per day, their size, and type. Specific issues of concern (e.g., location of school bus routes and stops) will be identified and addressed in the traffic management plan.

### **Roads & Pads**

- To plan for efficient use of the land, necessary infrastructure will be consolidated wherever possible.
- Existing roads and pad sites will be used to the maximum extent feasible, but only if located in a safe and environmentally sound location. No new roads and pad sites will be constructed without

agency authorization. If new roads and pad sites have been authorized, they will be designed and constructed by the operator to the appropriate agency standard, no higher than necessary to accommodate their intended function. Roads and pad sites will be routinely maintained by the operator maintain public safety and to minimize impacts to the environment such as erosion, sedimentation, fugitive dust, loss of vegetation.

- An access road siting and management plan will be prepared incorporating existing Agency standards regarding road design, construction, and maintenance such as those described in the BLM 9113 Manual and the *Surface Operating Standards for Oil and Gas Exploration and Development* (i.e., the Gold Book, 4<sup>th</sup> Edition, 2007).
- A traffic management plan will be prepared for the site access roads to ensure that no hazards would result from the increased truck traffic and that traffic flow would not be adversely impacted. This plan will incorporate measures such as informational signs, flaggers when equipment may result in blocked throughways, and traffic cones to identify any necessary changes in temporary lane configuration.
- Where possible, access roads will be located to follow natural contours and minimize side hill cuts and fills. Excessive grades on roads, road embankments, ditches, and drainages shall be avoided, especially in areas with erodible soils.
- Roads will be designed so that changes to surface water runoff are minimized and new erosion is not initiated.
- Access roads will be located to minimize stream crossings. All structures crossing streams will be located and constructed so that they do not decrease channel stability or increase water velocity. Operators will obtain all applicable federal and state water crossing permits.
- Roads will be located away from drainage bottoms and avoid wetlands, if practicable.

### **Geotechnical Analysis**

- The operator will perform a detailed geotechnical analysis prior to the construction of any structures; so they will be sited to avoid any hazards from subsidence or liquefaction (i.e., the changing of a saturated soil from a relatively stable solid state to a liquid during earthquakes or nearby blasting).

### **Visual Mitigation**

- The operator will incorporate visual design considerations into the planning and design of the project to minimize potential visual

impacts of the proposal and to meet the VRM objectives of the area and the agency.

### **Visual Design Considerations**

- Construct low-profile structures whenever possible to reduce structure visibility.
- Select and design materials and surface treatments to repeat or blend with landscape elements.
- Site projects outside of the viewsheds of publically accessible vantage points, or if this cannot be avoided, as far away as possible;
- Site projects to take advantage of both topography and vegetation as screening devices to restrict views of projects from visually sensitive areas;
- Site facilities away from and not adjacent to prominent landscape features (e.g., knobs and water features);
- Avoid placing facilities on ridgelines, summits, or other locations such that they will be silhouetted against the sky from important viewing locations;
- Collocate facilities to the extent possible to use existing and shared rights-of-way, existing and shared access and maintenance roads, and other infrastructure to reduce visual they do not bisect ridge tops or run down the center of valley bottoms.
- Site linear features (aboveground pipelines, rights-of-way, and roads) to follow natural land contours rather than straight lines (particularly up slopes) when possible. Fall-line cuts should be avoided.
- Site facilities, especially linear facilities, to take advantage of natural topographic breaks (i.e., pronounced changes in slope) to avoid siting facilities on steep side slopes.
- Where available, site linear features such as rights-of-ways and roads to follow the edges of clearings (where they will be less conspicuous) rather than passing through the centers of clearings.
- Site facilities to take advantage of existing clearings to reduce vegetation clearing and ground disturbance, where possible.
- Site linear features (e.g., trails, roads, rivers) to cross other linear features at right angles whenever possible to minimize viewing area and duration.
- Site and design structures and roads to minimize and balance cuts and fills and to preserve existing rocks, vegetation, and drainage patterns to the maximum extent possible.

- Use appropriately colored materials for structures or appropriate stains and coatings to blend with the project's backdrop. Refer to the Standard Environmental Colors chart available from the BLM.
- Use non-reflective or low-reflectivity materials, coatings, or paints whenever possible.
- Paint grouped structures the same color to reduce visual complexity and color contrast.
- Design and install efficient facility lighting so that the minimum amount of lighting required for safety and security is provided but not exceeded and so that upward light scattering (light pollution) is minimized. This may include, for example, installing shrouds to minimize light from straying off-site, properly directing light to only illuminate necessary areas, and installing motion sensors to only illuminate areas when necessary.
- Site construction staging areas and laydown areas outside of the viewsheds of publically accessible vantage points and visually sensitive areas, where possible, including siting in swales, around bends, and behind ridges and vegetative screens.
- Discuss visual impact mitigation objectives and activities with equipment operators prior to commencement of construction activities.
- Mulch or scatter slash from vegetation removal and spread it to cover fresh soil disturbances or, if not possible, bury or compost slash.
- If slash piles are necessary, stage them out of sight of sensitive viewing areas.
- Avoid installing gravel and pavement where possible to reduce color and texture contrasts with existing landscape.
- Use excess fill to fill uphill-side swales resulting from road construction in order to reduce unnatural-appearing slope interruption and to reduce fill piles.
- Avoid downslope wasting of excess fill material.
- Round road-cut slopes, vary cut and fill pitch to reduce contrasts in form and line, and vary slope to preserve specimen trees and nonhazardous rock outcroppings.
- Leave planting pockets on slopes where feasible.
- Combine methods of re-establishing native vegetation through seeding, planting of nursery stock, transplanting of local vegetation within the proposed disturbance areas and staging of construction enabling direct transplanting.

- Revegetate with native vegetation establishing a composition consistent with the form, line, color, and texture of the surrounding undisturbed landscape.”
- Provide benches in rock cuts to accent natural strata.
- Use split-face rock blasting to minimize unnatural form and texture resulting from blasting.
- Segregate topsoil from cut and fill activities and spread it on freshly disturbed areas to reduce color contrast and to aid rapid revegetation.
- Bury utility cables in or adjacent to the road where feasible.
- Minimize signage and paint or coat reverse sides of signs and mounts to reduce color contrast with existing landscape.
- Prohibit trash burning; store trash in containers to be hauled off-site for disposal.
- Undertake interim restoration during the operating life of the project as soon as possible after disturbances. During road maintenance activities, avoid blading existing forbs and grasses in ditches and along roads.
- Randomly scarify cut slopes to reduce texture contrast with existing landscape and to aid in revegetation.
- Cover disturbed areas with stockpiled topsoil or mulch, and revegetate with a mix of native species selected for visual compatibility with existing vegetation.
- Restore rocks, brush, and natural debris whenever possible to approximate preexisting visual conditions.

### **Air Quality and Climate**

- The operator will prepare and submit to the agency an Equipment Emissions Mitigation Plan for managing diesel exhaust. An Equipment Emissions Mitigation Plan will identify actions to reduce diesel particulate, carbon monoxide, hydrocarbons, and nitrogen oxides associated with construction and drilling activities. The Equipment Emissions Mitigation Plan will require that all drilling/construction-related engines are maintained and operated as follows:
  - Are tuned to the engine manufacturer’s specification in accordance with an appropriate time frame.
  - Do not idle for more than five minutes (unless, in the case of certain drilling engines, it is necessary for the operating scope).

- Are not tampered with in order to increase engine horsepower.
- Include particulate traps, oxidation catalysts, and other suitable control devices on all drilling/construction equipment used at the project site.
- Use diesel fuel having a sulfur content of 15 parts per million or less, or other suitable alternative diesel fuel, unless such fuel cannot be reasonably procured in the market area.
- Include control devices to reduce air emissions. The determination of which equipment is suitable for control devices should be made by an independent Licensed Mechanical Engineer. Equipment suitable for control devices may include drilling equipment, work over and service rigs, mud pumps, generators, compressors, graders, bulldozers, and dump trucks.

#### **Health and Safety**

- Operators will develop a hazardous materials management plan addressing storage, use, transportation, and disposal of each hazardous material anticipated to be used at the site. The plan will identify all hazardous materials that would be used, stored, or transported at the site. It will establish inspection procedures, storage requirements, storage quantity limits, inventory control, nonhazardous product substitutes, and disposition of excess materials. The plan will also identify requirements for notices to federal and local emergency response authorities and include emergency response plans.
- Operators will develop a waste management plan identifying the waste streams that are expected to be generated at the site and addressing hazardous waste determination procedures, waste storage locations, waste-specific management and disposal requirements, inspection procedures, and waste minimization procedures. This plan will address all solid and liquid wastes that may be generated at the site.
- Operators will develop a spill prevention and response plan identifying where hazardous materials and wastes are stored on site, spill prevention measures to be implemented, training requirements, appropriate spill response actions for each material or waste, the locations of spill response kits on site, a procedure for ensuring that the spill response kits are adequately stocked at all times, and procedures for making timely notifications to authorities.

- A safety assessment will be conducted to describe potential safety issues and the means that would be taken to mitigate them, including issues such as site access, construction, safe work practices, security, heavy equipment transportation, traffic management, emergency procedures, and fire control.
- A health and safety program will be developed to protect both workers and the general public during construction and operation of geothermal projects.
- Regarding occupational health and safety, the program will identify all applicable federal and state occupational safety standards; establish safe work practices for each task (e.g., requirements for personal protective equipment and safety harnesses; Occupational Safety and Health Administration [OSHA] standard practices for safe use of explosives and blasting agents; and measures for reducing occupational electric and magnetic fields [EMF] exposures); establish fire safety evacuation procedures; and define safety performance standards (e.g., electrical system standards and lightning protection standards). The program will include a training program to identify hazard training requirements for workers for each task and establish procedures for providing required training to all workers. Documentation of training and a mechanism for reporting serious accidents to appropriate agencies will be established.
- Regarding public health and safety, the health and safety program will establish a safety zone or setback for generators from residences and occupied buildings, roads, ROWs, and other public access areas that is sufficient to prevent accidents resulting from the operation of generators. It will identify requirements for temporary fencing around staging areas, storage yards, and excavations during construction or rehabilitation activities. It will also identify measures to be taken during the operation phase to limit public access to hazardous facilities (e.g., permanent fencing would be installed only around electrical substations, and facility access doors would be locked).
- Operators will consult with local planning authorities regarding increased traffic during the construction phase, including an assessment of the number of vehicles per day, their size, and type. Specific issues of concern (e.g., location of school bus routes and stops) will be identified and addressed in the traffic management plan.
- Operators will develop a fire management strategy to implement measures to minimize the potential for a human-caused fire.

### **Livestock Grazing**

- The operator will coordinate with livestock operators to minimize impacts to livestock operations.

### **Noxious Weeds and Pesticides**

- Operators will develop a plan for control of noxious weeds and invasive species, which could occur as a result of new surface disturbance activities at the site. The most recent recommendations at the state and local level should be incorporated into any operating plan for the geothermal exploration and development. The plan will address monitoring, education of personnel on weed identification, the manner in which weeds spread, and methods for treating infestations. The use of certified weed-free mulching will be required. If trucks and construction equipment are arriving from locations with known invasive vegetation problems, a controlled inspection and cleaning area will be established to visually inspect construction equipment arriving at the project area and to remove and collect seeds that may be adhering to tires and other equipment surfaces.
- If pesticides are used on the site, an integrated pest management plan will be developed to ensure that applications would be conducted within the framework of all Federal, State, and local laws and regulations and entail only the use of EPA-registered pesticides.

### **Vegetation and Fish and Wildlife**

- The operator shall prepare a habitat restoration plan to avoid (if possible), minimize, or mitigate negative impacts on vulnerable wildlife while maintaining or enhancing habitat values for other species. The plan will identify revegetation, soil stabilization, and erosion reduction measures that will be implemented to ensure that all temporary use areas are restored. The plan will require that restoration occur as soon as possible after completion of activities to reduce the amount of habitat converted at any one time and to speed up the recovery to natural habitats.

## **CONSTRUCTION**

### **Traffic Management**

- Traffic will be restricted to the roads developed for the project. Use of other unimproved roads will be restricted to emergency situations.
- Signs will be placed along roads to identify speed limits, travel restrictions, and other standard traffic control information. Signs directing vehicles to alternative park access and parking will be posted in the event construction temporarily obstructs recreational

parking areas near trailheads. Whenever active work is being performed, the area will be posted with “construction ahead” signs on any adjacent access roads or trails that might be affected.

- Project personnel and contractors will be instructed and required to adhere to speed limits commensurate with road types, traffic volumes, vehicle types, and site-specific conditions, to ensure safe and efficient traffic flow and to reduce wildlife collisions and disturbance and fugitive dust.
- When practical, construction activities will be avoided during high recreational use periods.

### **Roads & Pads**

- The operator will obtain agency authorization prior to borrowing soil or rock material from agency lands.
- Road use will be restricted during the wet season if road surfacing is not adequate to prevent soil displacement, rutting, etc., and resultant stream sedimentation.
- Access roads and on-site roads will be surfaced with aggregate materials where necessary to provide a stable road surface, support anticipated traffic, reduce fugitive dust, and prevent erosion,
- Dust abatement techniques will be used before and during surface clearing, excavation, or blasting activities. Dust abatement techniques will be used on unpaved, unvegetated surfaces to minimize fugitive dust. Speed limits (e.g., 25 mph [40 kph]) will be posted and enforced to reduce fugitive dust. Construction materials and stockpiled soils will be covered if they are a source of fugitive dust.
- Culvert outlets will be rip-rapped to dissipate water energy at the outlet and reduce erosion. Catch basins, roadway ditches, and culverts will be cleaned and maintained regularly.

### **Pipelines**

- Pipelines constructed above ground due to thermal gradient induced expansion and contraction will rest on cradles above ground level, allowing small animals to pass underneath. Projects should be analyzed to ensure adequate passage for all wildlife species. The pipeline will be raised higher to allow wildlife passage where needed. Because pipeline corridors through certain habitat types can alter local predator-prey dynamics by providing predators with lines of sight and travel corridors, large projects should be analyzed to ensure there will be no significant changes to predator-prey balance.

### **Utilities**

- Underground utilities will be installed to minimize the amount of open trenches at any given time, keeping trenching and backfilling crews close together. Avoid leaving trenches open overnight. Where trenches cannot be back-filled immediately, escape ramps should be constructed at least every 100 feet.

## **SPECIFIC RESOURCES**

### **Cultural and Paleontological Resources**

- Unexpected discovery of cultural or paleontological resources during construction will be brought to the attention of the responsible BLM authorized officer immediately. Work will be halted in the vicinity of the find to avoid further disturbance to the resources while they are being evaluated and appropriate mitigation measures are being developed.

### **Noise**

- The operator will take measurements to assess the existing background noise levels at a given site and compare them with the anticipated noise levels associated with the proposed project.
- Within [2] miles of existing, occupied residences, geothermal well drilling or major facility construction operations will be restricted to non-sleeping hours (7:00 am to 10:00 pm).
- All equipment will have sound-control devices no less effective than those provided on the original equipment. All construction equipment used will be adequately muffled and maintained.
- All stationary construction equipment (i.e., compressors and generators) will be located as far as practicable from nearby residences.
- If blasting or other noisy activities are required during the construction period, nearby residents will be notified by the operator at least 1 hour in advance.
- Explosives will be used only within specified times and at specified distances from sensitive wildlife or streams and lakes, as established by the federal and state agencies.

### **Noxious Weeds and Pesticides**

- The use of certified, weed-free mulch will be required when stabilizing areas of disturbed soil.
- If trucks and construction equipment are arriving from locations with known invasive vegetation problems, a controlled inspection and cleaning area will be established to visually inspect construction

equipment arriving at the project area and to remove and collect seeds that may be adhering to tires and other equipment surfaces.

- Fill materials and road surfacing materials that originate from areas with known invasive vegetation problems will not be used.
- Revegetation, habitat restoration and weed control activities will be initiated as soon as possible after construction activities are completed.
- Use of pesticides must be approved by the agency. Pesticide use will be limited agency approved pesticides and will only be applied in accordance with label and application permit directions and stipulations for terrestrial and aquatic applications.

### **Waste Management**

- All refueling will occur in a designated fueling area that includes a temporary berm to limit the spread of any spill.
- Drip pans will be used during refueling to contain accidental releases.
- Drip pans will be used under fuel pump and valve mechanisms of any bulk fueling vehicles parked at the construction site.
- Any containers used to collect liquids will be enclosed or screened to prevent access to contaminants by wildlife, livestock, and migratory birds.
- Spills will be immediately addressed per the spill management plan, and soil cleanup and removal initiated as soon as feasible.

### **Wild Horses and Burros**

- The operator will ensure employees, contractors, and site visitors avoid harassment and disturbance of wild horses and burros, especially during reproductive (e.g., breeding and birthing) seasons. In addition, any pets will be controlled to avoid harassment and disturbance of wild horses and burros.
- Observations of potential problems regarding wild horses or burros, including animal mortality, will be immediately reported to the agency.

### **Wildlife**

- The operator will ensure that employees, contractors, and site visitors avoid harassment and disturbance of wildlife, especially during reproductive (e.g., courtship and nesting) seasons. In addition, pets will be controlled or excluded to avoid harassment and disturbance of wildlife.

- Ponds, tanks and impoundments (including but not limited to drill pits) containing liquids can present hazards to wildlife. Any liquids contaminated by substances which may be harmful due to toxicity, or fouling of the fur or feathers (detergents, oils), should be excluded from wildlife access by fencing, netting or covering at all times when not in active use. Liquids at excessive temperature should likewise be excluded. If exclusion is not feasible, such as a large pond, a hazing program based on radar or visual detection, in conjunction with formal monitoring, should be implemented. Clean water impoundments can also present a trapping hazard if they are steep-sided or lined with smooth material. All pits, ponds and tanks should have escape ramps functional at any reasonably anticipated water level, down to almost empty. Escape ramps can take various forms depending on the configuration of the impoundment. Earthen pits may be constructed with one side sloped 3:1 or greater lined ponds can use textured material; straight-sided tanks can be fitted with expanded metal escape ladders.

#### **OPERATIONS/UTILIZATION**

- “Good housekeeping” procedures will be developed by the operator to ensure that during all phases of exploration and operation the site will be kept clean of noxious weeds, debris, litter, garbage, fugitive trash or waste, and graffiti. Scrap heaps and dumps are prohibited. Storage yards are to be minimized to that which is absolutely necessary.

#### **RECLAMATION**

The following objectives, performance standards, and recommended reclamation BMPs and mitigation measures are based on the standards and guidelines found in the BLM and Forest Service Gold Book, 4<sup>th</sup> Edition, updated in 2007.

[ ] Indicates site-specific values to be filled in by the authorized officer.

##### **Reclamation Objectives**

- The objective of interim reclamation is to restore vegetative cover and a portion of the landform sufficient to maintain healthy, biologically active topsoil; control erosion; and minimize habitat, visual, and forage loss during the life of the well or facilities.
- The long-term objective of final reclamation is to return the land to a condition approximating that which existed prior to disturbance. This includes restoration of the landform and natural vegetative community, hydrologic systems, visual resources, and wildlife habitats. To ensure that the long-term objective will be reached through human and natural processes, actions will be taken to

ensure standards are met for site stability, visual quality, hydrological functioning, and vegetative productivity.

### **Reclamation Performance Standards**

The following reclamation performance standards will be met:

**Interim Reclamation** – Includes disturbed areas that may be redisturbed during operations and will be redisturbed at final reclamation to achieve restoration of the original landform and a natural vegetative community.

- Will be judged successful when the BLM authorized officer determines that...
- Disturbed areas not needed for active, long-term production operations or vehicle travel have been recontoured, protected from erosion, and revegetated with a self-sustaining, vigorous, diverse, native (or as otherwise approved) plant community sufficient to minimize visual impacts, provide forage, stabilize soils, and impede the invasion of noxious, invasive, and non-native weeds.

**Final Reclamation** – Includes disturbed areas where the original landform and a natural vegetative community have been restored.

- Will be judged successful when the authorized officer determines that...
- The original landform has been restored for all disturbed areas including well pads, production facilities, roads, pipelines, and utility corridors.
- General: A self-sustaining, vigorous, diverse, native (or otherwise approved) plant community is established on the site, with a density sufficient to control erosion and invasion by non-native plants and to reestablish wildlife habitat or forage production. At a minimum, the established plant community will consist of species included in the seed mix and/or desirable species occurring in the surrounding natural vegetation.
- Specific: No single species will account for more than [30]% total vegetative composition unless it is evident at higher levels in the adjacent landscape. Permanent vegetative cover will be determined successful when the basal cover of desirable perennial species is at least [80]% of the basal cover on adjacent or nearby undisturbed areas where vegetation is in a healthy condition; or [80]% of the potential basal cover as defined in the National Resource Conservation Service Ecological Site(s) for the area. Plants must be resilient as evidenced by well-developed root systems and flowers. [Shrubs, will be well established and in a “young” age class at a

minimum (therefore, not comprised mainly of seedlings that may not survive until the following year).]

- In agricultural areas, irrigation systems and soil conditions are reestablished in such a way as to ensure successful cultivation and harvesting of crops.
- Erosion features are equal to or less than surrounding area and erosion control is sufficient so that water naturally infiltrates into the soil and gullying, headcutting, slumping, and deep or excessive rills (greater than 3 inches) are not observed.
- The site is free of State- or county-listed noxious weeds, oil field debris and equipment, and contaminated soil. Invasive and non-native weeds are controlled.

### **Reclamation Actions**

- During initial well pad, production facility, road, pipeline, and utility corridor construction and prior to completion of the final well on the well pad, pre-interim reclamation stormwater management actions will be taken to ensure disturbed areas are quickly stabilized to control surface water flow and to protect both the disturbed and adjacent areas from erosion and siltation. This may involve construction and maintenance of temporary silt ponds, silt fences, berms, ditches, and mulching.
- When the last well on the pad has been completed, some portions of the well location will undergo interim reclamation and some portions of the well pad will usually undergo final reclamation. Most well locations will have limited areas of bare ground, such as a small area around production facilities or the surface of a rocked road. Other areas will have interim reclamation where workover rigs and fracturing tanks may need a level area to set up in the future. Some areas will undergo final reclamation where portions of the well pad will no longer be needed for production operations and can be recontoured to restore the original landform.
- The following minimum reclamation actions will be taken to ensure that the reclamation objectives and standards are met. It may be necessary to take additional reclamation actions beyond the minimum in order to achieve the Reclamation Standards.

### **Reclamation - General**

#### **Procedure:**

- The agency will be notified 24 hours prior to commencement of any reclamation operations.

**Housekeeping:**

- Immediately upon well completion, the well location and surrounding areas(s) will be cleared of, and maintained free of, all debris, materials, trash, and equipment not required for production.
- No hazardous substances, trash, or litter will be buried or placed in pits. Upon well completion, any hydrocarbons in the pit will be remediated or removed.

**Vegetation Clearing:**

- Vegetation removal and the degree of surface disturbance will be minimized wherever possible.
- *[Example of site-specific requirement:* During vegetation clearing activities, trees and woody vegetation removed from the well pad and access road will be moved aside prior to any soil disturbing activities. Care will be taken to avoid mixing soil with the trees and woody vegetation. Trees left for wood gathering will be cut [twelve inches or less from the ground], delimbed, and the trunks, six (6) inches or more in diameter will be removed and placed either by the uphill side of the access road, or moved to the end of the road, or to a road junction for easy access for wood gatherers and to reduce vehicle traffic on the well pad. Trees with a trunk diameter less than six (6) inches and woody vegetation will be used to trap sediment, slow runoff, or scattered on reclaimed areas to stabilize slopes, control erosion, and improve visual resources.]

**Topsoil Management:**

- Operations will disturb the minimum amount of surface area necessary to conduct safe and efficient operations. When possible, equipment will be stored and operated on top of vegetated ground to minimize surface disturbance.
- In areas to be heavily disturbed, the top [eight (8)] inches of soil material, will be stripped and stockpiled around the perimeter of the well location to control run-on and run-off, and to make redistribution of topsoil more efficient during interim reclamation. Stockpiled topsoil may include vegetative material. Topsoil will be clearly segregated and stored separately from subsoils.
- Earthwork for interim and final reclamation will be completed within 6 months of well completion or plugging unless a delay is approved in writing by the BLM authorized officer.
- Salvaging and spreading topsoil will not be performed when the ground or topsoil is frozen or too wet to adequately support construction equipment. If such equipment creates ruts in excess of four (4) inches deep, the soil will be deemed too wet.

- No major depressions will be left that would trap water and cause ponding.

**Seeding:**

- Seedbed Preparation. Initial seedbed preparation will consist of recontouring to the appropriate interim or final reclamation standard. All compacted areas to be seeded will be ripped to a minimum depth of 18 inches with a minimum furrow spacing of 2 feet, followed by recontouring the surface and then evenly spreading the stockpiled topsoil. Prior to seeding, the seedbed will be scarified and left with a rough surface.
- If broadcast seeding is to be used and is delayed, final seedbed preparation will consist of contour cultivating to a depth of 4 to 6 inches within 24 hours prior to seeding, dozer tracking, or other imprinting in order to loosen up the soil and create seed germination micro-sites.
- Seed Application. Seeding will be conducted no more than 24 hours following completion of final seedbed preparation. A certified weed-free seed mix designed by BLM (shown below) to meet reclamation standards will be used. The following seed mix and rates will be used on all disturbed surfaces, including pipelines and road cut & fill slopes:

Species of Seed	Cultivar	App. Rate PLS (lbs/ac)
		Total:

- The application rate shown in the table is based on [45] pure live seeds (PLS) per square foot, drill-seeded to a depth of 0.25 to 0.5 inch, which is the method that will be used where feasible. [However, shrub species will be seeded during the winter on the ground surface or preferably on top of snow.] In areas that will not be drill-seeded, the seed mix will be broadcast-seeded at twice the application rate shown in the table and covered no more than

0.25 inch deep with a harrow, drag bar, or roller or will be broadcast-seeded into imprints, such as fresh dozer cleat marks.

- No seeding will occur from [May 15 to September 15]. Fall seeding is preferred and will be conducted after [September 15] and prior to ground freezing. [Shrub species will be seeded separately and will be seeded during the winter.] Spring seeding will be conducted after the frost leaves the ground and no later than [May 15].

***Erosion Control and Mulching:***

- Mulch, silt fencing, waddles, hay bales, and other erosion control devices will be used on areas at risk of soil movement from wind and water erosion.
- Mulch will be used if necessary to control erosion, create vegetation micro-sites, and retain soil moisture and may include hay, small-grain straw, wood fiber, live mulch, cotton, jute, or synthetic netting. Mulch will be free from mold, fungi, and certified free of noxious or invasive weed seeds.
- If straw mulch is used, it will contain fibers long enough to facilitate crimping and provide the greatest cover.

***Pit Closure:***

- Reserve pits will be closed and backfilled within **sixty (60)** days of release of the rig. All reserve pits remaining open after **sixty (60)** days will require written authorization of the authorized officer. Immediately upon well completion, any hydrocarbons or trash in the pit will be removed. Pits will be allowed to dry, be pumped dry, or solidified in-situ prior to backfilling.
- Following completion activities, pit liners will be completely removed or removed down to the solids level and disposed of at an approved landfill, or treated to prevent their reemergence to the surface and interference with long-term successful revegetation. If it was necessary to line the pit with a synthetic liner, the pit will not be trenched (cut) or filled (squeezed) while containing fluids. When dry, the pit will be backfilled with a minimum of 5 feet of soil material. In relatively flat areas the pit area will be slightly mounded above the surrounding grade to allow for settling and to promote surface drainage away from the backfilled pit.

***Management of Invasive, Noxious, and Non-Native Species:***

- All reclamation equipment will be cleaned prior to use to reduce the potential for introduction of noxious weeds or other undesirable non-native species.
- An intensive weed monitoring and control program will be implemented prior to site preparation for planting and will continue

until interim or final reclamation is approved by the authorized officer.

- Monitoring will be conducted at least annually during the growing season to determine the presence of any invasive, noxious, and non-native species. Invasive, noxious, and non-native species that have been identified during monitoring will be promptly treated and controlled. A Pesticide Use Proposal (PUP) will be submitted to the BLM for approval prior to the use of herbicides.

### **Interim Reclamation Procedures - Additional**

#### **Recontouring:**

- Interim reclamation actions will be completed no later than 6 months from when the final well on the location has been completed, weather permitting. The portions of the cleared well site not needed for active operational and safety purposes will be recontoured to the original contour if feasible, or if not feasible, to an interim contour that blends with the surrounding topography as much as possible. Sufficient semi-level area will remain for setup of a workover rig and to park equipment. In some cases, rig anchors may need to be pulled and reset after recontouring to allow for maximum interim reclamation.
- If the well is a producer, the interim cut and fill slopes prior to re-seeding will not be steeper than a 3:1 ratio, unless the adjacent native topography is steeper. Note: Constructed slopes may be much steeper during drilling, but will be recontoured to the above ratios during interim reclamation.
- Roads and well production equipment will be placed on location so as to permit maximum interim reclamation of disturbed areas. If equipment is found to interfere with the proper interim reclamation of disturbed areas, the equipment will be moved so proper recontouring and revegetation can occur.

#### **Application of Topsoil & Revegetation:**

- Topsoil will be evenly respread and aggressively revegetated over the entire disturbed area not needed for all-weather operations including road cuts & fills and to within a few feet of the production facilities, unless an all-weather, surfaced, access route or small “teardrop” turnaround is needed on the well pad.
- In order to inspect and operate the well or complete workover operations, it may be necessary to drive, park, and operate equipment on restored, interim vegetation within the previously disturbed area. Damage to soils and interim vegetation will be repaired and reclaimed following use. To prevent soil compaction,

under some situations, such as the presence of moist, clay soils, the vegetation and topsoil will be removed prior to workover operations and restored and reclaimed following workover operations.

**Visual Resources Mitigation for Reclamation:**

- Trees, if present, and vegetation will be left along the edges of the pads whenever feasible to provide screening.
- To help mitigate the contrast of recontoured slopes, reclamation will include measures to feather cleared lines of vegetation and to save and redistribute cleared trees, debris, and rock over recontoured cut and fill slopes.
- To reduce the view of production facilities from visibility corridors and private residences, facilities will not be placed in visually exposed locations (such as ridgelines and hilltops).
- Production facilities will be clustered and placed away from cut slopes and fill slopes to allow the maximum recontouring of the cut and fill slopes.
- All long-term above ground structures will be painted [Covert Green] (from the “Standard Environmental Colors” chart) to blend with the natural color of the late summer landscape background.

**Final Reclamation Procedures – Additional**

- Final reclamation actions will be completed within 6 months of well plugging, weather permitting.
- All disturbed areas, including roads, pipelines, pads, production facilities, and interim reclaimed areas will be recontoured to the contour existing prior to initial construction or a contour that blends indistinguishably with the surrounding landscape. Resalvaged topsoil will be respread evenly over the entire disturbed site to ensure successful revegetation. To help mitigate the contrast of recontoured slopes, reclamation will include measures to feather cleared lines of vegetation and to save and redistribute cleared trees, woody debris, and large rocks over recontoured cut and fill slopes.
- Water breaks and terracing will only be installed when absolutely necessary to prevent erosion of fill material. Water breaks and terracing are not permanent features and will be removed and reseeded when the rest of the site is successfully revegetated and stabilized.
- If necessary to ensure timely revegetation, the pad will be fenced to BLM standards to exclude livestock grazing for the first two growing seasons or until seeded species become firmly established,

whichever comes later. Fencing will meet standards found on page 18 of the BLM/FS Gold Book, 4<sup>th</sup> Edition, or will be fenced with operational electric fencing.

- Final abandonment of pipelines and flowlines will involve flushing and properly disposing of any fluids in the lines. All surface lines and any lines that are buried close to the surface that may become exposed in the foreseeable future due to water or wind erosion, soil movement, or anticipated subsequent use, must be removed. Deeply buried lines may remain in place unless otherwise directed by the authorized officer.

#### **Reclamation Monitoring and Final Abandonment Approval**

- Reclaimed areas will be monitored annually. Actions will be taken to ensure that reclamation standards are met as quickly as reasonably practical.
- Reclamation monitoring will be documented in an annual reclamation report submitted to the authorized officer by [March 1]. The report will document compliance with all aspects of the reclamation objectives and standards, identify whether the reclamation objectives and standards are likely to be achieved in the near future without additional actions, and identify actions that have been or will be taken to meet the objectives and standards. The report will also include acreage figures for: Initial Disturbed Acres; Successful Interim Reclaimed Acres; Successful Final Reclaimed Acres. Annual reports will not be submitted for sites approved by the authorized officer in writing as having met interim or final reclamation standards. Monitoring and reporting continues annually until interim or final reclamation is approved. Any time 30% or more of a reclaimed area is redisturbed, monitoring will be reinitiated.
- The authorized officer will be informed when reclamation has been completed, appears to be successful, and the site is ready for final inspection.

*This page intentionally left blank.*