

UNITED STATES DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT
Buffalo Field Office
Buffalo, Wyoming

SURFACE USE
CONDITIONS OF APPROVAL

POD Name: Wild West Unit 3H

Operator: Baytex Energy USA Ltd.

List of Wells:

Well Name & Number	QTR	Sec.	T	R	Lease #
Wild West Unit #3H	SWSE	15	44N	69W	WYW176437X

I Site Specific Conditions of Approval
General

1. All changes made at the onsite will be followed. They have all been incorporated into the operator's plan of development.
2. All proposed access roads and pads where engineered construction will occur will be slope staked prior to construction

Surface Use

1. All permanent above-ground structures (e.g., production equipment, tanks, etc.) not subject to safety requirements will be painted to blend with the natural color of the landscape. The paint used will be a color which simulates "Standard Environmental Colors." The color selected for the Wild West Unit #3H well is Covert Green.
2. The culvert locations will be staked prior to construction. The culvert invert grade and finished road grade will be clearly indicated on the stakes. Culverts will be installed on natural ground, or on a designed flow line of a ditch. The minimum cover over culverts will be 12" or one-half the diameter whichever is greater. Drainage laterals in the form of culverts or water bars shall be placed according to the following spacing:

3. Grade	4. Drainage Spacing
2-4%	310 ft
5-8%	260 ft
9-12%	200 ft

5. All rills, gullies, and other surface defects shall be ripped to the full depth of erosion across the entire width of the roadway prior to final grading and surfacing.

6. The operator is responsible for having the licensed professional engineer certify that the actual construction of the road meets the design criteria and is constructed to Bureau standards.
7. Reserve pit will be closed as soon as possible, but no later than **1 year** from time of drilling/well completion, unless the BLM Authorized Officer gives an extension. Squeezing of pit fluids and cuttings is prohibited. Pits must be dry of fluids or they must be removed via vac-truck or other environmentally acceptable method prior to backfilling, re-contouring and replacement of topsoil. Mud and cuttings left in pit must be buried at least 3-feet below re-contoured grade. The operator will be responsible for re-contouring any subsidence areas that develop from closing a pit before it is sufficiently dry.
8. Adequate drainage control must be in place at all stages of construction and culverts installed as soon as feasible.
9. If a dry hole, all rehabilitation work, including seeding, will be initiated within **30 days** after plugging operations are completed (pending seasonal conditions).
10. Interim Reclamation of disturbed areas will adhere to the following guidance (as per the Wyoming Policy on Reclamation (IM WY-90-231):
 - B. The reclaimed area shall be stable and exhibit none of the following characteristics:
 1. Large rills or gullies.
 2. Perceptible soil movement or head cutting in drainages.
 3. Slope instability on, or adjacent to, the reclaimed area in question.
 - C. The soil surface must be stable and have adequate surface roughness to reduce runoff and capture rainfall and snow melt. Additional short-term measures, such as the application of mulch, shall be used to reduce surface soil movement.
 - D. Vegetation canopy cover (on unforested sites), production and species diversity (including shrubs) shall approximate the surrounding undisturbed area. The vegetation shall stabilize the site and support the planned post disturbance land use, provide for natural plant community succession and development, and be capable of renewing itself.
 - E. This shall be demonstrated by: Successful onsite establishment of species included in the planting mixture or other desirable species. Evidence of vegetation reproduction, either spreading by rhizomatous species or seed production.
 - F. The reclaimed landscape shall have characteristics that approximate the visual quality of the adjacent area with regard to location, scale, shape, color and orientation of major landscape features and meet the needs of the planned post disturbance land use.
11. All topsoil removed during construction activities will be respread for interim reclamation success.
12. No surface disturbing activity shall occur within ½ mile of all identified raptor nests from February 1 through July 31, annually, prior to a raptor nest occupancy survey for the current breeding season. This condition will be implemented on an annual basis for the duration of surface disturbing activities.
 - B. Surveys to document nest occupancy shall be conducted by a biologist following BLM protocol, between April 15 and June 30. All survey results shall be submitted in writing to a Buffalo BLM biologist and approved prior to surface disturbing activities. Surveys outside this window may not depict nesting activity. If a survey

identifies active raptor nests, a ½ mile timing buffer will be implemented. The timing buffer restricts surface disturbing activities within ½ mile of occupied raptor nests from February 1 to July 31.

- C. Nest productivity checks shall be completed for the first five years following project completion. The productivity checks shall be conducted no earlier than June 1 or later than June 30 and any evidence of nesting success or production shall be recorded. Survey results will be submitted to a Buffalo BLM biologist in writing no later than July 31 of each survey year. Nests to be checked are within a ½ mile or less of the proposed development. If an undocumented raptor nest is located during project construction or operation, the Buffalo Field Office (307-684-1100) shall be notified within 24 hours and timing limitations will be applied.
- D. Well metering, maintenance and other site visits within 0.5 miles of raptor nests shall be minimized as much as possible during the breeding season (February 1 – July 31), and restricted to between 0900 and 1500 hours.

13. If an undocumented raptor nest is located during project construction or operation, the Buffalo Field Office (307-684-1100) shall be notified within 24 hours.

14. The operator will drill seed on the contour to a depth of 0.5 inch, followed by cultipaction to compact the seedbed, preventing soil and seed losses. To maintain quality and purity, the current years tested, certified seed with a minimum germination rate of 80% and a minimum purity of 90% will be used. On BLM surface or in lieu of a different specific mix desired by the surface owner, use the following:

**10-14" Precipitation Zone
Shallow Loamy Ecological Site**

Seed Mix

Species		% in Mix	Lbs PLS*
<i>Thickspike Wheatgrass</i> (<i>Elymus lanceolatus</i> ssp. lanceolatus)		50	4.2
<i>Bluebunch wheatgrass</i> (<i>Pseudoroegneria spicata</i> ssp. Spicata)		35	6
<i>Prairie coneflower</i> (<i>Ratibida columnifera</i>)		5	0.6
<i>White or purple prairie clover</i> (<i>Dalea candidum</i> , <i>purpureum</i>)		5	0.6

<i>Rocky Mountain beeplant</i> (<i>Cleome serrulata</i>) /or <i>American vetch</i> (<i>Vicia americana</i>)		5	0.6
Totals		100%	12 lbs/acre

*PLS = pure live seed

*Northern Plains adapted species

*Double this rate if broadcast seeding

This is a recommended seed mix based on the native plant species listed in the NRCS Ecological Site descriptions, U.W. College of Ag., and seed market availability

Raptors

The following conditions will alleviate impacts to raptors:

1. No surface disturbing activity shall occur from February 1 through July 31, annually, prior to a raptor nest survey for the current breeding season.
2. Surveys to document nest occupancy shall be conducted by a biologist following BLM protocol, between April 15 and June 30. All survey results shall be submitted in writing to a Buffalo BLM biologist and approved prior to surface disturbing activities. Surveys outside this window may not depict nesting activity. If a survey identifies active raptor nests, a 0.5 mile timing buffer will be implemented. The timing buffer restricts surface disturbing activities within 0.5 mile of occupied raptor nests from February 1 to July 31.
3. If an undocumented raptor nest is located during project construction or operation, the Buffalo Field Office (307-684-1100) shall be notified within 24 hours.
4. Well metering, maintenance and other site visits within 0.5 miles of raptor nests should be minimized as much as possible during the breeding season (February 1 – July 31).

II Standard Conditions of Approval

A. General

1. If any cultural values [sites, artifacts, human remains (Appendix L FEIS)] are observed during operation of this lease/permit/right-of-way, they will be left intact and the Buffalo Field Manager notified. The authorized officer will conduct an evaluation of the cultural values to establish appropriate mitigation, salvage or treatment. The operator is responsible for informing all persons in the area who are associated with this project that they will be subject to prosecution for knowingly disturbing historic or archaeological sites, or for collecting artifacts. If historic or archaeological materials are uncovered during construction, the operator is to immediately stop work that might further disturb such materials, and contact the authorized BLM officer (AO). Within five working days the AO will inform the operator as to:
 - whether the materials appear eligible for the National Register of Historic Places;
 - the mitigation measures the operator will likely have to undertake before the site can be used (assuming in situ preservation is not necessary); and,
 - a time-frame for the AO to complete an expedited review under 36 CFR 800.11 to confirm, through the State Historic Preservation Officer, that the findings of the AO are

correct and that mitigation is appropriate. The AO will provide technical and procedural guidelines for the conduct of mitigation. Upon verification from the AO that the required mitigation has been completed, the operator will then be allowed to resume construction measures.

2. If paleontological resources, either large or conspicuous, and/or a significant scientific value are discovered during construction, the find will be reported to the Authorized Officer immediately. Construction will be suspended within 250 feet of said find. An evaluation of the paleontological discovery will be made by a BLM approved professional paleontologist within five (5) working days, weather permitting, to determine the appropriate action(s) to prevent the potential loss of any significant paleontological values. Operations within 250 feet of such a discovery will not be resumed until written authorization to proceed is issued by the Authorized Officer. The applicant will bear the cost of any required paleontological appraisals, surface collection of fossils, or salvage of any large conspicuous fossils of significant scientific interest discovered during the operation.
3. The operator shall restrict travel on unimproved two-track roads during periods of inclement weather or spring thaw when the possibility exists for excessive surface resource damage (e.g., rutting in excess of 4-inches, travel outside two-track roadway, etc.).
4. By November 1 each year, companies will provide georeferenced spatial data depicting as-built locations of all facilities, wells, roads, pipelines, power lines, reservoirs, discharge points, and other related facilities to the BLM.
5. If any dead or injured threatened, endangered, proposed, or candidate species is located during construction or operation, the U.S. Fish and Wildlife Service's Wyoming Field Office (307-772-2374), their law enforcement office (307-261-6365), and the BLM Buffalo Field Office (307-684-1100) shall be notified within 24 hours. If any dead or injured sensitive species is located during construction or operation, the BLM Buffalo Field Office (307-684-1100) shall be notified within 24 hours.
6. All other conservation measures and terms and conditions identified in the Powder River Basin Oil and Gas Project Biological Opinion (WY07F0075) shall be complied with.
7. All contractors will have a copy of the engineered pad and road designs, as well as conditions of approval with them at all times.

B. Construction

1. The operator will limit vegetation removal and the degree of surface disturbance wherever possible. Where surface disturbance cannot be avoided, all practicable measures will be utilized to minimize erosion and stabilize disturbed soils.
2. Construction and drilling activity will not be conducted using frozen or saturated soil material during periods when watershed damage or excessive rutting is likely to occur.
3. Remove all available topsoil (depths vary from 4 inches on ridges to 12+ inches in bottoms) from constructed well locations including areas of cut and fill, and stockpile at the site. Topsoil will also be salvaged for use in reclamation on all other areas of surface disturbance (roads, pipelines, etc.). Clearly segregate topsoil from excess spoil material. Any topsoil stockpiled for one year or longer will be signed and stabilized with annual ryegrass or other suitable cover crop.

4. The operator will not push soil material and overburden over side slopes or into drainages. All soil material disturbed will be placed in an area where it can be retrieved without creating additional undue surface disturbance and where it does not impede watershed and drainage flows.
5. Construct the backslope no steeper than 1½:1, and construct the foreslope no steeper than 2:1, unless otherwise directed by the BLM Authorized Officer.
6. Maintain a minimum 20-foot undisturbed vegetative border between toe-of-fill of pad and/or pit areas and the edge of adjacent drainages, unless otherwise directed by the BLM Authorized Officer.
7. With the overall objective of minimizing surface disturbance and retaining land stability and productivity, the operator shall utilize equipment that is appropriate to the scope and scale of work being done for roads and well pads (utilize equipment no larger than needed for the job).
8. To minimize electrocution potential to raptors, all overhead electrical power lines will be constructed to Avian Power Line Interaction Committee (1996) standards and additional standards identified in the PRB FEIS Biological Opinion (Volume 3, Appendix K, page 43).
9. The operator shall utilize wheel trenchers or ditchers to construct all pipeline trenches, except where extreme topography or other environmental factors preclude their use.
10. Reserve pits will be adequately fenced during and after drilling operations until pit is reclaimed so as to effectively keep out wildlife and livestock. Adequate fencing, in lieu of more stringent requirements by the surface owner, is defined as follows:
 - Construction materials will consist of steel or wood posts. Three or four strand wire (smooth or barbed) fence or hog panel (16-foot length by 50-inch height) or plastic snow fence must be used with connectors such as fence staples, quick-connect clips, hog rings, hose clamps, twisted wire, etc. Electric fences will not be allowed.
 - Construction standards: Posts shall be firmly set in ground. If wire is used, it must be taut and evenly spaced, from ground level to top wire, to effectively keep out animals. Hog panels must be tied securely into posts and one another using fence staples, clamps, etc. Plastic snow fencing must be taut and sturdy. Fence must be at least 2-feet from edge of pit. 3 sides fenced before beginning drilling, the fourth side fenced immediately upon completion of drilling and prior to rig release. Fence must be left up and maintained in adequate condition until pit is closed.
11. The reserve pit will be oriented to prevent collection of surface runoff. After the drilling rig is removed, the operator may need to construct a trench on the uphill side of the reserve pit to divert surface drainage around it. If constructed, the trench will be left intact until the pit is closed.
12. The reserve pit will be lined with an impermeable liner if permeable subsurface material is encountered. An impermeable liner is any liner having a permeability less than 10^{-7} cm/sec. The liner will be installed so that it will not leak and will be chemically compatible with all substances that may be put in the pit. Liners made of any man-made synthetic material will be of sufficient strength and thickness to withstand normal installation and pit use. In gravelly

or rocky soils, a suitable bedding material such as sand will be used prior to installing the liner.

13. The reserve pit will be constructed so that at least half of its total volume is in solid cut material (below natural ground level).
14. Culverts will be placed on channel bottoms on firm, uniform beds, which have been shaped to accept them, and aligned parallel to the channel to minimize erosion. Backfill will be thoroughly compacted.
15. The minimum diameter for culverts will be 18 inches. However, all culverts will be appropriately sized in accordance with standards in BLM Manual 9113.
16. Construction and other project-related traffic will be restricted to approved routes. Cross-country vehicle travel will not be allowed.
17. Maximum design speed on all operator-constructed and maintained roads will not exceed 25 miles per hour.
18. Pipeline construction shall not block nor change the natural course of any drainage. Pipelines shall cross perpendicular to drainages. Pipelines shall not be run parallel in drainage bottoms. Suspended pipelines shall provide adequate clearance for maximum runoff.
19. Pipeline trenches shall be compacted during backfilling. Pipeline trenches shall be routinely inspected and maintained to ensure proper settling, stabilization and reclamation.
20. During construction, emissions of particulate matter from well pad and road construction would be minimized by application of water or other non-saline dust suppressants with at least 50 percent control efficiency. Dust inhibitors (surfacing materials, non-saline dust suppressants, and water) will be used as necessary on unpaved roads that present a fugitive dust problem. The use of chemical dust suppressants on public surface will require prior approval from the BLM Authorized Officer.
21. Operators are required to obtain a National Pollution Discharge Elimination System (NPDES) Storm Water Permit from the Wyoming DEQ for any projects that disturb five or more acres (changing to one acre in March 2005). This general construction storm water permit must be obtained from WDEQ prior to any surface disturbing activities and can be obtained by following directions on the WDEQ website at <http://deq.state.wy.us>. Further information can be obtained by contacting Barb Sahl at (307) 777-7570.
22. The operator shall submit a Sundry Notice (Form 3160-5) to BLM for approval prior to construction of any new surface disturbing activities that are not specifically addressed in the approved APD Surface Use Plan.
23. Companies will contact the counties to pursue development of maintenance agreements to ensure county roads are adequately maintained for the projected increase in use.

C. Operations/Maintenance

1. Confine all equipment and vehicles to the access road(s), pad(s), and area(s) specified in the approved APD.
2. All waste, other than human waste and drilling fluids, will be contained in a portable trash

cage. This waste will be transported to a State approved waste disposal site immediately upon completion of drilling operations. No trash or empty barrels will be placed in the reserve pit or buried on location. All state and local laws and regulations pertaining to disposal of human and solid waste will be complied with.

3. Rat and mouse holes shall be filled and compacted from the bottom to the top immediately upon release of the drilling rig from the location.
4. The operator will be responsible for prevention and control of noxious weeds and weeds of concern on all areas of surface disturbance associated with this project (well locations, roads, water management facilities, etc.) Use of pesticides shall comply with the applicable Federal and State laws. Pesticides shall be used only in accordance with their registered uses and within limitations imposed by the Secretary of Interior. Prior to the use of pesticides on public land, the holder shall obtain from the BLM authorized officer written approval of a plan showing the type and quantity of material to be used, pest(s) to be controlled, method of application, location of storage and disposal of containers, and any other information deemed necessary by the authorized officer to such use.
5. Sewage shall be placed in a self-contained, chemically treated porta-potty on location.
6. The operator and their contractors shall ensure that all use, production, storage, transport and disposal of hazardous and extremely hazardous materials associated with the drilling, completion and production of these wells will be in accordance with all applicable existing or hereafter promulgated federal, state and local government rules, regulations and guidelines. All project-related activities involving hazardous materials will be conducted in a manner to minimize potential environmental impacts. In accordance with OSHA requirements, a file will be maintained onsite containing current Material Safety Data Sheets (MSDS) for all chemicals, compounds and/or substances which are used in the course of construction, drilling, completion and production operations.
7. Produced fluids shall be put in test tanks on location during completion work. Produced water will be put in the reserve pit during completion work per Onshore Order #7.
8. The only fluids/waste materials which are authorized to go into the reserve pit are RCRA exempt exploration and production wastes. These include:

- drilling muds & cuttings
- rigwash
- excess cement and certain completion & stimulation fluids defined by EPA as exempt

It does not include drilling rig waste, such as:

- spent hydraulic fluids
- used engine oil
- used oil filter
- empty cement, drilling mud, or other product sacks
- empty paint, pipe dope, chemical or other product containers
- excess chemicals or chemical rinsate

Any evidence of non-exempt wastes being put into the reserve pit may result in the BLM Authorized Officer requiring specific testing and closure requirements.

9. Operators are advised that prior to installation of any oil and gas well production equipment which has the potential to emit air contaminants, the owner or operator of the equipment must notify the Wyoming Department of Environmental Quality, Air Quality Division (phone 307-777-7391) to determine permit requirements. Examples of pertinent well production equipment include fuel-fired equipment (e.g., diesel generators), separators, storage tanks, engines and dehydrators.
10. If this well is drilled during the fire season (June-October), the operator shall institute all necessary precautions to ensure that fire hazard is minimized, including but not limited to mowing vegetation on the access route(s) and well location(s), keeping firefighting equipment readily available when drilling, etc.

D. Dry Hole/Reclamation

1. All disturbed lands associated with this project, including the pipelines, access roads, water management facilities, etc will be expediently reclaimed and reseeded in accordance with the surface use plan and any pertinent site-specific COAs.
2. Disturbed lands will be re-contoured back to conform with existing undisturbed topography. No depressions will be left that trap water or form ponds.
3. The fluids and mud must be dry in the reserve pit before re-contouring pit area. The operator will be responsible for re-contouring of any subsidence areas that develop from closing a pit before it is completely dry. The plastic pit liner (if any) will be cut off below grade and properly disposed of at a state authorized landfill before beginning to re-contour the site.
4. Before the location has been reshaped and prior to redistributing the topsoil, the operator will rip or scarify the drilling platform and access road on the contour, to a depth of at least 12 inches. The rippers are to be no farther than 24 inches apart.
5. Distribute the topsoil evenly over the entire location and other disturbed areas. Prepare the seedbed by disking to a depth of 4-to-6 inches following the contour.
6. Phased reclamation plans will be submitted to BLM for approval prior to individual APD facility abandonment via a Notice of Intent (NOI) Sundry Notice. Individual facilities, such as well locations, pipelines, discharge points, impoundments, etc. need to be addressed in these plans as they are no longer needed. Individual items that will need to be addressed in reclamation plans include:
 - Configuration of reshaped topography, drainage systems, and other surface manipulations
 - Waste disposal
 - Revegetation methods, including specific seed mix (pounds pure live seed/acre) and soil treatments (seedbed preparation, fertilization, mulching, etc.). On private surface, the landowner should be consulted for the specific seed mix.
 - Other practices that will be used to reclaim and stabilize all disturbed areas, such as water bars, erosion fabric, hydro-mulching, etc.
 - An estimate of the timetables for beginning and completing various reclamation operations relative to weather and local land uses.
 - Methods and measures that will be used to control noxious weeds, addressing both ingress and egress to the individual well.
 - Decommissioning/removal of all surface facilities

7. BLM will not release the performance bond until all disturbed areas associated with the APD/POD have been successfully revegetated (evaluation will be made after the second complete growing season) and has met all other reclamation goals of the surface owner and surface management agency.
8. A Notice of Intent to Abandon and a Subsequent Report of Abandonment must be submitted for abandonment approval.
9. For performance bond release approval, a Final Abandonment Notice (with a surface owner release letter on split-estate) must be submitted prior to a final abandonment evaluation by BLM.
10. Soil fertility testing and the addition of soil amendments may be required to stabilize some disturbed lands.
11. Any mulch utilized for reclamation needs to be certified weed free.
12. Waterbars are to be constructed at least one (1) foot deep, on the contour with approximately two (2) feet of drop per 100 feet of waterbar to ensure drainage, and extended into established vegetation. All waterbars are to be constructed with the berm on the downhill side to prevent the soft material from silting in the trench. The initial waterbar should be constructed at the top of the backslope. Subsequent waterbars should follow the following general spacing guidelines:

Slope (percent)	Spacing Interval (feet)
< 2	200
2 - 4	100
4 - 5	75
> 5	50

E. Producing Well

1. Landscape those areas not required for production to the surrounding topography as soon as possible. The fluids and mud must be dry in the reserve pit before re-contouring pit area. The operator will be responsible for re-contouring and reseeded of any subsidence areas that develop from closing a pit before it is completely dry.
2. Reduce the backslope to 2:1 and the foreslope to 3:1, unless otherwise directed by the BLM Authorized Officer. Reduce slopes by pulling fill material up from foreslope into the toe of cut slopes.
3. Production facilities (including dikes) must be placed on the cut portion of the location and a minimum of 15 feet from the toe of the back cut unless otherwise approved by the BLM Authorized Officer.
4. Any spilled or leaked oil, produced water or treatment chemicals must be reported in accordance with NTL-3A and immediately cleaned up in accordance with BLM requirements. This includes clean-up and proper disposition of soils contaminated as a result of such spills/leaks.

5. Distribute stockpiled topsoil evenly over those areas not required for production and reseed as recommended.
6. Upgrade and maintain access roads and drainage control (e.g., culverts, drainage dips, ditching, crowning, surfacing, etc.) as necessary and as directed by the BLM Authorized Officer to prevent soil erosion and accommodate safe, environmentally-sound access.
7. Prior to construction of production facilities not specifically addressed in the APD/POD, the operator shall submit a Sundry Notice to the BLM Authorized Officer for approval.
8. If not already required prior to constructing and drilling the well location, the operator shall immediately upgrade the entire access road to BLM standards (including topsoiling, crowning, ditching, drainage culverts, surfacing, etc.) to ensure safe, environmentally-sound, year-round access. This requirement does not supercede or apply where specific road requirements are addressed in the APD/POD surface use plan (e.g., two track road, spot upgrade, etc.)
9. Waterbars shall be installed on all reclaimed pipeline corridors per the guidelines in D #12.

Please contact Meleah Corey – Natural Resource Specialist, @ (307) 684-1070, Bureau of Land Management, Buffalo, if there are any questions concerning COAs.