

**CONDITIONS OF APPROVAL FOR CONVENTIONAL APPLICATION
FOR PERMIT TO DRILL**

Operator: Yates Petroleum Corporation

Field Office: Buffalo Field Office
Address: 1425 Fort Street
Buffalo, Wyoming 82834

Office Telephone Number: 307-684-1100

#	Well Name	Lot	SEC	TWP	RNG	Surface hole Lease	Bottom hole Lease
1	Starlight Federal Com #29H	20	19	43N	73W	Fee	WYW4064

SITE SPECIFIC

1. The top of cement on the intermediate casing shall be verified by cement bond log. If this log has already been run then the results shall be forwarded to this office for review. If the log has not already been run, a new log shall be run prior to returning this well to production.
2. The operator will collect a water sample representative of the water produced from this (these) wells for analysis within 30 to 60 days of initial production. Results of the analysis will be submitted to the BLM Authorized Officer as soon as they become available. The constituents analyzed in the water quality analyses will be the same as those required by the WDEQ for WYPDES permit using approved EPA test procedures (40CFR136 or 40CRF136.5).
- ~~3. After well completion, the operator shall submit a Sundry Notice for approval of disposal of all produced water in accordance with Onshore Oil and Gas Order No. 7, Disposal of Produced Water.~~

STANDARD

Producing Well

1. Landscape those areas not required for production to the surrounding topography as soon as possible. The fluids and mud must be dry in the reserve pit before recontouring pit area. The operator will be responsible for recontouring and reseeding of any subsidence areas that develop from closing a pit before it is completely dry.
2. Reduce the backslope to 2:1 and the foreslope to 3:1, unless otherwise directed by the BLM Authorized Officer. Reduce slopes by pulling fill material up from foreslope into the toe of cut slopes.
3. Production facilities (including dikes) must be placed on the cut portion of the location and a minimum of 15 feet from the toe of the back cut unless otherwise approved by the BLM Authorized Officer.

- ~~4. A dike will be constructed completely around the production facilities (i.e. production tanks, water tanks, and heater treater). The dikes for the production facilities must be constructed of impermeable soil, hold 110% of the capacity of the largest tank plus 1 foot of freeboard, and be independent of the back cut.~~
5. Any chemicals used in treating the wells (e.g., corrosion inhibitor, emulsion breaker, etc.) will be in a secure, fenced-in area with appropriate secondary containment structure (dikes, catchment pan, etc.).
6. The load out line coming from the oil/condensate tank(s) will have a suitable containment structure to capture and recycle any oil spillage that might occur.
7. Individual production facilities (tanks, treaters, etc.) will be adequately fenced off (if entire facility not already fenced off).
8. Any spilled or leaked oil, produced water or treatment chemicals must be reported in accordance with NTL-3A and immediately cleaned up in accordance with BLM requirements. This includes clean-up and proper disposition of soils contaminated as a result of such spills/leaks.
9. Any spilled or leaked oil, produced water or treatment chemicals must be reported in accordance with NTL-3A and immediately cleaned up in accordance with BLM requirements. This includes clean-up and proper disposition of soils contaminated as a result of such spills/leaks.
10. Distribute stockpiled topsoil evenly over those areas not required for production and reseed as recommended.
11. Upgrade and maintain access roads and drainage control (e.g., culverts, drainage dips, ditching, crowning, surfacing, etc.) as necessary and as directed by the BLM Authorized Officer to prevent soil erosion and accommodate safe, environmentally-sound access.
12. Prior to construction of production facilities not specifically addressed in the APD/POD, the operator shall submit a Sundry Notice to the BLM Authorized Officer for approval.
13. If not already required prior to constructing and drilling the well location, the operator shall immediately upgrade the entire access road to BLM standards (including topsoiling, crowning, ditching, drainage culverts, surfacing, etc.) to ensure safe, environmentally-sound, year-round access.
14. Waterbars shall be installed on all reclaimed pipeline corridors per the guidelines in A.4.2.4 #6.

DRILLING AND PRODUCTION OPERATIONS

1. Verbal notification shall be given to the Authorized Officer at least 24 hours before formation tests, BOP tests, running and cementing casing, and drilling over lease expiration dates.
2. New hard-band drill pipe shall not be rotated inside any casing. Hard-band drill pipe shall be considered new until it has been run at least once.
3. All Blow Out Prevention Equipment tests shall include a 5 minute low pressure test between 250 psi and 500 psi with no drop in pressure with the only exception being the chokes. The chokes are only required to have the high pressure test held for a minimum length of time necessary to verify their functional integrity.

4. All operations must be conducted in accordance with all applicable laws and regulations: with the lease terms, Onshore Oil and Gas Orders, NTL's; and with other orders and instructions of the Authorized Officer, unless a variance has been granted in writing by the Authorized Officer.
5. The Operator shall install an identification sign consistent with the requirements of 43 CFR 3162.6 immediately upon or before the completion of the well pad construction operations.
6. All Blow Out Prevention Equipment rated 5M or greater shall be isolated from the casing and tested to stack working pressure. All Blow Out Prevention Equipment tests shall be performed by a suitable test pump, not the rig-mud pumps and recorded on a chart. The chart shall be submitted to the Buffalo Field Office.
7. Low test on Blow Out Prevention Equipment shall be performed and passed before moving onto the high test for each component.
8. If there are indications of inadequate primary cementing of the surface, intermediate, or production casing strings; such as but not limited to no returns to surface, cement channeling, fallback or mechanical failure of equipment, the operator will evaluate the adequacy of the cementing operations. This evaluation will consist of running a cement bond log (CBL) or an alternate method approved by the Authorized Officer (AO) no sooner than 12 hours and no later than 24 hours from the time the cement was first pumped.
9. If the evaluation indicates inadequate cementing, the operator shall contact a BLM Buffalo Field Office Petroleum Engineer for approval of remedial cementing work.
10. The adequacy of the remedial cementing operations shall be verified by a cement bond log (CBL) or an alternate method approved by the Authorized Officer (AO). All remedial work shall be completed and verified prior to drilling out the casing shoe or perforating the casing for purposes other than remedial cementing.
- ~~11. The cement mix water used must be of the same water quality used to develop the cement program.~~
11. The cement mix water used must be of adequate quality so as not to degrade the setting properties of the cement. Any water that does not meet municipal quality water standards shall be tested by mixing the water and cement in a lab and comparing the results to the municipal quality water mix results. If the results show that the cement qualities are not the same or greater, than the non-municipal water shall not be used for mixing cement in the well.
12. All oil and gas operations shall be conducted in a manner to prevent the pollution of all freshwater resources. All fresh waters and waters of present or probable future value for domestic, municipal, commercial, stock or agricultural purposes will be confined to their respective strata and shall be adequately protected. Special precautions will be taken to guard against any loss of artesian water from the strata in which it occurs and the contamination of fresh water by objectionable water, oil, condensate, gas or other deleterious substance to such fresh water.
13. Any changes to the approved drilling plan and/or these conditions of approval shall be approved by the BLM-Buffalo Field Office Petroleum Engineer prior to being implemented.

After hour's numbers:

Supervisory Petroleum Engineer: Matthew Warren Cell Telephone: 307-620-0103